

ADDENDUM # 2**DATE:** 06/04/2026**PROJECT:** Indiana State University Hulman Center Locker Room Renovations**RATIO PROJECT NUMBER:** 26029.000**OWNER:**

Indiana State University
Facilities Management
951 Sycamore Street
Terre Haute, Indiana 47809
(812) 237-8100

ARCHITECT:

RATIO ARCHITECTS, INC.
101 South Pennsylvania Street
Indianapolis, IN 46204-3684
(317) 633-4040

MEPT ENGINEER:

R.E. Dimond & Associates, Inc.
732 N Capitol Avenue
Indianapolis, IN 46204
(317) 634-4672

This Addendum is issued in accordance with the provisions of Contract Documents and becomes a part of the Contract Documents as provided therein. The information contained herein modifies the original Bidding Documents dated **May 15, 2026** and all prior Addenda as applicable. Requirements of the original Bidding Documents and previous Addenda remain in effect except as modified by this Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

PART 1 – GENERAL CLARIFICATIONS

1. N/A

PART 2 - PROJECT MANUAL CHANGES

1. 00 50 10 – TEMPORARY FACILITIES – RENOVATION PROJECTS
 - a. Added allowable parking location.
 - b. Added temporary deliveries staging location.
 - c. Added construction access.

PART 3 - DRAWING CHANGES

1. N/A

PART 4 – PREVIOUS ADDENDA

1. ADDENDUM 01 – June 1, 2026.

PART 5 – ATTACHMENTS

- A. Drawing Sheets (by division):
 - 1.
 - 2.

- B. Specifications
 - 1. 00 50 10 – TEMPORARY FACILITIES – RENOVATION PROJECTS
- C. Supplemental Documents:
 - 1.

END OF ADDENDUM # 2

01 50 10
TEMPORARY FACILITIES - RENOVATION PROJECTS

PART 1 – GENERAL

1.01 CONTRACTOR'S USE OF PREMISES AND FACILITIES

- A. Confine operations at site to areas permitted by:
 - 1. Construction Limits
 - 2. Contract Documents
 - 3. Written Owner Approval
- B. Do not load structure with weight that will endanger structure or existing adjacent structures including any subsurface construction.
- C. The Prime Contractor shall assume full responsibility for protection and safekeeping of product stored on premises.
- D. The Prime Contractor shall move any stored products which interfere with operations of Owner or other Contractor.
- E. The activities of the Prime Contractor, including his subcontractors, material suppliers, employees, and others engaged in the work, shall be strictly limited to the Owner's property. Under no circumstances shall parking, material storage, or other uses of adjacent private property be permitted. Locations of storage areas, field office, parking areas, and the like on the project site shall be only within the construction limits as indicated on the drawings or as approved by the Owner.
- F. Use of Installed Work: Construction personnel may use toilet facilities, sink, and other fixtures and equipment installed in work only as expressly permitted by Architect/Engineer or Owner. Any privileges granted may be revoked if abused.
- G. Construction personnel shall exercise care and shall provide whatever protective measures are required to assure that their particular portions of the work do not damage or alter portions of the work that have been previously installed, either partially or completely. All work so damaged or altered shall be repaired or replaced to the satisfaction of the Architect by the party whose work has been affected, and the expense thereof shall be borne by the party who caused the damage or alteration.
- H. Protection of Floors: In interior areas used for construction or field "shops", protect floors from physical damage, oil drippings, and other staining which might impair bonding of new floor coverings, utilizing such methods as heavy polyethylene covering, sawdust or sand boxes, rigid insulation or the like.
- I. **Contractors can use 2 parking spaces per project on Eagle St.**
- J. **Contractors can use the north patio for temporary deliveries staging.**
- K. **Access to the Premium Seating site will be through the north entry ground level, then through the inner concourse. Small amounts of materials or secure tool boxes can be stored at the Premium Seating location.**

1.02 FIELD OFFICE

- A. The Prime Contractor and their Sub-Contractors shall be allowed to use space as designated by Owner within the existing building for field office..
- B. The Prime Contractor shall provide telephone service, including cellular phone for the on-site foreman, for the duration of the project.
- C. Provide at all times fire extinguishers as required by applicable codes and regulations.
- D. Post in a conspicuous space near the telephone, pertinent emergency phone numbers and notices as may be required by governing authorities and fire protection department.

01 50 10
TEMPORARY FACILITIES - RENOVATION PROJECTS

1.03 SITE PROTECTION

- A. Contractor shall adhere to Factory Mutual Engineering and Research (FM) "Cutting and Welding" permit system. Permits are available through the Office of Environmental Safety's Fire Specialist Office at 812-237-4020.
- B. Prime Contractor shall provide a one hour fire watch at the end of each workday when any cutting or welding occurred to assure that no possibility of fire exists from any work performed that day.

1.04 TEMPORARY ELECTRIC SERVICE

- A. Responsibility: The Prime Contractor shall be allowed to utilize the Owner's electricity for all construction purposes. The Prime Contractor shall arrange for the distribution and continuance throughout the work and the removal at the completion of the work of temporary electrical service. All electrical installations shall be by a Licensed Bonded Electrical Contractor. All elements of such temporary electric service shall conform to the regulations of the National Electric Code, current edition, and OSHA. All temporary wiring shall include a green equipment grounding conductor, and the entire temporary electrical service shall have equipment grounding continuity; all outlets for the connection of portable equipment shall be of the GFCI type. The Contractor shall provide all necessary wiring. The Prime Contractor or their Sub Contractor shall provide extension cords, outlets, etc. required to extend temporary service from nearest outlets of adequate capacity for the power required to points of usage.
- B. Distribution Wiring: The temporary distribution wiring shall be adequate to provide whatever is required for the operation of 120 volts, single-phase portable tools and equipment not exceeding one horsepower; the distribution wiring shall provide a receptacle within 50 feet of all portions of the building area.
- C. Temporary Lighting: The Prime Contractor shall provide all wiring, light bulbs and fixtures necessary to furnish temporary lighting of one watt per sq. ft. of construction area, but provide a minimum of one light in each enclosed space. Keep such temporary lighting in operation during all working periods.
- D. Supervision: The Prime Contractor shall maintain strict supervision over the use of the temporary electrical service and shall be responsible for damages incurred by misuse.

1.05 TEMPORARY WATER SERVICE

- A. The Prime Contractor may use the Owner's existing water service for construction purposes. The Prime Contractor shall provide and maintain leak-free, all hoses, fitting, nozzles, and the like required to distribute water to points of usage. Maintain strict supervision over use and waste of water. Take care not to spill or run water in any part of the building. Repair, replace, or restore (whichever may be deemed necessary by the Architect/Engineer) at no additional cost to the Owner, all work, new or existing, including equipment, furnishings, machines, finished surfaces, and the like which may be damaged by water due to construction operations, and by the misuse of such temporary water service. At completion of the work remove all temporary water distribution items.

1.06 RESTROOM FACILITIES

- A. The Contractor shall be permitted to utilize the Owner's restroom facilities in lieu of providing temporary toilets. The Contractor shall exercise reasonable care so as not cause excess soiling or damage to the restroom facilities.
- B. Any Contractor abuse of the Owner's restrooms shall be just cause for the Owner to revoke the use of the restrooms for the duration of the Project.

1.07 TEMPORARY STORAGE

- A. The Prime Contractor and each of their Sub-Contractors shall be responsible for their own

01 50 10
TEMPORARY FACILITIES - RENOVATION PROJECTS

temporary storage.

- B. Provide secure areas as may be required for storage and protection of materials, tools and equipment.

1.08 SIGNS

- A. Identification Signs: No signs or advertisements shall be permitted on the project site or on temporary structures, except those which are required to conform to the safety requirements of the Contract Documents or those which are expressly permitted by the Architect/Engineer or specified herein.

1.09 TEMPORARY BARRIERS

- A. The Prime Contractor shall be responsible for seeing that all shafts and openings through the floors or roofs are adequately barricaded, marked, and lighted. They shall provide barriers, markers, or other provisions, or all, at all conditions, such as items protruding from the work, which might cause injury to persons. The design, locations, and requirements of protective barricades shall be subject to approval of the Architect/Engineer, but the Contractor shall be responsible for their adequacy. When such conditions no longer exist, barriers and the like shall be removed.

1.10 SITE SECURITY

- A. All temporary construction which may be required to maintain security of buildings or construction areas shall be provided by the Prime Contractor. At the end of each day's work, close all windows opened by construction personnel, and close all access doors to work areas. Work damaged in this regard shall be repaired or replaced to the satisfaction of the Architect/Engineer/Owner. Security guard service shall not be provided as a part of any Contract for this project for field office, storage sheds and storage areas, or for protection of construction tools, equipment, and materials. Such security may, at the Contractor's option, be provided at no additional cost to the Owner.

1.11 TRASH REMOVAL

- A. The Prime Contractor shall remove from the Construction site, and legally dispose of, all rubbish resulting from the work under his contract. Rubbish shall be removed daily and not be allowed to accumulate, other than the trash placed in trash containers outside the building.

1.12 RESTORATION OF TEMPORARY FACILITIES

- A. The Prime Contractor shall be responsible for his restoration of his own temporary facilities.
- B. Storage area and project offices: At completion of the work, remove from the project site all evidence of temporary services, field office, temporary sheds, covers, pallets, excess materials, scrap materials, equipment tools, waste, debris, and other foreign materials. Restore to the Architect/Engineer's satisfaction such area to its condition which existed prior to starting construction work, utilizing whatever methods are appropriate. Repair and patch to match all drive and parking lot surfaces damaged by construction processes; subject to the Architect/Engineer's approval. Fill, grade and reseed all lawn areas and replace all trees, plants or shrubs damaged by the construction process.

1.13 TEMPORARY CONSTRUCTION AREA ENCLOSURES/BARRIERS

- A. The Prime Contractor shall provide all temporary enclosures/barriers required to secure the construction area from the rest of the building.
- B. The enclosure/barrier shall be constructed in a manner to prevent unauthorized personnel from entering the construction area during non-hours of construction.
- C. The enclosure/barrier shall constructed in a manner to limit the migration of construction dust and debris into adjacent non-construction areas.

01 50 10
TEMPORARY FACILITIES - RENOVATION PROJECTS

- D. A lockable entrance assembly shall be installed in the designated point(s) of entry. The Prime Contractor shall supply their own locking mechanism for this entrance assembly. Furnish the Owner's representative(s) with a key for this locking mechanism for the duration of the Project.

PART 2 – NOT USED

PART 3 – NOT USED

END OF SECTION 01 50 10