Applied
Engineering Services

VPS
ARCHITECTURE

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe

Central Utility Plant (CUP)

W. 13th and N. Senate Ave.



PACKAGE

SEAL|DATE 06/10/22

Central Utility Plant DD 100%

OWNER

IU Health
Indiana University Health
340 W. 10th Street
Indianapolis, Indiana 46202

MECHANICAL/ELECTRICAL ENGINEER

Applied Engineering Services, Inc.
5975 Castle Creek Parkway N. Drive
Indianapolis, Indiana 46250
(317) 810-4141

ARCHITECT

VPS Architecture
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

STRUCTURAL ENGINEER

CE Solutions
8770 North Street, Suite 100,
Fishers, IN 46038
(317) 818-1912

CIVIL ENGINEER

Cripe
9339 Priority Way West Drive, Suite 100
Indianapolis, Indiana 46240
(317) 844-6777

VOLUME
1

APPLIED PROJECT NO.
21-154

OWNER PROJECT NO.
12345

DATE
01/20/23

PROJECT ADDRESS
Southeast Corner of
W. 13th Street and N Senate
Indianapolis, Indiana

VOLUME 1
SET NO.
DATE 01/20/23
APPLIED PROJECT NO. 21-154
PACKAGE Central Utility Plant DD 100%
PROJECT NAME Central Utility Plant (CUP)

Applied
Engineering Services

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 4:09:04 PM AESI Proj. No: 21-154

SHEET INDEX

GENERAL

G001A	TITLE SHEET
G002A	SHEET INDEX

ARCHITECTURAL

A001	GENERAL PROJECT INFORMATION
A002	APPLICABLE CODES AND LIFE SAFETY PLAN
A003	LIFE SAFETY PLANS
A101	FIRST FLOOR ARCHITECTURAL PLAN
A101 D	FIRST FLOOR DIMENSION PLAN
A102	SECOND FLOOR ARCHITECTURAL PLAN
A102 D	SECOND FLOOR DIMENSION PLAN
A103	PENTHOUSE ARCHITECTURAL PLAN
A104	ROOF PLAN
A105	ROOF DETAILS
A106	FIRST FLOOR EQUIPMENT AND FURNITURE PLAN
A107	SECOND FLOOR EQUIPMENT AND FURNITURE PLAN
A201	FIRST FLOOR REFLECTED CEILING PLAN
A202	SECOND FLOOR REFLECTED CEILING PLAN
A301	EXTERIOR ELEVATIONS
A302	EXTERIOR ELEVATIONS
A401	BUILDING SECTIONS
A402	BUILDING SECTIONS
A403	BUILDING SECTION
A404	WALL SECTIONS
A405	WALL SECTIONS
A406	WALL SECTIONS
A407	EXTERIOR ASSEMBLY DETAILS
A502	STAIR AND ELEVATOR ENLARGED PLAN
A503	STAIR DETAILS
A601	EXTERIOR DETAILS
A602	EXTERIOR DETAILS

EQUIPMENT

EQ301	LOWER LEVEL EQUIPMENT PLAN
EQ302	FIRST FLOOR EQUIPMENT PLAN
EQ303	SECOND FLOOR EQUIPMENT PLAN
EQ304	ROOF EQUIPMENT PLAN

MECHANICAL

M001	MECHANICAL SYMBOLS AND ABBREVIATIONS
M201	MECHANICAL SITE PLAN
M301	LOWER LEVEL PIPING PLAN - AREA A
M304	FIRST FLOOR PIPING PLAN - AREA A
M305	FIRST FLOOR PIPING PLAN - AREA B
M306	FIRST FLOOR PIPING PLAN - AREA C
M307	FIRST FLOOR PIPING PLAN - AREA D
M308	FIRST FLOOR PIPING PLAN - AREA E
M310	FIRST FLOOR PIPING PLAN - AREA G
M311	SECOND FLOOR PIPING PLAN - AREA A
M312	SECOND FLOOR PIPING PLAN - AREA B
M313	SECOND FLOOR PIPING PLAN - AREA C
M314	SECOND FLOOR PIPING PLAN - AREA D
M315	SECOND FLOOR PIPING PLAN - AREA E
M316	SECOND FLOOR PIPING PLAN - AREA F
M319	ROOF PIPING PLAN - AREA C
M320	ROOF PIPING PLAN - AREA D
M321	ROOF PIPING PLAN - AREA E
M402	MECHANICAL MEZZANINE PLANS
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M503	MECHANICAL EQUIPMENT DETAILS
M504	MECHANICAL EQUIPMENT DETAILS
M601	MECHANICAL SCHEDULES
M602	MECHANICAL SCHEDULES
M603	MECHANICAL SCHEDULES
M604	MECHANICAL SCHEDULES
M605	MECHANICAL SCHEDULES
M606	MECHANICAL SCHEDULES
M607	MECHANICAL SCHEDULES
M701	COOLING TOWER SYSTEM - COOLING TOWER P&ID
M702	CENTRAL TOWER-WATER SYSTEM SEQUENCES
M703	CHILLED WATER SYSTEM - CHILLED WATER P&ID
M704	CENTRAL CHILLED-WATER SYSTEM SEQUENCES
M705	CUP CHILLED WATER SYSTEM PI&D
M708	CHEMICAL TREATMENT P&ID
M709	STEAM P&ID
M710	HEATING HOT WATER SYSTEM P&ID
M711	CUP HEATING HOT WATER SYSTEM P&ID
M712	GENERATOR FUEL OIL P&ID

HVAC

H301	LOWER LEVEL HVAC PLAN - AREA A
H304	FIRST FLOOR HVAC PLAN - AREA A
H305	FIRST FLOOR HVAC PLAN - AREA B
H306	FIRST FLOOR HVAC PLAN - AREA C
H307	FIRST FLOOR HVAC PLAN - AREA D
H308	FIRST FLOOR HVAC PLAN - AREA E
H309	FIRST FLOOR HVAC PLAN - AREA F
H310	SECOND FLOOR HVAC PLAN - AREA A
H311	SECOND FLOOR HVAC PLAN - AREA B
H312	SECOND FLOOR HVAC PLAN - AREA C
H313	SECOND FLOOR HVAC PLAN - AREA D
H314	SECOND FLOOR HVAC PLAN - AREA E
H315	SECOND FLOOR HVAC PLAN - AREA F
H316	ROOF HVAC PLAN - AREA A
H317	ROOF HVAC PLAN - AREA B
H318	ROOF HVAC PLAN - AREA C
H319	ROOF HVAC PLAN - AREA D
H320	ROOF HVAC PLAN - AREA E
H321	ROOF HVAC PLAN - AREA F
H401	HVAC MEZZANINE PLANS
H402	HVAC SECTIONS
H403	HVAC 3D VIEWS
H501	HVAC DETAILS
H502	HVAC DETAILS
H503	HVAC EQUIPMENT DETAILS
H601	HVAC SCHEDULES
H602	HVAC SCHEDULES
H701	HVAC ONE LINE DIAGRAMS
H702	HVAC DIAGRAMS
H703	HVAC DIAGRAMS
H704	HVAC DIAGRAMS
H705	HVAC DIAGRAMS

PLUMBING

P001	PLUMBING SYMBOLS AND ABBREVIATIONS
P302	LOWER LEVEL PLUMBING PLAN
P303	FIRST FLOOR PLUMBING PLAN
P304	SECOND FLOOR PLUMBING PLAN
P305	ROOF PLUMBING PLAN
P306	TUNNEL PLUMBING PLAN
P501	PLUMBING DETAILS
P502	PLUMBING DETAILS
P601	PLUMBING SCHEDULES
P701	PLUMBING DIAGRAMS
P801	PLUMBING WASTE & VENT ISOMETRIC

FIRE PROTECTION

FP001	FIRE PROTECTION SYMBOLS AND ABBREVIATIONS
FP301	LOWER LEVEL FIRE PROTECTION PLAN
FP302	FIRST FLOOR FIRE PROTECTION PLAN
FP303	SECOND FLOOR FIRE RPOTECTION PLAN
FP304	ROOF FIRE PROTECTION PLAN
FP401	ENLARGED FIRE PROTECTION PLANS
FP501	FIRE PROTECTION SCHEDULES AND DETAILS
FP701	FIRE PROTECTION DIAGRAMS

ELECTRICAL - LIGHTING

E001	ELECTRICAL SYMBOLS AND ABBREVIATIONS
EL301	LOWER LEVEL LIGHTING PLAN - AREA A
EL301LT	LOWER LEVEL PHOTOMETRIC PLAN - AREA A
EL304	FIRST FLOOR LIGHTING PLAN - AREA A
EL304LT	FIRST FLOOR PHOTOMETRIC PLAN - AREA A
EL305	FIRST FLOOR LIGHTING PLAN - AREA B
EL305LT	FIRST FLOOR PHOTOMETRIC PLAN - AREA B
EL306	FIRST FLOOR LIGHTING PLAN - AREA C
EL306LT	FIRST FLOOR PHOTOMETRIC PLAN - AREA C
EL307	FIRST FLOOR LIGHTING PLAN - AREA D
EL307LT	FIRST FLOOR PHOTOMETRIC PLAN - AREA D
EL308	FIRST FLOOR LIGHTING PLAN - AREA E
EL308LT	FIRST FLOOR PHOTOMETRIC PLAN - AREA E
EL309	FIRST FLOOR LIGHTING PLAN - AREA F
EL309LT	FIRST FLOOR PHOTOMETRIC PLAN - AREA F
EL310	FIRST FLOOR LIGHTING PLAN - AREA G
EL310LT	FIRST FLOOR PHOTOMETRIC PLAN - AREA G
EL311	SECOND FLOOR LIGHTING PLAN - AREA A
EL311LT	SECOND FLOOR PHOTOMETRIC PLAN - AREA A
EL312	SECOND FLOOR LIGHTING PLAN - AREA B
EL312LT	SECOND FLOOR PHOTOMETRIC PLAN - AREA B
EL313	SECOND FLOOR LIGHTING PLAN - AREA C
EL313LT	SECOND FLOOR PHOTOMETRIC PLAN - AREA C
EL314	SECOND FLOOR LIGHTING PLAN - AREA D
EL314LT	SECOND FLOOR PHOTOMETRIC PLAN - AREA D
EL315	SECOND FLOOR LIGHTING PLAN - AREA E
EL315LT	SECOND FLOOR PHOTOMETRIC PLAN - AREA E
EL316	SECOND FLOOR LIGHTING PLAN - AREA F
EL316LT	SECOND FLOOR PHOTOMETRIC PLAN - AREA F
EL317	ROOF LIGHTING PLAN - AREA A
EL317LT	ROOF PHOTOMETRIC PLAN - AREA A
EL318	ROOF LIGHTING PLAN - AREA B
EL318LT	ROOF PHOTOMETRIC PLAN - AREA B
EL319	ROOF LIGHTING PLAN - AREA C
EL319LT	ROOF PHOTOMETRIC PLAN - AREA C
EL320	ROOF LIGHTING PLAN - AREA D
EL320LT	ROOF PHOTOMETRIC PLAN - AREA D
EL321	ROOF LIGHTING PLAN - AREA E
EL321LT	ROOF PHOTOMETRIC PLAN - AREA E
EL322	ROOF LIGHTING PLAN - AREA F
EL322LT	ROOF PHOTOMETRIC PLAN - AREA F
EL401	LIGHTING MEZZAINE PLAN
EL601	LIGHTING SCHEDULES
EL602	LIGHTING PANEL

ELECTRICAL - SYSTEMS

ES301	LOWER LEVEL SYSTEMS PLAN - AREA A
ES303	LOWER LEVEL SYSTEMS PLAN - AREA D
ES304	FIRST FLOOR SYSTEMS PLAN - AREA A
ES305	FIRST FLOOR SYSTEMS PLAN - AREA B
ES306	FIRST FLOOR SYSTEMS PLAN - AREA C
ES307	FIRST FLOOR SYSTEMS PLAN - AREA D
ES308	FIRST FLOOR SYSTEMS PLAN - AREA E
ES309	FIRST FLOOR SYSTEMS PLAN - AREA F
ES310	FIRST FLOOR SYSTEMS PLAN - AREA G
ES311	SECOND FLOOR SYSTEMS PLAN - AREA A
ES312	SECOND FLOOR SYSTEMS PLAN - AREA B
ES313	SECOND FLOOR SYSTEMS PLAN - AREA C
ES314	SECOND FLOOR SYSTEMS PLAN - AREA D
ES315	SECOND FLOOR SYSTEMS PLAN - AREA E
ES316	SECOND FLOOR SYSTEMS PLAN - AREA F
ES317	ROOF SYSTEMS PLAN - AREA A
ES319	ROOF SYSTEMS PLAN - AREA C
ES320	ROOF SYSTEMS PLAN - AREA D
ES401	ENLARGED SYSTEMS PLANS
ES402	MEZZANINE SYSTEMS PLANS
ES501	SYSTEMS DETAILS
ES601	SYSTEMS SCHEDULES
ES701	SYSTEMS DIAGRAMS

ELECTRICAL - POWER

EP301	LOWER LEVEL 13,200V POWER PLAN - AREA A
EP303	LOWER LEVEL 13,200V POWER PLAN - AREA C
EP304	FIRST FLOOR 13,200V POWER PLAN - AREA A
EP305	FIRST FLOOR 13,200V POWER PLAN - AREA B
EP306	FIRST FLOOR 13,200V POWER PLAN - AREA C
EP307	FIRST FLOOR 13,200V POWER PLAN - AREA D
EP308	FIRST FLOOR 13,200V POWER PLAN - AREA E
EP309	FIRST FLOOR 13,200V POWER PLAN - AREA F
EP311	SECOND FLOOR 13,200V POWER PLAN - AREA A
EP312	SECOND FLOOR 13,200V POWER PLAN - AREA B
EP313	SECOND FLOOR 13,200V POWER PLAN - AREA C
EP314	SECOND FLOOR 13,200V POWER PLAN - AREA D
EP315	SECOND FLOOR 13,200V POWER PLAN - AREA E
EP316	SECOND FLOOR 13,200V POWER PLAN - AREA F
EP319	ROOF 13,200V POWER PLAN - AREA C
EP334	FIRST FLOOR 480V POWER PLAN - AREA A
EP335	FIRST FLOOR 480V POWER PLAN - AREA B
EP336	FIRST FLOOR 480V POWER PLAN - AREA C
EP337	FIRST FLOOR 480V POWER PLAN - AREA D
EP338	FIRST FLOOR 480V POWER PLAN - AREA E
EP339	FIRST FLOOR 480V POWER PLAN - AREA F
EP341	SECOND FLOOR 480V POWER PLAN - AREA A
EP342	SECOND FLOOR 480V POWER PLAN - AREA B
EP343	SECOND FLOOR 480V POWER PLAN - AREA C
EP344	SECOND FLOOR 480V POWER PLAN - AREA D
EP345	SECOND FLOOR 480V POWER PLAN - AREA E
EP346	SECOND FLOOR 480V POWER PLAN - AREA F
EP347	ROOF 480V POWER PLAN - AREA A
EP348	ROOF 480V POWER PLAN - AREA B
EP350	ROOF 480V POWER PLAN - AREA D
EP351	ROOF 480V POWER PLAN - AREA E
EP352	ROOF 480V POWER PLAN - AREA F
EP361	LOWER LEVEL 208V POWER PLAN - AREA A
EP363	LOWER LEVEL 208V POWER PLAN - AREA D
EP364	FIRST FLOOR 208V POWER PLAN - AREA A
EP365	FIRST FLOOR 208V POWER PLAN - AREA B
EP366	FIRST FLOOR 208V POWER PLAN - AREA C
EP367	FIRST FLOOR 208V POWER PLAN - AREA D
EP368	FIRST FLOOR 208V POWER PLAN - AREA E
EP369	FIRST FLOOR 208V POWER PLAN - AREA F
EP370	FIRST FLOOR 208V POWER PLAN - AREA G
EP371	SECOND FLOOR 208V POWER PLAN - AREA A
EP372	SECOND FLOOR 208V POWER PLAN - AREA B
EP373	SECOND FLOOR 208V POWER PLAN - AREA C
EP374	SECOND FLOOR 208V POWER PLAN - AREA D
EP375	SECOND FLOOR 208V POWER PLAN - AREA E
EP376	SECOND FLOOR 208V POWER PLAN - AREA F
EP377	ROOF 208V POWER PLAN - AREA A
EP378	ROOF 208V POWER PLAN - AREA B
EP379	ROOF 208V POWER PLAN - AREA C
EP380	ROOF 208V POWER PLAN - AREA D
EP381	ROOF 208V POWER PLAN - AREA E
EP382	ROOF 208V POWER PLAN - AREA F
EP391	LOWER LEVEL GROUNDING PLAN - OVERALL
EP392	FIRST FLOOR GROUNDING PLAN - OVERALL
EP393	SECOND FLOOR GROUNDING PLAN - OVERALL
EP394	LIGHTNING PROTECTION PLAN
EP401	ENLARGED POWER PLANS
EP403	MEZZANINE 480V POWER PLANS
EP501	POWER DETAILS
EP502	SUBSTATION DETAILS - MSS DIAGRAM AND ELEVATION
EP503	SUBSTATION DETAILS - USS-CH-1 / CH-2
EP504	SUBSTATION DETAILS - USS-MECH1/MECH2 AND ESS
EP505	SUBSTATION DETAILS - PS DIAGRAM AND ELEVATION
EP506	ELECTRICAL DETAILS
EP507	ELECTRICAL DETAILS
EP508	ELECTRICAL DETAILS
EP509	ELECTRICAL DETAILS
EP510	ELECTRICAL DETAILS
EP511	ELECTRICAL DETAILS
EP512	ELECTRICAL DETAILS
EP513	ELECTRICAL DETAILS
EP514	ELECTRICAL DETAILS
EP515	ELECTRICAL DETAILS
EP601	POWER SCHEDULES
EP602	POWER SCHEDULES
EP603	POWER SCHEDULES
EP604	POWER SCHEDULES
EP605	POWER SCHEDULES
EP606	ELECTRICAL DETAILS
EP607	POWER SCHEDULES
EP608	POWER SCHEDULES
EP609	POWER SCHEDULES
EP701	PRIMARY ONE LINE DIAGRAM
EP702	MSS SINGLE LINE DIAGRAM
EP703	PS ONE LINE DIAGRAM
EP704	USS-MECH1 SINGLE LINE DIAGRAM
EP705	USS-MECH2 SINGLE LINE DIAGRAM
EP706	USS-CH1 SINGLE LINE DIAGRAM
EP707	USS-CH2 SINGLE LINE DIAGRAM
EP708	USS-CUP-ESS SINGLE LINE DIAGRAM
EP709	SWBD1 SINGLE LINE DIAGRAM
EP710	SWBD2 SINGLE LINE DIAGRAM
EP711	SWBD3 SINGLE LINE DIAGRAM
EP712	SWBD4 SINGLE LINE DIAGRAM
EP713	SWBD5 SINGLE LINE DIAGRAM
EP714	SWBD6 SINGLE LINE DIAGRAM
EP715	SWBD7 SINGLE LINE DIAGRAM
EP716	ELECTRICAL SCADA SYSTEM SCHEMATIC DIAGRAM
EP717	ONELINE DIAGRAM FOR ARC FLASH - OVERALL
EP718	HEAT TRACE SCHEMATIC
UE501	ELECTRICAL SITE DETAILS
UE502	ELECTRICAL SITE DETAILS

SPECIALTY - REFERENCE

C100	OVERALL SITE LAYOUT
C703	SSB TO AAHC DEMARK MANHOLES
C705	CUP TO SSB
C706	CUP SITE DEMARK POINTS

SPECIALTY - UTILITY TUNNEL

UT100	UTILITY TUNNEL
UT101	UTILITY TUNNEL - CUP
UT101.1	MECHANICAL
UT101.2	PLUMBING - FIRE PROTECTION
UT101.3	POWER - SYSTEMS
UT101.4	LIGHTING
UT101.5	UTILITY SUPPORT DETAILS
UT102	UTILITY TUNNEL - SSB
UT102.1	SSB - MECHANICAL
UT102.2	SSB - FIRE PROTECTION
UT102.3	SSB - SYSTEMS
UT103	PNEUMATIC TUBES

SPECIALTY - PNEUMATIC TUBES

PT0.000	PNEUMATIC TUBE COVER SHEET
PT1.000	PNEUMATIC TUBE RISER DIAGRAM
PT2.LL1	PNEUMATIC TUBE PLANS - LOWER LEVEL 1
PT2.LL2	PNEUMATIC TUBE PLANS - LOWER LEVEL 2
PT3.000	PNEUMATIC TUBE EQUIPMENT
PT3.100	PNEUMATIC TUBE MISC. PARTS
PT3.200	PNEUMATIC TUBE WALL & FLOOR PENETRATIONS

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: **Designer**
CHECKED BY: **Checker**
APPROVED BY: **Approver**
PROJECT NO.: **21-154**


CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE: **SHEET INDEX**

SHEET NUMBER: **G002B**


0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 4:09:04 PM AESI Proj. No: 21-154



PUBLIC ACCESSIBLE LAVATORY ELEVATION


NTS



ACCESSIBLE URINAL ELEVATION/PLAN

NTS

REACH NOTES:
1. AN OBSTRUCTION BETWEEN THE ELEMENT AND THE CLEAR FLOOR SPACE IS 10" MAXIMUM ATB48" SIDE REACH RANGE.




HIGH & LOW REACH LIMITS (UNOBSTRUCTED)

TOILET ROOM ACCESSORIES SUCH AS SOAP DISPENSERS, PAPER TOWEL DISPENSERS, AND TRASH RECEPTACLES MUST BE OPERABLE WITHIN THESE MAXIMUM REACH DIMENSIONS.


REACH DETAIL

NTS



PUBLIC ACCESSIBLE STALL ELEVATION


NTS



MIN. REQUIRED FLOOR CLEARANCE @ DOORS

NTS


NOTE: THIS REQUIREMENT APPLIES TO ALL NEW OR RELOCATED DOORS WITH BOTH CLOSER AND LATCHES.



PUBLIC RESTROOM MOUNTING HEIGHTS


NTS

DRINKING FOUNTAIN NOTES:
1. DIMENSIONS SHOWN BELOW APPLY TO EITHER HI-LOW ACCESSIBLE DRINKING FOUNTAINS OR SINGLE ACCESSIBLE DRINKING FOUNTAIN AS SHOWN



ACCESSIBLE DRINKING FOUNTAIN

NTS




PUBLIC AREAS MOUNTING HEIGHTS

NTS

ABBREVIATIONS:
FDVC= FIRE DEPARTMENT VALVE CABINET
FEC= FIRE EXTINGUISHER CABINET

NOTES:
USE FOR REFERENCE AND MOUNTING HEIGHTS TO COMPLY WITH LOCAL AND FEDERAL ACCESSIBILITY REQUIREMENTS. CONTRACTOR TO ALERT ARCHITECT WITH ANY DISCREPANCY IN DRAWINGS THAT CAN/NOT MEET DIMENSIONS PROVIDED HERE. COORDINATE WITH MEP DRAWINGS. COORDINATE WITH ARCHITECT IF THERE ARE DISCREPANCIES.



TYPICAL PARTITION TYPE

3/4" = 1'-0"

REFERENCE SYMBOLS

1. APPLY TO 'A' SERIES DRAWINGS ONLY
2. REFER TO REFLECTED CEILING PLANS & ROOF PLANS FOR ADDITIONAL SYMBOLS FOR THOSE DRAWINGS.
3. REFER TO CIVIL, STRUCTURAL, AND MEP DRAWINGS FOR SYMBOLS PERTAINING TO THOSE DRAWINGS.



COLUMN LINES - NEW CONSTRICTION

COLUMN LINES - EXISTING CONSTRICTION



GENERAL ROOM TAG - BLUE TEXT

GENERAL CEILING TAG - CEILING HEIGHT



GENERAL DOOR TAG - DOOR MARK



GENERAL WALL TAG - WALL TYPE

GENERAL WINDOW TAG - WINDOW TYPE




GENERAL REVISION TAG - REVISION BUBBLE




GENERAL REFERENCE NOTE




GENERAL DEMOLITION REFERENCE NOTE




GENERAL ELEVATION TAG




GENERAL SECTION - WALL SECTION



GENERAL SECTION - BUILDING SECTION



VIEW TITLE - DRAWING NUMBER W/ REFERENCING DETAIL SHEET



GENERAL CALLOUT DETAIL

ABBREVIATIONS

L	ANGLE	F	FLUSH	PC	PRECAST CONCRETE
°	DEGREES	FD	FLOOR DRAIN	PLAM	PLASTIC LAMINATE
Ø	DIAMETER	FE	FIRE EXTINGUISHER	PLUMB	PLUMBING
#	NUMBER	FEC	FIRE EXTINGUISHER CABINET & FIRE EXTINGUISHER	PLYWD	PLYWOOD
+/-	PLUS OR MINUS	FFE	FINISH FLOOR ELEVATION	PR	PAIR
ACOUST	ACOUSTIC/ ACOUSTICAL	FF & E	FURNISHING, FIXTURES AND EQUIPMENT	PREP	PREPARE
ACP	ACOUSTIC CEILING PANEL	FG	FULL GLASS	PT	PAINT
ACT	ACOUSTIC CEILING TILE	FHC	FIRE HOSE CABINET	PTD	PAINTED
ADA	AMERICAN DISABILITIES ACT	FL	FLOOR	PVC	POLYVINYL CHLORIDE
ADJ	ADJUSTABLE	FR	FIRE RESISTANT	QTY	QUANTITY
A/E	ARCHITECT/ENGINEER	FRT	FIRE RETARDANT TREATED	QZT	QUARTZ TOP
AED	AUTOMATED EXTERNAL DEFIBRILLATOR	FT	FLOOR TILE	R	RISER
AFF	ABOVE FINISHED FLOOR	FVC	FIRE VALVE CABINET	RAD	RADIOS
ANOD	ANODIZED	GA	GAUGE	RB	RESILIENT WALL BASE
AL	ALUMINUM	GB	GRAB BAR	RCP	REFLECTED CEILING PLAN
ALT	ALTERNATE	GALV	GALVANIZED	RD	ROOF DRAIN
AP	ACCESS PANEL	GL	GLASS	REINM	REINFORCE/REINFORCING
APPROX	APPROXIMATE	GYP	GYPSUM	REQD	REQUIRED
				REV	REVISION
BD	BOARD	H	HIGH	RH	RIGHT HAND
BEJ	BRICK EXTENSION JOINT	HDW	HARDWARE	RM	ROOM
BLDG	BUILDING	HG	HALF GLASS	RO	ROUGH OPENING
BLKG	BLOCKING	HT	HEIGHT	RE:	REFER TO
BLW	BELOW	HM	HOLLOW METAL	REF	REFERENCE
BOT	BOTTOM	HORIZ	HORIZONTAL		
BS	BOTH SIDES	HR	HOUR	SCH	SCHEDULE
BTWN	BETWEEN			SCW	SOLID CORE WOOD
		INSUL	INSULATION	SF	SQUARE FEET
C/C	CENTER TO CENTER	INT	INTERIOR	SHT	SHEET
CFCI	CONTRACTOR FURNISHED CONTRACTOR INSTALLED	JAN	JANITOR	SIM	SIMILAR
CG	CORNER GUARD	JT	JOINT	SM	SHEET METAL
CJ	CONTROL JOINT			SQ	SQUARE
CL	CENTERLINE	L	ANGLE	STD	STANDARD
CLG	CEILING	LAV	LAVATORY	SIM	SIMILAR
CLR	CLEAR	LAM	LAMINATE	SS	SOLID SURFACE
CMU	CONCRETE MASONRY UNIT	LB	POUND	SST	STAINLESS STEEL
COL	COLUMN	LG	LENGTH, LONG	STL	STEEL
CONC	CONCRETE	LH	LEFT HAND	STRUCT	STRUCTURAL
CONST	CONSTRUCTION	LLH	LONG LEG HORIZONTAL	SUSP	SUSPENDED/SUSPENSION
CONT	CONTINUOUS	LLV	LONG LEG VERTICAL	SYM	SYMMETRICAL
CONTR	CONTRACTOR	LVP	LUXURY VINYL PLANK		
COORD	COORDINATE	LVT	LUXURY VINYL TILE	T	TREAD
CORR	CORRIDOR			TB	TACK BOARD
CPT	CARPET	MAS	MASONRY	TBD	TO BE DETERMINED
CR	CARD READER	MAX	MAXIMUM	TEMP	TEMPERED
CT	CERAMIC TILE	MB	MARKER BOARD	TG	TEMPERED GLASS
CTB	CERAMIC TILE BASE	ME	MATCH EXIST	THK	THICK
		MECH	MECHANICAL	TO	TOP OF
DBL	DOUBLE	MEP	MECH./ELEC./ PLUMBING	TYP	TYPICAL
DEMO	DEMOLISH/DEMOLITION	MFR	MANUFACTURE	TZ	TERRAZZO
DET	DETAIL	MIN	MINIMUM		
DIA	DIAMETER	MISC	MISCELLANEOUS	UL	UNDERWRITERS LABORATORIES
DIM	DIMENSION	MO	MASONRY OPENING	UNO	UNLESS NOTED OTHERWISE
DN	DOWN	MTD	MOUNTED	UTIL	UTILITY
DR	DOOR	MTL	METAL		
DS	DOWNSPOUT	MUL	MULLION	VCT	VINYL COMPOSITION TILE
DWG	DRAWING			VERT	VERTICAL
		N/A	NOT APPLICABLE	VEST	VESTIBULE
EA	EACH	NIC	NOT IN CONTRACT	VIF	VERIFY IN FIELD
EJ	EXPANSION JOINT	NL	NARROW LIGHT	VTR	VENT THROUGH ROOF
EL	ELEVATION	NO.	NUMBER		
ELEC	ELECTRICAL	NOM	NOMINAL	W	WIDE, WIDTH
ELEV	ELEVATION/ELEVATOR	NTS	NOT TO SCALE	W/	WITH
EP	ELECTRICAL PANEL			WCP	WOOD CEILING PLANK
EQ	EQUAL	OC	ON CENTER	WCT	WOOD CEILING TILE
EQUIP.	EQUIPMENT	OD	OUTSIDE DIAMETER	WD	WOOD
ETR	EXISTING TO REMAIN	OFCI	OWNER FURNISHED/ CONTRACTOR INSTALLED	W/O	WITHOUT
EXIST.	EXISTING	OFOI	OWNER FURNISHED/ OWNER INSTALLED	WP	WALL PROTECTION
EXP	EXPANSION / EXPOSED	OH	OVERHEAD	WR	WATER RESISTANCE
EXT	EXTERIOR	OPG	OPENING	WT	WALL TILE, WEIGHT
EWC	ELECTRIC WATER COOLER	OPP	OPPOSITE		
		O.H.	OPPOSITE HAND		
		O/O	OUT TO OUT		

HATCH PATTERN LEGEND

BATT INSULATION / SOUND ATTENUATION BLANKET

CONCRETE

CONCRETE MASONRY UNIT

RIGID INSULATION

GYPSUM BOARD

BRICK

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	


SHEET TITLE

GENERAL PROJECT INFORMATION

SHEET NUMBER

A001

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:44 PM AESI Proj. No:
0 1/2" 1" 2"



LOWER LEVEL LIFE SAFETY PLAN
1/16" = 1'-0"

LIFE SAFETY PLAN LEGEND

- EXIT — INDICATES ROOM, SUITE, OR BUILDING EXIT
- INDICATES PATH OF EGRESS TRAVEL
- INDICATES MAXIMUM OVERALL DIAGONAL DISTANCE
- INDICATES DISTANCE BETWEEN EXITS
- 1H 1H — INDICATES 1-HOUR RATED WALL CONSTRUCTION
- 2H 2H — INDICATES 2-HOUR RATED WALL CONSTRUCTION
- F.E.C. — INDICATES RECESSED FIRE EXTINGUISHER CABINET LOCATION
- F.E. — INDICATES BRACKET-MOUNTED FIRE EXTINGUISHER LOCATION
- INDICATES EXTENTS OF MEZZANINE ABOVE

OCCUPANCY TYPE LEGEND

- GROUP B
- GROUP F-1
- GROUP H-3

APPLICABLE CODES AND STANDARDS

MUNICIPAL:
INDIANAPOLIS REGIONAL CENTER PLAN 2020, REGIONAL CENTERS DESIGN GUIDELINES
MARION COUNTY THOROUGHFARE PLAN
INDIANAPOLIS REGIONAL PEDESTRIAN PLAN
INDIANAPOLIS METROPOLITAN PLANNING AREA MULTI-MODAL CORRIDOR AND PUBLIC SPACE DESIGN GUIDELINES
ZONING CODE, CBD-S
INDIANAPOLIS DEPARTMENT OF PUBLIC WORKS SPECIFICATIONS AND MANUALS
CITIZENS ENERGY GROUP WASTEWATER STANDARDS MANUAL
CITIZENS ENERGY GROUP WATER STANDARDS MANUAL
IPL GOLD BOOK
INDIANAPOLIS-MARION COUNTY CONSOLIDATED ZONING AND SUBDIVISION ORDINANCE

STATE OF INDIANA:
INDIANA BUILDING CODE 2014 EDITION (2012 IBC W/ 2014 INDIANA AMENDMENTS)
INDIANA PLUMBING CODE 2012 EDITION (2006 IPC W/ INDIANA AMENDMENTS)
INDIANA ELECTRICAL CODE (2008 NATIONAL ELECTRICAL CODE W/ INDIANA AMENDMENTS)
INDIANA MECHANICAL CODE (2012 INTERNATIONAL MECHANICAL CODE W/ 2014 INDIANA AMENDMENTS)
INDIANA ENERGY CONVERSATION CODE (ASHRAE 90.1 2007 W/ INDIANA AMENDMENTS)
INDIANA SAFETY CODE FOR ELEVATORS, ESCALATORS, MAN LIFTS AND HOISTS (ANSI/ ASME A17.1 2007 W/ INDIANA AMENDMENTS)
INDIANA FIRE PREVENTION CODE (2012 INTERNATIONAL FIRE CODE W/ INDIANA AMENDMENTS)
INDIANA SUPPLEMENTARY FIRE SAFETY RULES, 2003
INDIANA SAFETY CODE FOR ELEVATORS, ESCALATORS, MAN LIFTS AND HOISTS: (ANSI/ASME 2007 W/ INDIANA AMENDMENTS)
NEW ELEVATOR SAFETY CODE, 2011
INDIANA FUEL GAS CODE: (2012 INTERNATIONAL FUEL GAS CODE W/ INDIANA AMENDMENTS
NATIONAL FIRE PROTECTION ASSOCIATION STANDARDS (NFPA)
2018 EDITION OF THE "GUIDELINE FOR DESIGN AND CONSTRUCTION OF HOSPITALS" PUBLISHED BY THE AMERICAN INSTITUTE OF ARCHITECTS.
INDIANA WASTEWATER TREATMENT FACILITIES; ISSUANCE OF PERMITS; CONSTRUCTION AND PERMIT REQUIREMENTS CODE (327-IAC-3)
INDIANA PUBLIC WATER SUPPLY CODE (327-IAC-8)

FEDERAL:
NATIONAL FIRE PROTECTION ASSOCIATION, NFPA 101 LIFE SAFETY CODE, 2012 EDITION
INDIANA UNIVERSITY HEALTH MEDICAL CENTER CAMPUS K. CONCEPT BASIS OF DESIGN (BOD) NARRATIVE PHASE I DELIVERABLES VOLUME 1 - INTRODUCTION AND CAMPUS-WIDE DESIGN REQUIREMENTS NOVEMBER 4, 2020
NATIONAL FIRE PROTECTION ASSOCIATION, NFPA 99, STANDARDS FOR HEALTH CARE FACILITIES CODE 2012 EDITION, EXCEPT FOR CHAPTERS 7--FORMATION TECHNOLOGY AND COMMUNICATIONS SYSTEMS FOR HEALTH CARE FACILITIES; 8—PLUMBING; 12—EMERGENCY MANAGEMENT; AND 13—SECURITY MANAGEMENT ALSO ADOPTED 2012 HCFC TENTATIVE INTERIM AMENDMENT 12–2, 12–3, 12–4, 12–5 AND 12–6.
2010 ADA STANDARDS FOR ACCESSIBLE DESIGN IS ENFORCED BY THE U.S. DEPARTMENT OF JUSTICE; ICC/ANSI A117.1—03 IS THE REFERENCED STANDARD IN THE 2009 INTERNATIONAL BUILDING CODE FOR ACCESSIBILITY.
FEDERAL AVIATION ADMINISTRATION ADVISORY CIRCULAR 150/5390-2C DATED 04/24/2012.
UNITED STATES CODE TITLE 21 -- FOOD AND DRUGS CHAPTER 9 - SUBCHAPTER V – DRUGS AND DEVICES PART A - SEC. 353A - PHARMACY COMPOUNDING REFERENCES
UNITED STATES PHARMACOPEIA'S (USP'S) GENERAL CHAPTER 797
PHARMACEUTICAL COMPOUNDING—STERILE PREPARATIONS
USP GENERAL CHAPTER 800 HAZARDOUS DRUGS HANDLING IN HEALTHCARE SETTINGS IS NOT CURRENTLY ENACTED BUT WOULD BE FOLLOWED AS A BEST PRACTICE AND IS EXPECTED TO BE ADOPTED IN NEAR-TERM FUTURE. [BECAUSE IT IS LIKELY TO BE ENACTED PRIOR TO PROJECT OCCUPANCY IT IS KEPT AS A MANDATORY REQUIRED STANDARD, RATHER THAN BEING LISTED AS A VOLUNTARY STANDARD.

STANDARDS:
PROPOSED ACCESSIBILITY GUIDELINES FOR PEDESTRIAN FACILITIES IN THE PUBLIC RIGHT-OF-WAY JULY 26, 2011; UNITED STATES ACCESS BOARD. (PROPOSED FOR REFERENCE IN THE PUBLIC RIGHT OF WAY, EVEN THOUGH THIS IS NOT ENACTED ENFORCEABLE STANDARD)
DESIGN GUIDE FOR IMPROVING HOSPITAL SAFETY IN EARTHQUAKES, FLOODS, AND HIGH WINDS FEMA 577 / JUNE 2007 THIS IS NOT A PRESCRIPTIVE OR ADOPTED STANDARD BUT SHOULD BE USED AS A REFERENCE DOCUMENT TO HAVE DISCUSSIONS IF PERFORMANCE STANDARDS EXCEEDING CODE REQUIREMENTS IS DESIRED. IT IS CITED AS A SOURCE FOR REFERENCE, AND TO BE USED FOR A SOURCE OF COMMON TERMINOLOGY AND FRAMEWORK IN THOSE DISCUSSIONS.)
2018 GUIDELINES FOR DESIGN AND CONSTRUCTION OF HOSPITALS AND OUTPATIENT FACILITIES; FACILITY GUIDELINES INSTITUTE.
ACR GUIDANCE DOCUMENT FOR SAFE MR PRACTICES: 2013
ASHRAE STANDARD 188 LEGIONELLOSIS: RISK MANAGEMENT FOR BUILDING WATER SYSTEMS, GUIDELINE 12 MINIMIZING THE RISK OF LEGIONELLOSIS ASSOCIATED WITH BUILDING WATER SYSTEMS
ASHRAE 189.3-2017: DESIGN, CONSTRUCTION, AND OPERATION OF SUSTAINABLE HIGH-PERFORMANCE HEALTH CARE FACILITIES
ASHRAE STANDARD 170-2013: VENTILATION OF HEALTH CARE FACILITIES
ASHRAE STANDARD 62.1-2019: VENTILATION FOR ACCEPTABLE INDOOR AIR QUALITY
ASHRAE STANDARD 90.1-2019: ENERGY STANDARD FOR BUILDINGS EXCEPT LOW-RISE RESIDENTIAL BUILDINGS (ASHRAE 90.1-2007 IS THE BASIS FOR THE INDIANA ENERGY CODE, HOWEVER ASHRAE 90.1-2019 IS THE CURRENT VERSION AND IS THE BASIS OF DESIGN FOR THE IUHMCC. MANDATORY REQUIREMENTS OF ASHRAE STANDARD 90.1-2010 MUST ALSO BE ACHIEVED FOR LEED V4 CERTIFICATION.)
LEED RATING SYSTEM (THIS IS NOT A PRESCRIPTIVE STANDARD; IT IS A THIRD-PARTY CERTIFICATION SYSTEM WITH A REFERENCE GUIDE.)
LEED FOR BUILDING DESIGN AND CONSTRUCTION V4: NEW CONSTRUCTION AND MAJOR RENOVATION
LEED FOR BUILDING DESIGN AND CONSTRUCTION V4: HEALTHCARE
LEED FOR INTERIOR DESIGN AND CONSTRUCTION V4: COMMERCIAL INTERIORS
SITES RATING SYSTEM (THIS IS NOT A PRESCRIPTIVE STANDARD; IT IS A THIRD-PARTY CERTIFICATION SYSTEM.)
THE SUSTAINABLE SITES INITIATIVE (SITES) V2
NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
AMERICAN SOCIETY FOR TESTING AND MATERIALS
AMERICAN CONCRETE INSTITUTE
AMERICANS WITH DISABILITIES ACT (ADA)
AMERICAN SOCIETY OF MECHANICAL ENGINEERS
AMERICAN WATER WORKS ASSOCIATION
MIDWEST INSULATION CONTRACTORS ASSOCIATION
AMERICAN NATIONAL STANDARDS INSTITUTE
AMERICAN PETROLEUM INSTITUTE
BUILDING INDUSTRY ASSOCIATION
TIA/EIA
BICSI
INSTITUTE OF ELECTRICAL AND ELECTRONIC ENGINEERS (IEEE)UNDERWRITERS LABORATORIES (UL) LISTINGS


BUILDING CODE SUMMARY

PROJECT SCOPE:	A NEW CENTRAL UTILITY PLANT (CUP) CONSTRUCTED ON GRADE AS A STANDALONE BUILDING OF TWO-LEVEL, F-1 OCCUPANCY THAT IS SIZED TO SUPPORT THE UTILITY LOADS DEMANDED BY THE INDIANA UNIVERSITY HEALTH MEDICAL CENTER (IUH MCC) AND CONFIGURED SUCH THAT IT IS ABLE TO EXPAND TO SUPPORT ANY FUTURE GROWTH ON THE INDIANA UNIVERSITY HEALTH MEDICAL CENTER CAMPUS (IUH MCC). MECHANICAL AND PLUMBING UTILITIES, SUCH AS HOT WATER, COLD WATER, AND HIGH-PRESSURE STEAM, GENERATED IN THE CUP WILL BE DISTRIBUTED TO THE IUHMC VIA PIPING IN A NEW UTILITY TUNNEL, BOTH NORMAL AND EMERGENCY POWER WILL BE DISTRIBUTED TO THE IUHMC VIA BELOW GRADE CONDUIT DUCT BANKS. A NEW, BELOW GRADE AES SERVICE LINE, PROVIDED BY AES, WILL ENTER THE CUP BUILDING. THE CUP IS INTENDED TO BE A TWO (2) STORY BUILDING WITH MECHANICAL AND PLUMBING EQUIPMENT LOCATED ON THE FIRST FLOOR; OFFICES, A LOCKER ROOM/BREAK ROOM, ELECTRICAL EQUIPMENT, AND REQUIRED INTAKE LOUVERS WILL BE LOCATED ON THE SECOND FLOOR; COOLING TOWERS, EXHAUST FANS, AND BOILER EXHAUSTS ARE TO BE LOCATED ON THE ROOF. ADDITIONALLY, THERE WILL BE FIVE (5) FUEL OIL STORAGE TANKS THAT WILL BE DIRECT BURIED ON THE SITE, BENEATH THE SERVICE YARD AND EASTERN SITE, IN A MANNER THAT ALLOWS FOR PROPER SUCTION FROM THE TANKS BY THE NEARBY FUEL PUMP ROOM WITHIN THE CUP. A TRUCK LAYBY AT GRADE WILL BE PROVIDED FOR REFUELING. THE SERVICE YARD WILL BE SCREENED FROM PUBLIC VIEW, AND WILL ACT AS A SPACE FOR PARKING, AS WELL AS DELIVERIES THROUGH AN OVERHEAD DOOR TO BE SIZED BASED ON THE LARGEST PIECE OF MACHINERY THAT IT WILL NEED TO ACCOMMODATE. A NEW UTILITY TUNNEL WILL BE CONSTRUCTED TO DELIVER UTILITIES, MEDICAL GASES, AND PNEUMATIC TUBES TO THE IUHMC. IT IS TO EXIT FROM THE CUP AND TERMINATE INTO THE DESIGNATED MECHANICAL SPACE WITHIN THE IUHMC. THE EXISTING PNEUMATIC TUBE SYSTEM WILL BE REDIRECTED FROM THE EXISTING, ABOVE GRADE PEOPLE MOVER AND BROUGHT BELOW GRADE TO MEET THE NEW UTILITY TUNNEL.
OCCUPANCY CLASSIFICATIONS:	MIXED OCCUPANCY INCLUDING THE FOLLOWING: 1. BUSINESS OCCUPANCY, GROUP B (AS AN INCIDENTAL USE) 2. MODERATE-HAZARD FACTORY INDUSTRIAL, GROUP F-1 3. HIGH-HAZARD, GROUP H-3, WHERE CLASS I, II OR IIIA FLAMMABLE OR COMBUSTIBLE LIQUIDS ARE USED OR STORED IN NORMALLY CLOSED CONTAINERS OR SYSTEMS PRESSURIZED AT 15 POUNDS PER SQUARE INCH GAUGE (103.4 KPA) OR LESS
CONSTRUCTION TYPE:	TYPE II – B, FULLY SPRINKLERED
ALLOWABLE HEIGHT:	TABULAR HEIGHT = 55 FEET AND 2 STORIES HEIGHT ALLOWABLE DUE TO AUTOMATIC SPRINKLERS = 75 FEET AND 3 STORIES WITH AUTOMATIC SPRINKLER INCREASE
ALLOWABLE FLOOR AREA:	TABULAR AREA = 15,500 SF. PER STORY AREA INCREASE DUE TO AUTOMATIC SPRINKLERS = 15,500 + 31,000 = 46,500 SF PER STORY ACTUAL PROPOSED AREA PER FLOOR = 39,293 SF
SPRINKLER HEIGHT INCREASE:	WHERE A BUILDING IS EQUIPPED THROUGHOUT WITH AN APPROVED AUTOMATIC SPRINKLER SYSTEM IN ACCORDANCE WITH SECTION 903.3.1.1 THE VALUES SPECIFIED IN TABLE 503 FOR MAXIMUM BUILDING HEIGHT IS INCREASED BY 20 FEET (6096 MM) AND THE MAXIMUM NUMBER OF STORIES IS INCREASED BY ONE. THESE INCREASES ARE PERMITTED IN ADDITION TO THE BUILDING AREA INCREASE IN ACCORDANCE WITH SECTIONS 506.2 AND 506.3.
AREA INCREASE DUE TO STREET FRONTAGE:	EVERY BUILDING SHALL ADJOIN OR HAVE ACCESS TO A PUBLIC WAY TO RECEIVE A BUILDING AREA INCREASE FOR FRONTAGE. WHERE A BUILDING HAS MORE THAN 25 PERCENT OF ITS PERIMETER ON A PUBLIC WAY OR OPEN SPACE HAVING A WIDTH OF NOT LESS THAN 20 FEET (6096 MM), THE FRONTAGE INCREASE SHALL BE DETERMINED IN ACCORDANCE WITH EQUATION 5-2: $I_f = [F/P - 0.25] W/30$ (EQUATION 5-2) WHERE: I_f = AREA INCREASE DUE TO FRONTAGE F = BUILDING PERIMETER THAT FRONTS ON A PUBLIC WAY OR OPEN SPACE HAVING 20 FEET (6096 MM) OPEN MINIMUM WIDTH (FEET) = 231'-0" + 145'-3" + 145'-3" = 521'-6" P = PERIMETER OF ENTIRE BUILDING (FEET) = (231'-0" X 2=462'-0")+(145'-3" X 2=290'-6")=752'-6" W = WIDTH OF PUBLIC WAY OR OPEN SPACE (FEET) IN ACCORDANCE WITH SECTION 506.2.1. I_f = [(521'- 6" / 752'- 6") - 0.25] 20/30 I_f = (.4430).6667 = .2953 X 15,500 SF. = 4,577.15 SF.
PROPOSED BUILDING AREA BY FLOOR:	LOWER LEVEL = 4,663 GROSS SF. FIRST FLOOR = 39,293 GROSS SF. SECOND FLOOR = 39,293 GROSS SF. TOTAL = 78,586 GROSS SF.
FIRE SEPARATION DISTANCE IN FEET:	A PORTION OF THE EXISTING ADJACENT JCI BUILDING IS SCHEDULED TO BE DEMOLISHED AND A PORTION IS SCHEDULED TO REMAIN IN PLACE, RESULTING IN A FIRE SEPARATION DISTANCE OF APPROXIMATELY 17 FEET. FOR OCCUPANCY GROUP F-1, CONSTRUCTION TYPE II-B, A FIRE SEPARATION DISTANCE OF BETWEEN 10 FEET AND 30 FEET REQUIRES NO FIRE RATING FOR EXTERIOR WALLS.
SEPARATED OCCUPANCIES:	PER TABLE 508.4: 1. NO SEPARATION IS REQUIRED BETWEEN B AND F-1 OCCUPANCIES. 2. A 1-HOUR FIRE SEPARATION IS REQUIRED BETWEEN AN H-3 AND B/F-1 OCCUPANCIES.
DESIGN OCCUPANT LOAD:	THE DESIGN OCCUPANT LOAD IS PERMITTED TO BE DETERMINED BASED UPON THE ACTUAL ANTICIPATED OCCUPANT LOAD. THE ASSUMPTION IS THAT THE CUP WILL BE OCCUPIED TWENTY-FOUR (24) HOURS PER DAY, SEVEN (7) DAYS PER WEEK, AND 365 DAYS PER YEAR. THERE WILL BE THREE (3) SHIFTS PER DAY OF FIVE (5) FULL TIME EMPLOYEES EACH SHIFT.
OCCUPANT LOAD FACTOR:	ACCESSORY STORAGE AREAS, MECHANICAL EQUIPMENT ROOM = 300 GROSS BUSINESS AREAS = 100 GROSS LOCKER ROOMS = 50 GROSS
MEANS OF EGRESS SIZING:	REQUIRED CAPACITY BASED ON OCCUPANT LOAD: STAIRWAYS = 0.3 INCH PER OCCUPANT. OTHER EGRESS COMPONENTS = 0.15 INCH PER OCCUPANT IN BUILDINGS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM.
EGRESS ACCESS TRAVEL DISTANCE:	FOR FULLY SPRINKLERED BUILDING: OCCUPANCY GROUP F-1 – 250 FEET OCCUPANCY GROUP H-3 – 150 FEET OCCUPANCY GROUP B – 300 FEET
NUMBER OF EXITS AND EXIT CONFIGURATION:	EACH STORY AND OCCUPIED ROOF SHALL HAVE A MINIMUM NUMBER OF EXITS, OR ACCESS TO EXITS. WHERE A BUILDING IS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM THE SEPARATION DISTANCE OF THE EXIT DOORS OR EXIT ACCESS DOORWAYS SHALL NOT BE LESS THAN ONE-THIRD OF THE LENGTH OF THE MAXIMUM OVERALL DIAGONAL DIMENSION OF THE AREA SERVED MAXIMUM OVERALL DIAGONAL = 302' - 1 3/4" / 3 = 100' - 8 9/16" MINIMUM EXIT SEPARATION
PLUMBING FIXTURES:	MINIMUM PLUMBING FIXTURES MUST BE PROVIDED IN ACCORDANCE WITH TABLE 2902.1. THE DESIGN OCCUPANT LOAD IS PERMITTED TO BE DETERMINED BASED UPON THE ACTUAL ANTICIPATED OCCUPANT LOAD. THE TOTAL OCCUPANT LOAD SHALL BE DIVIDED IN HALF FOR A DISTRIBUTION OF 50 PERCENT OF EACH SEX. FIXTURE COUNTS PROVIDED ARE BASED UPON 50% MALE / 50% FEMALE FOR THE BUILDING. MAXIMUM ANTICIPATED OCCUPANT LOAD = (5) FULLTIME EMPLOYEES PER SHIFT WITH (3) SHIFTS PER DAY, (24) HOURS PER DAY, (7) DAYS A WEEK. REQUIRED PLUMBING FIXTURES FOR F-1 OCCUPANCY: WATER CLOSETS: 1 PER 100 OCCUPANTS LAVATORIES: 1 PER 100 OCCUPANTS DRINKING FOUNTAIN: 1 PER 400 OCCUPANTS SERVICE SINKS: 1 PER BUILDING

GENERAL TUNNEL REQUIREMENTS

TUNNELS	**TRAVEL DISTANCE LIMITS**	SOME TUNNELS MAY ONLY BE PARTIALLY CONSTRUCTED WHICH WILL RESULT IN COMMON PATH OF TRAVEL ISSUES. WHERE A PARTIALLY CONSTRUCTED TUNNEL HAS A COMMON PATH OF TRAVEL OF MORE THAN 100' A VARIANCE* WILL BE REQUIRED OR THE SPACE MUST BE DESIGNATED A CONFINED SPACE WITH RESTRICTED ACCESS. IF A VARIANCE IS NECESSARY, A LADDER AND HATCH MAY BE REQUIRED DEPENDING ON HOW LONG THE TUNNEL IS.
	PARTIALLY CONSTRUCTED TUNNELS	**1. TUNNELS - EXITS:** TRAVEL DISTANCE WITHIN TUNNELS FROM THE MOST REMOTE POINT TO AN EXIT IS LIMITED TO A MAXIMUM OF: A. **PEDESTRIAN TUNNELS: 250'**. THIS COULD TECHNICALLY ALLOW UP TO A **500'** LONG TUNNEL WITHOUT AN INTERMEDIATE EXIT STAIR. (1) WHERE AN **ESFR SPRINKLER SYSTEM** IS INSTALLED IN THE TUNNEL THE TRAVEL DISTANCE MAXIMUM IS INCREASED TO **400'** FROM THE MOST REMOTE POINT TO AN EXIT. THIS COULD TECHNICALLY ALLOW UP TO AN **800'** LONG TUNNEL WITHOUT AN INTERMEDIATE EXIT STAIR. [ESFR: 1016.2.2, IBC] (2) WHERE A **HORIZONTAL EXIT** IS INSTALLED (AND NO SPRINKLERS) THE MAXIMUM PERMITTED "**EXIT STAIR DOOR TO HORIZONTAL EXIT DOOR**" TRAVEL DISTANCE IS INCREASED TO **500'** FROM THE MOST REMOTE POINT. THIS COULD TECHNICALLY ALLOW UP TO A **1,000'** LONG TUNNEL WITHOUT AN INTERMEDIATE EXIT STAIR. (3) WITH A **HORIZONTAL EXIT AND ESFR SPRINKLER SYSTEM** THE MAXIMUM "**EXIT STAIR TO HORIZONTAL EXIT DOOR**" DISTANCE IS INCREASED TO **800'**. THIS COULD TECHNICALLY ALLOW UP TO A **1,600'** LONG TUNNEL WITHOUT AN INTERMEDIATE EXIT STAIR. B. **MATERIAL MOVEMENT TUNNELS: 200'**. THIS COULD TECHNICALLY ALLOW UP TO A **400'** LONG TUNNEL WITHOUT AN INTERMEDIATE EXIT STAIR. (1) WHERE AN **ESFR SPRINKLER SYSTEM** IS INSTALLED IN THE TUNNEL THE TRAVEL DISTANCE MAXIMUM IS INCREASED TO **400'** FROM THE MOST REMOTE POINT TO AN EXIT. THIS COULD TECHNICALLY ALLOW UP TO AN **800'** LONG TUNNEL WITHOUT AN INTERMEDIATE EXIT STAIR. [ESFR: 1016.2.2, IBC] (2) WHERE A **HORIZONTAL EXIT** IS INSTALLED (AND NO SPRINKLERS) THE MAXIMUM PERMITTED "**EXIT STAIR DOOR TO HORIZONTAL EXIT DOOR**" TRAVEL DISTANCE IS INCREASED TO **400'** FROM THE MOST REMOTE POINT. THIS COULD TECHNICALLY ALLOW UP TO A **800'** LONG TUNNEL WITHOUT AN INTERMEDIATE EXIT STAIR. (3) WITH A **HORIZONTAL EXIT AND ESFR SPRINKLER SYSTEM** THE MAXIMUM "**EXIT STAIR TO HORIZONTAL EXIT DOOR**" DISTANCE IS INCREASED TO **800'**. THIS COULD TECHNICALLY ALLOW UP TO A **1,600'** LONG TUNNEL WITHOUT AN INTERMEDIATE EXIT STAIR. C. **UTILITY TUNNEL:** IF THIS SPACE WILL BE TREATED AS A CONFINED SPACE UNDER IOSHA RULES IT WILL NOT BE REGULATED BY NFPA 101 OR IBC. IF THE SPACE IS NOT CLASSIFIED A CONFINED SPACE THE RULES APPLICABLE TO THE MATERIALS MOVEMENT TUNNELS WILL APPLY.
	UNDERGROUND BUILDING CLASSIFICATION	**TUNNELS MORE THAN 30' DEEP - UNDERGROUND BUILDING RULES:** A. FLOORS OF PEDESTRIAN & MATERIALS MOVEMENT TUNNELS 30' OR MORE BELOW THE FINISHED FLOOR OF THE LOWEST LEVEL OF EXIT DISCHARGE ARE CLASSIFIED AN **UNDERGROUND BUILDING** AND REQUIRE THE FOLLOWING: (1) SMOKE CONTROL SYSTEM AND ASSOCIATED SMOKE DETECTION (2) SPRINKLER SYSTEM (3) SMOKE-PROOF EXIT STAIRS (4) STANDPIPES (5) FIRE ALARM SYSTEMS (6) STANDBY POWER (7) EMERGENCY POWER B. **PIPE/MECHANICAL TUNNELS NOT INTENDED FOR OCCUPANCY** ARE EXEMPT FROM THESE UNDERGROUND BUILDING REQUIREMENTS.

* A VARIANCE IS A VARIANCE FROM THE INDIANA BUILDING CODE APPROVED FROM THE FIRE PREVENTION AND BUILDING SAFETY COMMISSION. EQUIVALENCIES/WAIVERS FROM THE JOINT COMMISSION OR CMS ARE NOT POSSIBLE FOR NEW CONSTRUCTION.



FIRST FLOOR LIFE SAFETY PLAN
1/16" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:03:11 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 | Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

APPLICABLE CODES AND LIFE SAFETY PLAN

SHEET NUMBER

A002



SECOND FLOOR LIFE SAFETY PLAN
1/16" = 1'-0"

GENERAL LIFE SAFETY PLAN NOTES:


1. FOR COLUMN TO COLUMN DIMENSIONS AND TYPICAL INTERIOR PARTITION CONSTRUCTION, REFER TO STRUCTURAL DRAWINGS.

LIFE SAFETY PLAN LEGEND

- EXIT — INDICATES ROOM, SUITE, OR BUILDING EXIT
- INDICATES PATH OF EGRESS TRAVEL
- INDICATES MAXIMUM OVERALL DIAGONAL DISTANCE
- INDICATES DISTANCE BETWEEN EXITS
- 1H1H — INDICATES 1-HOUR RATED WALL CONSTRUCTION
- 2H2H — INDICATES 2-HOUR RATED WALL CONSTRUCTION
- F.E.C. — INDICATES RECESSED FIRE EXTINGUISHER CABINET LOCATION
- F.E. — INDICATES BRACKET-MOUNTED FIRE EXTINGUISHER LOCATION
- INDICATES EXTENTS OF MEZZANINE ABOVE

OCCUPANCY TYPE LEGEND

- GROUP B
- GROUP F-1
- GROUP H-3



MECHANICAL PENTHOUSE LIFT SAFETY PLAN
1/16" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:03:56 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 320 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **Mike Davis**
CHECKED BY **Mike Davis**
APPROVED BY **Mike Davis**
PROJECT NO.


CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE


LIFE SAFETY PLANS

SHEET NUMBER


A003



LOWER LEVEL ARCHITECTURAL FLOOR PLAN
3/32" = 1'-0"



LOWER LEVEL ARCHITECTURAL FLOOR PLAN - ELEVATOR PIT
3/32" = 1'-0"



FIRST FLOOR ARCHITECTURAL FLOOR PLAN
3/32" = 1'-0"

ORIGINAL SHEET SIZE (8.30" X 42" (ARCH E1)
2/9/2023 3:36:16 PM AESI Proj. No:

0 1/2" 1" 2"

LEVEL 1 PROPOSED VS PROGRAM AREAS TABLE

ROOM NAME	ROOM NUMBER	ACTUAL AREA	PROGRAM AREA
VEST.	101	194 SF	N/A
ENTRY	102	299 SF	N/A
FUEL OIL PUMP ROOM	103	570 SF	772
SERVICE YARD	104	4918 SF	
RECEIVING	105	5135 SF	974
STAIR #1	106	342 SF	N/A
FIRE PUMP ROOM	108	646 SF	442
BOILER ROOM	109	10241 SF	
STAIR #2	110	367 SF	N/A
TOILET ROOM	111	67 SF	N/A
CONTROL	112	173 SF	N/A
CHILLER PLANT ELECTRICAL ROOM	113	6798 SF	3274
CHILLER PLANT	114	12275 SF	12956
JANITOR	115	36 SF	N/A
ELEVATOR	116	100 SF	
Grand total: 15		42160 SF	

LOWER LEVEL ACTUAL VS PROGRAM AREAS TABLE

ROOM NAME	ROOM NUMBER	ACTUAL AREA	PROGRAM AREA
STAIR #1	001	579 SF	N/A
UTILITY TUNNEL	002	580 SF	N/A
Grand total: 2		1159 SF	

GENERAL FLOOR PLAN NOTES

1. DIMENSIONS OF INTERIOR WALLS ARE TO THE FACE OF CMU OR GYPSUM BOARD & DO NOT INCLUDE FINISHES OR PROTECTIVE COVERINGS UNLESS NOTED OTHERWISE.
2. LOCATE OUTSIDE EDGE OF NEW HM DOOR FRAMES A MINIMUM OF 4" FROM NEAREST CORNER, INTERSECTING PARTITION, COLUMN ENCLOSURE, ETC., OR CENTER IN ROOM AS INDICATED, TYPICAL, UNLESS NOTED OTHERWISE.
3. PROVIDE FIRE TREATED WOOD BLOCKING OR STEEL FLAT STRAP AND BACKING PLATE AT, BUT NOT LIMITED TO, THE FOLLOWING LOCATIONS: TOILET ACCESSORIES, CASEWORK, MILLWORK, DOOR STOPS, AND ALL OTHER WALL-MOUNTED EQUIPMENT OR DEVICES.
4. REFER TO **A703** FOR ROOM FINISH SCHEDULE.

ARCHITECTURAL PLAN REFERENCE NOTES

#	KEYNOTE INFORMATION
1	FUEL TANK BELOW GRADE
2	MEZZANINE OR WALKWAY ABOVE
3	FUTURE SOLID SURFACE COUNTERTOP, SINK AND PLASTIC LAMINATE CASEWORK, BY OWNER.
4	ROOF STRUCTURES, REFER TO SCTRUAL AND MECHANICAL PLAN

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	


SHEET TITLE

FIRST FLOOR ARCHITECTURAL PLAN

SHEET NUMBER

A101






DIMENSION PLAN REFERENCE NOTES	
#	KEYNOTE INFORMATION

GENERAL DIMENSION NOTES

1. FIELD VERIFY ALL EXISTING CONDITIONS. NOTIFY ARCHITECT/ENGINEER IMMEDIATELY OF ANY DISCREPANCIES THAT EXIST.
2. ALL DIMENSIONS ON FLOOR PLANS ARE FROM FACE OF FINISH GYPSUM BOARD, FACE OF MASONRY, FACE OF CONCRETE, OR CENTERLINE OF COLUMNS UNLESS NOTED OTHERWISE.
3. ALL DOORS ARE TO BE 8" FROM FACE OF WALL UNLESS NOTED OTHERWISE

FIRST FLOOR MEZZANINE
3/32" = 1'-0"

FIRST FLOOR MEZZANINE
3/32" = 1'-0"



FIRST FLOOR DIMENSION PLAN
3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:36:20 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS
NO. DATE DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

FIRST FLOOR DIMENSION PLAN


SHEET NUMBER

A101 D



SECOND FLOOR MEZZANINE - 207 & 208

3/32" = 1'-0"



SECOND FLOOR MEZZANINE - 213 & 214

3/32" = 1'-0"

ARCHITECTURAL PLAN REFERENCE NOTES


#	KEYNOTE INFORMATION
1	FUEL TANK BELOW GRADE
2	MEZZANINE OR WALKWAY ABOVE
3	FUTURE SOLID SURFACE COUNTERTOP. SINK AND PLASTIC LAMINATE CASEWORK, BY OWNER.
4	ROOF STRUCTURES, REFER TO SCTRUAL AND MECHANICAL PLAN

GENERAL FLOOR PLAN NOTES

1. DIMENSIONS OF INTERIOR WALLS ARE TO THE FACE OF CMU OR GYPSUM BOARD & DO NOT INCLUDE FINISHES OR PROTECTIVE COVERINGS UNLESS NOTED OTHERWISE.
2. LOCATE OUTSIDE EDGE OF NEW HM DOOR FRAMES A MINIMUM OF 4" FROM NEAREST CORNER, INTERSECTING PARTITION, COLUMN ENCLOSURE, ETC., OR CENTER IN ROOM AS INDICATED, TYPICAL, UNLESS NOTED OTHERWISE.
3. PROVIDE FIRE TREATED WOOD BLOCKING OR STEEL FLAT STRAP AND BACKING PLATE AT, BUT NOT LIMITED TO, THE FOLLOWING LOCATIONS: TOILET ACCESSORIES, CASEWORK, MILLWORK, DOOR STOPS, AND ALL OTHER WALL-MOUNTED EQUIPMENT OR DEVICES.
4. REFER TO **A703** FOR ROOM FINISH SCHEDULE.

LEVEL 2 ACTUAL VS PROGRAM AREAS

ROOM NAME	ROOM NUMBER	ACTUAL AREA	PROGRAM AREA
CORRIDOR	201	1905 SF	WRS01
OFFICE	203	225 SF	WRS01
OFFICE	204	162 SF	273 WRS01
LOCKER / BREAK RM	205	621 SF	839 WRS01
TOILET / SHOWER	205A	67 SF	
TOILET / CHANGING	205B	53 SF	
MECHANICAL	206	883 SF	
MAINTENANCE WORKROOM	207	557 SF	
GENERATOR CONTROL	208	435 SF	
CONTROL ROOM	209	738 SF	747
GENERATOR SWITCHGEAR	210	2540 SF	1331
BATTERY ROOM	211	797 SF	
15KV SWITCHGEAR	212	4535 SF	3931
FUEL OIL DAY TANKS B	213	531 SF	350
MAINTENANCE STORAGE	214	455 SF	
CUP EMERGENCY ELECTRICAL ROOM	215	1390 SF	678
MSS SERVICE SWITCHGEAR	216	1982 SF	2398
STAIR #2	217	383 SF	
GENERATOR ROOM B	218	4550 SF	5045
GENERATOR EXHAUST PLENUM 2	219	1103 SF	
GENERATOR ROOM A	220	4049 SF	4757
GENERATOR EXHAUST PLENUM 1	221	1109 SF	1875
FUEL OIL DAY TANKS A	222	439 SF	412
JANITOR / STORAGE	223	74 SF	
MECHANICAL	224	1008 SF	
MDF DATA	225	282 SF	220
OFFICE	226	194 SF	WRS01
CORRIDOR	227	3628 SF	
CORRIDOR	228	810 SF	WRS01
MSS BATTERY ROOM	229	450 SF	
Grand total: 30		35952 SF	



SECOND FLOOR ARCHITECTURAL FLOOR PLAN

3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:39:38 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

SECOND FLOOR ARCHITECTURAL PLAN


SHEET NUMBER

A102

DIMENSION PLAN REFERENCE NOTES	
#	KEYNOTE INFORMATION

GENERAL DIMENSION NOTES

1. FIELD VERIFY ALL EXISTING CONDITIONS. NOTIFY ARCHITECT/ENGINEER IMMEDIATELY OF ANY DISCREPANCIES THAT EXIST.
2. ALL DIMENSIONS ON FLOOR PLANS ARE FROM FACE OF FINISH GYPSUM BOARD, FACE OF MASONRY, FACE OF CONCRETE, OR CENTERLINE OF COLUMNS UNLESS NOTED OTHERWISE.
3. ALL DOORS ARE TO BE 8" FROM FACE OF WALL UNLESS NOTED OTHERWISE



SECOND FLOOR DIMENSION PLAN
3/32" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:36:44 PM AESI Proj No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

SECOND FLOOR DIMENSION PLAN


SHEET NUMBER

A102 D

ARCHITECTURAL PLAN REFERENCE NOTES	
#	KEYNOTE INFORMATION
1	FUEL TANK BELOW GRADE
2	MEZZANINE OR WALKWAY ABOVE
3	FUTURE SOLID SURFACE COUNTERTOP. SINK AND PLASTIC LAMINATE CASEWORK, BY OWNER.
4	ROOF STRUCTURES, REFER TO SCTRUAL AND MECHANICAL PLAN

GENERAL FLOOR PLAN NOTES

1. DIMENSIONS OF INTERIOR WALLS ARE TO THE FACE OF CMU OR GYPSUM BOARD & DO NOT INCLUDE FINISHES OR PROTECTIVE COVERINGS UNLESS NOTED OTHERWISE.
2. PROVIDE FIRE TREATED WOOD BLOCKING OR STEEL FLAT STRAP AND BACKING PLATE AT, BUT NOT LIMITED TO, THE FOLLOWING LOCATIONS: TOILET ACCESSORIES, CASEWORK, MILLWORK, DOOR STOPS, AND ALL OTHER WALL-MOUNTED EQUIPMENT OR DEVICES.



PENTHOUSE FLOOR PLAN
3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:38:49 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
87701 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023


REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **Designer**
CHECKED BY **Checker**
APPROVED BY **Approver**
PROJECT NO.


CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
PENTHOUSE ARCHITECTURAL PLAN


SHEET NUMBER
A103




2 A104 **EAST AIR MONITOR ELEVATION**
3/32" = 1'-0"




3 A104 **SOUTH AIR MONITOR ELEVATION**
3/32" = 1'-0"



4 A104 **WEST AIR MONITOR ELEVATION**
3/32" = 1'-0"



5 A104 **NORTH AIR MONITOR ELEVATION**
3/32" = 1'-0"



ROOF PLAN
3/32" = 1'-0"

ROOF PLAN REFERENCE NOTES	
#	KEYNOTE INFORMATION
1	THERMOPLASTIC POLYOLEFIN (TPO) MEMBRANE ROOFING (ADHERED) ON 6" MINIMUM POLYISO INSULATION ON 1/2" DENS-DECK (MECHANICALLY FASTENED) ON METAL ROOF DECK AND STRUCTURAL STEEL FRAMING. PROVIDE 1/4" PER FOOT MINIMUM POSITIVE SLOPE TO DRAIN. (U.N.O.)
2	METAL ROOFING
3	STEEL PLATFORM FOR COOLING TOWERS. REFER TO MECHANICAL AND STRUCTURAL DRAWINGS
4	SCUPPERS

ROOF PLAN LEGEND

- V.P. — INDICATES VENT PIPE
- INDICATES DIRECTION OF ROOF STRUCTURE SLOPE
- INDICATES DIRECTION OF ROOF SLOPE @ 1/4" PER FOOT MINIMUM
- INDICATES MECHANICAL SCREEN
- O.D. — OVERHEAD DRAIN
- R.D. — ROOF DRAIN

GENERAL ROOF PLAN NOTES

1. NOT ALL ROOF PENETRATIONS OR OTHER DETAILS REQUIRED ELSEWHERE IN THE DOCUMENTS TO COMPLETE THE ROOF WORK ARE CALLED OUT ON THE ROOF PLAN. PROVIDE TYPICAL ROOFING DETAILS AS INDICATED ELSEWHERE IN THE DOCUMENTS OR AS RECOMMENDED BY ROOFING MANUFACTURER AT ALL SUCH CONDITIONS WHETHER SHOWN OR NOT, INCLUDING WITHOUT LIMITATION THE FOLLOWING : CONDUIT PENETRATIONS, GUY WIRE TIE DOWN POINTS, PROTECTED WOOD SLEEPERS, CONDENSATE LINES,EXHAUST DUCTS, STEEL DUNNAGE, LIGHTNING PROTECTION ATTACHMENTS, ETC.
2. COORDINATE PROTECTIVE ROOF WALKWAY WITH ROOF TOP EQUIPMENT SUBMITTALS. PROVIDE WALKWAY TO ALL LOCATIONS REQUIRING REGULAR MAINTENANCE.
3. ALL ROOF PENETRATIONS SHALL BE FLASHED PER ROOFING MANUFACTURER'S SPECIFICATIONS FOR A COMPLETE WATERTIGHT INSTALLATION.
4. PROVIDE TAPERED INSULATION CRICKETS AT ALL .EXHAUST FANS, ROOF TOP UNITS, ROOF CURBS, ETC. TO ASSURE PROPER DRAINAGE.
5. ALL SADDLES AND CRICKETS SHALL HAVE A MINIMUM SLOPE OF 1/4" PER FOOT.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	


SHEET TITLE

ROOF PLAN


SHEET NUMBER

A104


ORIGINAL SHEET SIZE | IS 30" X 42" (ARCH E1) AESI Proj. No:
2/9/2023 3:36:56 PM



3 A105 **ROOF PENETRATION DETAIL**
3" = 1'-0"



2 A105 **CURB DETAIL**
1 1/2" = 1'-0"



1 A105 **ROOF DRAIN DETAIL**
3" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:36:59 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
87720 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **Designer**
CHECKED BY **Checker**
APPROVED BY **Approver**
PROJECT NO.

CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

ROOF DETAILS

SHEET NUMBER

A105

EQUIPMENT/ FURNITURE - FIRST FLOOR (X)


EQUIPMENT NUMBER	EQUIPMENT/ FURNITURE DESCRIPTION	COUNT	VENDOR PROVIDED	VENDOR INSTALLED	OWNER PROVIDED	OWNER INSTALLED	CONTRACTOR PROVIDED	CONTRACTOR INSTALLED
1	MOBILE SHELVING UNIT	1			Yes	Yes	No	No
2	TASK CHAIR	4	Yes	Yes	No	No		
3	COMPUTER	5			Yes	Yes		
4	DESK	1	Yes	Yes	No	No		
5	STORAGE CABINET	1	Yes	Yes	No	No		
6	TELEVISION AND WALL MOUNT	1			Yes	No	No	Yes

GENERAL EQUIPMENT PLAN NOTES


1. REFER TO MECHANICAL, PLUMBING AND ELECTRICAL DRAWING FOR EQUIPMENT DETAILS
2. EQUIPMENT/ FURNITURE TOTAL COUNTS ARE PER SHEET.

ENLARGED PLAN REFERENCE NOTES - FIRST FLOOR (X)


#	KEYNOTE INFORMATION
1	SOLID SURFACE COUNTERTOP WITH 4" BACKSPLASH AND RETURNS
2	PLASTIC LAMINATE SHELF
3	RADIO CHARGING STATION




4 A106 **ENLARGED PLAN @ FUEL OIL PUMP ROOM 103**
1/4" = 1'-0"



3 A106 **ENLARGED PLAN @ RECEIVING**
1/4" = 1'-0"



2 A106 **ENLARGED PLAN @ CONTROL 112**
1/4" = 1'-0"



FIRST FLOOR EQUIPMENT AND FURNITURE PLAN
3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:37:21 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
87720 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

FIRST FLOOR EQUIPMENT AND FURNITURE PLAN

SHEET NUMBER

A106

EQUIPMENT/ FURNITURE - SECOND FLOOR (X)


EQUIPMENT NUMBER	EQUIPMENT/ FURNITURE DESCRIPTION	COUNT	VENDOR PROVIDED	VENDOR INSTALLED	OWNER PROVIDED	OWNER INSTALLED	CONTRACTOR PROVIDED	CONTRACTOR INSTALLED
1	TRACK STORAGE SYSTEM	1	No		Yes	Yes	No	No
2	WALL MOUNTED PHONE	1			Yes	Yes		No
3	TASK CHAIR	5	Yes	Yes				
4	COMPUTER MONITOR	7			Yes	Yes		
5	SOFA	3	Yes	Yes				
6	DINING TABLE	2	Yes	Yes				
7	CHANGING CHAIR	1	Yes	Yes				
8	DESK	3	Yes	Yes				
9	GUEST CHAIR	6	Yes	Yes				
10	WORK TABLE	1	Yes	Yes				
11	COFFEE TABLE	1	Yes	Yes				
12	WORK STOOL	2	Yes	Yes				
13	DINING CHAIRS	8	Yes	Yes				
14	COFFEE MAKER	1			Yes	Yes		
15	MICROWAVE	1			Yes	Yes		
16	REFRIGERATOR	1			Yes	Yes		
17	WALL MOUNTED TELEVISION	2			Yes	Yes	No	No
18	TELEVISION WALL MOUNT	1			Yes	Yes	No	No
19	LOCKER	10					Yes	Yes
20	ICE MAKER	1			Yes	Yes		No
21	SHOWER SHELF	1					Yes	Yes

GENERAL EQUIPMENT PLAN NOTES


1. REFER TO MECHANICAL, PLUMBING AND ELECTRICAL DRAWING FOR EQUIPMENT DETAILS
2. EQUIPMENT/ FURNITURE TOTAL COUNTS ARE PER SHEET.

ENLARGED PLAN REFERENCE NOTES - SECOND FLOOR (X)


#	INFORMATION
1	SOLID SURFACE COUNTERTOP AND 4" BACKSPLASH
2	PLASTIC LAMINATE CASEWORK, SEE INTERIOR ELEVATIONS
3	PLUMBING FIXTURE, SEE PLUMBING DRAWINGS
5	PLASTIC LAMINATE SHELVES ON STANDARDS
6	INSTALL PLUMBING STUBS FOR FUTURE SINK. SEE PLUMBING DRAWINGS




6 A107 **ENLARGED PLAN @ MAINTENANCE WORKROOM 207**
1/4" = 1'-0"




5 A107 **ENLARGED PLAN @ BREAK ROOM**
1/4" = 1'-0"




4 A107 **ENLARGED PLAN @ CONTROL 209**
1/4" = 1'-0"




3 A107 **ENLARGED PLAN @ OFFICE 226**
1/4" = 1'-0"



2 A107 **ENLARGED PLAN @ OFFICE 204**
1/4" = 1'-0"



1 A107 **ENLARGED PLAN @ OFFICE 203**
1/4" = 1'-0"



SECOND FLOOR EQUIPMENT AND FURNITURE PLAN
3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1) AESI Proj. No:
2/9/2023 3:37:59 PM

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **Designer**
CHECKED BY **Checker**
APPROVED BY **Approver**
PROJECT NO.

CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
SECOND FLOOR EQUIPMENT AND FURNITURE PLAN

SHEET NUMBER
A107

REFLECTED CEILING PLAN REFERENCE NOTES	
#	KEYNOTE INFORMATION
1	EXPOSED STRUCTURE ABOVE
2	MEZZANINE
3	CONCRETE CAP
4	HATCH TO MEZZANINE ABOVE


REFLECTED CEILING PLAN LEGEND

REFER TO MECHANICAL, ELECTRICAL AND/OR PLUMBING DRAWINGS FOR SPECIFICATIONS OF ITEMS

- INDICATES AREA OF 5/8" GYPSUM BOARD CEILING/SOFFIT/BULKHEAD ON 3 5/8" METAL STUDS @ 16" O.C. (U.N.O.) PAINT
- INDICATES 2' X 2' LAY-IN CEILING TILE WITH METAL GRID
- 2' x 4' RECESSED LIGHT FIXTURE
- 2' x 2' RECESSED LIGHT FIXTURE
- 1' x 4' RECESSED LIGHT FIXTURE
- STRIP FIXTURE WITH WIRE GUARD
- RECESSED CAN TYPE LIGHT FIXTURE
- 2' X 2' SUPPLY AIR
- 2' X 2' RETURN AIR
- EXHAUST FAN
- E.S. EXPOSED STRUCTURE

GENERAL REFLECTED CEILING PLAN NOTES

1. CEILING ELEVATION TAGS REFER TO HEIGHT ABOVE FINISHED FLOOR IN AREAS TO REMAIN
2. CENTER PENETRATIONS IN ACOUSTICAL CEILING SYSTEMS WITHIN INDIVIDUAL CEILING PANELS, SUCH AS SPRINKLER HEADS, DIFFUSERS, LIGHT FIXTURES, ETC., UNLESS NOTED OTHERWISE.
3. PAINT EXPOSED HARD CEILING SURFACES U.N.O.
4. THE REFLECTED CEILING PLANS SHOW THE DESIGN INTENT OF MECHANICAL & ELECTRICAL BUILDING SYSTEMS TO BE INTEGRATED INTO CEILINGS. REFLECTED CEILING PLANS SHALL TAKE PRECEDENCE OVER MECHANICAL & ELECTRICAL DRAWINGS. REFER DISCREPANCIES TO THE ARCHITECT FOR DIRECTION.
5. ALL CUT EDGE OF CEILING PANELS SHALL BE PAINTED TO MATCH PANEL FACE.
6. REFER TO FINISH SCHEDULE FOR CEILING TYPES.
7. ALL BULKHEADS CONSTRUCTION SHALL BE 3 5/8" 22 GA. STUDS @ 16"O.C. WITH 5/8" GYP. BD. U.N.O.



FIRST FLOOR REFLECTED CEILING PLAN
3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1) 0 1/2" 1" 2"
2/9/2023 3:38:05 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
87720 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

FIRST FLOOR REFLECTED CEILING PLAN

SHEET NUMBER

A201

REFLECTED CEILING PLAN REFERENCE NOTES	
#	KEYNOTE INFORMATION
1	EXPOSED STRUCTURE ABOVE
2	MEZZANINE
3	CONCRETE CAP
4	HATCH TO MEZZANINE ABOVE


REFLECTED CEILING PLAN LEGEND

REFER TO MECHANICAL, ELECTRICAL AND/OR PLUMBING DRAWINGS FOR SPECIFICATIONS OF ITEMS

- INDICATES AREA OF 5/8" GYPSUM BOARD CEILING/SOFFIT/BULKHEAD ON 3 5/8" METAL STUDS @ 16" O.C. (U.N.O.) PAINT
- INDICATES 2' X 2' LAY-IN CEILING TILE WITH METAL GRID
- 2' x 4' RECESSED LIGHT FIXTURE
- 2' x 2' RECESSED LIGHT FIXTURE
- 1' x 4' RECESSED LIGHT FIXTURE
- STRIP FIXTURE WITH WIRE GUARD
- RECESSED CAN TYPE LIGHT FIXTURE
- 2' X 2' SUPPLY AIR
- 2' X 2' RETURN AIR
- EXHAUST FAN
- E.S. EXPOSED STRUCTURE

GENERAL REFLECTED CEILING PLAN NOTES

1. CEILING ELEVATION TAGS REFER TO HEIGHT ABOVE FINISHED FLOOR IN AREAS TO REMAIN
2. CENTER PENETRATIONS IN ACOUSTICAL CEILING SYSTEMS WITHIN INDIVIDUAL CEILING PANELS, SUCH AS SPRINKLER HEADS, DIFFUSERS, LIGHT FIXTURES, ETC., UNLESS NOTED OTHERWISE.
3. PAINT EXPOSED HARD CEILING SURFACES U.N.O.
4. THE REFLECTED CEILING PLANS SHOW THE DESIGN INTENT OF MECHANICAL & ELECTRICAL BUILDING SYSTEMS TO BE INTEGRATED INTO CEILINGS. REFLECTED CEILING PLANS SHALL TAKE PRECEDENCE OVER MECHANICAL & ELECTRICAL DRAWINGS. REFER DISCREPANCIES TO THE ARCHITECT FOR DIRECTION.
5. ALL CUT EDGE OF CEILING PANELS SHALL BE PAINTED TO MATCH PANEL FACE.
6. REFER TO FINISH SCHEDULE FOR CEILING TYPES.
7. ALL BULKHEADS CONSTRUCTION SHALL BE 3 5/8" 22 GA. STUDS @ 16"O.C. WITH 5/8" GYP. BD. U.N.O.



SECOND FLOOR REFLECTED CEILING PLAN
3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:38:09 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


SECOND FLOOR REFLECTED CEILING PLAN

SHEET NUMBER

A202



3 A301 **WEST BUILDING ELEVATION**
3/32" = 1'-0"



1 A301 **EAST BUILDING ELEVATION**
3/32" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:38:19 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


EXTERIOR ELEVATIONS

SHEET NUMBER


A301




5 A302 **WEST SERVICE YARD ELEVATION**
3/32" = 1'-0"




4 A302 **EAST SERVICE YARD ELEVATON**
3/32" = 1'-0"



1 A302 **NORTH SERVICE YARD ELEVATION**
3/32" = 1'-0"



2 A302 **NORTH BUILDING ELEVATION**
3/32" = 1'-0"



3 A302 **SOUTH BUILDING ELEVATION**
3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:38:27 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	


SHEET TITLE

EXTERIOR ELEVATIONS


SHEET NUMBER

A302


BUILDING SECTION REFERENCE NOTES	
#	KEYNOTE INFORMATION



2 A401 **BUILDING SECTION**
3/32" = 1'-0"



3 A401 **BUILDING SECTION**
1" = 10'-0"



1 A401 **BUILDING SECTION**
3/32" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:38:47 PM AESI Proj No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	


SHEET TITLE

BUILDING SECTIONS


SHEET NUMBER

A401

BUILDING SECTION REFERENCE NOTES	
#	KEYNOTE INFORMATION



2 A402 **BLDG SECTION**
1" = 10'-0"



1 A402 **BLDG SECTION**
1" = 10'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1) AESI Proj. No:
2/9/2023 3:39:15 PM

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	


SHEET TITLE

BUILDING SECTIONS


SHEET NUMBER

A402


BUILDING SECTION REFERENCE NOTES	
#	KEYNOTE INFORMATION



3 A403 **BLDG SECTION**
1" = 10'-0"



2 A403 **BLDG SECTION**
3/32" = 1'-0"



1 A403 **BLDG SECTION**
1" = 10'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:39:33 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


BUILDING SECTION

SHEET NUMBER


A403




5 A404 **WALL SECTION** 1/4" = 1'-0"




4 A404 **WALL SECTION** 1/4" = 1'-0"



3 A404 **WALL SECTION** 1/4" = 1'-0"



2 A404 **WALL SECTION** 1/4" = 1'-0"



1 A404 **WALL SECTION** 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:39:39 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: **Designer**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: **Checker**	
APPROVED BY: **Approver**	
PROJECT NO.	

SHEET TITLE


WALL SECTIONS

SHEET NUMBER


A404




5 A405 **WALL SECTION** 1/4" = 1'-0"




4 A405 **WALL SECTION** 1/4" = 1'-0"



3 A405 **WALL SECTION** 1/4" = 1'-0"



2 A405 **WALL SECTION** 1/4" = 1'-0"



1 A405 **WALL SECTION** 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1) 2/9/2023 3:39:44 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY **Designer**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY **Checker**	
APPROVED BY **Approver**	
PROJECT NO.	

SHEET TITLE


WALL SECTIONS

SHEET NUMBER


A405




5 A406 **WALL SECTION**
1/4" = 1'-0"




4 A406 **WALL SECTION**
1/4" = 1'-0"



3 A406 **WALL SECTION**
1/4" = 1'-0"



2 A406 **WALL SECTION**
1/4" = 1'-0"



1 A406 **WALL SECTION**
1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:39:55 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: **Designer**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: **Checker**	
APPROVED BY: **Approver**	
PROJECT NO.	

SHEET TITLE


WALL SECTIONS

SHEET NUMBER


A406




13 A407 **DETAIL** 1 1/2" = 1'-0"




8 A407 **DETAIL** 1 1/2" = 1'-0"




4 A407 **DETAIL** 1 1/2" = 1'-0"




12 A407 **DETAIL** 1 1/2" = 1'-0"



7 A407 **DETAIL** 1 1/2" = 1'-0"




3 A407 **DETAIL** 3" = 1'-0"




11 A407 **DETAIL** 1 1/2" = 1'-0"

6 A407 **DETAIL** 1 1/2" = 1'-0"

2 A407 **DETAIL** 3" = 1'-0"




10 A407 **DETAIL** 1 1/2" = 1'-0"



5 A407 **DETAIL** 1 1/2" = 1'-0"

9 A407 **DETAIL** 1 1/2" = 1'-0"



1 A407 **DETAIL** 1 1/2" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:40:01 PM AESI Proj. No:
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
87701 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


EXTERIOR ASSEMBLY DETAILS

SHEET NUMBER


A407




10 A501 **NORTH ELEVATOR ELEVATION** 1/2" = 1'-0"




9 A501 **WEST ELEVATOR ELEVATION** 1/2" = 1'-0"




8 A501 **SOUTH ELEVATOR ELEVATION** 1/2" = 1'-0"




7 A501 **EAST ELEVATOR ELEVATION** 1/2" = 1'-0"



1 A501 **SECTION B @ STAIR #1** 3/16" = 1'-0"




2 A501 **SECTION A @ STAIR #1** 3/16" = 1'-0"




6 A501 **BUILDING SECTION** 3/16" = 1'-0"

ENLARGED PLAN REFERENCE NOTES - FIRST FLOOR


#	KEYNOTE INFORMATION
1	SOLID SURFACE COUNTERTOP WITH 4" BACKSPLASH AND RETURNS
2	PLASTIC LAMINATE SHELF
3	RADIO CHARGING STATION



3 A501 **ENLARGED PLAN @ THIRD FLOOR** 1/4" = 1'-0"



4 A501 **ENLARGED PLAN @ SECOND FLOOR** 1/4" = 1'-0"



5 A501 **ENLARGED PLAN @ FIRST FLOOR** 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:40:12 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
87720 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


STAIR AND ELEVATOR ENLARGED PLAN & DETAILS

SHEET NUMBER


A501




1 BLDG SECTION
A502 1/4" = 1'-0"




5 ENLARGED ELEVATOR PLAN - ROOF
A502 1/4" = 1'-0"




6 ENLARGED ELEVATOR PLAN - SECOND FLOOR
A502 1/4" = 1'-0"




7 ENLARGED ELEVATOR PLAN - FIRST FLOOR
A502 1/4" = 1'-0"




8 ENLARGED STAIRWELL PLAN - SECOND FLOOR
A502 1/4" = 1'-0"



2 SECTION @ STAIR #2
A502 3/16" = 1'-0"



3 Section 8
A502 3/16" = 1'-0"



4 ENLARGED STAIRWELL PLAN - FIRST FLOOR
A502 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:40:22 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
87720 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


STAIR AND ELEVATOR ENLARGED PLAN

SHEET NUMBER


A502




17 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




12 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




16 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




11 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




15 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




10 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




14 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




9 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




13 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




8 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




7 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




6 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




5 A503 **PLAN DETAIL**
1 1/2" = 1'-0"




4 A503 **PLAN DETAIL**
1 1/2" = 1'-0"



3 A503 **PLAN DETAIL**
1 1/2" = 1'-0"



2 A503 **PLAN DETAIL**
1 1/2" = 1'-0"



1 A503 **PLAN DETAIL**
1 1/2" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:40:29 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **Designer**
CHECKED BY **Checker**
APPROVED BY **Approver**
PROJECT NO.


CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE


STAIR DETAILS

SHEET NUMBER


A503




21 A504 **SECTION AT BREAK SINK**
1" = 1'-0"



20 A504 **SECTION AT MICROWAVE SHELF**
1" = 1'-0"




19 A504 **SECTION AT COUNTERTOP**
1" = 1'-0"




18 A504 **SECTION AT ADJUSTABLE SHELVING**
1" = 1'-0"


X	INTERIOR ELEVATION NOTES
#	KEYNOTE INFORMATION
1	WALL BASE, SEE ROOM FINISH SCHEDULE.
2	25" DEEP PLASTIC LAMINATE COUNTERTOP WITH SIDE AND BACK SPLASH, AS INDICATED
3	25" DEEP SOLID SURFACE COUNTERTOP WITH SIDE AND BACK SPLASH, AS INDICATED
4	24" DEEP BASE CABINET; COUNFIGURE DOOR(S), DRAWERS(S), AND SHELVE(S) AS INDICATED
5	18" DEEP MICROWAVE SHELF.
6	16" DEEP PLASTIC LAMINATE SHELF ON ADJUSTABLE STANDARDS AND BRACKETS.
7	NEW EQUIPMENT/ FURNITURE. SEE EQUIPMENT/ FURNITURE SCHEDULE.
8	COUNTER SUPPORT BRACKET
9	WINDOW SHADE AND FASCIA. SEE INTERIOR SPECIFICATIONS.
10	WATER BOX. SEE PLUMBING DRAWINGS.
11	PLUMBING FIXTURE. SEE PLUMBING DRAWINGS.
12	CROSS-BRACING, SEE STRUCTURAL DRAWINGS.
13	COAT HOOK, SEE PRODUCT SPECIFICATIONS.
14	MIRROR. SEE PRODUCT SPECIFICATIONS.
15	SOAP DISPENSER. SEE PRODUCT SPECIFICATIONS.
16	PAPER TOWEL DISPENSER. SEE PRODUCT SPECIFICATIONS.
17	GRAB BAR. SEE PRODUCT SPECIFICATIONS.
18	TOILET TISSUE DISPENSER. SEE PRODUCT SPECIFICATIONS.
19	CURTAIN ROD, SEE PRODUCT SPECIFICATIONS.
20	SHOWER CURTAIN, SEE PRODUCT SPECIFICATIONS.
21	WALL MOUNTED PHONE. SEE EQUIPMENT/ FURNITURE SCHEDULE.
22	TELEVISION AND BRACKET. SEE EQUIPMENT/ FURNITURE SCHEDULE.
24	SHOWER SHELF. SEE PRODUCT SPECIFICATIONS.
25	FLOAT FLOOR UNDERLAYMENT SO FINISHED FLOOR MEETS TOP OF ENTRANCE TO SHOWER.
26	UTILITY SHELF. SEE PRODUCT SPECIFICATIONS.
27	SHOWER SEAT. SEE PRODUCT SPECIFICATIONS.
28	TOWEL BAR, SEE PRODUCT SPECIFICATIONS.
29	LOCKERS WITH SLOPED TOPS. SEE PRODUCT SPECIFICATIONS.
30	RADIO CHARGING STATION, OWNER PROVIDED AND INSTALLED.




7 A504 **WEST ELEVATION - LOCKER/ BREAK 205**
1/2" = 1'-0"




6 A504 **NORTH ELEVATION - LOCKER/ BREAK 205**
1/2" = 1'-0"




8 A504 **DETAIL OF BULKHEAD AND WINDOW SHADE**
1 1/2" = 1'-0"




5 A504 **SOUTH ELEVATION - LOCKER/ BREAK 205**
1/2" = 1'-0"




4 A504 **EAST ELEVATION - LOCKER/ BREAK 205**
1/2" = 1'-0"



3 A504 **EAST ELEVATION - OFFICE 203/ 226 SIM, OFFICE 204/ WORKROOM 207 OPP.**
1/2" = 1'-0"



2 A504 **EAST ELEVATION - CONTROL 112**
1/2" = 1'-0"



1 A504 **SOUTH ELEVATION - CONTROL 112**
1/2" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	CERTIFICATION
Designer	PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY	
Checker	
APPROVED BY	
Approver	
PROJECT NO.	

SHEET TITLE

INTERIOR ELEVATIONS

SHEET NUMBER

A504

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:40:39 PM AESI Proj. No:


0 1/2" 1" 2"

TOILET ACCESSORY SCHEDULE (X)


EQUIPMENT NUMBER	EQUIPMENT DESCRIPTION	MANUFACTURER	COUNT	VENDOR FURNISHED	VENDOR INSTALLED	CONTRACTOR FURNISHED	CONTRACTOR INSTALLED
1	GRAB BARS	Bradley Corporation	12			Yes	Yes
2	MIRROR	Bradley Corporation	3			Yes	Yes
3	COAT HOOK	Bradley Corporation	2			Yes	Yes
5	SHOWER CURTAIN	GRAINGER	1			Yes	Yes
6	SHOWER CURTAIN ROD	Bradley Corporation	1			Yes	Yes
7	SHOWER SEAT	Bradley Corporation	1			Yes	Yes
8	LIQUID SOAP DISPENSER	Bradley Corporation	4	Yes	Yes		No
9	TOILET TISSUE DISPENSER	Bradley Corporation	3	Yes	Yes	No	No
10	TOWEL BAR	Bradley Corporation	1			Yes	Yes
11	PAPER TOWEL DISPENSER	Bradley Corporation	4	Yes	Yes		No
12	UTILITY SHELF	Bradley Corporation	1			Yes	Yes

ENLARGED PLAN REFERENCE NOTES - SECOND FLOOR (X)


X	KEYNOTE INFORMATION
1	PLUMBING FIXTURE. SEE PLUMBING DRAWINGS.
2	PLASTIC LAMINATE SHELVES ON STANDARDS.




12 A505 **WEST ELEVATION - TOILET/ SHOWER 205A**
1/2" = 1'-0"




11 A505 **SOUTH ELEVATION - TOILET/ SHOWER 205A**
1/2" = 1'-0"




10 A505 **EAST ELEVATION - TOILET/ SHOWER 205A**
1/2" = 1'-0"




9 A505 **NORTH ELEVATION - TOILET ROOM 111**
1/2" = 1'-0"




8 A505 **WEST ELEVATION - TOILET ROOM 111**
1/2" = 1'-0"




7 A505 **SOUTH ELEVATION - TOILET ROOM 111**
1/2" = 1'-0"




6 A505 **EAST ELEVATION - TOILET ROOM 111**
1/2" = 1'-0"



5 A505 **WEST ELEVATION - JANITOR 115**
1/2" = 1'-0"




4 A505 **SOUTH ELEVATION - JANITOR 115**
1/2" = 1'-0"




3 A505 **EAST ELEVATION - JANITOR 115**
1/2" = 1'-0"

INTERIOR ELEVATION NOTES (X)

#	KEYNOTE INFORMATION
1	WALL BASE. SEE ROOM FINISH SCHEDULE.
2	25" DEEP PLASTIC LAMINATE COUNTERTOP WITH SIDE AND BACK SPLASH, AS INDICATED
3	25" DEEP SOLID SURFACE COUNTERTOP WITH SIDE AND BACK SPLASH, AS INDICATED
4	24" DEEP BASE CABINET; COUNFIGURE DOOR(S), DRAWERS(S), AND SHELVE(S) AS INDICATED
5	18" DEEP MICROWAVE SHELF.
6	16" DEEP PLASTIC LAMINATE SHELF ON ADJUSTABLE STANDARDS AND BRACKETS.
7	NEW EQUIPMENT/ FURNITURE. SEE EQUIPMENT/ FURNITURE SCHEDULE.
8	COUNTER SUPPORT BRACKET.
9	WINDOW SHADE AND FASCIA. SEE INTERIOR SPECIFICATIONS.
10	WATER BOX. SEE PLUMBING DRAWINGS.
11	PLUMBING FIXTURE. SEE PLUMBING DRAWINGS.
12	CROSS-BRACING, SEE STRUCTURAL DRAWINGS.
13	COAT HOOK, SEE PRODUCT SPECIFICATIONS.
14	MIRROR. SEE PRODUCT SPECIFICATIONS.
15	SOAP DISPENSER. SEE PRODUCT SPECIFICATIONS.
16	PAPER TOWEL DISPENSER. SEE PRODUCT SPECIFICATIONS.
17	GRAB BAR. SEE PRODUCT SPECIFICATIONS.
18	TOILET TISSUE DISPENSER. SEE PRODUCT SPECIFICATIONS.
19	CURTAIN ROD, SEE PRODUCT SPECIFICATIONS.
20	SHOWER CURTAIN, SEE PRODUCT SPECIFICATIONS.
21	WALL MOUNTED PHONE. SEE EQUIPMENT/ FURNITURE SCHEDULE.
22	TELEVISION AND BRACKET. SEE EQUIPMENT/ FURNITURE SCHEDULE.
24	SHOWER SHELF. SEE PRODUCT SPECIFICATIONS.
25	FLOAT FLOOR UNDERLAYMENT SO FINISHED FLOOR MEETS TOP OF ENTRANCE TO SHOWER.
26	UTILITY SHELF. SEE PRODUCT SPECIFICATIONS.
27	SHOWER SEAT. SEE PRODUCT SPECIFICATIONS.
28	TOWEL BAR. SEE PRODUCT SPECIFICATIONS.
29	LOCKERS WITH SLOPED TOPS. SEE PRODUCT SPECIFICATIONS.
30	RADIO CHARGING STATION, OWNER PROVIDED AND INSTALLED.



2 A505 **ENLARGED PLAN @ TOILET / CHANGING 205A & 205B**
1/2" = 1'-0"



1 A505 **ENLARGED PLAN @ TOILET 111**
1/2" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:40:48 PM AESI Proj. No:
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: Designer	CERTIFICATION
CHECKED BY: Checker	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


ENLARGED TOILET ROOM PLANS AND ELEVATIONS

SHEET NUMBER


A505



9 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"



6 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"




3 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"


8 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"

5 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"


2 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"



7 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"



4 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"



1 / A601 **PLAN DETAIL**
1 1/2" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:40:51 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY **Designer**	CERTIFICATION
CHECKED BY **Checker**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO.	

SHEET TITLE


EXTERIOR DETAILS

SHEET NUMBER


A601




7 A602 **PLAN DETAIL**
1 1/2" = 1'-0"




4 A602 **PLAN DETAIL**
1 1/2" = 1'-0"




6 A602 **PLAN DETAIL**
1 1/2" = 1'-0"




3 A602 **PLAN DETAIL**
1 1/2" = 1'-0"




2 A602 **PLAN DETAIL**
1 1/2" = 1'-0"



8 A602 **PLAN DETAIL**
1 1/2" = 1'-0"



5 A602 **PLAN DETAIL**
1 1/2" = 1'-0"



1 A602 **PLAN DETAIL**
1 1/2" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:40:55 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
87720 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


EXTERIOR DETAILS

SHEET NUMBER


A602

DOOR & HARDWARE SCHEDULE


DOOR NUMBER	ROOM NAME	DOOR INFORMATION: WIDTH	OVERALL WIDTH	HEIGHT	THICKNESS	# OF LEAFS	RATING	DOOR PANEL INFORMATION: ELEVATION ON	MATERIAL	FINISH	DOOR FRAME INFORMATION: ELEVATION ON	MATERIAL	FINISH	HARDWARE SET	FRAME DETAIL: HEAD	JAMB	SILL	REMARKS	DOOR NUMBER
LOWER LEVEL																			
109U	STAIR #1	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
FIRST FLOOR																			
101A	VEST.	3' - 0"	6' - 0"	7' - 0"		2		D3	AL	ANOD	F3	AL	ANOD						
101B	ENTRY	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
103A	FUEL OIL PUMP ROOM	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
103B	FUEL OIL PUMP ROOM	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
104B	SERVICE YARD	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
104C	SERVICE YARD	24' - 0"	24' - 0"	10' - 0"		1		CS	AL	ANOD		AL	ANOD						
105A	RECEIVING	16' - 0"	16' - 0"	14' - 0"		1	-	CS	AL	ANOD		AL	ANOD					OVERHEAD COILING DOOR	
106	STAIR #1	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
106A	STAIR #1	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		VG	HM	PT	F2	HM	PT						
108A	FIRE PUMP ROOM	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
108B	RECEIVING	3' - 6"	3' - 6"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
109	BOILER ROOM	16' - 0"	16' - 0"	14' - 0"		1		CS	AL	ANOD		AL	ANOD					OVERHEAD COILING DOOR	
109B	BOILER ROOM	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
110A	STAIR #2	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	VG	HM	PT	F2	HM	PT						
110B	STAIR #2	3' - 8 1/4"	3' - 8 1/4"	7' - 10 3/4"		1		G1	TG	-		AL	ANOD						
111	TOILET ROOM	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
112	CONTROL	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
113A	CHILLER PLANT ELECTRICAL ROOM	4' - 6"	9' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
113B	CHILLER PLANT ELECTRICAL ROOM	4' - 6"	9' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
113C	CHILLER PLANT ELECTRICAL ROOM	4' - 6"	9' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
113D	CHILLER PLANT ELECTRICAL ROOM	4' - 6"	9' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
114A	CHILLER PLANT	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
114B	CHILLER PLANT	16' - 0"	16' - 0"	14' - 0"	1 3/4"	1	-	CS	AL	ANOD		AL	ANOD					OVERHEAD COILING DOOR	
114C	CHILLER PLANT	3' - 6"	3' - 6"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
114D	CHILLER PLANT	3' - 0"	3' - 0"	7' - 0"				F	HM	PT	F2	HM	PT						
114E	CHILLER PLANT	16' - 0"	16' - 0"	14' - 0"	1 3/4"	1	-	CS	AL	ANOD		AL	ANOD					OVERHEAD COILING DOOR	
114F	CHILLER PLANT	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
114G	CHILLER PLANT	3' - 0"	3' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
115A	JANITOR	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2		F	HM	PT	F3	HM	PT						
FIRST FLOOR MEZZANINE																			
116	BOILER ROOM MEZZANINE	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
SECOND FLOOR																			
109Q	CORRIDOR	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		VG	HM	PT	F2	HM	PT						
203	OFFICE	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
204	OFFICE	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
205	LOCKER / BREAK RM	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
205A	TOILET / SHOWER	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
205B	TOILET / CHANGING	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
206	MECHANICAL	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
207	MAINTENANCE WORKROOM	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
208A	GENERATOR CONTROL	3' - 0"	6' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
208B	GENERATOR SWITCHGEAR	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
208C	GENERATOR ROOM A	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
209	CONTROL ROOM	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
210	GENERATOR SWITCHGEAR	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
211A	BATTERY ROOM	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
211B	BATTERY ROOM	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
212A	15KV SWITCHGEAR	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	T1	HM	PT					TRANSOM SHALL BE 16 GA. STEEL	
212B	15KV SWITCHGEAR	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	T1	HM	PT					TRANSOM SHALL BE 16 GA. STEEL	
212C	15KV SWITCHGEAR	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	T1	HM	PT					TRANSOM SHALL BE 16 GA. STEEL	
213A	FUEL OIL DAY TANKS B	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	45 MIN.	F	HM	PT	F3	HM	PT						
213B	FUEL OIL DAY TANKS B	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	45 MIN.	F	HM	PT	F2	HM	PT						
214A	MAINTENANCE STORAGE	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
214B	GENERATOR ROOM B	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
215A	CUP EMERGENCY ELECTRICAL ROOM	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
215B	CUP EMERGENCY ELECTRICAL ROOM	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
216A	MSS SERVICE SWITCHGEAR	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
216B	MSS SERVICE SWITCHGEAR	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
217	STAIR #2	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	90 MIN.	VG	HM	PT	F2	HM	PT						
218A	GENERATOR ROOM B	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
218B	GENERATOR ROOM A	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
218C	GENERATOR ROOM B	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
219	GENERATOR EXHAUST PLENUM 2	4' - 0"	4' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
220A	GENERATOR ROOM A	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
220B	GENERATOR SWITCHGEAR	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	T1	HM	PT					TRANSOM SHALL BE 16 GA. STEEL	
221	GENERATOR EXHAUST PLENUM 1	4' - 0"	4' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
222A	FUEL OIL DAY TANKS A	3' - 0"	6' - 0"	7' - 0"	1 3/4"	1	45 MIN.	F	HM	PT	F3	HM	PT						
222B	FUEL OIL DAY TANKS A	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
223	JANITOR / STORAGE	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
224	MECHANICAL	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2	-	F	HM	PT	F3	HM	PT						
225	MDF DATA	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
226	OFFICE	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1	-	F	HM	PT	F2	HM	PT						
229	MSS SERVICE SWITCHGEAR	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
ROOF																			
301	STAIR #1	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		VG	HM	PT	F2	HM	PT						
302A	EMERGENCY GENERATOR INTAKE MONITOR 1	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
302B	EMERGENCY GENERATOR INTAKE MONITOR 1	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
303	EMERGENCY GENERATOR INTAKE MONITOR 2	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						
304	VESTIBULE	3' - 0"	6' - 0"	7' - 0"	1 3/4"	2		VG	HM	PT	F3	HM	PT						
305	EQUIPMENT ROOM	3' - 0"	3' - 0"	7' - 0"	1 3/4"	1		F	HM	PT	F2	HM	PT						




TYPICAL DOOR FRAME ELEVATION
1/4" = 1'-0"




TYPICAL DOOR PANEL ELEVATION
1/4" = 1'-0"




13 A701 **HEAD DETAIL**
1 1/2" = 1'-0"




14 A701 **JAMB DETAIL**
1 1/2" = 1'-0"




11 A701 **HEAD DETAIL**
1 1/2" = 1'-0"




10 A701 **JAMB DETAIL**
1 1/2" = 1'-0"




8 A701 **HEAD DETAIL**
1 1/2" = 1'-0"




9 A701 **JAMB DETAIL**
1 1/2" = 1'-0"




6 A701 **HEAD DETAIL**
1 1/2" = 1'-0"




7 A701 **JAMB DETAIL**
1 1/2" = 1'-0"




5 A701 **HEAD DETAIL**
1 1/2" = 1'-0"




4 A701 **JAMB DETAIL**
1 1/2" = 1'-0"




18 A701 **HEAD DETAIL**
1 1/2" = 1'-0"



17 A701 **JAMB DETAIL**
1 1/2" = 1'-0"



16 A701 **HEAD DETAIL**
1 1/2" = 1'-0"



15 A701 **JAMB DETAIL**
1 1/2" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:41:01 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 317.818.1912
Fishers, IN 46038 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023


REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY: Designer
CHECKED BY: Checker
APPROVED BY: Approver
PROJECT NO.


CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
DOOR SCHEDULES AND DETAILS


SHEET NUMBER
A701




W1




W3




W4




W5




W9




W2 W6




W7




W8




C1




C2




C3




C4




C5



L1




L2




L3


L7 L8



L4



L5



L6

OPENING ELEVATION
1/8" = 1'-0"

ORIGINAL SHEET SIZE (8.30" X 42" (ARCH E1)
2/9/2023 3:41:05 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: Designer	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: Checker	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

OPENING ELEVATIONS AND SCHEDULE

SHEET NUMBER

A702

ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR FINISHES: SEALED CONCRETE (SC01)	FLOOR FINISHES: EPOXY SEALER (ES01)	FLOOR FINISHES: LUXURY VINYL TILE (LVT01)	FLOOR FINISHES: PORCELAIN FLOOR TILE (PFT01)	FLOOR FINISHES: RUBBER SHEET FLOORING (RS02)	FLOOR FINISHES: RUBBER STAIR TREADS (RST01)	FLOOR FINISHES: WALK OFF CARPET TILE (WOC01)	BASE FINISH: 4" RESILIENT COVE BASE (RB01)	BASE FINISH: 4" PORELAIN FLOOR TILE (PFT01)	BASE FINISH: NO BASE REQUIRED (NBR)	WALLS: PRECAST PANEL (PCP01)	WALLS: CONCRETE MASONRY UNIT (CMU)	WALLS: POURED CONCRETE (PC)	WALLS: GYPSUM WALLBOARD (GYP BD)	WALLS: MOISTURE RESISTANT GYPSUM BOARD (MRGB)	WALL FINISHES: PAINT (PT#)	WALL FINISHES: TEXTURED STAINLESS STEEL PANELS (TSSP01)	WALL FINISHES: EPOXY PAINT (EPT01)	WALL FINISHES: PORCELAIN FLOOR TILE (PFT02)	CEILING FINISHES: EXPOSED STRUCTURE, PAINT PT05	CEILING FINISHES: ACOUSTICAL CEILING PANEL SYSTEM (ACT01)	CEILING FINISHES: EPOXY PAINTED GYPSUM BOARD (EPGB01)	CEILING FINISHES: STAINLESS STEEL (SST)	COMMENTS	ROOM NUMBER
LOWER LEVEL																										
001	STAIR #1	SC01									NBR			PC			PT01				PT05					001
002	UTILITY TUNNEL	SC01									NBR			PC			PT01				PT05					002
FIRST FLOOR																										
101	VEST.							WOC01	RB01			PCP01	CMU				PT01						EPGB01			101
102	ENTRY	SC01							RB01				CMU				PT01				PT05					102
103	FUEL OIL PUMP ROOM	SC01							RB01			PCP01	CMU				PT01				PT05					103
104	SERVICE YARD	SC01									NBR		CMU						EPT01		PT05					104
105	RECEIVING	SC01							RB01			PCP01	CMU				PT01				PT05					105
106	STAIR #1	SC01				RS02	RST02		RB01			PCP01	CMU				PT01				PT05					106
108	FIRE PUMP ROOM	SC01							RB01			PCP01	CMU				PT01				PT05		EPGB01			108
109	BOILER ROOM																									109
110	STAIR #2	SC01							RB01			PCP01	CMU				PT01				PT05					110
111	TOILET ROOM				PFT01					PFT01			CMU						EPT01	PFT02		ACT01				111
112	CONTROL	SC01							RB01				CMU				PT01				PT05	ACT01				112
113	CHILLER PLANT ELECTRICAL ROOM		ES01						RB01			PCP01	CMU				PT01				PT05					113
114	CHILLER PLANT	SC01							RB01			PCP01	CMU				PT01				PT05					114
115	JANITOR	SC01							RB01				CMU				PT01				PT05					115
116	ELEVATOR					RS02					NBR							TSSP						SST	SEE SPECS - CEILING AND WALLS PROVIDED BY ELEVATOR VENDOR	116
FIRST FLOOR MEZZANINE																										
108M	FIRE PUMP ROOM MEZZAINE	SC01									NBR															108M
109M	BOILER ROOM MEZZANINE	SC01									NBR															109M
SECOND FLOOR																										
201	CORRIDOR	SC01							RB01			PCP01	CMU				PT01				PT05					201
203	OFFICE			LVT01					RB01			PCP01	CMU				PT01					ACT01				203
204	OFFICE			LVT01					RB01			PCP01	CMU				PT01					ACT01				204
205	LOCKER / BREAK RM			LVT01					RB01						GYP BD		PT01					ACT01				205
205A	TOILET / SHOWER				PFT01					PFT01						MRGB			EPT01	PFT02		ACT01	EPGB01		FIBERGLASS FACED TILE BACKER BOARD IN SHOWER AREA	205A
205B	TOILET / CHANGING				PFT01					PFT01						MRGB			EPT01	PFT02		ACT01				205B
206	MECHANICAL	SC01							RB01			PCP01	CMU				PT01				PT05					206
207	MAINTENANCE WORKROOM	SC01							RB01				CMU				PT01				PT05					207
208	GENERATOR CONTROL	SC01							RB01				CMU				PT01				PT05					208
209	CONTROL ROOM	SC01							RB01			PCP01	CMU				PT01				PT05					209
210	GENERATOR SWITCHGEAR		ES01						RB01				CMU				PT01				PT05					210
211	BATTERY ROOM	SC01							RB01				CMU				PT01				PT05					211
212	15KV SWITCHGEAR		ES01						RB01			PCP01	CMU				PT01				PT05					212
213	FUEL OIL DAY TANKS B	SC01							RB01				CMU				PT01								MEZZANINE	213
214	MAINTENANCE STORAGE	SC01							RB01				CMU				PT01								MEZZANINE	214
215	CUP EMERGENCY ELECTRICAL ROOM		ES01						RB01			PCP01	CMU				PT01				PT05					215
216	MSS SERVICE SWITCHGEAR		ES01						RB01				CMU		GYP BD		PT01				PT05					216
217	STAIR #2	SC01							RB01			PCP01	CMU				PT01				PT05					217
218	GENERATOR ROOM B	SC01							RB01				CMU				PT01				PT05					218
219	GENERATOR EXHAUST PLENUM 2	SC01											CMU													219
220	GENERATOR ROOM A	SC01							RB01				CMU				PT01				PT05					220
221	GENERATOR EXHAUST PLENUM 1	SC01											CMU													221
222	FUEL OIL DAY TANKS A	SC01							RB01				CMU				PT01				PT05					222
223	JANITOR / STORAGE	SC01							RB01				CMU				PT01				PT05					223
224	MECHANICAL	SC01							RB01			PCP01	CMU				PT01				PT05					224
225	MDF DATA		ES01						RB01			PCP01	CMU				PT01				PT05					225
226	OFFICE			LVT01					RB01			PCP01	CMU				PT01					ACT01				226
227	CORRIDOR	SC01							RB01				CMU				PT01				PT05					227
228	CORRIDOR	SC01							RB01			PCP01	CMU				PT01				PT05					228
229	MSS BATTERY ROOM	SC01							RB01			PCP01	CMU				PT01				PT05					229
SECOND FLOOR MEZZANINE																										
207M	MAINTENANCE WORKROOM AND CONTROL ROOM MEZZANINE	SC01									NBR															207M
214M	FUEL OIL DAY TANKS B MEZZANINE	SC01									NBR															214M
ROOF																										
301	STAIR #1					RS02	RST02		RB01			PCP01	CMU		GYP BD		PT01				PT05					301
302	EMERGENCY GENERATOR INTAKE MONITOR 1	SC01									NBR										PT05					302
303	EMERGENCY GENERATOR INTAKE MONITOR 2	SC01									NBR										PT05					303
304	VESTIBULE	SC01							RB01				CMU				PT01				PT05					304
305	EQUIPMENT ROOM	SC01							RB01				CMU				PT01				PT05					305

CASEWORK SPECIFICATIONS:

1. PLASTIC LAMINATE CASEWORK SHALL BE MANUFACTURED BY A CABINET MANUFACTURER APPROVED BY INDIANA UNIVERSITY HEALTH AND PROJECT ARCHITECT PRIOR TO CONSTRUCTION. UNITS SHALL BE OF THE SIZE AND ARRANGEMENT AS INDICATED ON THE DRAWINGS. CABINETS SHALL BE MADE FROM 3/4" HIGH DENSITY INDUSTRIAL MELAFACED PARTICLE BOARD. ALL EXTERIOR EXPOSED SURFACES SHALL BE COVERED WITH A HIGH PRESSURE PLASTIC LAMINATE FINISH (0.030" THICK VERTICAL GRADE MINIMUM). DOOR AND DRAWER EDGES SHALL HAVE A 3MM PVC EDGE HOT MELT GLUE APPLIED. THE INTERIOR OF THE CABINET AND THE SHELVES ARE TO BE AN OFF-WHITE MELAMINE FINISH. CABINETS SHALL BE BUILD WITH 170 DEGREE HINGES. ALL HARDWARE (HINGES, DRAWER SLIDES, ETC.) ARE TO BE "BLUM" OR APPROVED EQUAL. DOOR AND DRAWER PULLS SHALL HAVE 4" WIRE PULLS. EXPOSED SHELVING INSIDE BASE OR WALL UNIT (NO DOORS) SHALL BE 3/4" PLYWOOD WITH LAMINATE FINISH. CABINETS SHALL BE COMPLETE WITH ALL HARDWARE, SHELVING AND ACCESSORIES. FURNISH DETAILED SHOP DRAWINGS FOR ARCHITECT'S APPROVAL. CABINET LAMINATE AND EDGING SHALL BE SELECTED FROM MANUFACTURER'S RULL RANGE OF COLORS. INSTALL 3/8" DIAMETER ADHESIVE MOUNT CLEAR RUBBER BUMPERS AS REQUIRED WHERE WIRE PULLS, ETC. COME IN CONTACT WITH OTHER SURFACES. REFER TO MATERIAL FINISH LEGEND FOR CABINET LAMINATE COLORS.

2. PLASTIC LAMINATE COUNTERTOPS SHALL BE MANUFACTURED TO ANSI A161.2. EXPOSED SURFACES SHALL BE COVERED WITH HIGH PRESSURE PLASTIC LAMINATE, 0.050" THICK, GENERAL PURPOSE TYPE. SUBSTRATE TO BE SOLID 1-1/2" WATER RESISTANT DENSITY PARTICLE BOARD. COUNTER SHALL BE EDGED WITH 3MM PVC EDGING HOT MELT GLUE ATTACHED. ALL EXPOSED OUTSIDE CORNERS OF COUNTERTOP SHALL BE RADIUSED 2". FURNISH ALL COUNTERS WITH 4" HIGH BACKSPLASH AND RETURNS AT ENDS WITH WALLS TO MATCH COUNTER MATERIAL, UNLESS NOTED OTHERWISE. REFER TO MATERIAL FINISH LEGEND FOR COUNTERTOP LAMINATE COLORS

3. SOLID SURFACE COUNTERTOPS AND WINDOW STOOLS SHALL BE A NON-POROUS HOMOGENOUS BLEND OF POLYESTER OR ACRYLIC POLYMERS AND MINERAL FILLERS. PROVIDE SOLID SURFACE OVERLAY IN THICKNESS AS INDICATED ON DRAWINGS OR PER MANUFACTURER'S STANDARDS. SUBSTRATE TO BE WATER RESISTANT PLYWOOD. ALL EXPOSED OUTSIDE CORNERS OF COUNTERTOP TO BE RADIUSED 2" MINIMUM. EASE ALL EDGES, PROVIDE 1/4" ROUND EDGE AT COUNTER FRONT, TOP, AND BOTTOM. FURNISH ALL COUNTERS WITH 4" HIGH BACKSPLASH AND RETURNS AT ENDS WITH WALLS, UNLESS NOTED OTHERWISE. REFER TO MATERIAL FINISH LEGEND FOR COUNTERTOP SOLID SURFACE COLORS.

PAINT SPECIFICATIONS:

1. WORK INCLUDES SURFACE PREPARATION, PAINTING, AND FINISHING OF INTERIOR EXPOSED ITEMS AND SURFACES THROUGHOUT THE PROJECT, EXCEPT AS OTHERWISE INDICATED. DO NOT PAINT PRECAST PANELS. ITEMS WHEN FACTORY-FINISHING IS SPECIFIED, INCLUDING, BUT NOT LIMITED TO COUNTERTOPS, LOCKERS, ACOUSTICAL MATERIALS, FINISHED MECHANICAL AND ELECTRICAL EQUIPMENT, LIGHT FIXTURES, AND METAL SURFACES SHALL NOT REQUIRE FINISH PAINTING.

2. ALL PAINT PRODUCTS SHALL BE PREMIUM QUALITY LINES AS SUPPLIED BY SHERWIN-WILLIAMS, UNLESS NOTED OTHERWISE. APPLICATION SHALL BE DONE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS FOR ENVIRONMENTAL CONDITIONS AND SURFACE PREPARATION.

3. PROVIDE THE FOLLOWING PAINT SYSTEMS FOR VARIOUS SUBSTRATES AS INDICATED.

GYPSUM BOARD

PRIME: 1 COAT; PROMAR ZERO VOC LATEX PRIMER
FINAL (TOP COAT): 2 COATS, EGGSHELL; PROMAR 200 ZERO VOC INTERIOR LATEX

BLOCK AND CONCRETE

INTERIOR BLOCK AND CONCRETE SURFACES SYSTEM:
PRIME: 1 COAT; SW CONFLEX BLOCK FILLER
FINAL (TOP COAT) 2 COATS, EGGSHELL; PROMAR 200 VOC INTERIOR LATEX

EXTERIOR BLOCK AND CONCRETE SURFACES SYSTEM:
PRIME: 1 COAT; SCOFIELD CURESEAL-S, MATTE FINISH (OR EQUAL)
FINAL (TOP COAT) 2 COATS, GLOSS; PRO INDUSTRIAL HIGH PERFORMANCE EPOXY

FERROUS METALS OR SHOP PRIMED GALVANIZED METALS OR PRE-PRIMED METALS

PRIME: 1 COAT FLAT, PROMAR 200, ZERO VOC INTERIOR LATEX PRIMER (OR EQUAL)
FINAL (TOP COAT) 2 COATS ENAMEL, SEMI-GLOSS; PROMAR 200 INTERIOR ALKYD SEMI-GLOSS

MATERIAL FINISH LEGEND

SEALED CONCRETE

SC01 — GENERAL
MANUFACTURER: EUCLID CHEMICAL
NAME: DIAMOND HARD LIQUID DENSIFIER AND SEALER
FINISH: GLOSS

EPOXY SEALER

ES01 — MANUFACTURER: SHERWIN WILLIAMS
NAME: RESUTILE 4638
TYPE: HS POLYURETHANE FLOOR ENAMEL
COLOR: INDUSTRIAL GREY
FINISH: GLOSS

LUXURY VINYL TILE

LVT01 — MANUFACTURER: GERFLOR
STYLE: CREATION 70 CONNECT
COLOR: GENTLEMAN TAUPE
NUMBER: 0089
SIZE: 19.4" x 19.4", IU HEALTH STOCK
THICKNESS: 2.5 mm
WEAR LAYER: 28 MILS
INSTALLATION: LENGTH OF TILE PERPENDICULAR TO DOOR OPENING

PORCELAIN FLOOR TILE

PFT01 — MANUFACTURER: FLORIDA TILE
STYLE: AVENTIS
COLOR: TITANIUM
NUMBER: FTIAT3RF12X24
SIZE: 12"X24"
THICKNESS: 9MM, RECTIFIED
INSTALLATION: TRADITIONAL

PFT02 — MANUFACTURER: FLORIDA TILE
STYLE: AVENTIS
COLOR: COTTON
NUMBER: FTIAT5RF12X24
SIZE: 12"X24"
THICKNESS: 9MM, RECTIFIED
INSTALLATION: TRADITIONAL

RUBBER SHEET

RS01 — TOILETS
MANUFACTURER: NORA
STYLE: ENVIRONCARE (WELDED SEAMS)
COLOR: SNOW SHOEING
NUMBER: 7035
SIZE: 48" WIDE SHEETS
THICKNESS: 3 mm

RS02 — STAIRS/ ELEVATOR
MANUFACTURER: NORA
STYLE: NORAMENT GRANO
COLOR: CAMPHOR
NUMBER: 5306
SIZE: 40" x 40"
THICKNESS: 3 mm

RUBBER STAIR TREADS

RST01 — STAIR TREADS
MANUFACTURER: NORA
STYLE: GRANO STAIRTREAD
COLOR: ANGELICA ROOT
NUMBER: 5302

WALK-OFF CARPET

WOC01 — VESTIBULE
MANUFACTURER: INTERFACE
STYLE: STEP REPEAT
STYLE NUMBER: SR899
COLOR: IRON
NUMBER: 104940
SIZE: 19.69" x 19.69"
BACKING: GLASBAC
INSTALLATION: MONOLITHIC

RESILIENT COVE BASE

RB01 — MANUFACTURER: TARKETT/ JOHNSONITE
STYLE: TRADITIONAL VINYL COVE
COLOR: MOON ROCK
NUMBER: #29
SIZE: 4" HIGH, ON ROLL, 1/8" THICK

RB02 — TOILETS
MANUFACTURER: NORA
STYLE: SANITARY BASE, THERMOPLASTIC RUBBER
NUMBER: 7035
HEIGHT: 6"

MATERIAL FINISH LEGEND

PLASTIC LAMINATE

PL01 — MANUFACTURER: ARBORITE
LOCATION: SHELVES ON STANDARDS/BRACKETS
NAME: CHAMBRAY GRIS
FINISH: CASHMERE
NUMBER: P-399 CA

PL02 — MANUFACTURER: WILSONART
LOCATION: CABINETS (VERTICAL SURFACES)
NAME: CUMBERLAND WALNUT
FINISH: ALIGNED WALNUT
NUMBER: 17016-67

SOLID SURFACE

SS01 — MANUFACTURER: CORIAN
LOCATION: ALL COUNTERTOPS
NAME: WHITE JASMINE
FINISH: MATTE

PAINT

PT01 — GENERAL MANUFACTURER: SHERWIN WILLIAMS
COLOR: SNOWBOUND
NUMBER: SW7004
FINISH: ACRYLIC LATEX, EGGSHELL

PT02 — DOOR AND WINDOW TRIM
MANUFACTURER: SHERWIN WILLIAMS
COLOR: DOVETAIL
NUMBER: SW7018
FINISH: ACRYLIC LATEX, SEMI-GLOSS

PT03 — GENERAL IN TOILET ROOMS
MANUFACTURER: SHERWIN WILLIAMS
COLOR: SNOWBOUND
NUMBER: SW7004
FINISH: EPOXY, EGGSHELL

PT04 — CEILINGS, UNDERSIDE OF BULKHEADS
MANUFACTURER: SHERWIN WILLIAMS
COLOR: STANDARD CEILING WHITE
NUMBER:
FINISH: ACRYLIC LATEX, FLAT

PT05 — EXPOSED CEILINGS
MANUFACTURER: SHERWIN WILLIAMS
TYPE: PRO INDUSTRIAL WATERBORNE ACRYLIC DRYFALL
COLOR: STANDARD CEILING WHITE
NUMBER:
FINISH: FLAT

TEXTURED STAINLESS STEEL PANELS (BY ELEVATOR VENDOR)

TSSTP01 — MANUFACTURER: ELEVATOR VENDOR
STYLE: TEXTURED METAL PANELS
COLOR: STAINLESS STEEL
NUMBER:

CEILING

ACT01 — GENERAL
MANUFACTURER: ARMSTRONG COMMERCIAL
NAME: ULTIMA
NUMBER: 1941
EDGE TYPE: BEVELED TEGULAR
SIZE: 24" x 24" x 7/8"
FINISH: WHITE
GRID: 15/16" TEGULAR GRID
GRID COLOR: WHITE

SSTC01 — ELEVATOR
MANUFACTURER: (BY ELEVATOR VENDOR)
MATERIAL: STAINLESS STEEL
SURFACE: SMOOTH

WINDOW ROLLER SHADE

WRS01 — MANUFACTURER: DRAPER OR MECHO
STYLE: MANUAL CHAIN OPERATION
SHADE CLOTH: PHIFER SHEERWEAVE 4000 SERIES
OPENNESS: 5% OPEN
COLOR: PEWTER
NUMBER: U63
FASCIA COLOR: CLEAR ANODIZED
LOCATION: ALL WINDOWS INDICATED ON PLAN

TOILET ACCESSORIES LEGEND

GRAB BARS
MANUFACTURER: BRADLEY
MODEL NUMBER:
812001-36, BACK OF TOILET - HORIZONTAL
812001-42, SIDE OF TOILET - HORIZONTAL
812001-18, SIDE OF TOILET - VERTICAL, ENTRY TO SHOWER - VERTICAL, SIDE OF SHOWER - HORIZONTAL
812001-24, CONTROL SIDE OF SHOWER - HORIZONTAL
FINISH: SATIN STAINLESS STEEL

MIRROR
MANUFACTURER: BRADLEY
MODEL NUMBER: 780-1830
FINISH: SATIN STAINLESS STEEL

COAT HOOK
MANUFACTURER: BRADLEY
MODEL NUMBER: 9114
FINISH: SATIN STAINLESS STEEL

SHOWER UNIT
MANUFACTURER: INPRO
MODEL NUMBER: 36"X36" ADA TRANSFER SHOWER BASE
FINISH: SOLID SURFACE, BRIGHT WHITE

SHOWER WALLS
MANUFACTURER: INPRO
MODEL NUMBER: PRISM DECORATIVE SHOWER WALL
FINISH: SOLID PATTERN, SOLID SURFACE,
COLOR: BRIGHT WHITE P9011

SHOWER CURTAIN
MANUFACTURER: GRAINGER
MODEL NUMBER: 4EEY7 COTTON DUCK
FINISH: WHITE

SHOWER CURTAIN ROD
MANUFACTURER: BRADLEY
MODEL NUMBER: 9531
FINISH: SATIN STAINLESS STEEL

SHOWER SEAT
MANUFACTURER: BRADLEY
MODEL NUMBER: 9569
FINISH: WHITE

SHOWER SHELF
MANUFACTURER: ASI
SERIES: 20692
SIZE: CUSTOM, 4" WIDE x 12" LONG
FINISH: SATIN STAINLES STEEL

LIQUID SOAP DISPENSER (BY VENDOR)
MANUFACTURER: BRADLEY
MODEL NUMBER: 6563
FINISH: SATIN STAINLESS STEEL

TOILET TISSUE DISPENSER (BY VENDOR)
MANUFACTURER: BRADLEY
MODEL NUMBER: 5402
FINISH: SATIN STAINLESS STEEL

TOWEL BAR
MANUFACTURER: BRADLEY
MODEL NUMBER: 9054
FINISH: SATIN STAINLESS STEEL

PAPER TOWEL DISPENSER (BY VENDOR)
MANUFACTURER: BRADLEY
MODEL NUMBER:250-15
FINISH: SATIN STAINLESS STEEL

UTILITY SHELF
MANUFACTURER: BRADLEY
MODEL NUMBER: 9984
FINISH: SATIN STAINLESS STEEL

WASTE RECEPTACLE
MANUFACTURER: BRADLEY
MODEL NUMBER: 377-37
FINISH: SATIN STAINLESS STEEL

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Ave, Suite 100
Indianapolis, IN 46204
(317) 353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10th, 2023

REVISIONS
NO. DATE DESCRIPTION


DESIGNED BY: Designer
CHECKED BY: Checker
APPROVED BY: Approver
PROJECT NO.

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE: ROOM FINISH SCHEDULE

SHEET NUMBER: A703

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:41:10 PM AESI Proj. No:



LOWER LEVEL EQUIPMENT PLAN- OVERALL

Scale: 3/32" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:39:14 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

LOWER LEVEL EQUIPMENT PLAN


SHEET NUMBER

EQ301



FIRST FLOOR EQUIPMENT PLAN - OVERALL

Scale: 3/32" = 1'-0"



FIRST FLOOR MEZZANINE EQUIPMENT PLAN

Scale: 3/32" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:39:22 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR EQUIPMENT PLAN

SHEET NUMBER

EQ302



SECOND FLOOR EQUIPMENT PLAN - OVERALL

Scale: 3/32" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:39:26 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR EQUIPMENT PLAN

SHEET NUMBER

EQ303



ROOF EQUIPMENT PLAN - OVERALL

Scale: 3/32" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:39:27 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF EQUIPMENT PLAN

SHEET NUMBER

EQ304

NOTE: ALL SYMBOL DESCRIPTIONS ARE SUBJECT TO MODIFICATION ON THE DRAWINGS. ALL SYMBOLS NOT NECESSARILY USED ON THIS PROJECT.

VALVES & FITTINGS:

- GATE VALVE
- BALL VALVE
- BUTTERFLY VALVE
- CHECK VALVE
- GLOBE VALVE
- BALANCING VALVE
- PLUG VALVE
- CONTROL VALVE
- SOLENOID VALVE
- NEEDLE VALVE
- THERMAL EXPANSION VALVE
- AUTOMATIC BALANCE VALVE
- BACK FLOW PREVENTER
- PRESSURE REDUCING, SELF CONTAINED VALVE
- PRESSURE REDUCING, PILOT OPERATED VALVE
- RELIEF, PILOT OPERATED VALVE
- ANGLE GLOBE VALVE
- PRESSURE SAFETY, ANGLE TYPE VALVE
- THREE WAY BALL VALVE
- THREE WAY GLOBE VALVE
- THREE WAY PLUG VALVE
- MOTORIZED VALVE
- MOTORIZED VALVE
- THREE WAY CONTROL VALVE
- PIPE TURN 90°
- LINE BREAK
- PIPE ELBOW UP (RISER)
- PIPE ELBOW DOWN
- PIPE TEE DOWN
- CAP OR PLUG
- REDUCER, CONCENTRIC
- REDUCER, ECCENTRIC
- Y-STRAINER
- FLEXIBLE CONNECTION
- FLANGES
- UNION
- PIPE GUIDE
- PIPE ANCHOR
- FILTER (INLINE)
- GAUGE
- THERMOMETER
- STEAM TRAP
- PRESSURE SENSOR
- PUMP

VALVES & FITTINGS:

- MATERIAL CHANGE
- AUTOMATIC AIR VENT (AAV)
- DRAIN
- FLOW METER

GENERAL SYMBOLS:

- POINT OF CONNECTION
- POINT OF REMOVAL
- PLAN NOTE (#)
- DEMOLITION NOTE (#)
- REVISION
- DETAIL BUBBLE (X / X)
- SECTION BUBBLE (X / X)

DIFFUSERS & REGISTERS

SUPPLY DIFFUSER:
- SHADING INDICATES BLANKED-OFF QUADRANT OF DIFFUSION PATTERN
- SEE SCHEDULE FOR RUNOUT SIZE
- DIFFUSER TYPE
- DIFFUSER SIZE
- SDA / 750 — DIFFUSER CFM

SUPPLY DIFFUSER:
- SHADING INDICATES BLANKED-OFF QUADRANT OF DIFFUSION PATTERN
- SEE SCHEDULE FOR RUNOUT SIZE
- DIFFUSER TYPE
- DIFFUSER SIZE
- SDA / 750 — DIFFUSER CFM

RETURN/EXHAUST GRILLE:
- SEE SCHEDULE FOR RUNOUT SIZE
- GRILLE TYPE
- GRILLE SIZE
- RGA / 750 — GRILLE CFM

RETURN/EXHAUST GRILLE:
- SEE SCHEDULE FOR RUNOUT SIZE
- GRILLE TYPE
- GRILLE SIZE
- RGA / 750 — GRILLE CFM

LINEAR BAR & SLOT DIFFUSER:
- ARROW INDICATES DIRECTION OF AIR FLOW
- SEE SCHEDULE FOR RUNOUT SIZE
- DIFFUSER TYPE
- DIFFUSER SIZE
- LDA / 220 — DIFFUSER CFM

LINEAR BAR & SLOT DIFFUSER:
- ARROW INDICATES DIRECTION OF AIR FLOW
- SEE SCHEDULE FOR RUNOUT SIZE
- DIFFUSER TYPE
- DIFFUSER SIZE
- LDA / 220 — DIFFUSER CFM

TERMINAL BOXES

SINGLE-DUCT TERMINAL BOX WITH REHEAT COIL
- SEE SCHEDULE FOR RUNOUT SIZE
- TYPE OF TERMINAL BOX
- VAV-1
- CONTROL PANEL
- MAINTAIN CODE REQUIRED CLEARANCE IN FRONT OF CONTROL PANEL

DUAL DUCT TERMINAL BOX:
- SEE SCHEDULE FOR RUNOUT SIZE
- TYPE OF TERMINAL BOX
- VAV-1
- CONTROL PANEL(S)
- MAINTAIN CODE REQUIRED CLEARANCE IN FRONT OF CONTROL PANEL

DUCTWORK:

- SUPPLY ARROW
- RETURN/EXHAUST ARROW
- THERMOSTAT (T)
- HUMIDISTAT (H)
- SENSOR (S)
- SUPPLY UP
- SUPPLY DOWN
- RETURN/EXHAUST UP
- RETURN/EXHAUST DOWN
- ROUND UP
- ROUND DOWN
- FLAT OVAL SUPPLY UP
- FLAT OVAL SUPPLY DOWN
- 16x12 — RECTANGULAR DUCT WIDTH x HEIGHT
- 16"ø — ROUND DUCT DIAMETER
- 16x12ø — FLAT OVAL DUCT WIDTH x HEIGHT
- EXISTING DUCT
- 90° MITERED ELBOW WITH TURNING VANES
- ELBOW (W, r=w)
- DUCT END CAP
- 15° MAX — DUCT TRANSITION - SLOPED BOTH SIDES
- 15° MAX — DUCT TRANSITION - FLAT ON ONE SIDE
- FLEXIBLE DUCT
- VOLUME DAMPER
- FD — FIRE DAMPER
- MOTORIZED DAMPER
- BDD — BACKDRAFT DAMPER
- AD — ACCESS DOOR
- FAN (OR PUMP)

DUCTWORK:

SINGLE LINE REPRESENTATION:

- SUPPLY UP
- SUPPLY DOWN
- RETURN/EXHAUST UP
- RETURN/EXHAUST DOWN
- ROUND UP
- ROUND DOWN
- FLAT OVAL SUPPLY UP
- FLAT OVAL SUPPLY DOWN
- 16x12 — RECTANGULAR DUCT WIDTH x HEIGHT
- 16"ø — ROUND DUCT DIAMETER
- 16x12ø — FLAT OVAL DUCT WIDTH x HEIGHT
- EXISTING DUCT
- DUCT TURN 90°
- DUCT END CAP
- DUCT TRANSITION - SLOPED ON BOTH SIDES
- DUCT TRANSITION - FLAT ON ONE SIDE
- FLEXIBLE DUCT
- VOLUME BALANCE DAMPER
- FD — FIRE DAMPER
- MOTORIZED DAMPER
- BDD — BACKDRAFT DAMPER

PIPING DESIGNATIONS:

- NEW PIPING
- EXISTING PIPING TO REMAIN
- EXISTING PIPING TO BE REMOVED
- PIPE SLOPES IN DIRECTION OF ARROW

FLOW/CONTROL SYMBOLS:

- AI — ANALOG INPUT
- AO — ANALOG OUTPUT
- DI — DIGITAL BINARY INPUT
- DO — DIGITAL BINARY OUTPUT
- CO2 — CARBON DIOXIDE SENSOR
- CS — CURRENT SENSOR
- ΔP — DIFFERENTIAL PRESSURE SENSOR
- SD — DUCT SMOKE DETECTOR
- ES — END SWITCH
- H — HUMIDITY SENSOR
- LL — LOW LIMIT TEMPERATURE SENSOR
- M — DAMPER MOTOR
- P — PRESSURE SENSOR
- T — TEMPERATURE SENSOR
- AIR FLOW MEASURING STATION
- AIR HANDLER FAN
- CONTROL VALVE
- HYDRONIC PUMP
- MS — MOTOR STARTER
- VFD — VARIABLE FREQUENCY DRIVE
- FM — FLOW METER

MECHANICAL ABBREVIATIONS:

AE	ANALYSIS ELEMENT
AFF	ABOVE FINISHED FLOOR
AH	(PARAMETER) ALARM HIGH
AHU	AIR HANDLING UNIT
AIT	ANALYSIS INDICATING TRANSMITTER
AL	(PARAMETER) ALARM LOW
AS	AIR SEPARATOR
ASD	ADJUSTABLE SPEED DRIVE (ALSO VFD)
AV	AUTOMATIC AIR VENT
BAS	BUILDING AUTOMATION SYSTEM (ALSO BMS)
BCU	BLOWER COIL UNIT
BFV	BUTTERFLY VALVE
BDD	BACK DRAFT DAMPER
BHP	BRAKE HORSEPOWER
BLDG	BUILDING
BMS	BUILDING MANAGEMENT SYSTEM (ALSO BAS)
BOD	BOTTOM OF DUCT
BTU	BRITISH THERMAL UNIT
CA	COMPRESSED AIR
CBDV	CONTINUOUS BLOWDOWN VALVE
CH	CHILLER
CHM	CHEMICAL
CHWP	CHILLED WATER PUMP
CHWR	CHILLED WATER RETURN
CHWS	CHILLED WATER SUPPLY
CR	PUMPED CONDENSATE RETURN
CRAC	COMPUTER ROOM AIR CONDITIONER
CO	CLEANOUT
COND	CONDUCTIVITY
COP	COEFFICIENT OF PERFORMANCE
CP	CONDENSATE PUMP
CPVC	CHLORINATED POLYVINYL CHLORIDE
CT	COOLING TOWER
CTF	COOLING TOWER FAN
CTP	COOLING TOWER PUMP
CTWR	COOLING TOWER WATER RETURN
CTWS	COOLING TOWER WATER SUPPLY
CU	COPPER
CS	CARBON STEEL
CV	CONTROL VALVE
CW	COMESTIC COLD WATER
DB	DRY BULB
DCV	DOUBLE CHECK VALVE
DDC	DIRECT DIGITAL CONTROL
DIA	DIAMETER
DN	DOWN
DPI	DIFFERENTIAL PRESSURE INDICATOR
DPS	DIFFERENTIAL PRESSURE SENSOR
DPT	DIFFERENTIAL PRESSURE TRANSMITTER
DT	DAY TANK
ECM	ELECTRONICALLY COMMUTATED MOTOR
EA	EXHAUST AIR
EC	ELECTRICAL CONTRACTOR
EF	EXHAUST FAN
EG	EXHAUST GRILLE
EL	ELEVATION
ET	EXPANSION TANK
EX	EXHAUST
EXIST	EXISTING
EWT	ENTERING WATER TEMPERATURE
FCU	FAN COIL UNIT
FCV	FLOW CONTROL VALVE
FD	FLOOR DRAIN
FE	FLOW ELEMENT
FEP	FLUORINATED ETHYLENE PROPYLENE
FLA	FULL LOAD AMPS
FLTR	FILTER
FOR	FUEL OIL RETURN
FOS	FUEL OIL SUPPLY
FOT	FUEL OIL TANK
FOTV	FUEL OIL TANK VENT
FS	FLOW SWITCH
FT	FLOW TRANSMITTER
HE	HEAT EXCHANGER
HHW	HEATING HOT WATER
HHWP	HEATING HOT WATER PUMP
HHWR	HEATING HOT WATER RETURN
HHWS	HEATING HOT WATER SUPPLY
HP	HORSEPOWER
HPS	HIGH PRESSURE STEAM
HPSR	HIGH PRESSURE STEAM RETURN
HRC	HEAT RECOVERY CHILLER
HRCWP	HEAT RECOVERY CHILLED WATER PUMP
HRCHWP	HEAT RECOVERY HEATING HOT WATER PUMP
HV	HAND VALVE
HW	DOMESTIC HOT WATER
HWR	DOMESTIC HOT WATER RETURN
HWRP	HOT WATER RECIRCULATION PUMP
LCV	LEVEL CONTROL VALVE
LI	LEVEL INDICATOR
LPS	LOW PRESSURE STEAM
LPSR	LOW PRESSURE STEAM RETURN
LT	LEVEL TRANSMITTER
LSH	LEVEL SENSOR HIGH
LSL	LEVEL SENSOR LOW
LSLL	LEVEL SENSOR LOW LOW
LWT	LEAVING WATER TEMPERATURE
MC	MECHANICAL CONTRACTOR
MCA	MINIMUM CIRCUIT AMPS
MFG	MANUFACTURER
MOCP	MAXIMUM OVER CIRCUIT PROTECTION
MUA	MAKE UP AIR UNIT
MOV	MOTOR OPERATED VALVE
N2	NITROGEN
NC	NORMALLY CLOSED
NG	NATURAL GAS
NO	NORMALLY OPEN
OA	OUTDOOR AIR
ORP	OXIDATION-REDUCTION POTENTIAL
PDS	PRESSURE DIFFERENTIAL SWITCH
PE	PRESSURE ELEMENT
PI	PRESSURE INDICATOR
PIT	PRESSURE INDICATING TRANSMITTER
PRV	PRESSURE REGULATING VALVE
PS	PRESSURE SWITCH
PSV	PRESSURE SAFETY VALVE
PSIA	POUNDS PER SQUARE INCH ABSOLUTE
PSIG	POUNDS PER SQUARE INCH GAUGE
PT	PRESSURE TRANSMITTER
PTSA	CHEMICAL TREATMENT DYE
PVC	POLYVINYL CHLORIDE
PVDF	POLYVINYLIDENE FLUORIDE
PWR	PURIFIED WATER RETURN
PWS	PURIFIED WATER SUPPLY
RA	RETURN AIR
REF	REFRIGERANT
RF	RETURN FAN
RG	RETURN GRILLE
RO	REVERSE OSMOSIS
RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
SA	SUPPLY AIR
SC	SPEED CONTROLLER
SAN	SANITARY
SCW	SOFT COLD WATER
SD	SUPPLY DIFFUSER
SF	SUPPLY FAN
SFT	SOFT WATER
SRV	SAFETY RELIEF VALVE
SS	STAINLESS STEEL
SS FLTR	SIDE STREAM FILTER
STR	STRAINER
TCC	TEMPERATURE CONTROL CONTRACTOR
TCV	TEMPERATURE CONTROL VALVE
TE	TEMPERATURE ELEMENT
TI	TEMPERATURE INDICATOR
TT	TEMPERATURE TRANSMITTER
TW	THERMOWELL
V	VENT
VAV	VARIABLE AIR VOLUME
VD	VOLUME DAMPER
VFD	VARIABLE FREQUENCY DRIVE (ALSO ASD)
VTR	VENT THROUGH ROOF
WB	WET BULB
WH	WALL HYDRANT
XFMR	TRANSFORMER
XL	ACROSS THE LINE
ZS	LIMIT SWITCH

ORIGINAL SHEET SIZE IS 36" X 42" (ARCH E1)
2/10/2023 2:33:40 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

MECHANICAL SYMBOLS AND ABBREVIATIONS

SHEET NUMBER


M001

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.

(#) PLAN NOTES:

1. FILL LINES UP TO WALL MOUNTED TANK FILL STATION.
2. SLOPE FILL LINES TO TANKS. PROVIDE HIGH POINT AT RISE FROM REMOTE FILL STATION.
3. BURIED FUEL OIL TANKS. SEE STRUCTURAL AND CIVIL DRAWINGS FOR EXCAVATION AND DEADMAN INFORMATION.
4. FUEL OIL LINES UP. SEE M303 FOR CONTINUATION.
5. FUEL OIL TANK VENT LINES UP. SEE M310 FOR CONTINUATION.



1 **MECHANICAL SITE PLAN**
Scale: 1/8" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:33:42 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: EPW	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: SRB	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

MECHANICAL SITE PLAN

SHEET NUMBER

M201



1 **LOWER LEVEL PIPING PLAN- AREA A**
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.

(#) PLAN NOTES:

1. ROUTE HHW PIPING TO FCU-B1 & FCU-B2. CONNECT PIPING PER MANUFACTURER INSTRUCTIONS. SEE DETAIL X PM SHEET M50X

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

LOWER LEVEL PIPING PLAN - AREA A

SHEET NUMBER


M301



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:33:42 PM AESI Proj. No: 21-154



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.

(#) PLAN NOTES:

1. FUEL OIL PIPING FROM TANKS TO FUEL PUMP ROOM. SEE M201 SITE PLAN FOR CONNECTION TO TANKS, SEE M307 FOR ROOM ABOVE.

LOWER LEVEL PIPING PLAN- AREA D

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:33:45 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

LOWER LEVEL PIPING PLAN - AREA D

SHEET NUMBER

M303



FIRST FLOOR PIPING PLAN - AREA A


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. PIPE SIZE ON DRAWING FOR CHEMICAL TREATMENT PIPING IS SIZE OF PVC CONDUIT PIPING. SEE CHEMICAL TREATMENT P&ID FOR SIZE OF CHEMICAL TUBING.
3. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR CONSTRUCTION AND LOCATION.

PLAN NOTES:

1. RO WATER DOWN TO SINK. SEE ARCHITECTURAL PLANS FOR SINK LOCATION.
2. PROVIDE DOUBLE CHECK VALVE AND STATIC MIXER FOR ACID MIXING.
3. PROVIDE CORROSION COUPLING RACK AND CHEMICAL POT FEEDER.
4. PROVIDE CORROSION COUPLING RACK WITH CORROSION SENSOR.
5. PROVIDE TOWER WATER CORROSION COUPON RACK, AND ANALYZERS. SEE CHEMICAL TREATMENT P&ID FOR MORE INFORMATION.
6. 6" HHWS/R TO SERVE CUP LOADS. SEE M711 FOR BRANCH FLOW INFORMATION.
7. HHWS/R AND CHWS/R PIPING CONNECTIONS TO BCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
8. HHWS/R AND CHWS/R PIPING CONNECTIONS TO FCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM FCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
9. CHWS/R PIPING CONNECTIONS TO BCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
10. HHWS/R, CHWS/R, AND RO PIPING UP TO SECOND FLOOR. SEE SHEET M311 FOR CONTINUATION.
11. 18" HHWR BRANCH PIPING TO HEAT RECOVERY CHILLERS AT LOCATION INDICATED.
12. HEAT RECOVERY HEATING HOT WATER PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT HHW PIPING TO PUMP. SEE DETAIL 'X' ON SHEET M50X.
13. HEAT RECOVERY CHILLED WATER PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO PUMP. SEE DETAIL 'X' ON SHEET M50X.
14. CHILLED WATER PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO PUMP. SEE DETAIL 'X' ON SHEET M50X.
15. HEAT RECOVERY CHILLER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO CHILLER. SEE DETAILS '1' AND '3' ON SHEET M504. CONNECT HHW PIPING TO CHILLER. SEE DETAILS '2' AND '4' ON SHEET M504.
16. CENTRIFUGAL CHILLER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO CHILLER. SEE DETAILS '2' AND '3' ON SHEET M503. CONNECT CTW PIPING TO CHILLER. SEE DETAILS '1' AND '4' ON SHEET M503.
17. HEAT RECOVERY SYSTEM HEAT EXCHANGER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT HHW PIPING AND CTW PIPING TO HEAT EXCHANGER. SEE DETAIL 'X' ON SHEET M50X.
18. HHW PIPING DOWN THROUGH FLOOR INTO TUNNEL AT LOCATION INDICATED. SEE SHEET M301 FOR CONTINUATION.
19. CHWS FLOW METER.
20. HHWR FLOW METER.
21. HHWS FLOW METER.
22. 6" REFRIGERANT RELIEF PIPING DOWN TO CHILLER.
23. 3" CHW EXPANSION TAK PIPE UP THROUGH FLOOR TO EXPANSION TANKS IN MECHANICAL 224.
24. 3" CHW EXPANSION TANK CONNECTON TO CHWS PIPING.
25. 3" REFRIGERANT SRV RELIEF PIPING THROUGH WALL. FLASHS ANS SEAL WALL PENETRATION.
26. 3" REFRIGERANT RELIEF PIPING DOWN TO HRC CHILLER.
27. HEATING HOT WATER FLOW METER IN 20" HHWS PIPE TO CAMPUS AT LOCATION INDICATED. MAINTAIN 10 PIPE DIAMTERS OF STRAIGHT PIPE ON BOTH SIDES OF PIPE.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR PIPING PLAN - AREA A

SHEET NUMBER

M304

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:33:56 PM AESI Proj. No: 21-154



FIRST FLOOR PIPING PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR PAD CONSTRUCTION AND LOCATION.

(#) PLAN NOTES:

1. PROVIDE STEAM AND CONDENSATE ANCHOR ATTACHED TO COLUMN. SEE 2/M501 AND STRUCTURAL FOR MORE INFORMATION.
2. PROVIDE SAFETY RELIEF VALVE FOR EXPANSION TANKS. SEE SCHEDULE FOR MORE INFORMATION. ROUTE DISCHARGE TO FLOOR DRAIN.
3. PROVIDE CONDENSATE NEUTRALIZATION KITS FOR BOILER DRAINS. ROUTE DISCHARGE TO FLOOR DRAINS.
4. HHWS/R AND CHWS/R PIPING CONNECTIONS TO BCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
5. CHWS/R PIPING CONNECTIONS TO BCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
6. CHILLED WATER PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO PUMP, SEE DETAIL 'X' ON SHEET M50X.
7. CENTRIFUGAL CHILLER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO CHILLER, SEE DETAILS '2' AND '3' ON SHEET M503. CONNECT CTW PIPING TO CHILLER, SEE DETAILS '1' AND '4' ON SHEET M503.
8. HEATING HOT WATER PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT HHW PIPING TO PUMP, SEE DETAIL 'X' ON SHEET M50X.
9. HEATING HOT WATER SYSTEM EXPANSION TANKS POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT HHW PIPING TO TANKS, SEE DETAIL 'X' ON SHEET M50X.
10. CONDENSING, HEATING HOT WATER BOILER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT HHW PIPING TO BOILER, SEE DETAIL 'X' ON SHEET M50X.
11. HEATING HOT FILTER SKID POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT HHW PIPING TO FILTER SKID, SEE DETAIL 'X' ON SHEET M50X.
12. FUEL OIL PIPING ROUTED TO CONNECT TO HEATING HOT WATER BOILERS. FUEL OIL CONNECTION APPURTENANCES PROVIDED BY BOILER MANUFACTURER. SEE SHEET M312 FOR DETAIL.
13. HHWS/R AND CHWS/R PIPING CONTINUES ONTO EQUIPMENT MEZZANINE. SEE SHEET M402' FOR CONTINUATION.
14. 6" REFRIGERANT SRV RELIEF PIPING THROUGH WALL. FLASH AND SEAL PENETRATION.
15. 6" REFRIGERANT RELIEF PIPING DOWN TO CHILLER.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:34:08 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PIPING PLAN - AREA B

SHEET NUMBER

M305



FIRST FLOOR PIPING PLAN - AREA C

Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. PIPE SIZE ON DRAWING FOR CHEMICAL TREATMENT PIPING IS SIZE OF PVC CONDUIT PIPING. SEE CHEMICAL TREATMENT P&ID FOR SIZE OF CHEMICAL TUBING.
3. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR PAD CONSTRUCTION AND LOCATION.

(#) PLAN NOTES:

1. HHWS/R AND CHWS/R PIPING CONNECTIONS TO FCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM FCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
2. CHWS/R PIPING CONNECTIONS TO BCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
3. STEAM BOILER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT STEAM AND FEEDWATER PIPING TO BOILER, SEE DETAIL 'X' ON SHEET M50X.
4. RO WATER FILTRATION SKID POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT HHW PIPING TO FILTER SKID, SEE DETAIL 'X' ON SHEET M50X.
5. FUEL OIL PIPING ROUTED TO CONNECT TO STEAM BOILERS. FUEL OIL CONNECTION APPURTENANCES PROVIDED BY BOILER MANUFACTURER. SEE SHEET M312 FOR DETAIL.
6. STEAM PRESSURE REDUCING STATION TO 10 PSIG.
7. STEAM VENTS UP TO SECOND FLOOR. SEE M313 FOR CONTINUATION.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PIPING PLAN - AREA C

SHEET NUMBER

M306



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:34:19 PM AESI Proj. No.: 21-154


0 1/2" 1" 2"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.


(#) PLAN NOTES:

1. FUEL OIL TO GENERATOR DAY TANK ROOMS. SEE M311 FOR CONTINUATION ABOVE.
2. FUEL OIL 3" SUPPLY AND RETURN LINES FROM UNDERGOUND ROUTING FROM OUTSIDE BURIED TANKS. SEE SHEET M303 FOR CONTINUATION.
3. HHWS/R AND CHWS/R PIPING CONNECTIONS TO FCU. SEE DETAIL '2' ON H502. ROUTE CONDENSATE FROM FCU TO NEAREST DRAIN AS SHOWN. SEE DETAIL '2' ON H501.
4. HHWS/R PIPING CONNECTIONS TO REHEAT COIL. SEE DETAIL '2' ON H502.
5. MAKE-UP WATER CONNECTION. SEE P303 FOR CONTINUATION.
6. CTWS/R UP TO SECOND FLOOR. SEE M314 FOR CONTINUATION.
7. TOWER WATER PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CTW PIPING TO PUMP, SEE DETAIL 'X' ON SHEET M50X.
8. HEAT RECOVERY CHILLER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO CHILLER, SEE DETAILS '1' AND '3' ON SHEET M504. CONNECT HHW PIPING TO CHILLER, SEE DETAILS '2' AND '4' ON SHEET M504.
9. CENTRIFUGAL CHILLER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO CHILLER, SEE DETAILS '2' AND '3' ON SHEET M503. CONNECT CTW PIPING TO CHILLER, SEE DETAILS '1' AND '4' ON SHEET M503.
10. FUEL OIL TRANSFER PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT FUEL PIPING TO PUMP, SEE SHEET M712 FOR PIPING DETAILS.
11. FUEL OIL POLISHING FILTER SKID POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT FUEL PIPING TO PUMP, SEE SHEET M712 FOR PIPING DETAILS.
12. 2" ACID AND 1-1/4" BLEACH CHEMICAL TREATMENT PIPING UP THROUGH SECOND FLOOR CHASE. SEE SHEET 314 FOR CONTINUATION.
13. 6" REFRIGERANT RELIEF PIPING DOWN TO CHILLER.
14. 8" CTW MAKE-UP WATER.
15. 5" CTW BLOW DOWN PIPE.
16. 6" REFRIGERANT SRV RELIEF PIPING THROUGH WALL. FLASH AND SEAL WALL PENETRATION.
17. GRISWOLD QUICKSET BALANCING VALVE.
18. 3" REFRIGERANT SRV RELIEF PIPING THROUGH WALL. FLASHS ANS SEAL WALL PENETRATION.
19. 3" REFRIGERANT RELIEF PIPING DOWN TO HRC CHILLER.



FIRST FLOOR PIPING PLAN - AREA D

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR PIPING PLAN - AREA D

SHEET NUMBER

M307

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:34:31 PM AESI Proj No: 21-154



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. PIPE SIZE ON DRAWING FOR CHEMICAL TREATMENT PIPING IS SIZE OF PVC CONDUIT PIPING. SEE CHEMICAL TREATMENT P&ID FOR SIZE OF CHEMICAL TUBING.

(#) PLAN NOTES:

1. PROVIDE THREE (3) CHEMICAL INJECTION QUILL ASSEMBLY WITH CHECK VALVE AND ISOLATION VALVE. STOP CHEMICAL PIPING CONDUIT PIPING 2 FEET BEFORE INJECTION QUILL TO ALLOW FOR REMOVAL OF QUILL FOR MAINTENANCE.
2. EQUIPMENT MOUTNED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR PAD CONSTRUCTION AND LOCATION.
3. HHWS/R AND CHWS/R PIPING CONNECTIONS TO BCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
4. CHWS/R PIPING CONNECTIONS TO BCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
5. TOWER WATER PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CTW PIPING TO PUMP, SEE DETAIL 'X' ON SHEET M50X.
6. CENTRIFUGAL CHILLER POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT CHW PIPING TO CHILLER, SEE DETAILS '2' AND '3' ON SHEET M503. CONNECT CTW PIPING TO CHILLER, SEE DETAILS '1' AND '4' ON SHEET M503.
7. 2" CTW PIPING ROUTED TO CHECMICAL TREATMENT SKIDS.
8. 1-1/2" BLEACH CHEMICAL TREATMENT PIPING CONNECTED TO CTW AT LOCATION INDICATED. SEE SHEET M708 FOR DETAIL.
9. HHWS/R AND CHWS/R PIPING CONTINUES ONTO EQUIPMENT MEZZANINE. SEE SHEET 'M402' FOR CONTINUATION.
10. CTW FLOW METER.
11. 6" REFRIGERANT RELIEF PIPING DOW TO CHILLER
12. GRISWOLD QUICKSET BALANCING VALVE.

FIRST FLOOR PIPING PLAN - AREA E

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:34:39 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PIPING PLAN - AREA E

SHEET NUMBER

M308



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR PAD CONSTRUCTION AND LOCAITON.

(#) PLAN NOTES:

1. ACID AND BLEACH PIPING TO BE HEAT TRACED AND INSULATED PER SPECIFICATIONS 230533 AND 230719. PIPING FLANGES TO HAVE CHEMICAL LEAK DETECTION SLEEVES PER SPECIFICATION 230293.18.
2. WALL MOUNTED TANK FILL STATION WITH LEVEL INDICATORS FOR ALL TANKS.
3. FUEL OIL TANK VENTS FROM BELOW. TERMINATE ABOVE FILL OPENING AT FILL STATION. PROVIDE TURN DOWN WITH INSECT SCREEN.
4. PROVIDE VEHICLE IMPACT PROTECTION FOR FILL STATION AND VENT LINES PER PROTECTIVE POST DETAIL ON SHEET C202.
5. PROVIDE VEHICLE IMPACT PROTECTION FOR FILL STATION TANKS PER PRTECTIVE POST DETAIL ON SHEET C202.

FIRST FLOOR PIPING PLAN - AREA G

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR PIPING PLAN - AREA G

SHEET NUMBER

M310

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:34:45 PM AESI Proj No: 21-154



SECOND FLOOR PIPING PLAN - AREA A

Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR PAD CONSTRUCTION AND LOCATION.

(#) PLAN NOTES:

1. HHWS/R AND CHWS/R PIPING CONNECTIONS TO FCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM FCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
2. HHWS/R PIPING CONNECTIONS TO UNIT HEATER. SEE DETAIL '8' ON SHEET H501.
3. HHWS/R PIPING CONNECTIONS TO VAV BOX. SEE DETAIL '2' ON SHEET H502.
4. HHWS/R AND CHWS/R PIPING CONNECTIONS TO CRAC UNIT. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM CRAC UNIT TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
5. REFRIGERANT PIPING FROM CRAC UNIT UP TO ACCU LOCATED ON ROOF. CONNECT TO UNIT PER MANUFACTURER INSTRUCTIONS. SEE SHEET M317 FOR CONTINUATION.
6. HHWS/R AND CHWS/R PIPING CONNECTIONS TO MAU. SEE DETAIL '1' ON SHEET H501. ROUTE CONDENSATE FROM MAU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
7. HHWS/R AND CHWS/R PIPING UP FROM FIRST FLOOR. SEE SHEET M304 FOR CONTINUATION.
8. FUEL OIL DAYTANK PUMP POSITIONED ON EQUIPMENT PAD AS INDICATED. CONNECT FUEL PIPING TO PUMP, SEE SHEET M712 FOR PIPING DETAILS.
9. 10. FUEL OIL PIPING ROUTED TO GENERATOR FUEL PUMP CONNECTION. CONNECT TO GENERATOR PER MANUFACTURER INSTRUCTIONS, SEE SHEET M712 FOR PIPING DETAILS.
10. CHILLED WATER EXPANSION TANKS POSITIONED AS INDICATED.
11. 3" CHILLED WATER EXPANSION TANK PIPE DOWN TO FIRST FLOOR.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PIPING PLAN - AREA A

SHEET NUMBER


M311



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:34:54 PM AESI Proj No: 21-154



SECOND FLOOR PIPING PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR CONSTRUCTION AND LOCATION.

(#) PLAN NOTES:

1. HHWS/R PIPING CONNECTIONS TO UNIT HEATER. SEE DETAIL '8' ON SHEET H501.
2. 2. FUEL OIL PIPING ROUTED TO GENERATOR FUEL PUMP CONNECTION. CONNECT TO GENERATOR PER MANUFACTURER INSTRUCTIONS, SEE SHEET M712 FOR PIPING DETAILS.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:34:58 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PIPING PLAN - AREA B

SHEET NUMBER

M312



SECOND FLOOR PIPING PLAN - AREA C


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR CONSTRUCTION AND LOCATION.

(#) PLAN NOTES:

1. HHWS/R AND CHWS/R PIPING CONNECTIONS TO FCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
2. HHWS/R PIPING CONNECTIONS TO UNIT HEATER. SEE DETAIL '8' ON SHEET H501.
3. HHWS/R PIPING CONNECTIONS TO VAV BOX. SEE DETAIL '2' ON SHEET H502.
4. STEAM VENT UP TO ROOF. SEE SHEET M319 FOR CONTINUATION.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PIPING PLAN - AREA C

SHEET NUMBER

M313


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:00 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. EQUIPMENT MOUNTED ON EQUIPMENT PLANS. COORDINATE WITH STRUCTURAL PLANS FOR CONSTRUCTION AND LOCATION.


(#) PLAN NOTES:

1. HHWS/R PIPING CONNECTIONS TO VAV BOX. SEE DETAIL '2' ON SHEET H502.
2. HHWS/R AND CHWS/R PIPING CONNECTIONS TO MAU. SEE DETAIL '1' ON SHEET H501. ROUTE CONDENSATE FROM MAU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
3. HHWS/R AND CHWS/R PIPING CONTINUES ONTO EQUIPMENT MEZZANINE. SEE SHEET 'M402' FOR CONTINUATION.
4. CTWS/R UP TO ROOF. SEE SHEET M320 FOR CONTINUATION.
5. CHWS/R UP TO ROOF. SEE SHEET M320 FOR CONTINUATION.
6. FUEL OIL TO GENERATOR DAY TANK ROOMS. SEE M307 FOR CONTINUATION BELOW.
7. PROVIDE 1" DRAIN/BLOW DOWN PIPE FROM FILTER TO FLOOR DRAIN.



SECOND FLOOR PIPING PLAN - AREA D

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR PIPING PLAN - AREA D

SHEET NUMBER

M314

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:04 PM AESI Proj. No: 21-154



SECOND FLOOR PIPING PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL DRAWINGS FOR PAD CONSTRUCTION AND LOCATION.

(#) PLAN NOTES:

1. HHWS/R PIPING CONNECTIONS TO VAV BOX. SEE DETAIL '2' ON SHEET H502.
2. FUEL OIL PIPING ROUTED TO GENERATOR FUEL PUMP CONNECTION. CONNECT TO GENERATOR PER MANUFACTURER INSTRUCTIONS. SEE SHEET M712 FOR PIPING DETAILS.
3. HHWS/R AND CHWS/R PIPING CONTINUES ONTO EQUIPMENT MEZZANINE. SEE SHEET 'M402' FOR CONTINUATION.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1) AESI Proj. No: 21-154
2/10/2023 2:35:11 PM

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PIPING PLAN - AREA E

SHEET NUMBER

M315



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
2. EQUIPMENT MOUNTED ON EQUIPMENT PADS. COORDINATE WITH STRUCTURAL PLANS FOR CONSTRUCTION AND LOCAITON.

(#) PLAN NOTES:

1. HHWS/R PIPING CONNECTIONS TO UNIT HEATER. SEE DETAL '8' ON SHEET H501.
2. HHWS/R PIPING CONNECTIONS TO VAV BOX. SEE DETAIL '2' ON SHEET H502.

SECOND FLOOR PIPING PLAN - AREA F

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR PIPING PLAN - AREA F

SHEET NUMBER

M316

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:13 PM AESI Proj No: 21-154
0 1/2" 1" 2"



GENERAL NOTES:

1. SEE M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. REFRIGERANT PIPING FROM ACCU DOWN TO CRAC UNIT LOCATED ON SECOND FLOOR. CONNECT TO UNIT PER MANUFACTURER INSTRUCTIONS. SEE SHEET M311 FOR CONTINUATION.

ROOF PIPING PLAN - AREA A

Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF PIPING PLAN - AREA A

SHEET NUMBER


M317



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:15 PM AESI Proj No: 21-154




ROOF PIPING PLAN - AREA C
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. STEAM VENT PIPING UP THROUGH ROOF AT LOCATION INDICTED. SEE SHEET M313 FOR CONTINUATION FROM SECOND FLOOR. VENT PIPING SHALL TERMINATE APPROXIMATELY 23' ABOVE ROOF.
2. STEAM VENT SILENCER MOUNTED ON ROOF AT LOCATION INDICATED. STEAM VENT PIPING CONTINUES UP FROM SECOND FLOOR BELOW, SEE SHEET M313 FOR CONTINUATION. EXTEND 14" VENT OFF TOP OF SILENCER. 14" EXTENSION TO TERMINATE AT APPROXIMATELY 23' ABOVE ROOF.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF PIPING PLAN - AREA C

SHEET NUMBER

M319

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:20 PM AESI Proj No: 21-154



ROOF PIPING PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. TOWER WATER BASIN SWEEP PIPING UP TO COOLING TOWER BASINS ABOVE. REFER TO COOLING TOWER MANUFACTURER FOR PIPING CONNECTION DETAILS.
2. BUTTERFLY ISOLATION VALVE AND MOTOR CONTROL VALVE IN VERTICAL PIPE.
3. BUTTERFLY ISOLATION VALVE IN VERTICAL PIPE.
4. COOLING TOWER SUPPLY PIPING DOWN FROM COOLING TOWER ABOVE. REFER TO COOLING TOWER MANUFACTURER FOR PIPING CONNECTION DETAILS.
5. COOLING TOWER RETURN PIPING UP TO COOLING TOWER ABOVE. REFER TO COOLING TOWER MANUFACTURER FOR PIPING CONNECTION DETAILS.
6. COOLING TOWER BASIN EQUALIZER PIPING DOWN FROM COOLING TOWER ABOVE. REFER TO COOLING TOWER MANUFACTURER FOR PIPING CONNECTION DETAILS.
7. 48" COOLING TOWER SUPPLY AND RETURN WATER PIPING DOWN THROUGH ROOF TO SECOND AND FIRST FLOORS BELOW. SEE SHEET M314 FOR CONTINUATION. FLASH AND SEAL ROOF PENETRATIONS.
8. 6" COOLING TOWER BASIN SWEEP PIPING DOWN THROUGH ROOF TO SECOND AND FIRST FLOORS BELOW. SEE SHEET M314 FOR CONTINUATION. FLASH AND SEAL ROOF PENETRATIONS.
9. HHWS/R AND CHWS/R PIPING CONNECTIONS TO BCU. SEE DETAIL '2' ON SHEET H502. ROUTE CONDENSATE FROM BCU DOWN TO FLOOR BELOW. SEE SHEET H314 FOR CONTINUATION. SEE DETAIL '2' ON SHEET H501.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF PIPING PLAN - AREA D

SHEET NUMBER

M320

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:23 PM AESI Proj. No: 21-154



ROOF PIPING PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE M001 FOR SYMBOLS AND ABBREVIATIONS.

PLAN NOTES:

1. TOWER WATER BASIN SWEEP PIPING UP TO COOLING TOWER BASINS ABOVE. REFER TO COOLING TOWER MANUFACTURER FOR PIPING CONNECTION DETAILS.
2. COOLING TOWER SUPPLY PIPE CAPPED FOR FUTURE CONNECTION.
3. BUTTERFLY ISOLATION VALVE AND MOTOR CONTROL VALVE IN VERTICAL PIPE.
4. COOLING TOWER EQUALIZER PIPE CAPPED FOR FUTURE CONNECTION.
5. COOLING TOWER RETURN PIPE CAPPED FOR FUTURE CONNECTION.
6. COOLING TOWER SUPPLY PIPING DOWN FROM COOLING TOWER ABOVE, REFER TO COOLING TOWER MANUFACTURER FOR PIPING CONNECTION DETAILS.
7. COOLING TOWER RETURN PIPING UP TO COOLING TOWER ABOVE, REFER TO COOLING TOWER MANUFACTURER FOR PIPING CONNECTION DETAILS.
8. COOLING TOWER BASIN EQUALIZER PIPING DOWN FROM COOLING TOWER ABOVE. REFER TO COOLING TOWER MANUFACTURER FOR PIPING CONNECTION DETAILS.
9. BUTTERFLY ISOLATION VALVE IN VERTICAL PIPE.
10. SEASONAL COOLING TOWER ISOLATION VALVES.
11. COOLING TOWER SUPPLY PIPE FLANGED OFF FOR FUTURE CONNECTION.
12. COOLING TOWER RETURN PIPE FLANGED OFF FOR FUTURE CONNECTION.
13. COOLING TOWER EQUALIZER PIPE FLANGED OFF FOR FUTURE CONNECTION.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:27 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ROOF PIPING PLAN - AREA E

SHEET NUMBER


M321




3 **FIRST FLOOR BOILER HEAT RECOVERY SECTION LOOKING EAST**
Scale: 1/2" = 1'-0"



1 **FIRST FLOOR ACID MIXING AND TANKS SECTION LOOKING WEST**
Scale: 1/2" = 1'-0"



4 **FIRST FLOOR CHEMICAL TREATMENT SECTION LOOKING NORTH**
Scale: 1/2" = 1'-0"



2 **FIRST FLOOR CHEMICAL TREATMENT SECTION LOOKING WEST**
Scale: 1/4" = 1'-0"

(#) PLAN NOTES:

1. CHEMICAL TREATMENT ANALYZERS: COND, ORP, PH, PTSA.
2. CORROSION COUPON RACK.
3. PIPE SIZES NOTED ON DRAWING ARE FOR PVC CASING PIPE.
4. PIPE TO BE 1/2" FEP TUBINING IN 1-1/2" PVC CONDUITS USING SWEEPING ELBOWS.
5. PIPE TO BE 1/4" FEP TUBINING IN 1" PVC CONDUITS USING SWEEPING ELBOWS.
6. CORROSION COUPON RACK WITH CORROSION SENSOR.
7. BLEACH VENT BACK TO TOP OF BLEACH TANK.
8. WASTE DRAIN DOWN FROM COOLING TOWERS
9. CONNECT TO DOMESTIC WATER SERVICE
10. TANK LOADING LINE, VALVE, HOSE CONNECTION AND STAINLESS STEEL DRIP PAN.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ENLARGED MECHANICAL SECTIONS

SHEET NUMBER

M401


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:34 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

GENERAL NOTES:


1. GENERAL NOTES FOR INDIVIDUAL SHEETS.
2. NEXT LINE OF NOTES HAVE NO SPACING BETWEEN LINES.

(#) PLAN NOTES:


1. HHWS/R AND CHWS/R PIPING CONNECTIONS TO MAU. SEE DETAIL '1' ON SHEET H501. ROUTE CONDENSATE FROM MAU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
2. HHWS/R AND CHWS/R PIPING CONNECTIONS TO AHU. SEE DETAIL '1' ON SHEET H501. ROUTE CONDENSATE FROM AHU TO NEAREST FLOOR DRAIN AS SHOWN. SEE DETAIL '2' ON SHEET H501.
3. HHWS/R PIPING CONNECTIONS TO VAV BOX. SEE DETAIL '2' ON SHEET H502.



1 **FIRST FLOOR MEZZANINE PIPING PLAN**
Scale: 1/4" = 1'-0"



2 **SECOND FLOOR MEZZANINE 1 PIPING PLAN**
Scale: 1/4" = 1'-0"



3 **SECOND FLOOR MEZZANINE 2 PIPING PLAN**
Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:37 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

MECHANICAL MEZZANINE PLANS

SHEET NUMBER


M402



NOTES:

1. PAINT STRUCTURAL STEEL AND MISC. METAL PER PAINT SPECIFICATION.

2 **STEAM ANCHOR DETAIL**
Scale: 12" = 1'-0"



MAIN SIZE	DRIP LEG SIZE	DRIP LEG LENGTH	VALVE & DRAIN PIPE SIZES
2"	2"	10"	1"
3"	3"	10"	1"
4"	4"	10"	1"
6"	4"	10"	1"
8"	6"	12"	1 1/2"
10"	8"	15"	1 1/2"
12"	8"	18"	1 1/2"
14"	8"	21"	1 1/2"
16"	8"	24"	1 1/2"
18"	8"	27"	1 1/2"

3 **STEAM DRIP LEG DETAIL**
Scale: 12" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	


SHEET TITLE

MECHANICAL DETAILS


SHEET NUMBER

M501


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:37 PM AESI Proj No: 21-154
0 1/2" 1" 2"




11 **PIPE STAND DETAIL**
Scale: NONE




10 **REFRIGERANT VENT WALL PENETRATION DETAIL**
Scale: NONE




9 **TYPE 7 PIPE SUPPORT DETAIL**
Scale: NONE



6 **ELBOW HANGER DETAIL**
Scale: NONE




5 **TOWER WATER BLOWDOWN DETAIL**
Scale: NONE




NOTES:

1. FOR PIPE STANDS ON SECTIONS OF PIPE OTHER THAN ELBOW, SHAPE 8" SCH 40 CS PIPE TO FIT SYSTEM PIPE OR COMPONENT.


1 **FLOOR PIPE ELBOW SUPPORT DETAIL**
Scale: NONE



PLAN



FRONT VIEW




TRAPEZE HANGER DIMENSIONS					
PIPE SIZE	CHANNEL SIZE	PRIMARY HANGER RODS			SEISMIC ROD SIZE
		SIZE	SPACING	CHANNEL SPACERS	
48"	C10 X 15.3	1 1/2"	60"	2"	5/8"
42"	C10 X 15.3	1 1/2"	54"	2"	5/8"
36"	C10 X 15.3	1/2"	48"	2"	5/8"
30"	C6 X 8.2	1"	42"	2"	1/2"
24"	C6 X 8.2	1"	36"	2"	1/2"
EXPANSION TANKS	C4 X 5.4	1/2"	70"	1"	3/8"


NOTES:

1. HANGER SYMBOLS USED ON PLANS
   - (A) - SIMPLE TRAPEZE HANGER WITH NO SEISMIC BRACING
   - (A) - TRAPEZE HANGER WITH TRANSVERSE BRACING ONLY
   - (A) - TRAPEZE HANGER WITH TRASVERSE AND LONGITUDINAL BRACING
2. CHANNEL SPACERS INDICATED IN SCHEDULE ARE S40 PIPE
3. ROOF STEEL SHOWN LEVEL ON THIS DWG ACTUALLY HAS GRADUAL SLOPE

12 **TRAPEZE HANGER DETAIL**
Scale: NONE




7 **H-3 & H-4 PIPE HANGER DETAIL**
Scale: NONE



ELEVATION

NOTE
1.ROOFING MEMBRANE BY OTHERS


2 **ROOF PENETRATION COLD PIPE NO INSULATION DETAIL**
Scale: NONE




NOTES:

1. THE FLEXIBLE STEEL CONNECTOR SHALL BE STAINLESS STEEL, TYPE MFP, STYLE HNE, FLEXIBLE PUMP CONNECTOR VIBRATION MOUNTING AND CONTROL, INC., OR AN APPROVED EQUAL.
2. THE RELIEF VALVE WILL BE PROVIDED BY THE CONTRACTOR AND INSTALLED BY THE CONTRACTOR.


3 **REFRIGERANT RUPTURE DISK DETAIL**
Scale: NONE



13 **AUTOMATIC AIR VENT DETAIL**
Scale: NONE



8 **H-2 PIPE HANGER DETAIL**
Scale: NONE



NOTES:

1. TANK CONNECTION LOCATIONS MAY VARY DEPENDING ON TANK SIZE AND MODEL.
2. PROVIDE ANTI-THERMOSYPHON LOOP TO PREVENT GRAVITY HEATING OF TANK. 12" MIN. DROP.

4 **EXPANSION TANK PIPING DETAIL**
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

MECHANICAL DETAILS


SHEET NUMBER

M502

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:38 PM AESI Proj. No: 21-154
0 1/2" 1" 2"




4 **Chiller - CTWS&R (TYP)**
Scale: 3/8" = 1'-0"



1 **Chiller - CTWS&R (TYP)**
Scale:

2 **Chiller - CHWS&R (TYP)**
Scale:



3 **Chiller CHWS&R (TYP)**
Scale: 3/8" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:44 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


MECHANICAL EQUIPMENT DETAILS

SHEET NUMBER


M503




1 **HRC - CHWS&R (TYP)**
Scale: 3/8" = 1'-0"



3 **HRC - CHWS&R (TYP)**
Scale:



2 **HRC - HHWS&R (TYP)**
Scale: 3/8" = 1'-0"



4 **HRC - HHWS&R (TYP)**
Scale:

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:50 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

MECHANICAL EQUIPMENT DETAILS

SHEET NUMBER

M504

COOLING TOWER SCHEDULE

NOTES:
1. TWO (2) LADDERS WITH SAFETY CAGE TO ACCESS TOP OF TOWERS FROM COOLING TOWER ACCESS PLATFOMS.
2. SAFETY RAILING AROUND FAN DECK AT TOP OF TOWER.
3. FAN DECK EXTENSION PLATFORM.
4. INTERNAL ACCESS WALKWAY THROUGH CENTER OF TOWERS WITH ACCESS DOORS ON EACH END OF TOWER CELLS. INTERNAL FAN MAINTENANCE PLATFORM WITH INTERNAL ACCESS LADDER.
5. 18" BOTTOM FLANGED RETURN PIPING TO INTERNAL TOWER RETURN PIPE. INCLUDES PIPING THRU TOWER AND OVER TOP DECK TO DISTRIBUTION NOZZLES. INTERNAL PIPING SHALL BE SCH 40 HDPE.
6. 2" MOTORIZED FILL VALVE FOR EACH BASIN. LOW WATER AND HIGH WATER LEVEL ALARM FOR EACH COLLECTION BASIN.
7. TWO (2) 18" EQUALIZER PIPE CONNECTION(S) OUT BOTTOM OF TOWER BASINS.
8. PVC FILL WITH INTEGRAL LOUVERS.
9. FAN VELOCITY RECOVERY STACK.
10. LOW OIL LEVEL SWITCH FOR EACH GEAR DRIVE.
11. SOLID STATE FAN VIBRATION SWITCH AND TRANSMITTER FOR EACH FAN.
12. BASIN TEMPERATURE SENSOR FOR EACH BASIN.
13. BASE BID; 300 SERIES STAINLESS STEEL HOT WATER AND COLLECTION WATER BASIN WITH STAINLESS STEEL FRAME. STAINLESS STEEL INTERNAL WALKWAYS, LADDERS, HANDRAILS AND PLATFORMS. GALVANIZED STEEEL CASING, EXTERNAL FAN DECK PLATFORMS, LADDRS, AND HANDRAILS.
14. ALTERNATE BID-1 ; ALL 300 SERIES STAINLESS STEEL CONSTRUCTION ,HOT WATER AND COLLECTION WATER BASINS, STAINLESS STEEL FRAME, STAINLESS STEEL CASING, STAINLESS STEEL INTERNAL WALKWAYS, LADEERS, HAINRAILS AND PLATFORMS. GALVANIZED STEEL EXTERNAL FAN DECK HANDRAILS.
15. ALTERNATE BID-X ; PROVIDE FAN DECK LEVEL INTERCONNECTION PLATFORMS WITH HAINRAILS BETWEEN COOLING TOWER CELLS.
16. TOWER MANUFACTURER TO PROVIDE 60 kW TOWER BASIN HEATERS WITH REMOTE TEST AND MONITORING OF HEATING ELEMENTS.

			DESIGN CRITERIA						INLET		OUTLET		FAN(S)					FAN MOTOR(S)								FAN MOTOR(S)				FAN ELECTRICAL DATA			ELECTRIC BASIN HEATER							BASIN HEATER					BASIS OF DESIGN		MISCELLANEOUS				
UNIT TAG	LOCATION	TYPE	CAPACITY	HEAT REJECTION (BTU/HR)	EWB	FLOW	EWT	LWT	SIZE	LOCATION	SIZE	LOCATION	NO.	AIRFLOW	DRIVE TYPE	DIA	FAN SPEED RPM	NO. MOTORS	HP	BHP	RPM	VOLTS	PH	Hz	FLA	MCA	MOCP	MOTOR TYPE	DISC SW BY	STARTER TYPE	STARTER BY	NO OF HEATERS	KW PER HEATER	VOLTS	PH	HZ	DESIGN AIR TEMP	BASIN TEMP	FLA	MCA	MOCP	DISCONNECT SWITCH BY SECONDARY	CONTROL BY SECONDARY	MANUFACTURER	MODEL NO.	LENGTH	WIDTH	HEIGHT	SHIPPING WEIGHT	OPERATING WEIGHT	NOTES
CT-1	ROOF	CROSSFLOW	2,000	30,000,000	78.0 °F	6,000 GPM	95.0 °F	85.0 °F	18"	BOTTOM	24"	BOTTOM	1	552,900 CFM	GEAR	19'	202	1	125	110.1	1,800	480 V	3	60 Hz	151 A	0 A	0 A	TEFC	EC	VFD	EC	4	15	480 V	3	60 Hz	-20.0 °F	40.0 °F	78 A	0 A	0 A	EC	MFG	MARLEY	NC8422YAN1	22' - 4 3/4"	29' - 6"	27' - 0 1/16"	44,278 lb	103,800 lb	2, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16
CT-2	ROOF	CROSSFLOW	2,000	30,000,000	78.0 °F	6,000 GPM	95.0 °F	85.0 °F	18"	BOTTOM	24"	BOTTOM	1	552,900 CFM	GEAR	19'	202	1	125	110.1	1,800	480 V	3	60 Hz	151 A	0 A	0 A	TEFC	EC	VFD	EC	4	15	480 V	3	60 Hz	-20.0 °F	40.0 °F	78 A	0 A	0 A	EC	MFG	MARLEY	NC8422YAN1	22' - 4 3/4"	29' - 6"	27' - 0 1/16"	44,278 lb	103,800 lb	2, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16
CT-3	ROOF	CROSSFLOW	2,000	30,000,000	78.0 °F	6,000 GPM	95.0 °F	85.0 °F	18"	BOTTOM	24"	BOTTOM	1	552,900 CFM	GEAR	19'	202	1	125	110.1	1,800	480 V	3	60 Hz	151 A	0 A	0 A	TEFC	EC	VFD	EC	4	15	480 V	3	60 Hz	-20.0 °F	40.0 °F	78 A	0 A	0 A	EC	MFG	MARLEY	NC8422YAN1	22' - 4 3/4"	29' - 6"	27' - 0 1/16"	44,278 lb	103,800 lb	2, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16
CT-4	ROOF	CROSSFLOW	2,000	30,000,000	78.0 °F	6,000 GPM	95.0 °F	85.0 °F	18"	BOTTOM	24"	BOTTOM	1	552,900 CFM	GEAR	19'	202	1	125	110.1	1,800	480 V	3	60 Hz	151 A	0 A	0 A	TEFC	EC	VFD	EC	4	15	480 V	3	60 Hz	-20.0 °F	40.0 °F	78 A	0 A	0 A	EC	MFG	MARLEY	NC8422YAN1	22' - 4 3/4"	29' - 6"	27' - 0 1/16"	44,278 lb	103,800 lb	2, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16
CT-5	ROOF	CROSSFLOW	2,000	30,000,000	78.0 °F	6,000 GPM	95.0 °F	85.0 °F	18"	BOTTOM	24"	BOTTOM	1	552,900 CFM	GEAR	19'	202	1	125	110.1	1,800	480 V	3	60 Hz	151 A	0 A	0 A	TEFC	EC	VFD	EC	4	15	480 V	3	60 Hz	-20.0 °F	40.0 °F	78 A	0 A	0 A	EC	MFG	MARLEY	NC8422YAN1	22' - 4 3/4"	29' - 6"	27' - 0 1/16"	44,278 lb	103,800 lb	2, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16
CT-6	ROOF	CROSSFLOW	2,000	30,000,000	78.0 °F	6,000 GPM	95.0 °F	85.0 °F	18"	BOTTOM	24"	BOTTOM	1	552,900 CFM	GEAR	19'	202	1	125	110.1	1,800	480 V	3	60 Hz	151 A	0 A	0 A	TEFC	EC	VFD	EC	4	15	480 V	3	60 Hz	-20.0 °F	40.0 °F	78 A	0 A	0 A	EC	MFG	MARLEY	NC8422YAN1	22' - 4 3/4"	29' - 6"	27' - 0 1/16"	44,278 lb	103,800 lb	2, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16

CHILLER SCHEDULE

NOTES:
1. UNIT MOUNTED 4160 V AUTO TRANSFORMER AND CONTROL PANEL.
2. SEISMIC VIBRATION ISOLATORS AT CHILLER SUPPORTS
3. TWP STAGE VSD MAGNETIC BEARING CENTRIFUGAL.
4. 150# ASME DESIGN, HINGED COVER MARINE WATER BOXES ON BOTH EVAPORATORS AND CONDENSERS. HINGED COVERS ON EVAPORATORS AND CONDENSERS OPPOSITE END OF MARINE WATER BOXES.
5. UNIT MOUNTED 460 V VFD AND CONTROL PANEL.

						EVAPORATOR						EVAPORATOR			CONDENSER							COMPRESSOR																BASIS OF DESIGN			
UNIT TAG	LOCATION	TOTAL POWER KW	COOLING NPLV.IP KW/TON	CHILLER HEATING COP.H KW/KW	HEATING AND COOLING COP.SHC KW/KW	TONS	FLUID	FOULING FACTOR HR-SQFT DEG F/BTU	NO. OF PASSES	FLOW	GPM MIN	EWT	LWT	WATER PRESS DROP	FLUID	FOULING FACTOR HR-SQFT DEG F/HR	NO OF PASSES	FLOW	GPM SECONDARY	EWT	LWT	WATER PRESS DROP	TYPE	QTY.	REFRIG.TYPE	REFRIGERANT CHARGE	NO. OF STAGES	MOTOR LRA	FLA	MCA	MOP	VOLTS	PH	Hz	DISC SW BY	STARTER BY	STARTER TYPE	EM. POWER	CONTROL TYPE	MANUFACTURER	MODEL NO.	OPERATING WEIGHT	NOTES
CH-1	CHILLER PLANT 114	1217	0.5066	N/A	N/A	2000	CHW	0.0004	2	3000 GPM	1122 GPM	58.0 °F	42.0 °F	9.06 FT	CTW	0.00025	2	6000 GPM	2316 GPM	85.0 °F	95.0 °F	22.9 FT	CENTRIFUGAL	1	R-12332D	2950.00 lb	2	994	194 A	242 A	390 A	4160 V	1	60 Hz	MFG	MFG	AUTO TRANSFORMER	Y	DAC	TRANE	CVHW	73,027 lb	1, 2, 4
CH-2	CHILLER PLANT 114	1217	0.5066	N/A	N/A	2000	CHW	0.0004	2	3000 GPM	1122 GPM	58.0 °F	42.0 °F	9.06 FT	CTW	0.00025	2	6000 GPM	2316 GPM	85.0 °F	95.0 °F	22.9 FT	CENTRIFUGAL	1	R-12332D	2950.00 lb	2	994	194 A	242 A	390 A	4160 V	1	60 Hz	MFG	MFG	AUTO TRANSFORMER	Y	DAC	TRANE	CVHW	73,027 lb	1, 2, 4
CH-3	CHILLER PLANT 114	1217	0.5066	N/A	N/A	2000	CHW	0.0004	2	3000 GPM	1122 GPM	58.0 °F	42.0 °F	9.06 FT	CTW	0.00025	2	6000 GPM	2316 GPM	85.0 °F	95.0 °F	22.9 FT	CENTRIFUGAL	1	R-12332D	2950.00 lb	2	994	194 A	242 A	390 A	4160 V	1	60 Hz	MFG	MFG	AUTO TRANSFORMER	Y	DAC	TRANE	CVHW	73,027 lb	1, 2, 4
CH-4	CHILLER PLANT 114	1217	0.5066	N/A	N/A	2000	CHW	0.0004	2	3000 GPM	1122 GPM	58.0 °F	42.0 °F	9.06 FT	CTW	0.00025	2	6000 GPM	2316 GPM	85.0 °F	95.0 °F	22.9 FT	CENTRIFUGAL	1	R-12332D	2950.00 lb	2	994	194 A	242 A	390 A	4160 V	1	60 Hz	MFG	MFG	AUTO TRANSFORMER	Y	DAC	TRANE	CVHW	73,027 lb	1, 2, 4
CH-5	CHILLER PLANT 114	1217	0.5066	N/A	N/A	2000	CHW	0.0004	2	3000 GPM	1122 GPM	58.0 °F	42.0 °F	9.06 FT	CTW	0.00025	2	6000 GPM	2316 GPM	85.0 °F	95.0 °F	22.9 FT	CENTRIFUGAL	1	R-12332D	2950.00 lb	2	994	194 A	242 A	390 A	4160 V	1	60 Hz	MFG	MFG	AUTO TRANSFORMER	Y	DAC	TRANE	CVHW	73,027 lb	1, 2, 4
CH-6	CHILLER PLANT 114	1217	0.5066	N/A	N/A	2000	CHW	0.0004	2	3000 GPM	1122 GPM	58.0 °F	42.0 °F	9.06 FT	CTW	0.00025	2	6000 GPM	2316 GPM	85.0 °F	95.0 °F	22.9 FT	CENTRIFUGAL	1	R-12332D	2950.00 lb	2	994	194 A	242 A	390 A	4160 V	1	60 Hz	MFG	MFG	AUTO TRANSFORMER	Y	DAC	TRANE	CVHW	73,027 lb	1, 2, 4
HRC-1	CHILLER PLANT 114	329.7	0.3790	4.18	N/A	300	CHW	0.0001	2	448 GPM	295 GPM	58.0 °F	42.0 °F	3.88 FT	CTW	0.00025	2	461 GPM	425 GPM	100.0 °F	120.0 °F	32.97 FT	VSD CENTRIFUGAL	1	R-5131	800.00 lb	2	1000	244 A	304 A	500 A	480 V	3	60 Hz	MFG	MFG	VFD	Y	DDC	TRANE	HDWA	16,564 lb	3, 4, 5
HRC-2	CHILLER PLANT 114	329.7	0.3790	4.18	N/A	300	CHW	0.0001	2	448 GPM	295 GPM	58.0 °F	42.0 °F	3.88 FT	CTW	0.00025	2	461 GPM	425 GPM	100.0 °F	120.0 °F	32.97 FT	VSD CENTRIFUGAL	1	R-5131	800.00 lb	2	1000	244 A	304 A	500 A	480 V	3	60 Hz	MFG	MFG	VFD	Y	DDC	TRANE	HDWA	16,564 lb	3, 4, 5
HRC-3	CHILLER PLANT 114	329.7	0.3790	4.18	N/A	300	CHW	0.0001	2	448 GPM	295 GPM	58.0 °F	42.0 °F	3.88 FT	CTW	0.00025	2	461 GPM	425 GPM	100.0 °F	120.0 °F	32.97 FT	VSD CENTRIFUGAL	1	R-5131	800.00 lb	2	1000	244 A	304 A	500 A	480 V	3	60 Hz	MFG	MFG	VFD	Y	DDC	TRANE	HDWA	16,564 lb	3, 4, 5
HRC-4	CHILLER PLANT 114	329.7	0.3790	4.18	N/A	300	CHW	0.0001	2	448 GPM	295 GPM	58.0 °F	42.0 °F	3.88 FT	CTW	0.00025	2	461 GPM	425 GPM	100.0 °F	120.0 °F	32.97 FT	VSD CENTRIFUGAL	1	R-5131	800.00 lb	2	1000	244 A	304 A	500 A	480 V	3	60 Hz	MFG	MFG	VFD	Y	DDC	TRANE	HDWA	16,564 lb	3, 4, 5
HRC-5	CHILLER PLANT 114	329.7	0.3790	4.18	N/A	300	CHW	0.0001	2	448 GPM	295 GPM	58.0 °F	42.0 °F	3.88 FT	CTW	0.00025	2	461 GPM	425 GPM	100.0 °F	120.0 °F	32.97 FT	VSD CENTRIFUGAL	1	R-5131	800.00 lb	2	1000	244 A	304 A	500 A	480 V	3	60 Hz	MFG	MFG	VFD	Y	DDC	TRANE	HDWA	16,564 lb	3, 4, 5

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY **AESI**	
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

MECHANICAL SCHEDULES

SHEET NUMBER

M601

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:52 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

CONTROL TYPE:

DDC	DIRECT DIGITAL CONTROL
HOA	HAND OFF AUTOMATIC
IC	INTEGRAL CONTROLS
IL	INTERLOCK WITH OTHER EQUIPMENT
PB	PUSH BUTTON
RC	RUNS CONSTANTLY
TC	TIME CLOCK
WS	WALL SWITCH
WSPL	WALL SWITCH WITH PILOT LIGHT

PUMP SCHEDULE

NOTES:
1. WITH OSHA COUPLING GUARD
2. 304 SS SHAFT
3. 300 PSI WORKING PRESSURE
4. 175 PSI WORKING PRESSURE

		DESIGN CRITERIA									MOTOR DATA								ELECTRICAL				BASIS OF DESIGN		
UNIT TAG	LOCATION	TYPE	MINIMUM SHUTOFF HEAD FT.	NPSHR MAX	PUMP BASIN RPM	FLOW	TDH	FLUID	MIN. FLUID TEMP.	MAX. FLUID TEMP.	MIN. IMPELLER DIA.	MIN. EFFICIENCY	BHP	HP	RPM	VOLTS	PH	FLA	MCA	MOCP	STARTER BY	STARTER TYPE	EM. POWER	CONTROL TYPE	MANUFACTURER	MODEL NO.	NOTES
CHWP-1	RECEIVING 105	BASE MOUNTED	303	9.36	1781	3000 GPM	252 FT	CHILLED WATER	42.0 °F	60.0 °F	17.5	82.1%	232	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-8x10x17.5B	1, 2, 3
CHWP-2	RECEIVING 105	BASE MOUNTED	303	9.36	1781	3000 GPM	252 FT	CHILLED WATER	42.0 °F	60.0 °F	17.5	82.1%	232	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-8x10x17.5B	1, 2, 3
CHWP-3	RECEIVING 105	BASE MOUNTED	303	9.36	1781	3000 GPM	252 FT	CHILLED WATER	42.0 °F	60.0 °F	17.5	82.1%	232	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-8x10x17.5B	1, 2, 3
CHWP-4	RECEIVING 105	BASE MOUNTED	303	9.36	1781	3000 GPM	252 FT	CHILLED WATER	42.0 °F	60.0 °F	17.5	82.1%	232	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-8x10x17.5B	1, 2, 3
CHWP-5	RECEIVING 105	BASE MOUNTED	303	9.36	1781	3000 GPM	252 FT	CHILLED WATER	42.0 °F	60.0 °F	17.5	82.1%	232	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-8x10x17.5B	1, 2, 3
CHWP-6	RECEIVING 105	BASE MOUNTED	303	9.36	1781	3000 GPM	252 FT	CHILLED WATER	42.0 °F	60.0 °F	17.5	82.1%	232	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-8x10x17.5B	1, 2, 3
CHWP-7	RECEIVING 105	BASE MOUNTED	303	9.36	1781	3000 GPM	252 FT	CHILLED WATER	42.0 °F	60.0 °F	17.5	82.1%	232	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-8x10x17.5B	1, 2, 3
CTWP-1	CHILLER PLANT 114	BASE MOUNTED	164	38.7	1724	6000 GPM	116 FT	CONDENSER WATER	55.0 °F	95.0 °F	13	81.6%	215	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-10X12X13.5 A	1, 2, 4
CTWP-2	CHILLER PLANT 114	BASE MOUNTED	164	38.7	1724	6000 GPM	116 FT	CONDENSER WATER	55.0 °F	95.0 °F	13	81.6%	215	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-10X12X13.5 A	1, 2, 4
CTWP-3	CHILLER PLANT 114	BASE MOUNTED	164	38.7	1724	6000 GPM	116 FT	CONDENSER WATER	55.0 °F	95.0 °F	13	81.6%	215	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-10X12X13.5 A	1, 2, 4
CTWP-4	CHILLER PLANT 114	BASE MOUNTED	164	38.7	1724	6000 GPM	116 FT	CONDENSER WATER	55.0 °F	95.0 °F	13	81.6%	215	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-10X12X13.5 A	1, 2, 4
CTWP-5	CHILLER PLANT 114	BASE MOUNTED	164	38.7	1724	6000 GPM	116 FT	CONDENSER WATER	55.0 °F	95.0 °F	13	81.6%	215	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-10X12X13.5 A	1, 2, 4
CTWP-6	CHILLER PLANT 114	BASE MOUNTED	164	38.7	1724	6000 GPM	116 FT	CONDENSER WATER	55.0 °F	95.0 °F	13	81.6%	215	250	1800	480 V	3	280 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC-10X12X13.5 A	1, 2, 4
HHWP-1	BOILER ROOM 109	BASE MOUNTED	277	10.1	1685	1000 GPM	245 FT	HEATING HOT WATER	60.0 °F	130.0 °F	16.5	73.5	84.1	125	1800	480 V	3	156 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC 4X8X17.5A	
HHWP-2	BOILER ROOM 109	BASE MOUNTED	277	10.1	1685	1000 GPM	245 FT	HEATING HOT WATER	60.0 °F	130.0 °F	16.5	73.5	84.1	125	1800	480 V	3	156 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC 4X6X17.5A	
HHWP-3	BOILER ROOM 109	BASE MOUNTED	277	10.1	1685	1000 GPM	245 FT	HEATING HOT WATER	60.0 °F	130.0 °F	16.5	73.5	84.1	125	1800	480 V	3	156 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC 4X6X17.5A	
HHWP-4	BOILER ROOM 109	BASE MOUNTED	277	10.1	1685	1000 GPM	245 FT	HEATING HOT WATER	60.0 °F	130.0 °F	16.5	73.5	84.1	125	1800	480 V	3	156 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC 4X6X17.5A	
HHWP-5	BOILER ROOM 109	BASE MOUNTED	277	10.1	1685	1000 GPM	245 FT	HEATING HOT WATER	60.0 °F	130.0 °F	16.5	73.5	84.1	125	1800	480 V	3	156 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC 4X6X17.5A	
HHWP-6	BOILER ROOM 109	BASE MOUNTED	277	10.1	1685	1000 GPM	245 FT	HEATING HOT WATER	60.0 °F	130.0 °F	16.5	73.5	84.1	125	1800	480 V	3	156 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	VSC 4X6X17.5A	
HRCWP-1	RECEIVING 105	BASE MOUNTED	157	14.5	1656	1400 GPM	107 FT	CHILLED WATER	42.0 °F	60.0 °F	13	77.9%	48.5	60	1800	480 V	3	75.5 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	E1510-5GB	1, 2, 4
HRCWP-2	RECEIVING 105	BASE MOUNTED	157	14.5	1656	1400 GPM	107 FT	CHILLED WATER	42.0 °F	60.0 °F	13	77.9%	48.5	60	1800	480 V	3	75.5 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	E1510-5GB	1, 2, 4
HRCWP-3	RECEIVING 105	BASE MOUNTED	157	14.5	1656	1400 GPM	107 FT	CHILLED WATER	42.0 °F	60.0 °F	13	77.9%	48.5	60	1800	480 V	3	75.5 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	E1510-5GB	1, 2, 4
HRHHWP-1	RECEIVING 105	BASE MOUNTED	145	12.8	1727	1800 GPM	115 FT	HEATING HOT WATER	60.0 °F	130.0 °F	11.875	84.6%	61.3	75	1800	480 V	3	91 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	E-1510-6G	1, 2, 4
HRHHWP-2	RECEIVING 105	BASE MOUNTED	145	12.8	1727	1800 GPM	115 FT	HEATING HOT WATER	60.0 °F	130.0 °F	11.875	84.6%	61.3	75	1800	480 V	3	91 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	E-1510-6G	1, 2, 4
HRHHWP-3	RECEIVING 105	BASE MOUNTED	145	12.8	1727	1800 GPM	115 FT	HEATING HOT WATER	60.0 °F	130.0 °F	11.875	84.6%	61.3	75	1800	480 V	3	91 A	0 A	0 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	E-1510-6G	1, 2, 4

CHEMICAL TANK SCHEDULE

NOTES:
1. TANK TO BE HEAT TRACED AND INSULATED
2. INCLUDE INTERSITAL LEAK DETECTOR
3. TANK TO HAVE INTEGRAL PUMP SHELF
4. INCLUDE NOZZLE ON TOP FOR LEVEL INDICATION
5. INCLUDE CHEMICALLY COMPATABLE NOZZLE ON TOP INLET PIPING AND BOTTOM OUTLET PIPING
6. INCLUDED WITH RO CIP SKID. INCLUDES TANK STAND, AND INLET AND OUTLET VALVES AND PIPING/HOSES FOR CLEANING RO UNIT.

					MIN. WATER TEMP.	MAX. WATER TEMP.		BASIS OF DESIGN		
UNIT TAG	LOCATION	UNIT TYPE	SYSTEM SERVED	UNIT VOLUME GALLONS			PRESS. AT TANK	MANUFACTURER	MODEL NO.	NOTES
ROT-1	BOILER ROOM 109	SINGLE WALL HDPE	RO WATER	3000.0 gal	60.0 °F	100.0 °F	14.6 psia	ASSMANN	ICT3000	4,5
ROT-2	BOILER ROOM 109	SINGLE WALL HDPE	RO WATER CIP	200.0 gal	60.0 °F	120.0 °F	14.6 psia	ASSMANN	IMT200	6
TK-1		DOUBLE WALL HDPE	ACID	1550.0 gal	60.0 °F	120.0 °F	14.6 psia	ASSMANN	IMT 1550	1,2,4,5
TK-2		DOUBLE WALL HDPE	BLEACH	1550.0 gal	60.0 °F	120.0 °F	14.6 psia	ASSMANN	IMT 1550	1,2,4,5
TK-3	RECEIVING 105	DOUBLE WALL HDPE	CSP-301	405.0 gal	60.0 °F	100.0 °F	14.6 psia	ASSMANN	IMT405	2,3
TK-4	RECEIVING 105	DOUBLE WALL HDPE	7424 MB	250.0 gal	60.0 °F	100.0 °F	14.6 psia	ASSMANN	IMT250	2,3
TK-5	RECEIVING 105	DOUBLE WALL HDPE	B104	250.0 gal	60.0 °F	100.0 °F	14.6 psia	ASSMANN	IMT250	2,3
TK-6	RECEIVING 105	DOUBLE WALL HDPE	B172	250.0 gal	60.0 °F	100.0 °F	14.6 psia	ASSMANN	IMT250	2,3
TK-7	RECEIVING 105	DOUBLE WALL HDPE	B-521-3	250.0 gal	60.0 °F	100.0 °F	14.6 psia	ASSMANN	IMT250	2,3
TK-8	RECEIVING 105	DOUBLE WALL HDPE	B-140-8	250.0 gal	60.0 °F	100.0 °F	14.6 psia	ASSMANN	IMT250	2,3

FLOW METERS

NOTES:
1. PROVIDE FLOW STRAIGHTENER WITH FLOW METER

UNIT TAG	UNIT SERVICE	UNIT TYPE	TEMPERATURE MAX	PIPE SIZE - INLET	METER SIZE	UNIT MANUFACTURER	UNIT MODEL NO.	NOTES
			-459.7 °F		3"			
FIT-CHM1	TOWER WATER	FLOW SWITCH	-459.7 °F		2"			
FIT-CHM2	TOWER WATER	FLOW SWITCH	-459.7 °F		1"			
FM			-459.7 °F		6"			
FM-1			-459.7 °F		8"			
FM-2	CONDNESATE	VORTEX SHEDDING	210.0 °F		3"	ENDRESS+HAUSER		

CHEMICAL PUMP SCHEDULE

NOTES:
1. INCLUDE FOOT VALVE AND DISCHARGE VALVE ACCESSORIES
2. PROVIDE PUMP WITH AUTOGASSSING VALVE

		DESIGN CRITERIA								MOTOR DATA								ELECTRICAL				BASIS OF DESIGN		
UNIT TAG	LOCATION	TYPE	FLOW	TDH	FLUID	MIN. FLUID TEMP.	MAX. FLUID TEMP.	MIN. IMPELLER DIA.	MIN. EFFICIENCY	BHP	HP	RPM	VOLTS	PH	FLA	MCA	MOCP	STARTER BY	STARTER TYPE	EM. POWER	CONTROL TYPE	MANUFACTURER	MODEL NO.	NOTES
CP-9	RECEIVING 105	INLINE	4800 gal/h	67.19 lb/in²	TOWER WATER	60.0 °F	120.0 °F			7	10	3600	480 V	3	14 A	30 A	30 A	TCC	VFD	NO	DCC	BELL & GOSSETT	E80 1.5x1.5x7C	
MP-1	RECEIVING 105	Metering Pump	3.8 gal/h	102 lb/in²	ACID	60.0 °F	100.0 °F				0.25		110 V	1	6 A	15 A	15 A	CHEM	PLUG	NO	DCC	PROMINENT	GAMMALX-071 5	1
MP-2	RECEIVING 105	Metering Pump	3.8 gal/h	102 lb/in²	BLEACH	60.0 °F	100.0 °F				0.25		110 V	1	6 A	15 A	15 A	CHEM	PLUG	NO	DCC	PROMINENT	GAMMALX-071 5	1,2
MP-3	RECEIVING 105	Metering Pump	3.8 gal/h	102 lb/in²	CSP-301	60.0 °F	100.0 °F				0.25		110 V	1	6 A	15 A	15 A	CHEM	PLUG	NO	DCC	PROMINENT	GAMMALX-071 5	1
MP-4	RECEIVING 105	Metering Pump	3.8 gal/h	102 lb/in²	7424 MB	60.0 °F	100.0 °F				0.25		110 V	1	6 A	15 A	15 A	CHEM	PLUG	NO	DCC	PROMINENT	GAMMALX-071 5	1
MP-5	RECEIVING 105	Metering Pump	1.03 gal/h	102 lb/in²	B104	60.0 °F	100.0 °F				0.25		110 V	1	6 A	15 A	15 A	CHEM	PLUG	NO	DCC	PROMINENT	CONCEPT B-0704	1
MP-6	RECEIVING 105	Metering Pump	1.03 gal/h	102 lb/in²	B172	60.0 °F	100.0 °F				0.25		110 V	1	6 A	15 A	15 A	CHEM	PLUG	NO	DCC	PROMINENT	CONCEPT B-0704	1
MP-7	RECEIVING 105	Metering Pump	1.03 gal/h	102 lb/in²	B-521-3	60.0 °F	100.0 °F				0.25		110 V	1	6 A	15 A	15 A	CHEM	PLUG	NO	DCC	PROMINENT	CONCEPT B-0704	1
MP-8	RECEIVING 105	Metering Pump	0.79 gal/h	145 lb/in²	B-140-8	60.0 °F	100.0 °F				0.25		110 V	1	6 A	15 A	15 A	CHEM	PLUG	NO	DCC	PROMINENT	CONCEPT B-1003	1

HOT WATER BOILER SCHEDULE

NOTES:
1. PROVIDE BOILER WITH STOP AND CHECK VALVE, WATER SAFETY RELIEF VALVES,
2. PROVIDE BOILER WITH 2" INSULATED DOUBLE WALL POSITIVE PRESSURE SPECIAL GAS VENT LISTED FOR CONDENSING APPLICATIONS. INNER LINER TO BE 29-4C STAINLESS STEEL OUTER JACKET TO BE ALUMINZED STEEL.
3. PROVIDE ROOM COMBUSTION AIR MAKEUP UNIT INTERLOCK WITH BOILER COMBUSTION AIR FAN. BOILER PREVENTED FROM FIRING UNLESS ROOM COMBUSTION AIR MAKEUP UNIT IS OPERATIONAL.
4. PROVIDE BOILER WITH NATURAL GAS PRIMARY BURNER, PRIMARY NATURAL GAS TRAINS, GAS REGULATORS AND ASSOCIATED CONTROLS.
5. PROVIDE BOILER WITH DUAL FUEL FIRING CONTROLS AND EQUIPMENT. SECONDARY FUEL TO BE LOW SULPHER #2 FUEL OIL. PROVIDE #2 OIL TRAIN, BURNER MOUNTED OIL PUMP, SECONDARY PROPANE FUELED PILOT LIGHT, AND ALL CONTROLS AND APPERTANANCES FOR DUAL FUEL USE.
6. PROVIDE BOILER CONTROL SYSTEM WITH BACNET AND WEB BASED CONNECTIVITY. CONTROLS TO ALLOW FOR ADJUSTMENT AND MONITOR BOILER OPERATION, ALARMS, AND STATUS.

				GAS PRESSURE										ELECTRICAL DATE							BASIS OF DESIGN		WEIGHT		
UNIT TAG	LOCATION	TYPE	FUEL	MIN.	MAX.	INPUT MBH	OUTPUT MBH	MIN. TURN DOWN	GPM	EWT	LWT	MAX. WATER P.D.	WATER VOLUME	RELIEF VALVE SETTING	STARTER BY	EM. POWER	FLA	MCA	MOCP	VOLTS	PH	MANUFACTURER	MODEL NO.	SHIPPING	OPERATING	NOTES
HHWB-1	BOILER ROOM 109	CONDENSING	NG AND FUEL OIL	1.4 psi	7 psi	10000	9400	5:1	630 GPM	100.0 °F	130.0 °F	5 psi	950.0 gal	160 psi	MANUF	Y	23 A	29 A	52 A	460 V	3	CLEAVER BROOKS	SFC 10000	17041 lb	24960 lb	1,2,3,4,5,6
HHWB-2	BOILER ROOM 109	CONDENSING	NG AND FUEL OIL	1.4 psi	7 psi	10000	9400	5:1	630 GPM	100.0 °F	130.0 °F	5 psi	950.0 gal	160 psi	MANUF	Y	23 A	29 A	52 A	460 V	3	CLEAVER BROOKS	SFC 10000	17041 lb	24960 lb	1,2,3,4,5,6
HHWB-3	BOILER ROOM 109	CONDENSING	NG AND FUEL OIL	1.4 psi	7 psi	10000	9400	5:1	630 GPM	100.0 °F	130.0 °F	5 psi	950.0 gal	160 psi	MANUF	Y	23 A	29 A	52 A	460 V	3	CLEAVER BROOKS	SFC 10000	17041 lb	24960 lb	1,2,3,4,5,6
HHWB-4	BOILER ROOM 109	CONDENSING	NG AND FUEL OIL	1.4 psi	7 psi	10000	9400	5:1	630 GPM	100.0 °F	130.0 °F	5 psi	950.0 gal	160 psi	MANUF	Y	23 A	29 A	52 A	460 V	3	CLEAVER BROOKS	SFC 10000	17041 lb	24960 lb	1,2,3,4,5,6
HHWB-5	BOILER ROOM 109	CONDENSING	NG AND FUEL OIL	1.4 psi	7 psi	10000	9400	5:1	630 GPM	100.0 °F	130.0 °F	5 psi	950.0 gal	160 psi	MANUF	Y	23 A	29 A	52 A	460 V	3	CLEAVER BROOKS	SFC 10000	17041 lb	24960 lb	1,2,3,4,5,6
HHWB-6	BOILER ROOM 109	CONDENSING	NG AND FUEL OIL	1.4 psi	7 psi	10000	9400	5:1	630 GPM	100.0 °F	130.0 °F	5 psi	950.0 gal	160 psi	MANUF	Y	23 A	29 A	52 A	460 V	3	CLEAVER BROOKS	SFC 10000	17041 lb	24960 lb	1,2,3,4,5,6
HHWB-7	BOILER ROOM 109	CONDENSING	NG AND FUEL OIL	1.4 psi	7 psi	10000	9400	5:1	630 GPM	100.0 °F	130.0 °F	5 psi	950.0 gal	160 psi	MANUF	Y	23 A	29 A	52 A	460 V	3	CLEAVER BROOKS	SFC 10000	17041 lb	24960 lb	1,2,3,4,5,6
HHWB-8	BOILER ROOM 109	CONDENSING	NG AND FUEL OIL	1.4 psi	7 psi	10000	9400	5:1	630 GPM	100.0 °F	130.0 °F	5 psi	950.0 gal	160 psi	MANUF	Y	23 A	29 A	52 A	460 V	3	CLEAVER BROOKS	SFC 10000	17041 lb	24960 lb	1,2,3,4,5,6

EXPANSION TANK SCHEDULE

NOTES:
1. SCHEDULE NOTES
2. SCHEDULE NOTES

							MAX. OPER. PRESS.				BASIS OF DESIGN		
UNIT TAG	LOCATION	SYSTEM SERVED	APPROX. SYSTEM VOLUME	MIN. WATER TEMP.	MAX. WATER TEMP.	PRESS. AT TANK	RELIEF VALVE	AT TANK	MIN. VOLUME	MIN. ACCEPT. VOLUME	MANUFACTURER	MODEL NO.	NOTES
ET-1	MECHANICAL 224	CHILLED WATER	350,000 gal	42.0 °F	110.0 °F	41 psi	0 psi	150 psi	660 gal	660 gal	BELL & GOSSETT	SERIES "B" MODEL NO. B-3500	
ET-2	MECHANICAL 224	CHILLED WATER	350,000 gal	42.0 °F	110.0 °F	0 psi	0 psi	150 psi	660 gal	660 gal	BELL & GOSSETT	SERIES "B" MODEL NO. B-3500	
ET-3	BOILER ROOM 109	HEATING HOT WATER	0 gal	60.0 °F	160.0 °F	0 psi	150 psi	0 psi	0 gal	0 gal	BELL & GOSSETT	SERIES "B" MODEL NO. B-5000	
ET-4	BOILER ROOM 109	HEATING HOT WATER	0 gal	60.0 °F	160.0 °F	0 psi	150 psi	0 psi	0 gal	0 gal	BELL & GOSSETT	SERIES "B" MODEL NO. B-5000	

STEAM BOILER SCHEDULE

NOTES:
1. PROVIDE BOILER WITH STOP AND CHECK VALVE, AND THREE STEAM SAFETY RELIEV VALVES SET AT 150 PSIG.
2. PROVIDE BOILER WITH 2" INSULATED DOUBLE WALL POSITIVE PRESSURE CHIMENY. INNER LINER TO BE 304 STAINLESS STEEL OUTER JACKET TO BE GALVANIZED STEEL.
3. PROVIDE ROOM COMBUSTION AIR MAKEUP UNIT INTERLOCK WITH BOILER COMBUSTIN AIR FAN. BOILER TO BE PREVENTED FROM FIRING UNLESS ROOM COMBUSTION AIR MAKEUP UNIT IS OPERATIONAL
4. PROVIDE BOILER WITH DDC FEEDWATER CONTROL BALL VALVE AND CONTROLLER. PROVIDE BOILER SIGHT GLASS WATER COLUMN WITH TWO LOW WATER CUTOUTS, LEVEL CONTROLLER, HIGH WATER CUTOUT, TEST /DRAIN VALVE, AND PRESSURE GAUGE.
5. PROVIDE BOILER BLOW DOWN CONTROL SYSTEM . SYSTEM TO INCLUDE STOP VALVE, SURFACE BLOW DOWN CONTROL VALVE, CONDUCTIVITY SENSOR AND DDC CONTROLLER. BOTTOM BLOWDOWN TO INCLUDE STOP VALVE AND BOTTOM BLOW DOWN VALVE.
6. ROVIDE BOILER WITH NATURAL GAS PRIMARY BURNER, PRIMARY NATURAL GAS TRAINS, GAS REGULATORS AND ASSOCIATED CONTROLS.
7. PROVIDE BOILER WITH DUAL FUEL FIRING CONTROLS AND EQUIPMENT. SECONDARY FUEL TO BE LOW SULPHER #2 FUEL OIL. PROVIDE #2 OIL TRAIN, BURNER MOUNTED OIL PUMP, SECONDARY PROPANE FUELED PILOT LIGHT, AND ALL CONTROLS AND APPERTANANCES
8. PROVIDE BURNER WITH 10:1 PARELLEL POSITIONING PRIMARY NATURAL GAS CONTROLS WITH OXYGEN TRIM. FUEL OIL CONTROLS TO HAVE 8:1 TURNDOWN.
9. PROVIDE BOILER CONTROL SYSTEM WITH BACNET AND WEB BASED CONNECTIVITY. CONTROLS TO ALLOW FOR ADJUSTMENT AND MONITOR BOILER OPERATION, ALARMS, AND STATUS.

				WORKING/ OPERATING PRESSURE	DESIGN PRESSURE		GAS PRESSURE						RELIEF VALVE SETTING	ELECTRICAL DATE							BASIS OF DESIGN		WEIGHT		
UNIT TAG	LOCATION	TYPE	BHP			FUEL	MIN.	MAX.	INPUT MBH	OUTPUT MBH	MIN. TURN DOWN	WATER VOLUME		STARTER BY	EM. POWER	FLA	MCA	MOCP	VOLTS	PH	MANUFACTURER	MODEL NO.	SHIPPING	OPERATING	NOTES
SB-1	BOILER ROOM 109	TWO PASS WETBACK FIRE TUBE STEAM BOILER	700	125 psi	150 psi	NG AND FUEL OIL	95 in-wg	127 in-wg	27568	23433	10:1	0.0 gal	150 psi	MANUFACTURER	YES	76 A	0 A	0 A	480 V	3	CLEAVER BROOKS	CBDEX-2D-700	38500.00 lb	63550.00 lb	1,2,3,4,5,6,7,8,9
SB-2	BOILER ROOM 109	TWO PASS WETBACK FIRE TUBE STEAM BOILER	700	125 psi	150 psi	NG AND FUEL OIL	95 in-wg	127 in-wg	27568	23433	10:1	0.0 gal	150 psi	MANUFACTURER	YES	76 A	0 A	0 A	480 V	3	CLEAVER BROOKS	CBDEX-2D-700	38500.00 lb	63550.00 lb	1,2,3,4,5,6,7,8,9
SB-3	BOILER ROOM 109	TWO PASS WETBACK FIRE TUBE STEAM BOILER	700	125 psi	150 psi	NG AND FUEL OIL	95 in-wg	127 in-wg	27568	23433	10:1	0.0 gal	150 psi	MANUFACTURER	YES	76 A	0 A	0 A	480 V	3	CLEAVER BROOKS	CBDEX-2D-700	38500.00 lb	63550.00 lb	1,2,3,4,5,6,7,8,9

HEAT EXCHANGER SCHEDULE - WATER TO WATER

NOTES:
1. PROVIDE WITH INSULATION BLANKET.
2. PROVIDE WITH ASME SECTION VIII DIVISION 1U STAMP.
3. PROVIDE 304 SS PORT STRAINER FOR EACH INLET PORT.
4. PROVIDE 3041 SS DRAIN PAN AND ELASTOMERIC THERMAL BREAK ISOLATION PADS UNDER HEAT EXCHANGER.

			HOT SIDE						COLD SIDE						HEAT TRANSFER (BTU/HR)	BASIS OF DESIGN		OPERATING WEIGHT	NOTES
UNIT TAG	LOCATION	UNIT TYPE	PLATE THICKNESS	MEDIA	FLOW	TEMP. IN	TEMP. OUT	MAX. PRESS. DROP	MEDIA	FLOW	TEMP. IN	TEMP. OUT	MAX. PRESS. DROP	MIN. SURFACE AREA	NO. OF PLATES		MANUFACTURER	MODEL		
HRC-HX-1	CHILLER PLANT 114	PLATE AND FRAME	0.02"	CONDENSED WATER	5400 GPM	98.0 °F	88.0 °F	11.5 ftH2O	TOWER WATER	5400 GPM	85.0 °F	95.0 °F	11.5 ftH2O	13901 ft²	617	26902	BELL & GOSSETT	AP201	46989.00 lb	

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: **AESI**
CHECKED BY: **AESI**
APPROVED BY: **Approver**
PROJECT NO.: **21-154**

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE: **MECHANICAL SCHEDULES**

SHEET NUMBER: **M602**

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:55 PM AESI Proj. No: 21-154

MISCELLANEOUS EQUIPMENT SCHEDULE

NOTES:
1. PROVIDE COMPLETE SYSTEM. USE PURGE VALVE WITHOUT BAGS IN BAG FILTER FIRST 60 DAYS AND THEN INSERT BAGS AND TURN OFF PURGE VALVE.

				MOTOR								ELECTRICAL DATA				BASIS OF DESIGN			
UNIT TAG	LOCATION	DESCRIPTION	CAPACITY	BHP	HP	RPM	VOLTS	PH	FLA	MCA	MOCP	STARTER BY	STARTER TYPE	EM. POWER	CONTROL TYPE	MANUFACTURER	MODEL NO.	DRY WEIGHT	NOTES
BAS PANEL	CONTROL 112				0	0	120 V	1	0 A	0 A	0 A							0.00 lb	
BAS PANEL	CONTROL ROOM 209				0	0	120 V	1	0 A	0 A	0 A							0.00 lb	
BAS PANEL	CUP EMERGENCY ELECTRICAL ROOM 215				0	0	120 V	1	0 A	0 A	0 A							0.00 lb	
CHW-FLTR-1	CHILLER PLANT 114	CHILLED WATER SIDE STREAM FILTER	1100 GPM	20	20	1750	460 V	3	26 A	33 A	40 A	E.C.	ACROSS THE LINE	NO	LOCAL WITH BMS ALARM	LAKOS	PACKAGED CENTRIFUGAL SEPARATOR. LAKOS MODEL #TBX-1100-SRV-TC SYSTEM WITH HTX-0500-TC SEPARATOR, AND SRV 816 WITH 74 MICRON FILTER BAG FILTER, AUTOMATIC PURGE VALVE AND DRY CONTACT DIFFERENTIAL PRESSURE SWITCH	2038.00 lb	1
CT-BS-FLTR-1	MECHANICAL 206	COOLING TOWER BASIN SWEEPER SYSTEM	610 GPM	15	15	1750	460 V	3	19 A	25 A	30 A	E.C.	ACROSS THE LINE	NO	LOCAL WITH BMS ALARM	LAKOS	PACKAGED CENTRIFUGAL SEPARATOR. LAKOS MODEL #eTBX-0610-SRV/ACP1 TC SYSTEM WITH eHTX-0260 SEPARATOR, SRV 833 WITH 74 MICRON FILTER BAG FILTER, AUTOMATIC PURGE VALVE AND DRY CONTACT DIFFERENTIAL PRESSURE SWITCH, AND MULTI-TOWER BASIN CLEANING KIT FOR THREE ONE CELL COOLING TOWERS	1553.00 lb	1
CT-BS-FLTR-2	MECHANICAL 206	COOLING TOWER BASIN SWEEPER SYSTEM	610 GPM	15	15	1750	460 V	3	19 A	24 A	30 A	E.C.	ACROSS THE LINE	NO	LOCAL WITH BMS ALARM	LAKOS	PACKAGED CENTRIFUGAL SEPARATOR. LAKOS MODEL #eTBX-0610-SRV/ACP1 TC SYSTEM WITH eHTX-0280 SEPARATOR, SRV 833 WITH 74 MICRON FILTER BAG FILTER, AUTOMATIC PURGE VALVE AND DRY CONTACT DIFFERENTIAL PRESSURE SWITCH, AND MULTI-TOWER BASIN CLEANING KIT FOR THREE ONE CELL COOLING TOWERS	1553.00 lb	1
CT-FLTR-1	CHILLER PLANT 114	COOLING TOWER SIDE STREAM FILTER	825 GPM	20	20	1250	460 V	3	26 A	33 A	40 A	E.C.	ACROSS THE LINE	NO	LOCAL WITH BMS ALARM	LAKOS	PACKAGED CENTRIFUGAL SEPARATOR. LAKOS MODEL #TBX-0825-SRV WITH HTX-0450 SEPARATOR, AND SRV 816 WITH 74 MICRON FILTER BAG FILTER, AUTOMATIC PURGE VALVE AND DRY CONTACT DIFFERENTIAL PRESSURE SWITCH	1973.00 lb	1
HHW-FLTR-1	BOILER ROOM 109	HEATING HOT WATER SIDE STREAM FILTER	825 GPM	20	20	1750	460 V	3	26 A	33 A	40 A	E.C.	ACROSS THE LINE	NO	LOCAL WITH BMS ALARM	LAKOS	PACKAGED CENTRIFUGAL SEPARATOR. LAKOS MODEL #TBX-0825-SRV WITH HTX-0450 SEPARATOR, AND SRV 816 WITH 74 MICRON FILTER BAG FILTER, AUTOMATIC PURGE VALVE AND DRY CONTACT DIFFERENTIAL PRESSURE SWITCH	1973.00 lb	1
REFRIGERANT MONITOR SYSTEM CONTROL PANEL	CHILLER PLANT 114				0	0	0 V	1	0 A	0 A	0 A							0.00 lb	

AIR VENT SCHEDULE

TAG NO.	LOCATION	SYSTEM SERVED	INLET SIZE (NPT)	VENT SIZE (NPT)	PRESSURE RATING (PSIG)	TEMP. RATING (DEG F)	DESCRIPTION	MFGR	MODEL #	NOTES
AV-1	TOP CHWR / R BRANCH DROP AT EACH CHILLER	CHILLED WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-2	HIGH POINTS IN CHW PUMP PIPING	CHILLED WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-3	HIGH POINTS IN CHWS / R PIPING	CHILLED WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-4	HIGH POINTS HX-1 CTWS / R	TOWER WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-5	HIGH POINTS BRANCH PIPING EACH CHILLER CTWS / R	TOWER WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-6	HIGH POINTS IN CHW PUMP PIPING	TOWER WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-7	HIGH POINT HX-1 HHWS & HHWR	HEATING HOT WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-8	HIGH POINT BRANCH PIPING EACH BOILER HHWS / R	HEATING HOT WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-9	HIGH POINTS IN HHW PUMP PIPING	HEATING HOT WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-10	HIGH POINTS IN HHWS / R PIPING	HEATING HOT WATER	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS
AV-11	HIGH POINTS IN SIDE STREAM FILTER PIPING	HHW, CHW, CTW	3/4"	1/4"	250	300	AUTOMATIC AIR VENT VALVE , CAST IRON BODY WITH STAINLESS STEEL FLOAT AND INTERNALS	HOFFMAN	792	MULTIPLE LOCATIONS

MISCELLANEOUS FUEL OIL EQUIPMENT SCHEDULE

NOTES:
1. NOTES
2. NOTES

					PUMP MOTOR									ELECTRICAL DATA				BASIS OF DESIGN			
UNIT TAG	SERVICE	SIZE	DESCRIPTION	PUMP/ACCESSORY DATA	QTY	HP	RPM	VOLTS	PH	Hz	FLA	MCA	MOCP	STARTER BY	STARTER TYPE	EM. POWER	CONTROL TYPE	MANUFACTURER	MODEL NO.	WEIGHT	NOTES
FO-DT-1	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-DT-2	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-DT-3	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-DT-4	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-DT-5	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-DT-6	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-DT-7	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-DT-8	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-DT-9	FUEL OIL - GENERATORS	250 GALLON	DAY TANK WITH LEVEL CONTROLLER AND GENERATOR TRANSFER PUMP	PROVIDE WITH 225 GPH FUEL TRANSFER PUMP TO FEED GENERATOR	1	0.25	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	DT-260-S-R-UL	2.94 lb	
FO-FLTR-1	FUEL OIL	1200 GPH FUEL POLISHING SKID WITH WASTE WATER REMOVAL SYSTEM (WR-01)	FUEL POLISHING SKID, FILTERS FUEL FROM TANK AND REMOVES MOISTURE.	PROVIDE WITH 1200 GPH PUMP TO PULL FUEL FROM STORAGE TANK	1	0.75	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	PF-505	0.00 lb	
FO-FLTR-2	FUEL OIL	1200 GPH FUEL POLISHING SKID WITH WASTE WATER REMOVAL SYSTEM (WR-01)	FUEL POLISHING SKID, FILTERS FUEL FROM TANK AND REMOVES MOISTURE.	PROVIDE WITH 1200 GPH PUMP TO PULL FUEL FROM STORAGE TANK	1	0.75	1725	120 V	1	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	PF-505	0.00 lb	
FO-P-1	FUEL OIL	1000 GPH	SIZED FOR 5 GENERATORS. FEEDS ONE DAY TANK ROOM ON THE SECOND FLOOR.		1	2	1140	460 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	ATPSF-206	0.00 lb	
FO-P-2	FUEL OIL	1000 GPH	SIZED FOR 6 GENERATORS. FEEDS ONE DAY TANK ROOM ON THE SECOND FLOOR.		1	2	1140	460 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	ATPSF-206	0.00 lb	
FO-P-3	FUEL OIL	800 GPH	SIZED FOR 2 FIRING STEAM BOILERS. FEEDS TO BOILER ROOM.		1	0.75	1140	460 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	ATPSF-202	0.00 lb	
FO-P-4	FUEL OIL	800 GPH	SIZED FOR 8 FIRING HHW BOILERS. FEEDS TO BOILER ROOM.		1	0.75	1140	460 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	PREFERRED MFG	ATPSF-202	0.00 lb	
FO-T-1	FUEL OIL	50,000 GALLON	BURIED DOUBLE WALL STORAGE TANK	PROVIDE INTERSTITIAL LEAK MONITORING	1	0	0	0 V	1	0 Hz	0 A	0 A	0 A					HIGHLAND TANK	50000HGDW144	0.00 lb	
FO-T-2	FUEL OIL	50,000 GALLON	BURIED DOUBLE WALL STORAGE TANK	PROVIDE INTERSTITIAL LEAK MONITORING	1	0	0	0 V	1	0 Hz	0 A	0 A	0 A					HIGHLAND TANK	50000HGDW144	0.00 lb	
FO-T-3	FUEL OIL	50,000 GALLON	BURIED DOUBLE WALL STORAGE TANK	PROVIDE INTERSTITIAL LEAK MONITORING	1	0	0	0 V	1	0 Hz	0 A	0 A	0 A					HIGHLAND TANK	50000HGDW144	0.00 lb	

MISCELLANEOUS STEAM EQUIPMENT SCHEDULE

NOTES:
1. NOTES
2. NOTES

						PUMP MOTOR										ELECTRICAL DATA				BASIS OF DESIGN			
UNIT TAG	LOCATION	SERVICE	SIZE	DESCRIPTION	PUMP/ACCESSORY DATA	QTY	BHP	HP	RPM	VOLTS	PH	Hz	FLA	MCA	MOCP	STARTER BY	STARTER TYPE	EM POWER	CONTROL TYPE	MANUFACTURER	MODEL NO.	WEIGHT	NOTES
BDS-1	BOILER ROOM 109	BLOW DOWN SEPARATOR	18 GALLON VERTICAL BLOWDOWN SEPPARATOR TANK WITH TANGENTIAL INLET, VENT, DRAIN, TANK DISCHARGE COOLING WATER CONTROLS	ASME 75 PSIG RATED CARBON STEEL BLOW DOWN SEPARATOR TANK NOMINAL 16" D X 26" H WITH 6" ANSI 150# TOP VENT , 4" ANSI 150# FLANGE BOTTOM DRAIN, 1-1/4" NPT TANGENTAL SIDE INLET WITH 316 SS WEAR PLATE. AND 1-1/2" ANGLE IRON SUPPORT LEGS	FLANGED DISCHARGE CONDENSATE COOLER ASSEMBLY TO INCLUDE THERMOMETER, 3/4" NPT COOLING WATER ADJSUTABLE CAPILARY TEMERATRUE CONTROL VALVE, 3/4" NPT COOLING WATER INLET CHECK VALVE AND STRAINER	0	0	0	0	0 V	1	0 Hz	0 A	0 A	0 A					CLEAVER BROOKS	BDS-A34B-150	9915.00 lb	
BHR-1	BOILER ROOM 109	BLOWDOWN HEAT RECOVERY	SIZE FOR 14 GPM MAX FLOW FOR THREE 700 HP BOILERS CONTINUOUS BLOWDOWN			1	0	0	0	0 V	1	0 Hz	0 A	0 A	0 A			NO		STICKLE STEAM SPECIALTIES	550-	640.00 lb	
CF-1	BOILER ROOM 109	DUPLEX CARBON FILTER SKID	65 GPM CONTINUOUS FLOW, DUPLEX SYSTEM WITH TWO 48"X60" TANKS	DUPLEX CARBON FILTER SKID WITH CONTROLS AND VALVES FOR REGENERATIONS	CONTROLS, SS EXTERNAL AND INTERNAL PIPING AND VALVES FOR REGENERATION	1	0	0	0	110 V	1	60 Hz	0 A	0 A	0 A			NO		MARLO	MFS-ACA-48		
CST-1	BOILER ROOM 109	CONDENSATE RETURN TANK AND PUMPS	1,200 GALLON HORIZONTAL ATMOSPHERIC STAINLESS STEEL FEED WATER TANK WITH TWO MULTI STAGE FEED WATER PUMPS WITH SIGHTGLASS, TANK MAKEUP WATER LEVEL CONTROLS, FEEDWATER PUMP SEQUENCING AND ALTERNATING CONTROLS, ALL PIPING, VENT, AND DRAIN CONNECTIONS	54" DIA. X 120" L 304 STAINLESS STEEL FEED WATER TANK ELEVATED ON STEEL ANGLE IRON FRAME WITH TWO BOILER FEED WATER PUMPS, STARTERS,PUMP CONTROLS, TANK LEVEL CONTROLS, TANLK LEVEL AND TEMPERATURE ALARMS AND SAFETIES. BOILER CONTROL PANEL CONTROL AND MONITORING OF TANK AND PUMP OPERATION	TWO B&G MODEL MULTI STAGE PUMPS EACH SIZED TO FEED DAEARATOR TANK FOR REDUNDANCY.	2	10	10	3550	460 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	CLEAVER BROOKS	SRG-1200-ADAC-1000	9915.00 lb	
CST-2	BOILER ROOM 109	CONDENSATE RETURN TANK AND PUMPS	1,200 GALLON HORIZONTAL ATMOSPHERIC STAINLESS STEEL FEED WATER TANK WITH TWO MULTI STAGE FEED WATER PUMPS WITH SIGHTGLASS, TANK MAKEUP WATER LEVEL CONTROLS, FEEDWATER PUMP SEQUENCING AND ALTERNATING CONTROLS, ALL PIPING, VENT, AND DRAIN CONNECTIONS	54" DIA. X 120" L 304 STAINLESS STEEL FEED WATER TANK ELEVATED ON STEEL ANGLE IRON FRAME WITH TWO BOILER FEED WATER PUMPS, STARTERS,PUMP CONTROLS, TANK LEVEL CONTROLS, TANLK LEVEL AND TEMPERATURE ALARMS AND SAFETIES. BOILER CONTROL PANEL CONTROL AND MONITORING OF TANK AND PUMP OPERATION	TWO B&G MODEL MULTI STAGE PUMPS EACH SIZED TO FEED DAEARATOR TANK FOR REDUNDANCY.	2	10	10	3550	460 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	CLEAVER BROOKS	SRG-1200-ADAC-1000	9915.00 lb	
DA-1	BOILER ROOM 109	DEAERATOR AND BOILER FEED WATER SYSTEM	1,100 GALLON HORIZONTAL ATMOSPHERIC STAINLESS STEEL FEED WATER TANK WITH THREE MULTI STAGE FEED WATER PUMPS, STEAM SPARGER FEED WATER HEATER WITH TEMPERATURE CONTROLS, SIGHTGLASS, TANK MAKEUP WATER LEVEL CONTROLS, FEEDWATER PUMP SEQUENCING AND ALTERNATING CONTROLS, ALL PIPING, VENT, AND DRAIN CONNECTIONS	54" DIA. X 120" L 304 STAINLESS STEEL FEED WATER TANK ELEVATED ON STEEL ANGLE IRON FRAME WITH THREE BOILER FEED WATER PUMPS, STARTERS,PUMP CONTROLS, TANK LEVEL CONTROLS,TANK TEMPERATURE CONTROLS, TANLK LEVELAND TEMPERATURE ALARMS AND SAFETIES. BOILER CONTROL PANEL CONTROL AND MONITORING OF TANK AND PUMP OPERATION	FOUR B&G MODEL MULTI STAGE PUMPS EACH SIZED TO FEED ONE BOILER AND ONE EXTRA FOR REDUNDANCY.	4	15	15	3550	460 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	CLEAVER BROOKS	SM-45-1105-ADC-1000	9915.00 lb	
RO-1	BOILER ROOM 109	REVERSE OSMOSIS SYSTEM	50 GPM RO SYSTEM, 66 GMP INLET, 16 GPM REJECT WITH CLEANING SYSTEM	50 GPM OUTLET REVERSE OSMOSIS UNIT	20 HP FEED PUMP, 5 MICRON CARTRIDGE PRE-FILTER, RO MEMBRANES WITH HOUSING, CONCENTRATE AND RECYCLE FLOW CONTROL VALVES, PLC WITH CONTOL PANEL, CONDUCTIVITY MONITOR, INTEGRAL CIP SKID WITH 5 HP PUMP	1	20	20	1800	480 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	NO	HOA	MARLO	MRO-72K-BH		
ROP-1A,1B	BOILER ROOM 109	DUPLEX RO TRANSFER PUMP SKID	TWO (2) 50 GPM AT 50 PSIG TRANSFER PUMPS WITH MOTOR CONTROL PANEL AND DISCONNECT, SKID MOUNTED			2	3	3	1800	460 V	3	60 Hz	0 A	0 A	0 A	VENDOR	X/L	YES	HOA	MARLO	DTPS-50		

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**
CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
MECHANICAL SCHEDULES

SHEET NUMBER
M603

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:58 PM AESI Proj. No: 21-154

CHILLED WATER , HEATING HOT WATER, AND CONDENSER WATER CONTROL VALVE SCHEDULE

NOTES:

1. CONTROL VALVES SHOWN IN THIS TABLE SHALL BE PROVIDED BY THE TEMPERATURE CONTROLS CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR.
2. SEE DRAWINGS...
3. PROVIDE FAIL...

TAG NO.	LOCATION	SERVICE	FLUID	FLOW GPM	CONNECTION SIZE (NPS)	END CONNECTION TYPE	INLET TEMPERATURE °F	VALVE TYPE	VALVE CV	VALVE FLOW CHARACTERISTIC	MATERIAL OF CONSTRUCTION	DESIGN PRESSURE	CLOSE OFF PRESSURE PSIG	CLOSE OFF DIFFERENTIAL PRESSURE (PSIG)	CONTROL TYPE	ACTUATOR TYPE	ACTUATOR	MFG.	MODEL #	NOTES
CH-1-MOV-01	CH-1 14" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	3,000	14	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	6,440	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-1-MOV-02	CH-1 20" TOWER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	TOWER WATER	6,000	20	CLASS 150 FLANGED	85	HIGH PERFORMANCE V-PORT SEGMENTED BALL	13,020	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-2-MOV-01	CH-2 12" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	3,000	14	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	6,440	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-2-MOV-02	CH-2 14" TOWER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	TOWER WATER	6,000	20	CLASS 150 FLANGED	85	HIGH PERFORMANCE V-PORT SEGMENTED BALL	13,020	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-3-MOV-01	CH-3 12" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	3,000	14	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	6,440	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-3-MOV-02	CH-3 14" TOWER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	TOWER WATER	6,000	20	CLASS 150 FLANGED	85	HIGH PERFORMANCE V-PORT SEGMENTED BALL	13,020	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-4-MOV-01	CH-4 12" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	3,000	14	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	6,440	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-4-MOV-02	CH-4 14" TOWER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	TOWER WATER	6,000	20	CLASS 150 FLANGED	85	HIGH PERFORMANCE V-PORT SEGMENTED BALL	13,020	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-5-MOV-01	CH-5 12" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	3,000	14	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	6,440	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-5-MOV-02	CH-5 14" TOWER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	TOWER WATER	6,000	20	CLASS 150 FLANGED	85	HIGH PERFORMANCE V-PORT SEGMENTED BALL	13,020	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-6-MOV-01	CH-6 12" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	3,000	14	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	6,440	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CH-6-MOV-02	CH-6 14" TOWER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	TOWER WATER	6,000	20	CLASS 150 FLANGED	85	HIGH PERFORMANCE V-PORT SEGMENTED BALL	13,020	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-1-MOV-01	HRC-1 6" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	540	6	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	1,260	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-1-MOV-02	HRC-1 8" CONDENSER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	HHW	1,080	8	CLASS 150 FLANGED	110	HIGH PERFORMANCE V-PORT SEGMENTED BALL	2,030	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-2-MOV-01	HRC-1 6" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	540	6	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	1,260	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-2-MOV-02	HRC-1 8" CONDENSER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	HHW	1,080	8	CLASS 150 FLANGED	110	HIGH PERFORMANCE V-PORT SEGMENTED BALL	2,030	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-3-MOV-01	HRC-1 6" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	540	6	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	1,260	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-3-MOV-02	HRC-1 8" CONDENSER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	HHW	1,080	8	CLASS 150 FLANGED	110	HIGH PERFORMANCE V-PORT SEGMENTED BALL	2,030	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-4-MOV-01	HRC-1 6" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	540	6	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	1,260	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-4-MOV-02	HRC-1 8" CONDENSER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	HHW	1,080	8	CLASS 150 FLANGED	110	HIGH PERFORMANCE V-PORT SEGMENTED BALL	2,030	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-5-MOV-01	HRC-1 6" CHILLED WATER INLET PIPING	CHILLER EVAPORATOR FLOW CONTROL	CHILLED WATER	540	6	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	1,260	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HRC-5-MOV-02	HRC-1 8" CONDENSER WATER INLET PIPING	CHILLER CONDENSER FLOW CONTROL VALVE	HHW	1,080	8	CLASS 150 FLANGED	110	HIGH PERFORMANCE V-PORT SEGMENTED BALL	2,030	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HX-1-MOV-1	HX-1 1 8" CONDENSER WATER RETURN PIPING	HX-1 CONDENSER WATER FLOW CONTROL VALVE	HHW	5,400	16	CLASS 150 FLANGED	110	HIGH PERFORMANCE V-PORT SEGMENTED BALL	8,510	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
HX-1-MOV-2	HX-1 1 8" TOWER WATER RETURN PIPING	HX-1 TOWER WATER FLOW CONTROL VALVE	TOWER WATER	5,400	16	CLASS 150 FLANGED	110	HIGH PERFORMANCE V-PORT SEGMENTED BALL	8,510	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CT-1-MOV-01	CT-1 18" TOWER WATER INLET PIPING	COOLING TOWER FLOW CONTROL	TOWER WATER	6,000	18	CLASS 150 FLANGED	95	2-WAY MOTOR OPERATED BUTTERFLY	17,240	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W TWO AUXILLARY SWITCHES AND BEACON INDICATOR	BRAY	NYL SERIES	
CT-2-MOV-01	CT-2 18" TOWER WATER INLET PIPING	COOLING TOWER FLOW CONTROL	TOWER WATER	6,000	18	CLASS 150 FLANGED	95	2-WAY MOTOR OPERATED BUTTERFLY	17,240	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W TWO AUXILLARY SWITCHES AND BEACON INDICATOR	BRAY	NYL SERIES	
CT-3-MOV-01	CT-3 18" TOWER WATER INLET PIPING	COOLING TOWER FLOW CONTROL	TOWER WATER	6,000	18	CLASS 150 FLANGED	95	2-WAY MOTOR OPERATED BUTTERFLY	17,240	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W TWO AUXILLARY SWITCHES AND BEACON INDICATOR	BRAY	NYL SERIES	
CT-4-MOV-01	CT-4 18" TOWER WATER INLET PIPING	COOLING TOWER FLOW CONTROL	TOWER WATER	6,000	18	CLASS 150 FLANGED	95	2-WAY MOTOR OPERATED BUTTERFLY	17,240	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W TWO AUXILLARY SWITCHES AND BEACON INDICATOR	BRAY	NYL SERIES	
CT-5-MOV-01	CT-5 18" TOWER WATER INLET PIPING	COOLING TOWER FLOW CONTROL	TOWER WATER	6,000	18	CLASS 150 FLANGED	95	2-WAY MOTOR OPERATED BUTTERFLY	17,240	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W TWO AUXILLARY SWITCHES AND BEACON INDICATOR	BRAY	NYL SERIES	
CT-6-MOV-01	CT-6 18" TOWER WATER INLET PIPING	COOLING TOWER FLOW CONTROL	TOWER WATER	6,000	18	CLASS 150 FLANGED	95	2-WAY MOTOR OPERATED BUTTERFLY	17,240	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W TWO AUXILLARY SWITCHES AND BEACON INDICATOR	BRAY	NYL SERIES	
CHW-BP-MOV-01	14" CHW BYPASS PIPING	BYPASS FLOW CONTROL	CHILLED WATER	3,000	14	CLASS 150 FLANGED	58	HIGH PERFORMANCE V-PORT SEGMENTED BALL	6,440	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
CTW-BP-MOV-1	16" CHW BYPASS PIPING	BYPASS FLOW CONTROL	TOWER WATER	5,400	16	CLASS 150 FLANGED	110	HIGH PERFORMANCE V-PORT SEGMENTED BALL	8,510	EQUAL PERCENTAGE	316 SS METAL SEAT, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	275	175	175	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:35:59 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: **AESI**
CHECKED BY: **AESI**
APPROVED BY: **Approver**
PROJECT NO.: **21-154**

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

MECHANICAL SCHEDULES

SHEET NUMBER

M604

CHILLER AND BOILER CONTROL VALVE SCHEDULE (CONT.)

NOTES:

1. CONTROL VALVES SHOWN IN THIS TABLE SHALL BE PROVIDED BY THE TEMPERATURE CONTROLS CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR.
2. SEE DRAWINGS...
3. PROVIDE FAIL...

CT-1- BS-MOV-01	6" BASIN SWEEPER CTW CONTROL VALVE	CT-1 TOWER WATER SUPPLY CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-1- BS-MOV-02	6" BASIN SWEEPER CTW CONTROL VALVE	CT-1 TOWER WATER RETURN CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-2- BS-MOV-01	6" BASIN SWEEPER CTW CONTROL VALVE	CT-2 TOWER WATER SUPPLY CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-2- BS-MOV-02	6" BASIN SWEEPER CTW CONTROL VALVE	CT-2 TOWER WATER RETURN CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATINGF	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-3- BS-MOV-01	6" BASIN SWEEPER CTW CONTROL VALVE	CT-3 TOWER WATER SUPPLY CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-3- BS-MOV-02	6" BASIN SWEEPER CTW CONTROL VALVE	CT-3 TOWER WATER RETURN CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-4- BS-MOV-01	6" BASIN SWEEPER CTW CONTROL VALVE	CT-4 TOWER WATER SUPPLY CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-4- BS-MOV-02	6" BASIN SWEEPER CTW CONTROL VALVE	CT-4 TOWER WATER RETURN CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-5- BS-MOV-01	6" BASIN SWEEPER CTW CONTROL VALVE	CT-5 TOWER WATER SUPPLY CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC MODULATING. NON-RETURN ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-5- BS-MOV-02	6" BASIN SWEEPER CTW CONTROL VALVE	CT-5 TOWER WATER RETURN CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-6- BS-MOV-01	6" BASIN SWEEPER CTW CONTROL VALVE	CT-6 TOWER WATER SUPPLY CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CT-6- BS-MOV-02	6" BASIN SWEEPER CTW CONTROL VALVE	CT-6 TOWER WATER RETURN CONTROL VALVE	TOWER WATER	1,300	6	CLASS 150 FLANGED	95	2 WAY PROPORTIONAL NON-SPRING RETURN	1,850	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	175	175	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-CHM-MOV-01	4" CTW BLOW DOWN CONTROL	COOLING TOWER WATER BLOWDOWN VALVE	TOWER WATER	80	4	CLASS 150 FLANGED	95	2 WAY MOTOR OPERATED BUTTERFLY	154	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	PRO-PORTIONAL	ELECTRIC MODULATING NON-SPRING RETURN WITH POSITION FEEDBACK	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W TWO AUXILLARY SWITCHES AND BEACON INDICATOR	BRAY	NYL SERIES	
CUP-B-1-MOV-01	B-1 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	4-20 mA	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-1-MOV-01	B-1 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-2-MOV-01	B-2 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	4-20 mA	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-3-MOV-01	B-3 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-4-MOV-01	B-3 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-5-MOV-01	B-3 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-6-MOV-01	B-3 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-7-MOV-01	B-3 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-8-MOV-01	B-3 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-9-MOV-01	B-3 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	
CUP-B-10-MOV-01	B-4 8" HHWS OUTLET CONTROL VALVE	BOILER HEATING HOT WATER SUPPLY CONTROL VALVE	HEATING HOT WATER SUPPLY	634	8	CLASS 150 FLANGED	150	2-WAY MOTOR OPERATED BUTTERFLY	2,004	MODIFIED EQUAL PERCENTAGE	CAST IRON BODY, DUCTILE IRON NYLON COATED DISC, EPDM SEAT, 416 SS TRIM	250	150	150	ON / OFF FLOATING	ELECTRIC ON/OFF NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE/W POSITION FEEDBACK	BRAY	NYL SERIES	

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**
CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
MECHANICAL SCHEDULES

SHEET NUMBER
M605

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:00 PM AESI Proj No: 21-154

BALANCE VALVE SCHEDULE

NOTES:
1. PROVIDE...
2. FUTURE (NIC)

TAG NO.	LOCATION	SERVICE	FLUID	FLOW GPM	CONNECTION SIZE (NPS)	END CONNECTION TYPE	CV	MATERIALS OF CONSTRUCTION	DESIGN PRESSURE	WEIGHT (LBS)	MFG.	MODEL #	NOTES
BV-CH-1-A	CH-1	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	14	FLANGE	6,225	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	378.3	GRISWOLD	3QFV FLANGED END QUICKSET	1
BV-CH-1-B	CH-1	CHILLER CONDENSER FLOW	TOWER WATER	6,000	20	FLANGE	19,950	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	750	GRISWOLD	3QFY FLANGED END QUICKSET	1
BV-CH-2-A	CH-2	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	14	FLANGE	6,225	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	378.3	GRISWOLD	3QFV FLANGED END QUICKSET	1
BV-CH-2-B	CH-2	CHILLER CONDENSER FLOW	TOWER WATER	6,000	20	FLANGE	19,950	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	750	GRISWOLD	3QFY FLANGED END QUICKSET	1
BV-CH-3-A	CH-3	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	14	FLANGE	6,225	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	378.3	GRISWOLD	3QFV FLANGED END QUICKSET	1
BV-CH-3-B	CH-3	CHILLER CONDENSER FLOW	TOWER WATER	6,000	20	FLANGE	19,950	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	750	GRISWOLD	3QFY FLANGED END QUICKSET	1
BV-CH-4-A	CH-4	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	14	FLANGE	6,225	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	378.3	GRISWOLD	3QFV FLANGED END QUICKSET	1
BV-CH-4-B	CH-4	CHILLER CONDENSER FLOW	TOWER WATER	6,000	20	FLANGE	19,950	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	750	GRISWOLD	3QFY FLANGED END QUICKSET	1
BV-CH-5-A	CH-5	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	14	FLANGE	6,225	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	378.3	GRISWOLD	3QFV FLANGED END QUICKSET	1
BV-CH-5-B	CH-5	CHILLER CONDENSER FLOW	TOWER WATER	6,000	20	FLANGE	19,950	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	750	GRISWOLD	3QFY FLANGED END QUICKSET	1
BV-CH-6-A	CH-6	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	14	FLANGE	6,225	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	378.3	GRISWOLD	3QFV FLANGED END QUICKSET	1
BV-CH-6-B	CH-6	CHILLER CONDENSER FLOW	TOWER WATER	6,000	20	FLANGE	19,950	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	750	GRISWOLD	3QFY FLANGED END QUICKSET	1
BV-HRC-1-A	HRC-1	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	6	FLANGE	980	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER HANDLE OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	70.3	GRISWOLD	3QFR FLANGED END QUICKSET	1
BV-HRC-1-B	HRC-1	CHILLER CONDENSER FLOW	HHW	1,080	8	FLANGE	1,745	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	126.5	GRISWOLD	3QFS FLANGED END QUICKSET	1
BV-HRC-2-A	HRC-2	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	6	FLANGE	980	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER HANDLE OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	70.3	GRISWOLD	3QFR FLANGED END QUICKSET	1
BV-HRC-2-B	HRC-2	CHILLER CONDENSER FLOW	HHW	1,080	8	FLANGE	1,745	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	126.5	GRISWOLD	3QFS FLANGED END QUICKSET	1
BV-HRC-3-A	HRC-3	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	6	FLANGE	980	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER HANDLE OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	70.3	GRISWOLD	3QFR FLANGED END QUICKSET	1
BV-HRC-3-B	HRC-3	CHILLER CONDENSER FLOW	HHW	1,080	8	FLANGE	1,745	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	126.5	GRISWOLD	3QFS FLANGED END QUICKSET	1
BV-HRC-4-A	HRC-4	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	6	FLANGE	980	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER HANDLE OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	70.3	GRISWOLD	3QFR FLANGED END QUICKSET	1
BV-HRC-4-B	HRC-4	CHILLER CONDENSER FLOW	HHW	1,080	8	FLANGE	1,745	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	126.5	GRISWOLD	3QFS FLANGED END QUICKSET	1
BV-HRC-5-A	HRC-5	CHILLER EVAPORATOR FLOW	CHILLED WATER	3,000	6	FLANGE	980	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER HANDLE OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	70.3	GRISWOLD	3QFR FLANGED END QUICKSET	1
BV-HRC-5-B	HRC-5	CHILLER CONDENSER FLOW	HHW	1,080	8	FLANGE	1,745	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	126.5	GRISWOLD	3QFS FLANGED END QUICKSET	1
BV-HX-1A	HX-1	HX RETURN WATER FLOW	HHW	5,400	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1
BV-HX-1B	HX-1	HX RETURN WATER FLOW	CONDENSER WATER	5,400	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1
BV-CT-1A	CT-1	RETURN WATER FLOW	TOWER WATER	6,000	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1
BV-CT-2A	CT-2	RETURN WATER FLOW	TOWER WATER	3,000	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1
BV-CT-3A	CT-3	RETURN WATER FLOW	TOWER WATER	3,000	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1
BV-CT-4A	CT-4	RETURN WATER FLOW	TOWER WATER	3,000	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1
BV-CT-5A	CT-5	RETURN WATER FLOW	TOWER WATER	3,000	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1
BV-CT-6A	CT-6	RETURN WATER FLOW	TOWER WATER	3,000	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:01 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

MECHANICAL SCHEDULES

SHEET NUMBER

M606

BALANCE VALVE SCHEDULE (CONT.)

NOTES:
1. PROVIDE...
2. FUTURE (NIC)

BV-BS-7A	TOWER WATER BASIN SWEEPER CT-1	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7B	TOWER WATER BASIN SWEEPER CT-1	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7C	TOWER WATER BASIN SWEEPER CT-2	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7D	TOWER WATER BASIN SWEEPER CT-2	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7E	TOWER WATER BASIN SWEEPER CT-3	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7F	TOWER WATER BASIN SWEEPER CT-3	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7G	TOWER WATER BASIN SWEEPER CT-4	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7H	TOWER WATER BASIN SWEEPER CT-4	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7I	TOWER WATER BASIN SWEEPER CT-5	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7J	TOWER WATER BASIN SWEEPER CT-5	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7K	TOWER WATER BASIN SWEEPER CT-6	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BS-7L	TOWER WATER BASIN SWEEPER CT-6	BASIN SWEEPER	TOWER WATER	310	4	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	43	GRISWOLD	3QFP FLANGED END QUICKSET	1
BV-BD-6A	TOWER WATER BLOW DOWN VALVE	BLOW DOWN	TOWER WATER	80	3	FLANGE	201	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 LEVER OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	30	GRISWOLD	3QFN FLANGED END QUICKSET	1
BV-BP-6A	TOWER WATER BYPASS VALVE	BYPASS	TOWER WATER	3,000	18	FLANGE	12,057	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	614.2	GRISWOLD	3QFX FLANGED END QUICKSET	1
BV-BP-6C	CHILLED WATER BYPASS VALVE	BYPASS	CHILLED WATER	3,000	14	FLANGE	6,225	CARBON STEEL BODY WITH CARBON STEEL PIEZO-RING AVERAING FLOW SENSOR, SS PRESSURE TAPS, CLASS 150 CS STEEL FLANGES, CLASSS 150 HAND WHEEL GEAR OPERATED LUG TYPE BUTTERFLY VALVE WITH RESILIANT SEAT	175	378.3	GRISWOLD	3QFV FLANGED END QUICKSET	1

STEAM AND CONDENSATE CONTROL VALVE SCHEDULE

NOTES:
1. CONTROL VALVES SHOWN IN THIS TABLE SHALL BE PROVIDED BY THE TEMPERATURE CONTROLS CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR.
2. SEE DRAWINGS, SPECIFICATIONS, AND CONTROL SEQUENCES FOR ADDITIONAL CONTROL VALVE TYPES, LOCATIONS, AND FUNCTIONS. VALVES IN THIS SCHEDULE DO NOT CONSTITUTE ALL REQUIRED CONTROL VALVES.
3. PROVIDE FAIL OPEN SPRING ACTUATOR WITH TWO AUXILIARY SWITCHES AND MANUAL HAND WHEEL

UNIT TAG	LOCATION	SERVICE	FLUID	FLOW	END CONNECTION SIZE (NPS)	END CONNECTION TYPE	INLET TEMPERATURE	VALVE TYPE	VALVE CV	VALVE FLOW CHARACTERISTIC	MATERIAL OF CONSTRUCTION	DESIGN PRESSURE	CLOSE OFF PRESSURE	CLOSE OFF DIFFERENTIAL PRESSURE	CONTROL TYPE	ACTUATOR TYPE	ACTUATOR	BASIS OF DESIGN		NOTES
																		MANUFACTURER	MODEL NO.	
MOTORIZED ISOLATION CONTROL VALVE				0 GPM	0"	CLASS 150 FLANGED	-459.7 °F	HIGH PERFORMANCE V-PORT SEGMENTED BALL	0	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	0 psi	0 psig	0 psig	4-20 mA	ELECTRIC MODULATING NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
MOTORIZED ISOLATION CONTROL VALVE				0 GPM	0"	CLASS 150 FLANGED	-459.7 °F	HIGH PERFORMANCE V-PORT SEGMENTED BALL	0	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	0 psi	0 psig	0 psig	4-20 mA	ELECTRIC MODULATING NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	
MOTORIZED ISOLATION CONTROL VALVE				0 GPM	0"	CLASS 150 FLANGED	-459.7 °F	HIGH PERFORMANCE V-PORT SEGMENTED BALL	0	EQUAL PERCENTAGE	316 SS METAL SEAT, LEAK CLASS IV, INCONEL 625 SPRING, FILLED PTFE, CAST SS BODY, 316 SS SHAFT	0 psi	0 psig	0 psig	4-20 mA	ELECTRIC MODULATING NON-SPRING RETURN WITH TWO AUXILLARY SWITCHES	0-10V DC TO 90 DEG ROTARY 120 VOLT POWERED ACTUATOR, BUTTERFLY VALVE W/ TWO AUXILLARY SWITCHES AND BEACON INDICATOR	NELES	RE SERIES	

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

MECHANICAL SCHEDULES

SHEET NUMBER

M607

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:02 PM AESI Proj No: 21-154

COOLING TOWER SYSTEM - COOLING TOWER P&ID

Scale: 6" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DS	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

COOLING TOWER SYSTEM - COOLING TOWER P&ID

SHEET NUMBER

M701

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:03 PM AESI Proj. No. 21-154

CENTRAL TOWER-WATER SYSTEM SEQUENCES

A. TOWER-WATER PLANT:

1. The central utility plant (CUP) tower-water system serves the new IU Health downtown campus. It is a variable primary system that is made up of six (6) 2,000 ton cross flow cooling towers, six 6,000 gpm variable speed cooling tower water pumps, two 600 gpm cooling tower basin sweeper systems, one 810 gpm centrifugal side stream filter system, one heat recovery chiller plate and frame heat exchanger, cooling tower blowdown system, make up water system and water treatment system. . The CUP tower water system operates year round.
2. Towers and associated pumps are enabled / disabled by the building BMS. The BMS controls and coordinates the staging of equipment and equipment operating speed to minimize total plant energy consumption. Advanced control algorithms, weather forecasts and historic data are used to predict and calculate energy usage and when and how equipment will operate to meet the campus load. The BMS control actions are based upon .
   a. Campus Chilled Water Load: Chilled water load as determined by the chilled water flow rate to the campus and chilled water supply / return temperature difference,
   b. Campus simultaneous heating hot water load and use of heat recovery chillers to meet chilled water and heating hot water demand.
   c. Individual Chiller Operating Power: Chiller amperage compared to chiller full load amperage maybe used as a surrogate for chilled water
   d. Cooling Tower Condenser Supply / Return Water Temperature
   e. Tower Water Pump Speed: Tower water supply/ return differential pressure.
   f. Tower Water number of Pumps: Number of Chillers running.
   g. Chiller Condenser Water Flow: Chiller condenser water supply / return differential pressure.
   h. Chiller Condenser Water: Number of Chillers running
   i. Heating hot water
   j. Building occupancy time of day schedule and equipment run time schedules
   k. Campus historical weather and space set point data and building equipment historical operating data.

B. COOLING TOWER

1. BMS commands Cooling Tower System to stand by whenever the CHW system is enabled. In stand by
2. When BMS commands HX-1 and / or lead 2,000 ton chiller compressor to run;
   a. The corresponding equipment condenser water isolation MOV is opened and a condenser water flow circuit is established.
   b. The lead cooling tower is enabled, and the BMS determines if the CTWS water temperature is too cold to run through the chiller.
      1. if the cooling tower water supply (CTWS) temperature is greater than 65 °F (adjustable), the lead cooling tower isolation MOV is opened.
      2. if the CTWS temperature is less than 60 °F (adjustable), the lead cooling tower MOV remains closed while the CTW bypass valve is modulated open. CTWR bypasses the cooling towers until the CTWS temperature rises to 85 °F (adjustable). When the CTWS rises to 85 °F, the CTW bypass is closed, and the lead cooling tower CTW isolation valve is opened.
   c. The lead cooling tower pump starts and runs after condenser / HX-1 isolation valve is proved open.
   d. The HX or chiller proof of flow switch closes and the BMS initiates the HX startup sequence, or the Chiller DDC initiates the chiller startup sequence.
3. BMS determines when an additional 2,000 ton chiller is to be added. When a 2,000 ton chiller is to be added:
   a. Open next chiller in succession condenser water isolation valve.
   b. Start next in succession CTW pump. All operating CTW pump VSD's modulate at the same speed to control CTWS/R differential pressure set point.
   c. Simultaneously open next in succession cooling tower inlet MOV.
   d. Chiller condenser water minimum flow permissive confirmed by chiller condenser water minimum flow switch.
      1. Chiller held offline until minimum flow established to chiller condenser. Flow required to be established within 1 minute (adjustable) of chiller condenser water valve opening.
      2. Chiller condenser water flow measured by flow differential pressure transducer across chiller condenser. BMS controls chiller condenser water flow by modulating condenser isolation control valve. BMS determines condenser flow rate based on chiller manufacturers allowable condenser flow limits, chiller and overall plant energy consumption
   e. BMS to monitor and log individual chiller condenser flow as measured at condenser differential pressure transmitters.
4. BMS determines when a 2,000 ton chiller is to be removed. When a 2,000 ton chiller is to be removed:
   a. Chiller DDC control stop sequence is initiated. When chiller DDC controls shut down sequence and timers confirm chiller ready for shut down:
      1. Close last chiller on condenser water isolation valve.
   b. Operating CTW pump VSD modulate to same speed to control pressure set point. BMS calculates CTW pump contribution to overall plant energy and determines if a CTW pump should be shut down.
      1. If a pump is to be removed, stop last CTW pump that was staged on. Pump off staging order is reverse of pump on staging.
   c. BMS calculates operating cooling tower energy contribution to overall plant energy use and determines if a cooling tower should be shut down. If a cooling tower is to be shut down, cooling tower off staging is reverse order of cooling tower on staging. close last cooling tower on inlet MOV.
5. BMS to monitor and log individual chiller condenser flow as measured at condenser differential pressure transmitter.

C. COOLING TOWER PUMP CONTROL:

1. There are six (6) parallel tower water variable distribution pumps located in the CUP CTWS piping (The pump and tower quantity has N+1 redundancy).
   a. Cooling tower pumps run whenever the 2,000 ton chillers operate or the heat recovery heat exchanger (HX-1) operates. At least one corresponding condenser water isolation valves for the 2,000 centrifugal chillers or the heat exchanger condenser water isolation valve must prove open for the cooling tower pumps to run.
   b. The BMS stages the pumps on / off and modulates their VFD speed to maintain a differential pressure of 14 psig (adjustable) between the CTWS and CTWR mains at the CTWS/R differential pressure transmitter located in the mechanical room on the second floor.
   c. The BMS controls all active CTWS distribution pumps to run at the same speed.
   d. The distribution pumps are designed for 6,000 gpm per pump (design flow rate of a 2,000 ton chiller). The BMS will calculate the apparent number of tower water pumps required based on cooling load, active 2,000 chillers, heat recovery heat exchanger status, and CTW pump energy consumption and overall plant energy consumption.
      1. When flow per cooling tower exceeds 5,000 gpm an additional pump will be started.
      2. When flow per cooling tower is less than 3,000 gpm a running pump will be stopped.
2. Pump VSD ramp rate will set to 10% / minute (adjustable).
3. BMS will monitor position of chiller condenser isolation valves and heat recovery heat exchanger HX-1 isolation control valves and prevent cooling tower pumps from running until isolation valves are opened.

D. DRUN TIME ALTERNATE TOWERS, AND PUMPS:

1. Operate towers and associated pumps on 14 day (adjustable) *lead-lag-standby* schedule, alternating based on adjustable 336 hour set point. When time elapses rotate *lead-lag-standby* designation, so *lag* becomes *lead*, *standby* becomes *lag* and *lead* becomes *standby*. Make provisions for future seventh and eight tower, and associated pumps.
2. Equipment staging
   a. Cooling towers and cooling tower pumps are staged on and off as scheduled once all safeties and prerequisites are met, and need is established.
3. Optimization: BMS will monitor and control CUP energy use at the equipment level and use advanced control algorithms to minimize over all plant energy use, KW metering, cooling tower and chilled water flow, outdoor air temperature, time of day, and previous occupancy / chiller load / outdoor and indoor temperature history and forecasts, rest schedules and predictive load calculations will be used to stage chillers, towers, and pumps on and off to minimize e energy use while maintaining system control.

E. COOLING TOWER MAKEUP WATER FILL

1. Cooling Tower Drain Valves
   a. Make Up Water: Tower water branch supply and return lines are provided with manual shut off isolation valves. Brach piping section also have manual drain valves. Branch valves can be closed, and pipe sections drained for tower maintenance or winter shutdown. For Summer operation, the drain valves are closed, and the branch isolation valves are opened.
2. Cooling Tower Makeup Water
   a. The water level in the cooling tower cold water basins is controlled by the BMS, individual cooling tower basin ultrasonic level sensors, and motorized make up water valves located in the chilled water pump room on the first floor of the CUP.
      1. The water level of each cooling tower basin is transmitted to the BMS by each cooling towers ultrasonic level sensor. The level for each sensor is preset to account for cooling tower sump level changes associated with transient cooling tower water traveling through the cooling tower fill.
      2. BMS level set points provided for cooling tower basin water level include;
         a. Low low level alarm low level condition to BMS
         b. Low level add makeup water; open makeup valve
         c. High level stop adding makeup water; close makeup valve
         d. High high level alarm high level condition to BMS
      3. If cooling tower is shut down for winter, monitor basin water level but do not use basin water level to operate cooling tower makeup valve. Only use non-winterized cooling towers to operate makeup valves.
   b. There is one 2" cooling tower makeup valve each cooling tower. The valves are manifolded into a common 6" header that injects makeup water into the 48" cooling tower supply main on the suction side of the cooling tower supply pumps. The BMS determines the number of makeup valves to operate on a call for makeup water. In general if a cooling tower is operating as determined by its 18" CTR inlet valve status as opened, the corresponding makeup water valve on the 6" header will be enabled and modulate open / closed tin response to makeup water level controls.

F. COOLING TOWER TEMPERATURE AND FLOW CONTROL OPTIMIZATION

1. The tower water design supply temperature is 85 °F and the return design water temperature is 95 °F.
2. Cooling towers are designed for 6,000 gpm flow. They are capable of running at flows as low as 50% design flow (3,000 gpm).
3. The cooling tower fans are outfitted with a VFD motor controls. The cooling tower fan speed is modulated to control the leaving tower water temperature.
   a. The normal summer CTWS temperature is 85 F.
   b. When temperatures are cooler, the CTWS temperature is reset to the cooling tower to entering air wet bulb temperature plus 5 °F. The cooling tower fan speed is modulated to control CTWS set point.
   c. In winter, the cooling tower fan will modulate, and stage on / off to maintain minimum CTWS above 60 F.
   d. The cooling tower fans can run in reverse in winter when needed for de-icing the fan / tower.
4. The chiller condenser are capable of variable flow from chiller minimum flow (about 3,000 gpm) to chiller design flow 6,000 gpm. The condenser flow to the active chillers is allowed to vary between 1.5 to 3 gpm / ton based on least total plant energy use. The condenser flow will be split equally across all active cooling towers and the cooling tower VFD fans will all operate at the same speed. Number of active cooling towers will prevent flow through any tower from being less than 3,000
5. The BMS controls shall analyze the combined chiller, chiller pump, cooling tower, and cooling tower pump energy use and calculate new set points for the chiller flow, and cooling tower supply water temperature resulting in the least energy to meet the campus building load.

G. COOLING-TOWER SUMP HEATER:

1. Energize sump heater if sump temperature falls below 40 deg F temperature set point.
2. Cooling tower supply basin water temperature is input to BMS.
3. Each electric heating element is monitored for on /off status and element failure status.
4. Close cooling tower supply and return motor operated valves, close cooling tower make up water solenoid valve, open cooling tower supply solenoid drain valve and cooling tower return solenoid drain valve if sump temperature falls below 35 deg F temperature set point.
5. Disable sump heater if sump water level is below sump low water level.

H. HEAT RECOVERY CONDENSER WATER SIDE STREAM CHW PUMPS

1. Three 1,800 gpm HRC condenser side pumps (N+1 quantity) circulate chilled water through the active heat recovery chillers in the HHW sidecar loop. Heat recovery heating hot water side stream pumps start and run when the HRC's run.
   a. The HRC HHWP Pumps stage on /off and the VSD indexes number of pumps and speed to correspond to the number of active HRC'ers.
   b. The HRC heating hot water pumps provide a constant flow per operational HRC.
      1. In heat recovery mode the BMS modulates each active HRC condenser isolation valve to maintain 450 gpm as measured by the HRC condenser differential pressure transmitter.
      2. In cooling only mode the BMS modulates each active HRC condenser isolation valve to maintain 1080 gpm as measured by the HRC condenser differential pressure transmitter.
2. In heat recovery mode, the condenser water from the heat recovery chillers flows back into the HHWR main and through the standby boilers. The lead boiler fires to provide supplemental heating as required to reach HHW set point.
3. In Cooling only mode a three way diverting valve in the HHWS pipe from the HRC's diverts flow through HX-1 to the suction side of the HRC condenser side stream pumps. Cooling tower water isolation valve in the HX-1 return pipe opens to provide cooling tower water to HX-1.

I. INDICATE ON THE OPERATOR'S WORKSTATION DISPLAY TERMINAL:

1. DDC system graphic.
2. DDC system status, on-off.
3. Low-level cooling-tower sump alarm.
4. Outdoor temperature.
5. Cooling (software) demand indication.
6. Time and time schedule.
7. Condenser-water pump(s) on-off status (enabled or disabled).
8. Condenser-water pump(s) on-off indication (operating or not operating).
9. Condenser-water flow indication.
10. Cooling-tower fan(s) on-off indication (operating or not operating).
11. Refrigeration machine on-off indication (operating or not operating).
12. Condenser-water sump (return) control-point temperature.
13. Condenser-water sump (return) temperature.
14. Condenser-water control-valve position.
15. Cooling-tower fan(s) on-off indication (operating or not operating).
16. Cooling Tower Fan Speed
17. Cooling Tower Fan direction Forward / Reverse
18. Cooling Tower Fan Vibration Alarm
19. Cooling Tower Supply Water Basin Temperature
20. Cooling Tower Supply Basin Water Level Status
21. Condenser-water supply temperature.
22. Cooling-tower sump temperature.
23. Cooling-tower sump heater element on-off indication (operating or not operating).
24. Cooling Tower Basin Heater element failure alarm
25. Cooling-tower sump drain indication.
26. Condenser-water pressure drop through chiller.
27. Condenser-water flow through chiller.
28. Chiller / HX-1 condenser-water supply and return temperature.

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:03 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DS	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

CENTRAL TOWER-WATER SYSTEM SEQUENCES

SHEET NUMBER

M702



1 **CHILLED WATER SYSTEM - CHILLED WATER P&ID**
Scale: none

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:38:04 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	DS
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

CHILLED WATER SYSTEM - CHILLED WATER P&ID

SHEET NUMBER

M703

CENTRAL CHILLED-WATER SYSTEM SEQUENCES

A. CHILLED WATER PLANT:

1. The central utility plant (CUP) chilled water system serves the new IU Health downtown campus. It is a variable primary chilled water system that is made up of five (5) 300 ton variable speed centrifugal heat recovery chillers, six (6) 2,000 ton constant speed water cooled centrifugal chillers, seven (7) 3,000 gpm variable speed primary CHW pumps, three 1,400 gpm variable speed heat recovery chiller chilled water sidecar pumps, three 1,800 gpm variable speed heat recovery condenser water sidecar pumps, six (6) 2,000 ton cross flow cooling towers, and six 6,000 gpm variable speed cooling tower water pumps. The CUP chilled water system operates year round.
2. The campus chilled water supply (CHWS) and chilled water return (CHWR) design temperatures are 42°F and 58°F respectively. The chilled water is piped from the CUP to the hospital and support buildings through 36" CHWS&R mains located in a tunnel beneath Senate Avenue.

B. HEAT RECOVERY CHILLERS:

1. There are five (5) 300 ton variable speed centrifugal heat recovery chillers arranged in parallel sidecar fashion up stream of the 2,000 ton centrifugal chillers.
2. he HRC's can run in heat recovery mode or cooling only mode. The BMS controls the HRC operational mode based on simultaneous heating and cooling need and total least energy usage. Preference is given to running and base loading the heat recovery chillers in Heat Recovery Mode.
3. Any time the CUP CHW system is energized the lead 2,000 ton centrifugal chiller enters standby mode. The lead 2,000 ton chiller chilled water isolation valve is opened to provide a CHW flow path from the CHWR to CHWS piping.
4. The heat recovery chillers are the first chillers to stage on and last to stage off. They are meant to run year round. They are required to run when total CHW load is less than 500 tons / 1,200 gpm since these loads / flows are the lower operating limit for a 2,000 ton centrifugal chiller.
5. The heat recovery chillers are nominal 400 ton VFD centrifugal chillers derated to 300 tons in heat recovery mode. They have limited operating range in heat recovery mode due to the high compressor lift (42°F chilled water to 120 °F heating hot water). In cooling only mode the HRC's can produce capacity near 400 tons each (lift 42°F chilled water to 98 °F condenser water).
   a. HRC capacity and load range is lift dependent and mapped into the BMS for both heat recovery and cooling only operating modes.
   b. In either mode the BMS will stage the HRC 's on /off and chiller DDC controls will monitor / control compressor speed to supply 42 ° F chilled water, unless HRC DDC control is overridden by BMS command for load limiting constraints or the chilled water rest schedule changes the CHWS set point.
6. In the heat recovery mode the HRC's are designed to cool the CHW from 58°F to 42°F while heating the HHWR from 100 °F to 120°F.
   a. Condenser water (HHWR) is pumped at 1.5 gpm / cooling ton through HRC's. Condenser water isolation valve is modulated to control HRC condenser flow rate to 450 gpm as measured at HRC condenser differential pressure transmitter.
   b. Condenser water may be bypassed through a plate and frame heat exchanger (HX-1) at variable flow rate that rejects excess heat to the cooling towers. HX-1 condenser water three way diverting valve is modulated to control HHWR to the HHWR main from HRC condenser as measured by flow meter HHWR-FM-2 to match HHWR flow rate to boilers as measured at HHWR-FM-1 flow meter-1.
7. In cooling only mode the chillers are designed to cool the CHW from 58°F to 42°F while heating the condenser water from 88 °F to 98°F.
   a. Condenser water is pumped through a plate and frame heat exchanger (HX-1) at an increased rate (3 gpm) that rejects heat to the cooling towers. Condenser water isolation valve is modulated to control HRC condenser flow rate to 1080 gpm as measured at HRC condenser differential pressure transmitter
   b. Condenser water is bypassed through plate and frame heat exchanger (HX-1) at variable flow rates that rejects condenser heat to the cooling towers. HX-1 condenser water three way diverting valve is positioned to bypass all condenser water through HX-1.
8. BMS will calculate the cooling / heating loads and determine the number of HRC's to run and the mode in which they will run.
   a. Total cooling loads below 1,500 tons with simultaneous heating hot water loads will be met by running the HRC in heat recovery mode.
   b. HX-1 may be utilized when total cooling load exceeds simultaneous total heating load to fully /partially dump excess heat to the cooling towers.
9. When CUP total cooling load exceeds 1,500 tons, the larger 2,000 ton centrifugal chillers are staged on in combination with the heat recovery chillers.
   a. The BMS will command the operating HRC's to enter into load limiting to create a nominal 300 ton chilled water load for the 2,000 ton centrifugal chiller (minimum stable operating load). The HRC % load limit will be variable and calculated based on the current chilled water flow rate through the 2,000 ton chiller and differential water temperature deviation from set point (42 °F adjustable).
   b. If the HRC load falls below allowable minimum HRC capacity, active HRC'ers will be staged off sequentially until the HRC'ers are in a stable operating zone.
   c. The 2,000 ton chiller will start and run to maintain 42 °F discharge water unless
      1. The chilled water is already at 42 °F
      2. The flow through the 2,000 ton chiller is less than 1,200 gpm
      3. The total chilled water load is less than 900 tons.
      4. The 2,000 ton chiller load is less than 250 tons.
      5. The chiller minimum off timer has not timed out.
   d. The BMS will decrease / increase the HRC load limit as the total chilled water system load decreases / increases. The HRC's will exit load limiting whenever the total system load
      1. Increases above 1,800 tons
      2. Decreases below 900 tons and the 2,000 ton chiller is returned to standby mode.
   e. When the chilled water flow through the lead 2,000 ton chiller exceeds 3,200 gpm (adjustable) a second 2,000 ton chiller CHW and CTW isolation valves will open, and the lag 2,000 ton chiller will be staged on. After the second 2,000 ton chillers will follow suit based on BMS energy optimization control algorithms.

C. HEAT RECOVERY CHILLER SIDE STREAM CHW PUMPS

1. Three 1,400 gpm HR CHW pumps (N+1 quantity) circulate chilled water through the active heat recovery chiller's evaporators in the HR CHW sidecar loop. Lead HRCW side stream pump starts and runs when the lead HRC runs.
   a. The BMS stages the HRC CHWP pumps on / off. BMS modulates the pump VSD's pump speed to meet HRC side stream loop flow set point.
   b. Based on HRC mode and CHW load the BMS determines the HRC side stream circulation flow rate and number of HR CHW pumps to run.
   c. The BMS indexes the VSD pump speed to correspond to the operational mode and number of active HRC's. When multiple HR CHW pumps run, they are run at the same speed.
   d. The heat recovery loop CHWR flow is measured and monitored by the BMS at CHWR-FM-02 downstream of the HR CHW pumps. The CHWR flow is used as HR CHW pump VSD control feedback. Pump VSD speed is modulated to maintain HRC side stream loop set point.
   e. The CHWR flow through the HRC's is stepped and varies with operational mode.
      1. In heat recovery mode the BMS modulates each active HRC CHW isolation valve to maintain 450 gpm as measured by the HRC chiller evaporator differential pressure transmitter.
      2. In cooling only mode the BMS modulates each active HRC CHW isolation valve to maintain 540 gpm as measured by the HRC chiller evaporator differential pressure transmitter
2. The HRC chilled water flows back into the 36" CHWR main up stream of the 2,000 ton centrifugal chillers.

D. CENTRIFUGAL CHILLERS

1. When the CHW system is enabled, the lead 2,000 ton chiller is placed in standby.
   a. The lead chiller CHW isolation valve is opened and CHWR is allowed to flow through the chiller. The chiller refrigeration circuit will be locked out.
   b. The BMS calculates total CHW system load based on system flow as measured at CHWS-FM-01 and supply/ return differential temperature. The BMS determines which chillers and how many chillers to run.
   c. The HRC are preferentially loaded. CHW from the HRC sidecar loop is sent to the lead 2,000 ton centrifugal chiller. When the total CHW system load exceeds the HRC capacity (900 tons to 1500 tons), and CHW system flow rate is greater than 1,200 gpm the 2,000 ton chiller refrigeration system is enabled. The chiller compressor may or may not run depending on the campus CHW and HHW simultaneous cooling and heating loads and the HRC operating status.
   d. When the centrifugal chiller refrigeration system is enabled and the chiller compressor is needed the 2,000 ton lead chiller
      1. Condenser water isolation valve will open
      2. Chilled water lead pump will start and run if it not already running.
      3. The chiller CTW flow switch will establish proof of chiller CTW flow.
      4. The chiller DDC controls will start the chiller in accordance with the chiller DDC startup sequence.
      5. The chiller compressor will be free to start and run according to the Chiller on board DDC controls.
2. When the BMS calculates that the total chilled water load has or will exceed the total heat recovery chiller capacity and the cooling load is increasing or expected to increase,
   a. The BMS will command the operating HRC's to enter into load limiting to create a nominal 300 ton chilled water load for the lead 2,000 ton centrifugal chiller (2,000 ton minimum stable operating load).
   b. The HRC % load limit will be variable and calculated based on the current chilled water flow rate through the lead 2,000 ton chiller and lead 2,000 ton chiller differential water temperature deviation from set point.
   c. The BMS will command the active HRC's VFD's to limit the HRC speed and power to the calculated set point. This will reduce the cooling and heating ability of the HRC's and create the 300 ton chilled water load for the lead 2,000 ton chiller.
   d. The HRC's operating envelope is highly dependent on the HRC required lift. If the HRC's cooling load falls below allowable minimum HRC capacity, active HRC's will be staged off sequentially, shifting load to the remaining active HRC's until the remaining active HRC's are in a stable operating zone.
   e. The 2,000 ton chiller will start and run to maintain 42 °F discharge water unless
      1. The chilled water is already at 42 °F
      2. The flow through the 2,000 ton chiller is less than 1,200 gpm
      3. The total chilled water load is less than 900 tons.
      4. The 2,000 ton chiller load is less than 250 tons.
      5. The 2,000 ton chiller compressor minimum off timer has not timed out.
   f. The BMS will decrease / increase the HRC load limit as the total chilled water system load decreases / increases. The HRC's will exit load limiting whenever the total system load
      1. Increases above 1,800 tons (2,000 ton chiller and HRC's both run based on load)
      2. Decreases below 900 tons and the 2,000 ton chiller is returned to standby mode.
   g. When the chilled water flow through the lead 2,000 ton chiller exceeds 3,200 gpm (adjustable) a second 2,000 ton chiller will be staged on. After the second 2,000 ton chiller is online the subsequent 2,000 ton chillers will be staged on / off by the BMS to maximize energy savings.
3. Add a Chiller when one is already running: Simultaneously do the following:
   a. Calculate chiller and campus chilled water load. When all operating chillers are loaded to 100% flow capacity or 75 % load for 15 minutes and weather forecast / BMS historical chilled water system load data indicates chilled water load are likely to increase in the next 30 minutes, bring next chiller in succession online.
   b. Unload any operating chillers to 40% load while maintaining operating chilled water pump(s) speed / flow rate(s).
      1. Allow chilled water supply temperature to float without chiller control action temporarily until next chiller brought online (5 minutes adjustable).
   c. Open next chiller condenser water isolation valve
   d. Open next cooling tower return water isolation valve.
   e. Start next cooling tower pump. Modulate VSD to establish condenser flow uniformly across all active 2,000 ton chillers.
   f. Open next chiller chilled water isolation valve.
   g. Start next chilled water pump. Modulate VSD to establish evaporator flow uniformly across all active 2,000 ton chillers.
   h. Modulate chilled water and tower water bypass valves when necessary.
   i. BMS returns control to chiller DDC discharge temperature controller.
   j. Chilled water and condenser water pumps modulate for pressure control in unison.
4. Remove Chiller: Simultaneously do the following:
   a. Calculate chiller and campus chilled water load. When all operating chillers are loaded to 40% capacity for 15 minutes and / or chilled water system flow drops to 40% design flow for 15 minutes and weather forecast / BMS historical chilled water system load data indicates chilled water load are likely to decrease in the next 30 minutes, remove a chiller in reverse order of adding chillers.
   b. Unload any operating chillers and allow chilled water temperature to float without chiller control action temporarily until chiller is offline and associated cooling towers, chilled water and cooling tower pumps are offline.
   c. Stop lag chiller per chiller shutdown sequence. Close chiller chilled water inlet isolation valve after manufacturer recommended time delay.
   d. BMS to determine required number of CHW pumps needed. Stop lag chilled water pump if needed, and modulate operating chilled water pumps to control chilled water supply / return main differential pressure set point.
   e. Close chiller condenser isolation valve.
   f. Stop cooling tower lag pump. Remaining pump VFD's modulate to control condenser water supply / return differential pressure.
   g. Determine if all operational cooling towers should remain operational (there may be energy savings by operating one more cooling than operating chiller. BMS to calculate projected hp and select equipment to operate.)
      1. If so split flow across all operating towers equally.
      2. If not, then close lag cooling tower inlet motor operated valve. Allow flow to distribute equally over operating cooling tower.

E. CHILLED WATER DISTRIBUTION PUMPS:

1. There are seven (7) parallel chilled water variable primary distribution pumps located in the CUP CHWS piping (The pump quantity has N+1 redundancy).
   a. The BMS stages the pumps on / off and modulates their VFD speed to maintain a differential pressure of 65 psig between the CHWS and CHWR mains at the CHWS/R differential pressure transmitter located in the utility tunnel chilled water piping mains at the hospital entrance.
   b. The lead CHW pump is always enabled. The BMS controls all active CHWS distribution pumps to run at the same speed.
   c. The distribution pumps are designed for 3,000 gpm per pump (design flow rate of a 2,000 ton chiller). The BMS will calculate the apparent number of chilled water pumps required based on system flow rate and cooling load.
      1. When flow per pump exceeds 2,000 gpm and the BMS determines energy saving can be had by running an additional pump an additional pump will be started.
      2. When minimum allowable flow per pump is less than 1,000 gpm a running pump will be stopped to protect the pumps.
2. Pump VSD ramp rate will set to 10% / minute (adjustable).
3. BMS will monitor IUHMC control valve positions and implement differential pressure rest based on IUHMC valve position.

F. CHILLED WATER DISTRIBUTION BYPASS VALVE:

1. The chilled water distribution bypass valve is located in the CUP between the CHWS/R 36" mains at the tunnel entrance.
2. The BMS will open and modulate the bypass valve to maintain minimum CHW flow to protect the operating chillers.
   a. Chillers
      1. The minimum CHW flow through a heat recovery chillers is 450 gpm.
      2. The minimum chilled water flow through a 2,000 ton is 1,200 gpm.
      3. The BMS will monitor the active chillers and the CHWS flow and modulate the bypass valve to maintain minimum flow per number of active chillers if the total CHWS flow is less than the calculated minimum flow.
3. The BMS will open and modulate the bypass valve to maintain minimum CHW flow to protect the operating distribution pumps.
   a. CHW Pumps
      1. The minimum CHW distribution pump flow is 932 gpm.
4. The BMS will monitor the number of active distribution pumps and the total CHWS flow and modulate the bypass valve to maintain the minimum CHW distribution pump flow based on the number of active chilled water pumps.
5. Chilled water pump pressure control PID loop and chilled water control bypass valve PID loops work in concert with each other. For stability, the chilled water pressure control loop time period is reset once per second and the chilled water bypass control valve loop time period is reset once per ten seconds.

G. CHW SYSTEM FLOW METERING

1. The chilled water is piped to / from the CUP to the hospital and support buildings through 36" CHWS&R mains located in a tunnel beneath Senate Avenue. A flow meter is installed in the 36" CHWS pipe in the CUP before the bypass valve. The flow signal is sent to the BMS.
2. A second flow meter is installed in the 36" CHWR in the tunnel after branch piping to SSB building upstream of the CUP CHW bypass valve. The flow signal is sent to the BMS.
3. Each chiller evaporator and condenser has a differential pressure transmitter calibrate for flow through the respective device. The flow signal is sent to the BMS.

H. CHILLER PLANT OPTIMIZATION

1. Chillers and associated pumps are enabled/ disabled by the building BMS. The BMS and chiller controllers' control and coordinate the staging of equipment and equipment operating speed to minimize total chilled water plant energy consumption. Advanced control algorithms, weather forecasts and historic data are used to predict and calculate energy usage and when and how equipment will operate to meet the campus load. The chiller staging controllers' actions are based upon .
   a. Campus Chilled Water Load: Chilled water load as determined by the chilled water flow rate to the campus and chilled water supply / return temperature difference,
   b. Campus simultaneous heating hot water load and use of heat recovery chillers to meet chilled water and heating hot water demand.
   c. Individual Chiller Operating Power: Chiller amperage compared to chiller full load amperage maybe used as a surrogate for chilled water
   d. Cooling Tower Condenser Supply / Return Water Temperature
   e. Tower Water Pump Speed: Tower water supply/ return differential pressure.
   f. Tower Water number of Pumps: Number of Chillers running.
   g. Chiller Condenser Water Flow: Chiller condenser water supply / return differential pressure.
   h. Chiller Condenser Water: Number of Chillers running
   i. Heating hot water
   j. Building occupancy time of day schedule and equipment run time schedules
   k. Campus historical weather and space set point data and building equipment historical operating data
2. Chilled-Water System Occupied Time Schedule:
   a. Chillers have a 24 hour per day, seven day per week, 365 day per year time of day schedule with four adjustable enabled / disabled time periods per day. Chillers have separate time of day schedules for weekends, holidays, and weekdays. Time of day schedules will:
      1. Enable startup, initiation, and control of chilled water and tower water system based on day type and occupied / unoccupied schedules.
3. Run Time Alternate Chillers and pumps:
   a. Operate chillers, and associated pumps on 14 day (adjustable) *lead-lag-next up* schedule, alternating based on adjustable 366 hour set point. When time elapses rotate *lead-lag-next up* designation, so *lag* becomes *lead*, *next up* becomes *lag* and *lead* becomes *last next up*. Provide control expansion provisions for future 7th and 8th centrifugal chiller and associated pumps.

I. INDICATE ON THE OPERATOR'S WORKSTATION DISPLAY TERMINAL:

1. DDC system graphic.
2. DDC system status, on-off.
3. Outdoor temperature.
4. Cooling (software) demand indication.
5. Time and time schedule.
6. Condenser-water flow indication.
7. Chilled-water pump(s) on-off status (enabled or disabled).
8. Chilled-water pump(s) on-off indication (operating or not operating).
9. Chilled-water flow indication.
10. Refrigeration machine on-off indication (operating or not operating).
11. Chilled-water supply temperature.
12. Chilled-water return temperature.
13. Chilled-water temperature control-point adjustment.
14. Chiller(s) on-off status (enabled or disabled).
15. Chiller(s) on-off indication (operating or not operating).
16. Chiller "failure-to-start" indication.
17. Expansion tank low-level alarm.
18. Condenser-water control-valve position.
19. Condenser-water supply temperature.
20. Chiller(s) power input (instantaneous).
21. Chilled-water pressure drop through chiller.
22. Chilled-water flow through chiller.
23. Condenser-water pressure drop through chiller.
24. Condenser-water flow through chiller.
25. Chiller condenser-water supply and return temperature.
26. Chiller chilled-water supply and return temperature.
27. System capacity in tons.

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:05 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DS	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

CENTRAL CHILLED-WATER SYSTEM SEQUENCES

SHEET NUMBER

M704



1 **CUP CHILLED WATER FLOW DIAGRAM**
Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:05 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DS	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


CUP CHILLED WATER SYSTEM PI&D

SHEET NUMBER

M705

NOTES:

1. TEFLON LINED ACID PIPE TO BE MANUFACTURED WITH AS FEW JOINTS AS POSSIBLE.
2. FLANGES AND VALVES FOR ACID AND BLEACH PIPING SHALL BE PROVIDED WITH SAFETY SHIELDS TO PROTECT FROM LEAKS.
3. PROVIDE HEAT TRACE AND 2" INSULATION FOR OUTSIDE CHEMICAL TANKS AND PIPING.



1 **CHEMICAL TREATMENT P&ID**
Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:05 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	AW
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154


CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

CHEMICAL TREATMENT P&ID

SHEET NUMBER

M708



DESIGN CRITERIA	
STM TO HOSPITAL	42,000 lb/hr
LP RETURNS	80% OF STM TO PLANT
LP RET TEMP	180°F
MAKE-UP WATER TEMP	60°F
CB AS % OF STM OUT OF BOILER	3.0%
CBHX BLOWDOWN DISCHARGE TEMP	65°F
BOILER PRESSURE	125 PSIG
DA PRESSURE	5 PSIG

1 **STEAM P&ID**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:06 PM AESI Proj. No.: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AW	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

STEAM P&ID

SHEET NUMBER

M709



1 **HEATING HOT WATER SYSTEM P&ID**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:06 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	LB
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154


CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

HEATING HOT WATER SYSTEM P&ID

SHEET NUMBER

M710



1 **CUP HEATING HOT WATER FLOW DIAGRAM**
Scale: 12" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	CERTIFICATION
DS	PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY	
AESI	
APPROVED BY	
Approver	
PROJECT NO.	
21-154	

SHEET TITLE


CUP HEATING HOT WATER SYSTEM P&ID

SHEET NUMBER


M711

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:07 PM AESI Proj. No.: 21-154



2 TYPICAL DAY TANK ARRANGEMENT
Scale: NONE



1 GENERATOR FUEL OIL P&ID
Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:36:07 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	AESI
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154


CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

GENERATOR FUEL OIL P&ID

SHEET NUMBER

M712



LOWER LEVEL HVAC PLAN- AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS

(#) PLAN NOTES:

1. INSTALL HEATING ONLY FAN COIL UNIT IN LOCATION ON STAIRWELL SHOWN. MOUNT UNIT FLUSH WITH WALL. SEE DETAIL X ON SHEET M50X.
2. SUPPLY AIR DUCT FROM MUA-2-2 THROUGH FIRST FLOOR SLAB. SEE SHEET H304 FOR CONTINUATION. CONTRACTOR SHALL INSTALL FIRE DAMPER IN SLAB. SEE DETAIL 'X' ON SHEET M50X. DUCT IN TUNNEL IS OPEN ENDED.
3. MAU-2-2 COMBINATION THERMOSTAT/HUMIDISTAT MOUNTED ON TUNNEL WALL AT LOCATION SHOWN.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

LOWER LEVEL HVAC PLAN - AREA A

SHEET NUMBER


H301



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:00:31 PM AESI Proj. No: 21-154




FIRST FLOOR HVAC PLAN - AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. BLOWER COIL UNIT SUSPENDED FROM STRUCTURE AT LOCATION SHOWN. SEE STRUCTURAL SHEETS FOR MOUNTING DETAIL.
2. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. CHILLER ROOM EMERGENCY REFRIGERANT EXHAUST DUCT ROUTED AS SHOWN. PROVIDE CONTROL DAMPER AND BALANCING DAMPER IN VERTICAL SEGMENT OF DUCT. EXHAUST GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
5. SUPPLY AIR DUCT FROM MUA-2-2. SEE SHEETS H301 AND H310 FOR CONTINUATION. CONTRACTOR SHALL POSITION FIRE DAMPER IN SLAB OF FIRST FLOOR WHERE DUCT PASSES INTO TUNNEL BELOW. SEE DETAIL 7' ON SHEET H501.
6. INSTALL SUSPENDED FAN COIL UNIT IN LOCATION SHOWN. INSTALL UNIT PER MANUFACTURER'S SPECIFICATIONS. SEE MECHANICAL DRAWINGS FOR PIPE ROUTING.
7. CHILLER ROOM MAKE UP AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
8. BLOWER COIL UNIT THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
9. BALANCE DAMPER FOR MAKE UP AIR TO FIRST FLOOR CONTROL ROOM. SEE SHEET H305 FOR DUCT CONTINUATION.
10. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL "17" ON SHEET H501.
11. CHILLER ROOM TRANSFER AIR DUCT THROUGH WALL AS SHOWN. PROVIDE BACK DRAFT DAMPER MOUNTED AT WALL INTO CHILLER ROOM.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR HVAC PLAN - AREA A

SHEET NUMBER

H304

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:00:35 PM AESI Proj. No: 21-154



FIRST FLOOR HVAC PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMOBLS AND ABBREVIATIONS.

PLAN NOTES:

1. BLOWER COIL UNIT SUSPENDED FROM STRUCTURE AT LOCATION SHOWN. SEE STRUCTURAL SHEETS FOR DETAIL.
2. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. CHILLER ROOM EMERGENCY REFRIGERANT EXHAUST DUCT ROUTED AS SHOWN. PROVIDE CONTROL DAMPER AND BALANCING DAMPER IN VERTICAL SEGMENT OF DUCT. EXHAUST GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
5. CHILLER ROOM GENERAL EXHAUST GRILLE. PROVIDE CONTROL DAMPER AND BALANCING DAMPER.
6. BLOWER COIL UNIT THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
7. EXHAUST GRILLE IN LAY-IN CEILING. COORDINATE WITH REFLECTED CEILING PLAN IN ARCHITECTURAL DRAWINGS.
8. 20" BOILER FLUE ROUTED AS SHOWN. BOILER FLUE SHALL SLOPE DOWNARD TOWARD BOILER OUTLET AT 1/4"/L.F. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. BOILER FLUES UP TO FLOOR ABOVE. SEE SHEET H311 FOR CONTINUATION.
9. CONNECT BOILER FLUE TO BOILER. REFER TO MANUFACTURER INSTRUCTIONS FOR CONNECTION DETAILS. PROVIDE CONDENSATE NEUTRALIZATION KITS FOR FLUE DRAINS AT EACH BOILER.
10. BOILER FLUE UP TO FLOOR ABOVE. SEE SHEET H311 FOR CONTINUATION.
11. SUPPLY AIR DUCT TO EQUIPMENT MEZZANINE. SEE DETAIL 1 ON SHEET H402 FOR CONTINUATION.
12. BOILER FLUE CONTINUES ON MEZZANIE. SEE DETAIL 1 ON SHEET H402 FOR CONTINUATION.
13. CHILLER ROOM MAKE UP AIR DUCT ROUTED AS SHOWN. CONNECT INTO RETURN AIR DUCT FOR FIRST FLOOR CONTROL ROOM AT LOCATION INDICATED. BALANCE DUCT TO PROVIDE 35 CFM OF MAKE UP AIR TO CONTROL ROOM. SEE SHEET H304 FOR BALANCE DAMPER LOCATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
14. PROVIDE DRAINS AND CONDENSATE NEUTRALIZATION KITS FOR FLUE DRAINS AT BOTTOM OF RISERS.
15. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL "I" ON SHEET H501.
16. DRUM LOUVER DIFFUSER WITH INTEGRAL BALANCING DAMPER MOUNTED ON DUCT POINTED DOWNWARD TOWARD BOILER BURNER INTAKE. PROVIDE CONTROL DAMPER IN DUCT AND INTERLOCK TO OPEN WITH ASSOCIATED BOILER'S ACTIVATION. ANGLE DIFFUSER DOWN TOWARDS BURNER INTAKE WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT.
17. DESIGNATED LOCATION FOR BAS CONTROLS PANEL. COORDINATE EXACT LOCATION IN ROOM WITH OTHER DISCIPLINES. SEE ELECTRICAL SHEETS FOR POWER INFORMATION.
18. CHILLER ROOM TRANSFER AIR DUCT THROUGH WALL AS SHOWN. PROVIDE BACK DRAFT DAMPER MOUNTED AT WALL INTO CHILLER ROOM.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR HVAC PLAN - AREA B

SHEET NUMBER

H305

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:00:44 PM AESI Proj. No: 21-154




FIRST FLOOR HVAC PLAN - AREA C
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMOBLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. BLOWER COIL UNIT SUSPENDED FROM STRUCTURE AT LOCATION SHOWN. SEE STRUCTURAL SHEETS FOR DETAIL.
2. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EMERGENCY BOILER ROOM OUTDOOR AIR LOUVER LOCATED IN WALL AS SHOWN. SEE PLANS FOR SIZE. EXTEND PLENUM NO LESS THAN 36" FROM BACK OF LOUVER INTO BUILDING. SEE DETAIL "12' ON SHEET H501.
4. SUPPLY AIR DUCT TO EQUIPMENT MEZZANINE. SEE DETAIL 1 ON SHEET H402 FOR CONTINUATION.
5. CONNECT BOILER FLUE TO BOILER AND BOILER ECONOMIZER. REFER TO MANUFACTURER INSTRUCTIONS FOR CONNECTION DETAILS. ECOMIZER TO BE SUPPORTED BY BOILER USING MANUFACTURER'S PROVIDED ECONOMIZER SUPPORT STEEL.
6. 20" BOILER FLUE ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. BOILER FLUES UP TO FLOOR ABOVE. SEE SHEET H312 FOR CONTINUATION. PROVIDE DRAINS AND CONDENSATE NEUTRALIZATION KITS FOR FLUE DRAINS AT BOTTOM OF RISERS.
7. 24" BOILER FLUE ROUTED AS SHOWN. PROVIDE TEE WITH DRAIN PIPE TO FLOOR AT BOTTOM OF RISER. SEE SHEET H312 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEED SEISMIC ZONE C REQUIREMENTS.
8. INSTALL SUSPENDED FAN COIL UNIT IN LOCATION SHOWN. INSTALL UNIT PER MANUFACTURER'S SPECIFICATIONS. SEE MECHANICAL DRAWINGS FOR PIPE ROUTING.
9. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL "17' ON SHEET H501.
10. BLOWER COIL UNIT THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
11. PROVIDE DRAINS AND CONDENSATE NEUTRALIZATION KITS FOR FLUE DRAINS AT BOTTOM OF RISERS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR HVAC PLAN - AREA C

SHEET NUMBER

H306

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:00:49 PM AESI Proj No: 21-154



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMOBLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. BLOWER COIL UNIT SUSPENDED FROM STRUCTURE AT LOCATION SHOWN. SEE STRUCTURAL SHEETS FOR DETAIL.
2. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. CHILLER ROOM MAKE UP AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. CHILLER ROOM EMERGENCY REFRIGERANT EXHAUST DUCT ROUTED AS SHOWN. PROVIDE CONTROL DAMPER AND BALANCING DAMPER IN VERTICAL SEGMENT OF DUCT. EXHAUST GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
5. INSTALL VERTICAL WALL INSET FAN COIL UNIT IN LOCATION SHOWN. INSTALL UNIT PER MANUFACTURER'S SPECIFICATIONS. SEE MECHANICAL DRAWINGS FOR PIPE ROUTING.
6. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL '17' ON SHEET H501.
7. FUEL PUMP ROOM EXHAUST DUCT ROUTED AS SHOWN. PROVIDE VOLUME DAMPER IN VERTICAL DUCT. EXHAUST GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
8. FUEL PUMP ROOM SUPPLY DUCT ROUTED AS SHOWN. PROVIDE VOLUME DAMPER IN VERTICAL DUCT. SUPPLY GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
9. CHILLER ROOM SUPPLY AIR FROM ABOVE. SEE H313 FOR CONTINUATION FROM MUA-2-1.
10. CHILLER ROOM EXHAUST AIR UP THROUGH CEILING. SEE H313 FOR CONTINUATION TO MAU-2-1 AND REF-1&2.
11. EXHAUST AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
12. BLOWER COIL UNIT, REHEAT COIL OR MAKE UP AIR UNIT THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
13. DUCT MOUNTED RE-HEAT COIL IN LOCATION INDICATED. SEE DETAILS '2' & '3' ON SHEET H502.
14. FUEL PUMP ROOM EXHAUST AIR UP THROUGH CEILING. SEE H313 FOR CONTINUATION TO EF-1-1.

FIRST FLOOR HVAC PLAN - AREA D

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR HVAC PLAN - AREA D

SHEET NUMBER

H307

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:00:55 PM AESI Proj. No.: 21-154



FIRST FLOOR HVAC PLAN - AREA E


Scale: 1/4" = 1'-0"

PLAN NOTES:

1. BLOWER COIL UNIT SUSPENDED FROM STRUCTURE AT LOCATION SHOWN. SEE STRUCTURAL SHEETS FOR DETAIL.
2. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. CHILLER ROOM EMERGENCY REFRIGERANT EXHAUST DUCT ROUTED AS SHOWN. PROVIDE CONTROL DAMPER AND BALANCING DAMPER IN VERTICAL SEGMENT OF DUCT. EXHAUST GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
5. DUCT TO EQUIPMENT MEZZANINE. SEE DETAIL 1 ON SHEET H402 FOR CONTINUATION.
6. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL '17' ON SHEET H501.
7. CHILLER ROOM GENERAL EXHAUST GRILLE. PROVIDE CONTROL DAMPER AND BALANCING DAMPER.
8. OUTDOOR AIR DUCT ROUTED AS SHOWN. MODULATING CONTROL DAMPER MOUNTED IN DUCT AT LOCATION INDICATED. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
9. OPEN RETURN DUCT WITH MODULATING CONTROL DAMPER MOUNTED ON TOP OF DUCT AT LOCATION INDICATED.
10. RETURN AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
11. OUTDOOR AIR LOUVER LOCATED IN WALL AS SHOWN. SEE PLANS FOR SIZE, BOTTOM OF LOUVER SHALL BE AS NOTED ON PLANS. EXTEND PLENUM NO LESS THAN 36" FROM LOUVER INTO BUILDING. SEE DETAIL '12' ON SHEET H501.
12. BLOWER COIL UNIT OR AIR HANDLING UNIT THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMOBLS AND ABBREVIATIONS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: SRB	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR HVAC PLAN - AREA E

SHEET NUMBER

H308

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:00:59 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMOBLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
2. SUPPLY AIR DUCT TO EQUIPMENT MEZZANINE. SEE DETAIL 1 ON SHEET H402 FOR CONTINUATION.
3. OUTDOOR AIR DUCT ROUTED AS SHOWN. MODULATING CONTROL DAMPER MOUNTED IN DUCT AT LOCATION INDICATED. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. OPEN RETURN DUCT WITH MODULATING CONTROL DAMPER MOUNTED ON TOP OF DUCT AT LOCATION INDICATED.
5. RETURN AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
6. OUTDOOR AIR LOUVER LOCATED IN WALL AS SHOWN. SEE PLANS FOR SIZE, BOTTOM OF LOUVER SHALL BE AS NOTED ON PLANS. EXTEND PLENUM NO LESS THAN 36" FROM LOUVER INTO BUILDING. SEE DETAIL '12' ON SHEET H501.
7. DUCTWORK CONTINUES ON MEZZANIE. SEE DETAIL 1 ON SHEET H402 FOR CONTINUATION.
8. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL '17' ON SHEET H501.
9. AIR HANDLING UNIT, REHEAT COIL OR MAKE UP AIR UNIT THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.

FIRST FLOOR HVAC PLAN - AREA F

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: SRB	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


FIRST FLOOR HVAC PLAN - AREA F

SHEET NUMBER

H309

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:03 PM AESI Proj. No: 21-154

0 1/2" 1" 2"



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

PLAN NOTES:

1. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
2. VAV BOX SUSPENDED IN SUPPLY AIR DUCT AT LOCATION INDICATED. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST AIR DUCT ROUTED AS SHOWN. EXHAUST AIR DUCT ROUTED THROUGH TO ROOF. SEE SHEET H316 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. RETURN AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
5. CONTRACTOR SHALL CONNECT GENERATOR RADIATOR FANS THROUGH WALL WITH DUCTWORK AND FLEXIBLE CONNECTORS. ALIGN DUCTWORK TO BE CENTERED WITH GENERATOR RADIATOR FAN. COORDINATE WITH GENERATOR MANUFACTURER FOR APPROVED CONNECTION METHODS TO GENERATOR RADIATOR FAN. SPRING OPEN, MOTORIZED CONTROL DAMPER SHALL BE MOUNTED TO DUCTWORK AT WALL.
6. RETURN AIR DUCTWORK MOUNTED THROUGH WALL AT LOCATION INDICATED ABOVE GENERATOR RADIATOR FAN. MODULATING CONTROL DAMPER SHALL BE MOUNTED TO DUCTWORK AT WALL.
7. GENERATOR FLUE ROUTED UP THROUGH ROOF AS SHOWN. SEE SHEET H316 FOR CONTINUATION. GENERATOR FLUE TO CONNECT TO GENERATOR EXHAUST SILENCER AT LOCATION INDICATED. SEE STRUCTURAL DRAWINGS FOR GENERATOR SILENCER SUPPORTS.
8. GENERATOR RELIEF AIR PLENUM SOUND ATTENUATORS POSITIONED AS SHOWN. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
9. GENERATOR RADIATOR FAN DISCHARGE LOUVER ARRAY LOCATED IN WALL AS SHOWN. SEE DETAIL '13' ON SHEET H501. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
10. CONTRACTOR TO PROVIDE 2" THICK, BUILT UP AIR HANDLER CASING AROUND SOUND ATTENUATORS AND SOUND ATTENUATOR STRUCTURAL FRAMING. SEAL CASING PER EXHAUST AIR PLENUM PRESSURE RATING IN SPECIFICATIONS.
11. GENERATOR ROOM AIR INLET FROM AIR MONITORS ABOVE. SEE SHEET H316 FOR AIR MONITOR PLANS. SEE STRUCTURAL AND ARCHITECTURAL SHEETS FOR FLOOR FRAMING OPENING. COORDINATE WITH ALL DISCIPLINES TO KEEP OPENING FREE OF OBSTRUCTIONS.
12. BOTTOM DISCHARGE, TOP RETURN COMPUTER ROOM AIR CONDITIONER POSITIONED AS SHOWN. UNIT SHALL BE POSITIONED ON FLOOR STAND WITH FACTORY SUPPLIED SUPPLY AIR CONNECTIONS. SEE MECHANICAL SHEETS FOR PIPING CONNECTIONS.
13. SPRING CLOSE, MOTORIZED DAMPER FOR CRAC UNIT DUCTWORK SHALL BE MOUNTED AT MDF ROOM WALL.
14. GENERATOR ROOM THERMOSTAT MOUNTED ON COLUMN AT LOCATION SHOWN. MONITORS GENERATOR ROOM TEMPERATURE DURING GENERATOR OPERATION.
15. MAU-2-2 MOUNTED ON EQUIPMENT PAD AT LOCATION INDICATED. SEE STRUCTURAL SHEETS FOR EQUIPMENT PAD DETAILS. DASHED LINES INDICATED EQUIPMENT SERVICE CLEARENCES. COORDINATE WITH ALL DISCIPLINES TO KEEP SERVICE CLEARENCES FREE OF OBSTRUCTIONS. SEE MECHANICAL SHEETS FOR PIPE ROUTING. SEE ELECTRICAL SHEETS FOR ELECTRICAL CONNECTION DETAILS.
16. OUTDOOR AIR DUCT UP THROUGH ROOF. SEE H316 FOR CONTINUATION.
17. SUPPLY AIR DUCT DOWN THROUGH SLAB TO FIRST FLOOR AND UTILITY TUNNEL. SEE H304 FOR CONTINUATION.
18. DIFFUSER IN LAY-IN CEILING. SEE DETAILS '9' & '11' ON SHEET H501. COORDINATE WITH REFLECTED CEILING PLAN IN ARCHITECTURAL DRAWINGS.
19. RETURN GRILLE IN LAY-IN CEILING. SEE DETAIL '10' ON SHEET H501.COORDINATE WITH REFLECTED CEILING PLAN IN ARCHITECTURAL DRAWINGS.
20. INSTALL SUSPENDED FAN COIL UNIT IN LOCATION SHOWN. INSTALL UNIT PER MANUFACTURER'S SPECIFICATIONS. SEE MECHANICAL DRAWINGS FOR PIPE ROUTING.
21. FUEL TANK ROOM EXHAUST DUCT ROUTED AS SHOWN. EXHAUST GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
22. FUEL TANK ROOM TRANSFER AIR DUCT ROUTED AS SHOWN. PROVIDE BACK DRAFT DAMPER MOUNTED AT WALL INTO FUEL TANK ROOM. TRANSFER GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
23. EXHAUST AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. BALANCE DAMPER FOR EXHAUST GRILLE MAY BE FOUND ON SHEET H313.
24. UNIT HEATER SUSPENDED AT LOCTION SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. SEE MECHANICAL DRAWINGS FOR PIPE ROUTING. SEE DETAIL '8' ON SHEET H501.
25. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL '17' ON SHEET H501.
26. TRANSFER AIR GRILLE LOCATED IN WALL AT LOCATION SHOWN.
27. FINNED TUBE RADIATOR, UH, CRAC UNIT OR VAV BOX THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
28. OUTDOOR AIR MAKE UP GRILLE TO GENERATOR ROOM. SEE MEZZANINE PLAN ON SHEET H401 FOR DUCT CONTINUATION.

SECOND FLOOR HVAC PLAN - AREA A

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:09 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR HVAC PLAN - AREA A

SHEET NUMBER

H310



SECOND FLOOR HVAC PLAN - AREA B


Scale: 1/4" = 1'-0"

PLAN NOTES:

1. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
2. EXHAUST AIR DUCT ROUTED AS SHOWN. EXHAUST AIR DUCT ROUTED THROUGH TO ROOF. SEE SHEET H318 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F. PROVIDE BALANCE DAMPER IN VERTICAL DUCT.
4. CONTRACTOR SHALL CONNECT GENERATOR RADIATOR FANS THROUGH WALL WITH DUCTWORK AND FLEXIBLE CONNECTORS. ALIGN DUCTWORK TO BE CENTERED WITH GENERATOR RADIATOR FAN. COORDINATE WITH GENERATOR MANUFACTURER FOR APPROVED CONNECTION METHODS TO GENERATOR RADIATOR FAN. SPRING OPEN, MOTORIZED CONTROL DAMPER SHALL BE MOUNTED TO DUCTWORK AT WALL.
5. RETURN AIR DUCTWORK MOUNTED THROUGH WALL AT LOCATION INDICATED ABOVE GENERATOR RADIATOR FAN. MODULATING CONTROL DAMPER SHALL BE MOUNTED TO DUCTWORK AT WALL.
6. GENERATOR FLUE ROUTED UP THROUGH ROOF AS SHOWN. SEE SHEET H317 FOR CONTINUATION. GENERATOR FLUE TO CONNECT TO GENERATOR EXHAUST SILENCER AT LOCATION INDICATED. SEE STRUCTURAL DRAWINGS FOR GENERATOR SILENCER SUPPORTS.
7. GENERATOR RELIEF AIR PLENUM SOUND ATTENUATORS POSITIONED AS SHOWN. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
8. GENERATOR RADIATOR FAN DISCHARGE LOUVER ARRAY LOCATED IN WALL AS SHOWN, SEE DETAIL '12' ON SHEET H501. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
9. CONTRACTOR TO PROVIDE 2" THICK, BUILT UP AIR HANDLER CASING AROUND SOUND ATTENUATORS AND SOUND ATTENUATOR STRUCTURAL FRAMING. SEAL CASING PER EXHAUST AIR PLENUM PRESSURE RATING IN SPECIFICATIONS.
10. GENERATOR ROOM AIR INLET FROM AIR MONITORS ABOVE. SEE SHEET H317 FOR AIR MONITOR PLANS. SEE STRUCTURAL AND ARCHITECTURAL SHEETS FOR FLOOR FRAMING OPENING. COORDINATE WITH ALL DISCIPLINES TO KEEP OPENING FREE OF OBSTRUCTIONS.
11. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL '17' ON SHEET H501.
12. 20" BOILER FLUE ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. BOILER FLUES UP FROM FLOOR BELOW THROUGH TO ROOF. SEE SHEET H305 AND SHEET H317 FOR CONTINUATION.
13. UNIT HEATER SUSPENDED AT LOCTION SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. SEE MECHANICAL DRAWINGS FOR PIPE ROUTING. SEE DETAIL 8 ON SHEET H502.
14. UH THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
15. GENERATOR ROOM THERMOSTAT MOUNTED ON COLUMN AT LOCATION SHOWN. MONITORS GENERATOR ROOM TEMPERATURE DURING GENERATOR OPERATION.

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:14 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	AESI
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154


CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

SECOND FLOOR HVAC PLAN - AREA B

SHEET NUMBER

H311



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
2. VAV BOX SUSPENDED IN SUPPLY AIR DUCT AT LOCATION INDICATED. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. RETURN AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. CONTRACTOR SHALL PROVIDE EXHUAST AIR DUCT IDENTICAL TO GENERATOR RADIATOR FAN EXHAUST DUCTS THROUGH WALL FOR FUTURE CONNECTION. SPRING OPEN, MOTORIZED CONTROL DAMPER SHALL BE MOUNTED TO DUCTWORK AT WALL. DUCTWORK SHALL BE CAPPED FOR FUTURE USE.
5. RETURN AIR DUCTWORK MOUNTED THROUGH WALL AT LOCATION INDICATED ABOVE GENERATOR RADIATOR FAN. MODULATING CONTROL DAMPER SHALL BE MOUNTED TO DUCTWORK AT WALL. DUCTWORK SHALL BE CAPPED FOR FUTURE USE.
6. LOCATION OF FUTURE GENERATOR EXHAUST FLUE, SEE SHEET H318 FOR CONTINUATION. SEE STRUCTURAL DRAWINGS FOR FUTURE GENERATOR SILENCER SUPPORTS AND ROOF PENETRATION.
7. GENERATOR RELIEF AIR PLENUM SOUND ATTENUATORS POSITIONED AS SHOWN. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
8. GENERATOR RELIEF AIR LOUVER ARRAY LOCATED IN WALL AS SHOWN. SEE DETAIL '12' ON SHEET H501. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
9. CONTRACTOR TO PROVIDE 2" THICK, BUILT UP AIR HANDLER CASING AROUND SOUND ATTENUATORS AND SOUND ATTENUATOR STRUCTURAL FRAMING. SEAL CASING PER EXHAUST AIR PLENUM PRESSURE RATING IN SPECIFICATIONS.
10. GENERATOR ROOM AIR INLET FROM AIR MONITORS ABOVE. SEE SHEET H318 FOR AIR MONITOR PLANS. SEE STRUCTURAL AND ARCHITECTURAL SHEETS FOR FLOOR FRAMING OPENING. COORDINATE WITH ALL DISCIPLINES TO KEEP OPENING FREE OF OBSTRUCTIONS.
11. INSTALL SUSPENDED FAN COIL UNIT IN LOCATION SHOWN. INSTALL UNIT PER MANUFACTURER'S SPECIFICATIONS. SEE MECHANICAL DRAWINGS FOR PIPE ROUTING.
12. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL '17' ON SHEET H501.
13. BOILER FLUES UP FROM FIRST FLOOR AND THROUGH ROOF. SEE SHEET H306 AND SHEET H318 FOR CONTINUATION.
14. UH OR VAV BOX THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
15. UNIT HEATER SUSPENDED AT LOCTION SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. SEE MECHANICAL DRAWINGS FOR PIPE ROUTING. SEE DETAIL '8' ON SHEET H502.
16. EXHAUST AIR DUCT ROUTED AS SHOWN. EXHAUST AIR DUCT ROUTED THROUGH TO ROOF. SEE SHEET H318 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.

SECOND FLOOR HVAC PLAN - AREA C

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR HVAC PLAN - AREA C

SHEET NUMBER

H312

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:19 PM AESI Proj No: 21-154
0 1/2" 1" 2"



SECOND FLOOR HVAC PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

PLAN NOTES:

1. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
2. VAV BOX SUSPENDED IN SUPPLY AIR DUCT AT LOCATION INDICATED. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST AIR DUCT ROUTED AS SHOWN. EXHAUST AIR DUCT ROUTED THROUGH TO ROOF. SEE SHEET H319 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. EXHAUST AIR DUCT ROUTED FROM FIRST FLOOR THROUGH TO ROOF AS SHOWN. SEE SHEET H319 AND SHEET H307 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
5. RETURN AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
6. MAU-2-1 MOUNTED ON EQUIPMENT PAD AT LOCATION INDICATED. SEE STRUCTURAL SHEETS FOR EQUIPMENT PAD DETAILS. SUPPLY AIR DUCT DISHARGES DOWNWARD THROUGH EQUIPMENT PAD. SEE SHEET H307 FOR CONTINUATION. DASHED LINES INDICATED EQUIPMENT SERVICE CLEARENCES, COORDINATE WITH ALL DISCIPLINES TO KEEP SERVICE CLEARENCES FREE OF OBSTRUCTIONS. SEE MECHANICAL SHEETS FOR PIPE ROUTING. SEE ELECTRICAL SHEETS FOR ELECTRICAL CONNECTION DETAILS.
7. OUTDOOR AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL INSTALL SIESMIC BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
8. RELEIF AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL INSTALL SIESMIC BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. DUCT IS ROUTED UP THROUGH ROOF AT LOCATION INDICATED. SEE SHEET H319 FOR CONTINUATION.
9. DIFFUSER IN LAY-IN CEILING. SEE DETAIL '9' ON SHEET H501. COORDINATE WITH REFLECTED CEILING PLAN IN ARCHITECTURAL DRAWINGS.
10. RETURN GRILLE IN LAY-IN CEILING. SEE DETAIL '10' ON SHEET H501.COORDINATE WITH REFLECTED CEILING PLAN IN ARCHITECTURAL DRAWINGS.
11. SUPPLY DIFFUSER FOR GENERATOR CONTROL ROOM SUSPENDED IN ROOM AT 10'-0" A.F.F. AT LOCATION INDICATED.
12. RETURN GRILLE FOR GENERATOR CONTROL ROOM SUSPENDED IN ROOM AT 10'-0" A.F.F. AT LOCATION INDICATED. RETURN DUCT CONTINUES UPWARD THROUGH CEILING INTO EQUIPMENT MEZZANINE. SEE SHEET H401 FOR CONTINUATION.
13. DESIGNATED LOCATION FOR BAS CONTROLS PANEL. COORDINATE EXACT LOCATION IN ROOM WITH OTHER DISCIPLINES. SEE ELECTRICAL SHEETS FOR POWER INFORMATION.
14. DUCT TO EQUIPMENT MEZZANINE. SEE DETAIL 2 ON SHEET H401 FOR CONTINUATION.
15. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL '17' ON SHEET H501.
16. FINNED TUBE RADIATOR OR VAV BOX THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
17. OUTDOOR AIR MAKE UP GRILLE TO GENERATOR ROOM. SEE MEZZANINE PLAN ON SHEET H401 FOR DUCT CONTINUATION.
18. OUTDOOR AIR LOUVER LOCATED IN WALL AS SHOWN. SEE PLANS FOR SIZE, BOTTOM OF LOUVER SHALL BE AS NOTED ON PLANS, EXTEND PLENUM NO LESS THAN 36" FROM LOUVER INTO BUILDING. SEE DETAIL '12' ON SHEET H501.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:25 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR HVAC PLAN - AREA D

SHEET NUMBER

H313



SECOND FLOOR HVAC PLAN - AREA E


Scale: 1/4" = 1'-0"

PLAN NOTES:

1. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
2. VAV BOX SUSPENDED IN SUPPLY AIR DUCT AT LOCATION INDICATED. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST AIR DUCT ROUTED AS SHOWN. EXHAUST AIR DUCT ROUTED THROUGH TO ROOF. SEE SHEET H320 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. EXHAUST AIR DUCT ROUTED FROM FIRST FLOOR THROUGH TO MEZZANINE AS SHOWN. SEE SHEET H401 AND SHEET H308 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
5. RETURN AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
6. DUCT TO EQUIPMENT MEZZANINE. SEE DETAIL 3 ON SHEET H401 FOR CONTINUATION.
7. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL '17' ON SHEET H501.
8. FUEL TANK ROOM EXHAUST DUCT ROUTED AS SHOWN. EXHAUST GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F. A FIRE DAMPER SHALL BE POSITIONED IN THE VERTICAL RISER PASSING INTO THE EQUIPMENT MEZZANINE ABOVE. SEE SHEET H401 FOR CONTINUATION.
9. FUEL TANK ROOM TRANSFER AIR DUCT ROUTED AS SHOWN. PROVIDE BACK DRAFT DAMPER MOUNTED AT WALL INTO FUEL TANK ROOM. TRANSFER GRILLE SHALL BE MOUNTED WITH BOTTOM OF GRILLE LOCATED 1'-6" A.F.F.
10. TRANSFER AIR GRILLE LOCATED IN WALL AT LOCATION SHOWN.
11. VAV BOX THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
21/0/2023 2:01:29 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR HVAC PLAN - AREA E

SHEET NUMBER

H314



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
2. VAV BOX SUSPENDED IN SUPPLY AIR DUCT AT LOCATION INDICATED. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST AIR DUCT ROUTED FROM FIRST FLOOR THROUGH TO MEZZANINE AS SHOWN. SEE SHEET H401 AND SHEET H308 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. RETURN AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
5. OUTDOOR AIR DUCT DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. DUCT ROUTED UP THROUGH ROOF. SEE H321 FOR CONTINUATION.
6. TRANSFER AIR GRILLE LOCATED IN WALL AT LOCATION SHOWN.
7. DRUM LOUVER DIFFUSER SIDE WALL MOUNTED ON DUCT WITH INTEGRAL BALANCING DAMPER. ANGLE DIFFUSER DOWN TOWARDS FLOOR WITH DIFFUSER INTREGRAL PITCH ADJUSTMENT. SEE DETAIL "17' ON SHEET H501.
8. RELEIF AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL INSTALL SIESMIC BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. DUCT IS ROUTED UP THROUGH ROOF AT LOCATION INDICATED. SEE SHEET H321 FOR CONTINUATION.
9. DUCT TO EQUIPMENT MEZZANINE. SEE DETAIL 3 ON SHEET H401 FOR CONTINUATION.
10. UH OR VAV BOX THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
11. OUTDOOR AIR MAKE UP GRILLE TO GENERATOR ROOM. SEE MEZZANINE PLAN ON SHEET H401 FOR DUCT CONTINUATION.
12. DESIGNATED LOCATION FOR BAS CONTROLS PANEL. COORDINATE EXACT LOCATION IN ROOM WITH OTHER DISCIPLINES. SEE ELECTRICAL SHEETS FOR POWER INFORMATION.

SECOND FLOOR HVAC PLAN - AREA F

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


SECOND FLOOR HVAC PLAN - AREA F

SHEET NUMBER

H315

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:34 PM AESI Proj No: 21-154

0 1/2" 1" 2"



ROOF HVAC PLAN - AREA A


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. EXHAUST FAN MOUNTED ON ROOF AT LOCATION INDICATED. EXHAUST AIR DUCT ROUTED FROM SECOND FLOOR TO ROOF. SEE SHEET H310 FOR CONTINUATION OF EXHAUST DUCT. SEE DETAIL '3' ON SHEET H501.
2. OUTDOOR AIR INLET HOOD ON ROOF AT LOCATION INDICATED. OUTDOOR AIR DUCT TO SECOND FLOOR FROM ROOF. SEE SHEET H310 FOR CONTINUATION OF OUTDOOR AIR DUCT. SEE DETAIL '15' ON SHEET H501.
3. GENERATOR AIR MONITOR INLET LOUVER ARRAY LOCATED IN WALL AS SHOWN. BOTTOM OF LOUVERS SHALL BE AT 3'-0" ABOVE ROOFLINE. SEE DETAIL '12' ON SHEET H501. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
4. INSTALL CONTROL DAMPER ARRAY ON BACKSIDE OF LOUVER ARRAY. PROVIDE 10" DEEP PLENUM TO OFFSET DAMPERS FOR MAINTENANCE CLEARANCE FOR DAMPER ACTUATOR. SEAL LOUVERS NOT CONNECTED TO DAMPER PLENUM WEATHER TIGHT WITH LOUVER BLANK OFF PANEL. SEE DETAIL '12' ON SHEET H501.
5. GENERATOR ROOM AIR INLET. SEE SHEET H310 FOR CONTINUATION INTO GENERATOR ROOM BELOW. SEE STRUCTURAL AND ARCHITECTURAL SHEETS FOR FLOOR FRAMING OPENING. COORDINATE WITH ALL DISCIPLINES TO KEEP OPENING FREE OF OBSTRUCTIONS.
6. GENERATOR AIR INLET MONITOR SOUND ATTENUATORS POSITIONED AS SHOWN. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
7. CONTRACTOR TO PROVIDE 2" THICK, BUILT UP AIR HANDLER CASING AROUND SOUND ATTENUATORS AND SOUND ATTENUATOR STRUCTURAL FRAMING. SEAL CASING PER EXHAUST AIR PLENUM PRESSURE RATING IN SPECIFICATIONS.
8. GENERATOR FLUE ROUTED UP THROUGH ROOF AS SHOWN. SEE SHEET H310 FOR CONTINUATION FROM GENERATOR ROOM. SEE DETAIL 'X' ON SHEET H50X.
9. ROOF MOUNTED AIR COOLED CONDENSING UNIT FOR MDF ROOM CRAC UNIT. SEE ARCHITECTURAL SHEETS FOR MOUNTING DETAILS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF HVAC PLAN - AREA A

SHEET NUMBER

H316

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:37 PM AESI Proj No: 21-154



ROOF HVAC PLAN - AREA B


Scale: 1/4" = 1'-0"

PLAN NOTES:

1. EXHAUST FAN MOUNTED ON ROOF AT LOCATION INDICATED. EXHAUST AIR DUCT ROUTED FROM SECOND FLOOR TO ROOF. SEE SHEET H310 FOR CONTINUATION OF EXHAUST DUCT. SEE DETAIL '3' ON SHEET H501.
2. GENERATOR AIR MONITOR INLET LOUVER ARRAY LOCATED IN WALL AS SHOWN. BOTTOM OF LOUVERS SHALL BE AT 3'-0" ABOVE ROOFLINE. SEE DETAIL '12' ON SHEET H501. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
3. INSTALL CONTROL DAMPER ARRAY ON BACKSIDE OF LOUVER ARRAY. PROVIDE 10" DEEP PLENUM TO OFFSET DAMPERS FOR MAINTENANCE CLEARANCE FOR DAMPER ACTUATOR. SEAL LOUVERS NOT CONNECTED TO DAMPER PLENUM WEATHER TIGHT WITH LOUVER BLANK OFF PANEL. SEE DETAIL '12' ON SHEET H501.
4. GENERATOR ROOM AIR INLET. SEE SHEET H310 FOR CONTINUATION INTO GENERATOR ROOM BELOW. SEE STRUCTURAL AND ARCHITECTURAL SHEETS FOR FLOOR FRAMING OPENING. COORDINATE WITH ALL DISCIPLINES TO KEEP OPENING FREE OF OBSTRUCTIONS.
5. GENERATOR AIR INLET MONITOR SOUND ATTENUATORS POSITIONED AS SHOWN. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
6. CONTRACTOR TO PROVIDE 2" THICK, BUILT UP AIR HANDLER CASING AROUND SOUND ATTENUATORS AND SOUND ATTENUATOR STRUCTURAL FRAMING. SEAL CASING PER EXHAUST AIR PLENUM PRESSURE RATING IN SPECIFICATIONS.
7. GENERATOR FLUE ROUTED UP THROUGH ROOF AS SHOWN. SEE SHEET H310 FOR CONTINUATION FROM GENERATOR ROOM. SEE DETAIL 'X' ON SHEET H60X.
8. 20" BOILER FLUE ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. BOILER FLUES UP FROM FLOOR BELOW THROUGH ROOF. SEE SHEET H311 FOR CONTINUATION.

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:42 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF HVAC PLAN - AREA B

SHEET NUMBER

H317




ROOF HVAC PLAN - AREA C
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. GENERATOR AIR MONITOR INLET LOUVER ARRAY LOCATED IN WALL AS SHOWN. BOTTOM OF LOUVERS SHALL BE AT 3'-0" ABOVE ROOFLINE. SEE DETAIL '12' ON SHEET H501. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
2. INSTALL CONTROL DAMPER ARRAY ON BACKSIDE OF LOUVER ARRAY. PROVIDE 10" DEEP PLENUM TO OFFSET DAMPERS FOR MAINTENANCE CLEARANCE FOR DAMPER ACTUATOR. SEAL LOUVERS NOT CONNECTED TO DAMPER PLENUM WEATHER TIGHT WITH LOUVER BLANK OFF PANEL. SEE DETAIL '12' ON SHEET H501.
3. GENERATOR ROOM AIR INLET. SEE SHEET H310 FOR CONTINUATION INTO GENERATOR ROOM BELOW. SEE STRUCTURAL AND ARCHITECTURAL SHEETS FOR FLOOR FRAMING OPENING. COORDINATE WITH ALL DISCIPLINES TO KEEP OPENING FREE OF OBSTRUCTIONS.
4. GENERATOR AIR INLET MONITOR SOUND ATTENUATORS POSITIONED AS SHOWN. SEE SCHEDULES FOR SIZE. SEE STRUCTURAL DRAWINGS FOR MOUNTING AND SUPPORT DETAILS.
5. CONTRACTOR TO PROVIDE 2" THICK, BUILT UP AIR HANDLER CASING AROUND SOUND ATTENUATORS AND SOUND ATTENUATOR STRUCTURAL FRAMING. SEAL CASING PER EXHAUST AIR PLENUM PRESSURE RATING IN SPECIFICATIONS.
6. BOILER FLUE ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. PROVIDE BOILER FLUE WITH LOW LOSS END CAP. BOILER FLUES UP FROM FLOOR BELOW THROUGH ROOF. SEE SHEET H312 FOR CONTINUATION.
7. EXHAUST FAN MOUNTED ON ROOF AT LOCATION INDICATED. EXHAUST AIR DUCT ROUTED FROM SECOND FLOOR TO ROOF. SEE SHEET H313 FOR CONTINUATION OF EXHAUST DUCT. SEE DETAIL '3' ON SHEET H501.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF HVAC PLAN - AREA C

SHEET NUMBER

H318

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:44 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



ROOF HVAC PLAN - AREA D

Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. EXHAUST FAN MOUNTED ON ROOF AT LOCATION INDICATED. EXHAUST AIR DUCT ROUTED FROM SECOND FLOOR TO ROOF. SEE SHEET H313 FOR CONTINUATION OF EXHAUST DUCT. SEE DETAIL '3' ON SHEET H501.
2. BLOWER COIL UNIT SUSPENDED FROM STRUCTURE AT LOCATION SHOWN. SEE STRUCTURAL SHEETS FOR MOUNTING DETAIL.
3. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. BLOWER COIL UNIT THERMOSTAT MOUNTED ON WALL AT LOCATION SHOWN. COORDINATE WITH OTHER DISIPLINES.
5. RELEIF FAN MOUNTED ON ROOF AT LOCATION INDICATED. RELEIF AIR DUCT ROUTED FROM SECOND FLOOR TO ROOF. SEE SHEET H313 FOR CONTINUATION OF EXHAUST DUCT. SEE DETAIL '16' ON SHEET H501.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF HVAC PLAN - AREA D


SHEET NUMBER

H319



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:47 PM AESI Proj. No: 21-154



ROOF HVAC PLAN - AREA E


Scale: 1/4" = 1'-0"

PLAN NOTES:

1. EXHAUST FAN MOUNTED ON ROOF AT LOCATION INDICATED. EXHAUST AIR DUCT ROUTED FROM SECOND FLOOR TO ROOF. SEE SHEET H313 FOR CONTINUATION OF EXHAUST DUCT. SEE DETAIL '3' ON SHEET H501.

GENERAL NOTES:

1. SEE M001 FOR SYMBOLS AND ABBREVIATIONS.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:49 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF HVAC PLAN - AREA E

SHEET NUMBER

H320



GENERAL NOTES:


1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.

(#) PLAN NOTES:

1. EXHAUST FAN MOUNTED ON ROOF AT LOCATION INDICATED. EXHAUST AIR DUCT ROUTED FROM SECOND FLOOR TO ROOF. SEE SHEET H313 FOR CONTINUATION OF EXHAUST DUCT. SEE DETAIL '3' ON SHEET H501.
2. OUTDOOR AIR INLET HOOD ON ROOF AT LOCATION INDICATED. OUTDOOR AIR DUCT TO SECOND FLOOR FROM ROOF. SEE SHEET H310 FOR CONTINUATION OF OUTDOOR AIR DUCT. SEE DETAIL '15' ON SHEET H501.
3. RELEIF FAN MOUNTED ON ROOF AT LOCATION INDICATED. RELEIF AIR DUCT ROUTED FROM SECOND FLOOR TO ROOF. SEE SHEET H313 FOR CONTINUATION OF EXHAUST DUCT. SEE DETAIL '16' ON SHEET H501.

ROOF HVAC PLAN - AREA F

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF HVAC PLAN - AREA F

SHEET NUMBER

H321

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:51 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



FIRST FLOOR MEZZANINE HVAC PLAN


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE SHEET M001 FOR SYMBOLS AND ABBREVIATIONS.
2. SEE ARCHITECTURAL SHEETS FOR MEZZANINE FINISHED FLOOR HEIGHTS.


PLAN NOTES:

1. SUPPLY AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
2. VAV BOX SUSPENDED IN SUPPLY AIR DUCT AT LOCATION INDICATED. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
3. EXHAUST AIR DUCT ROUTED AS SHOWN. EXHAUST AIR DUCT ROUTED THROUGH TO FLOOR ABOVE. SEE SHEET H314 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
4. RETURN AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
5. AIR HANDLING UNIT OR MAKE UP AIR UNIT MOUNTED ON EQUIPMENT PAD AT LOCATION INDICATED. SEE STRUCTURAL SHEETS FOR EQUIPMENT PAD DETAILS. DASHED LINES INDICATED EQUIPMENT SERVICE CLEARENCES, COORDINATE WITH ALL DISCIPLINES TO KEEP SERVICE CLEARENCES FREE OF OBSTRUCTIONS. SEE MECHANICAL SHEETS FOR PIPE ROUTING. SEE ELECTRICAL SHEETS FOR ELECTRICAL CONNECTION DETAILS.
6. OUTDOOR AIR DUCT UP THROUGH ROOF. SEE H316 FOR CONTINUATION.
7. SUPPLY AIR DUCT DOWN THROUGH SLAB TO FLOOR BELOW. SEE H313 FOR CONTINUATION.
8. EXHAUST AIR DUCT ROUTED FROM FLOOR BELOW THROUGH MEZZANINE TO ROOF AS SHOWN. SEE SHEET H320 AND SHEET H314 FOR CONTINUATION. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.
9. RELEIF AIR DUCT ROUTED AS SHOWN. CONTRACTOR SHALL INSTALL SIESMIC BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. DUCT IS ROUTED UP THROUGH ROOF AT LOCATION INDICATED. SEE SHEET H319 FOR CONTINUATION.
10. SUPPLY AIR DUCT DOWN THROUGH SLAB TO FLOOR BELOW. SEE H309 FOR CONTINUATION.
11. RETURN AIR DUCT DOWN THROUGH SLAB TO FLOOR BELOW. SEE H313 FOR CONTINUATION.
12. DUCT FROM EQUIPMENT MEZZANINE. SEE H313 FOR CONTINUATION.
13. OPEN RETURN DUCT WITH BALANCE DAMPER MOUNTED ON TOP OF DUCT AT LOCATION INDICATED. TAB CONTRACTOR SHALL SET BALANCE DAMPER TO 2000CFM.
14. OPEN RETURN DUCT WITH BALANCE DAMPER MOUNTED ON TOP OF DUCT AT LOCATION INDICATED. TAB CONTRACTOR SHALL SET BALANCE DAMPER TO 6000CFM.
15. DUCT FROM EQUIPMENT MEZZANINE. SEE H314 FOR CONTINUATION.
16. DUCT FROM EQUIPMENT MEZZANINE. SEE H315 FOR CONTINUATION.
17. DUCT FROM EQUIPMENT MEZZANINE. SEE H309 FOR CONTINUATION.
18. 20" BOILER FLUE ROUTED AS SHOWN. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS. BOILER FLUES UP TO FLOOR ABOVE. SEE SHEET H311 FOR CONTINUATION.
19. OUTDOOR AIR MAKE UP DUCT TO GENERATOR ROOM. CONTRACTOR SHALL PROVIDE SEISMIC SWAY BRACING AS REQUIRED TO MEET SEISMIC ZONE C REQUIREMENTS.



SECOND FLOOR MEZZANINE 1 HVAC PLAN

Scale: 1/4" = 1'-0"



SECOND FLOOR MEZZANINE 2 HVAC PLAN

Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

HVAC MEZZANINE PLANS


SHEET NUMBER

H401


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:01:54 PM AESI Proj. No: 21-154




5 **NORTH CORRIDOR LOOKING EAST**
Scale: 1/4" = 1'-0"




6 **MECHANICAL ROOM 204 LOOKING SOUTH**
Scale: 1/4" = 1'-0"




7 **SOUTH CORRIDOR SECTION**
Scale: 1/4" = 1'-0"




1 **SOUTH MEZZANINE LOOKING EAST**
Scale: 1/4" = 1'-0"



2 **SOUTH MEZZANINE LOOKING SOUTH**
Scale: 1/4" = 1'-0"



3 **NORTH MEZZANINE LOOKING EAST**
Scale: 1/4" = 1'-0"



4 **NORTH MEZZANINE LOOKING WEST**
Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:05 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	AESI
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154


CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE


HVAC SECTIONS

SHEET NUMBER


H402




CHILLER ROOM WEST WALL 3D VIEW




FIRST FLOOR MEZZANINE 3D VIEW




NORTH CORRIDOR 3D VIEW 2




NORTH CORRIDOR 3D VIEW 1




NORTH MEZZANINE 3D VIEW 2




NORTH MEZZANINE 3D VIEW 1



SOUTH MEZZANINE 3D VIEW 2



SOUTH MEZZANINE 3D VIEW 1



SOUTH CORRIDOR 3D VIEW

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	CERTIFICATION
AESI	PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY	
AESI	
APPROVED BY	
Approver	
PROJECT NO.	
21-154	

SHEET TITLE


HVAC 3D VIEWS

SHEET NUMBER


H403

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:23 PM AESI Proj No: 21-154




14 **ROOF CURB DETAIL**
Scale: NONE




NOTE:
1. RETURN AIR GRILLE SHALL BE CUT TO SIZE ON PLANS


10 **RETURN AIR GRILLE IN LAY-IN CEILING DETAIL**
Scale: NONE




5 **FIRE DAMPER INSTALLATION DETAIL**
Scale: NONE




1 **2 - WAY AHU WATER COIL PIPING DETAIL**
Scale: NONE




15 **AIR INTAKE HOOD DETAIL**
Scale: NON



11 **SUPPLY DIFFUSER DETAIL**
Scale: NONE




6 **FIRE DAMPER ACCESS PANEL DETAIL**
Scale: NONE




NOTE:
ARRANGE PIPING FOR EASY REMOVAL

2 **DRAW - THRU UNITS COOLING DRAIN DETAIL**
Scale: NONE




12 **LOUVER AND PLENUM DETAIL**
Scale: NONE



NOTES:

1. DAMPER SLEEVE MUST BE MINIMUM 26 GAGE UP TO MAXIMUM 10 GAGE STEEL. SLEEVE THICKNESS MUST BE EQUAL TO OR THICKER THAN THE DUCT CONNECTED TO IT. SLEEVE GAGE REQUIREMENTS ARE LISTED IN THE SMACNA FIRE, SMOKE AND RADIATION DAMPER INSTALLATION GUIDE FOR HVAC SYSTEMS AND IN NFPA 90A. SLEEVE MUST BE 14 GAGE MINIMUM WHEN DAMPER EXCEEDS 36" WIDE OR 24" HIGH. SLEEVE MUST NOT EXTEND MORE THAN 6" OUT OF THE WALL OR FLOOR.
2. GALVANIZED DAMPERS 50" X 60" OR 60" X 50" OR SMALLER REQUIRE MINIMUM OF 1 1/2" X 1 1/2" X 16 GAGE CONVENTIONAL MOUNTING ANGLES FASTENED TO THE DAMPER SLEEVE WITH NO. 10 (M5) BOLTS OR SCREWS, 3/16" RIVETS, TACK WELDS OR SPOT WELDS, SPACED A MAXIMUM OF 6" ON CENTER. MOUNTING ANGLES MUST OVERLAP THE WALL OR FLOOR A MINIMUM OF 1". DO NOT FASTEN ANGLES TOGETHER AT CORNERS OF THE DAMPER/SLEEVE ASSEMBLY.


7 **FIRE DAMPER HORIZONTAL INSTALLATION DETAIL**
Scale: NONE




NOTES:

1. M.C. SHALL VERIFY ACTUAL SIZES OF ROOF CURB AND ROOF OPENING FOR THE PARTICULAR FAN MFG. SELECTED. COORDINATE THESE SIZES WITH ROOFING AND STRUCTURAL CONTRACTORS.
2. FAN TO BE INSTALLED LEVEL AND PLUMB.


3 **EXHAUST FAN MOUNTING DETAIL**
Scale: NONE




16 **HOODED EXHAUST FAN DETAIL**
Scale: NONE



13 **LOUVER DETAIL**
Scale: NONE




8 **HOT WATER UNIT HEATER DETAIL**
Scale: NONE




NOTES:

1. M.C. SHALL VERIFY ACTUAL SIZES OF ROOF CURB AND ROOF OPENING FOR THE PARTICULAR FAN MFG. SELECTED. COORDINATE THESE SIZES WITH ROOFING AND STRUCTURAL CONTRACTORS.
2. FAN TO BE INSTALLED LEVEL AND PLUMB.


4 **UP-BLAST PROPELLER EXHAUST FAN DETAIL**
Scale: NONE



17 **SIDE WALL DRUM LOUVER AND GRILLE DETAIL**
Scale: NONE



SQUARE GRILLE



9 **GRILLE AND DIFFUSER IN CEILING INSULATION DETAIL**
Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:24 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


HVAC DETAILS

SHEET NUMBER

H501




4 **AIR MONITOR DETAIL**
Scale: 1/4" = 1'-0"




NOTES:

1. PROVIDE VALVED AND CAPPED BLOWDOWN WITH HOSE THREADS.
2. USE BALL VALVES FOR 2" PIPE SIZE AND SMALLER - USE BUTTERFLY VALVES FOR PIPE SIZE ABOVE 2" (TYPICAL).
3. PROVIDE SOLAR THERMOMETER INSTALLED AND ARRANGED FOR EASY VIEWING AND TO CAPTURE MAXIMUM LIGHT.
4. VERIFY NUMBER OF COILS AND PIPE SEPARATELY AS SHOWN.
5. INSTALL AIR VENT AT HIGHEST POINT IN PIPING CONNECTION.
6. 1/2" BALL VALVE MANUAL DRAIN W/ HOSE CONNECTION EXTENDED THROUGH INSULATION.
7. SEE INLINE PUMP DETAIL.
8. PROVIDE CALIBRATED BALANCING VALVE.


1 **PUMPED COIL DETAIL**
Scale: NONE



5 **GENERATOR ROOM DETAIL**
Scale: 1/4" = 1'-0"



2 **2-WAY VAV BOX, FAN COIL UNIT REHEAT COIL DETAIL**
Scale: NONE



3 **DUCT MOUNTED REHEAT COIL DETAIL**
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


HVAC DETAILS

SHEET NUMBER


H502

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:26 PM AESI Proj No: 21-154


0 1/2" 1" 2"




9 **MAU-2-2 DETAIL**
Scale: 1/4" = 1'-0"





5 **AHU-2-4 DETAIL**
Scale: 1/4" = 1'-0"







1 **AHU-1-1 DETAIL**
Scale: 1/4" = 1'-0"







6 **MAU-1-1 DETAIL**
Scale: 1/4" = 1'-0"







2 **AHU-2-1 DETAIL**
Scale: 1/4" = 1'-0"







3 **AHU-2-2 DETAIL**
Scale: 1/4" = 1'-0"







4 **AHU-2-3 DETAIL**
Scale: 1/4" = 1'-0"





7 **MAU-1-2 DETAIL**
Scale: 1/4" = 1'-0"





8 **MAU-2-1 DETAIL**
Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

HVAC EQUIPMENT DETAILS

SHEET NUMBER

H503

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:26 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

BLOWER AND FAN COIL UNIT SCHEDULE

NOTES:
1. UNIT IS PROVIDED WITH HEATING COIL AND COOLING COIL.
2. UNIT IS PROVIDED ONLY WITH COOLING COIL.
3. UNIT IS PROVIDED WITH HEATING COIL ONLY
4. UNIT MOTOR SHALL BE ECM.
5. UNIT SHALL BE SEISMIC CLASS C RATED WITH 1.5 COMPONENT FACTOR.
6. UNIT REQUIRES SUPPLY DUCT CONNECTION.
7. UNIT REQUIRES RETURN DUCT CONNECTION.

			FAN				COOLING COIL							HEATING COIL						MOTOR DATA						ELECTRICAL DATA		CABINET				BASIS OF DESIGN			
UNIT TAG	LOCATION	TYPE	CFM	ESP	TSP	DRIVE	MBH	EDB	EWB	EWT	LWT	GPM	ROWS	WATER P.D.	MBH	EWT	LWT	GPM	ROWS	WATER P.D.	HP	RPM	VOLTS	PH	FLA	MCA	MOCP	EM POWER	CONTROL TYPE	DEPTH	LENGTH	HEIGHT	FILTER TYPE	MANUFACTURER	MODEL NO.	WEIGHT	NOTES
BCU-1	RECEIVING 105	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.423 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	104.43	130.0 °F	100.0 °F	6.68 GPM	2	0.93 ftH2O	1.5	1065	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	1,4,5,6
BCU-2	RECEIVING 105	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	2,4,5,6
BCU-3	RECEIVING 105	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.423 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	104.43	130.0 °F	100.0 °F	6.68 GPM	2	0.93 ftH2O	1.5	1065	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	1,4,5,6
BCU-4	RECEIVING 105	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	2,4,5,6
BCU-5	RECEIVING 105	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	2,4,5,6
BCU-6	FIRE PUMP ROOM 108	HORIZONTAL, EXPOSED	1600 CFM	0.500 in-wg	1.224 in-wg	DIRECT	55.95	85.0 °F	65.0 °F	42.0 °F	58.0 °F	7.23 GPM	4	3.12 ftH2O	56.83	130.0 °F	100.0 °F	3.64 GPM	2	0.97 ftH2O	1	1406	460 V	3	2.50 A	3.13 A	15 A	YES	DDC	46"	35.8"	18"	1" THROWAWAY	TRANE	BCHE054	223.00 lb	1,4,5,6
BCU-7	BOILER ROOM 109	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.00 A	4.00 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	2,4,5,6
BCU-8	BOILER ROOM 109	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	2,4,5,6
BCU-9	BOILER ROOM 109	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.00 A	4.00 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHD090	303.40 lb	2,4,5,6
BCU-10	JANITOR 115	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.423 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.00 A	4.00 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	2,4,5,6
BCU-11	BOILER ROOM 109	HORIZONTAL, EXPOSED	600 CFM	0.500 in-wg	1.074 in-wg	DIRECT	13.02	75.0 °F	62.0 °F	42.0 °F	58.0 °F	1.63 GPM	4	3.12 ftH2O	0	130.0 °F	100.0 °F	0 GPM	0	0 ftH2O	1	1340	460 V	3	2.50 A	3.13 A	15 A	YES	DDC	36.19"	28.69"	20.25"	1" THROWAWAY			0.00 lb	1,5,6
BCU-12	CHILLER PLANT 114	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	2,4,5,6
BCU-13	CHILLER PLANT 114	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	0	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	1.5	942	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	303.40 lb	2,4,5,6
BCU-14	CHILLER PLANT 114	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.109 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	104.43	130.0 °F	100.0 °F	6.68 GPM	2	0.93 ftH2O	1.5	1065	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	307.70 lb	1,4,5,6
BCU-15	CHILLER PLANT 114	HORIZONTAL, EXPOSED	3000 CFM	0.500 in-wg	1.432 in-wg	DIRECT	101.04	85.0 °F	65.0 °F	42.0 °F	58.0 °F	13.14 GPM	4	4.11 ftH2O	104.43	130.0 °F	100.0 °F	6.68 GPM	2	0.93 ftH2O	1.5	1065	460 V	3	3.30 A	4.13 A	15 A	YES	DDC	48"	40.65"	26"	1" THROWAWAY	TRANE	BCHE090	307.70 lb	2,4,5,6
BCU-16	VESTIBULE 304	HORIZONTAL, EXPOSED	1200 CFM	0.500 in-wg	1.159 in-wg	DIRECT	37.77	85.0 °F	65.0 °F	42.0 °F	58.0 °F	4.99 GPM	4	4.23 ftH2O	39.06	130.0 °F	100.0 °F	2.61 GPM	2	1 ftH2O	1	1611	460 V	3	2.50 A	3.13 A	15 A	YES	DDC	42"	33.1"	17"	1" THROWAWAY	TRANE	BCHE036	171.00 lb	1,4,5,6,7
FCU-N-1	STAIR #1 106	HORIZONTAL, EXPOSED	1000 CFM	0.050 in-wg	0.493 in-wg	DIRECT	16.87	76.0 °F	60.0 °F	42.0 °F	58.0 °F	2.1 GPM	3	1.38 ftH2O	20.93	130.0 °F	100.0 °F	1.4 GPM	1	10.79 ftH2O	0.25	1446	120 V	1	6.07 A	7.59 A	15 A	YES	THERMOSTAT	26"	75"	10"	1" THROWAWAY	TRANE	FCDB120	218.00 lb	1,4,5
FCU-N-2	STAIR #1 106	HORIZONTAL, EXPOSED	1000 CFM	0.050 in-wg	0.493 in-wg	DIRECT	16.87	76.0 °F	60.0 °F	42.0 °F	58.0 °F	2.1 GPM	3	1.38 ftH2O	20.93	130.0 °F	100.0 °F	1.4 GPM	1	10.79 ftH2O	0.25	1446	120 V	1	6.07 A	7.59 A	15 A	YES	THERMOSTAT	26"	75"	10"	1" THROWAWAY	TRANE	FCDB120	218.00 lb	1,4,5
FCU-N-T	Room 1	VERTICAL, CONCEALED	800 CFM	0.050 in-wg	0.400 in-wg	DIRECT	0	0.0 °F	0.0 °F	0.0 °F	0.0 °F	0 GPM	0	0 ftH2O	21.91	130.0 °F	100.0 °F	1.46 GPM	2	0.78 ftH2O	0.146	1306	120 V	1	3.88 A	4.85 A	15 A	YES	THERMOSTAT	10.38"	65.5"	57.5"	1" THROWAWAY	TRANE	FFHB080	139.00 lb	3,4,5
FCU-S-1	STAIR #2 110	HORIZONTAL, EXPOSED	1000 CFM	0.050 in-wg	0.493 in-wg	DIRECT	16.87	76.0 °F	60.0 °F	42.0 °F	58.0 °F	2.1 GPM	3	1.38 ftH2O	20.93	130.0 °F	100.0 °F	1.4 GPM	1	10.79 ftH2O	0.25	1446	120 V	1	6.07 A	7.59 A	15 A	YES	THERMOSTAT	26"	75"	10"	1" THROWAWAY	TRANE	FCDB120	218.00 lb	1,4,5
FCU-S-2	STAIR #2 217	HORIZONTAL, EXPOSED	1000 CFM	0.050 in-wg	0.493 in-wg	DIRECT	16.87	76.0 °F	60.0 °F	42.0 °F	58.0 °F	2.1 GPM	3	1.38 ftH2O	20.93	130.0 °F	100.0 °F	1.4 GPM	1	10.79 ftH2O	0.25	1446	120 V	1	6.07 A	7.59 A	15 A	YES	THERMOSTAT	26"	75"	10"	1" THROWAWAY	TRANE	FCDB120	218.00 lb	1,4,5

COMPUTER ROOM AIR CONDITIONING UNIT SCHEDULE

NOTES:
1. LOCKING DISCONNECT BY E.C.
2. MANUFACTURER TO PROVIDE REMOTE THERMOSTAT AND HUMIDISTAT, UNIT MOUNTED SMOKE DETECTOR, HIGH LIMIT TEMPERATURE SENSOR, LEAK POINT SENSOR AND LOW VOLTAGE TERMINAL PACK.
3.HUMIDIFIER SHALL BE RATED FOR USE WITH REVERSE OSMOSIS WATER

				AIRFLOW	CHILLED WATER COIL							HEATING WATER COIL					FAN							ELECTRICAL DATA						HUMIDIFIER		FILTERS			BASIS OF DESIGN			
UNIT TAG	LOCATION	AREA SERVED	TYPE	CFM	TOTAL MBH	SENSIBLE MBH	EDB	EWB	GPM	WATER P.D.	ROWS	FACE VELOCITY	TOTAL MBH	EDB	GPM	ROWS	FACE VELOCITY	TYPE	DRIVE	NO.	EXTERNAL SP	FAN RPM	VOLTS	PH	FLA	MCA	MOCP	EM POWER	CONTROL TYPE	TYPE	CAPACITY	TYPE	MERV RAITING	SIZE	MANUFACTURER	MODEL NO.	WEIGHT	NOTES
CRAC-1	MECHANICAL 224	MDF ROOM	BOTTOM DISCHARGE	3500 CFM	71	66.8	72.0 °F	58.7 °F	18.4 GPM	10 ftH2O	4	500 FPM	30.58	64.0 °F	2.1 GPM	1	500 FPM	ECM	DIRECT	1	0.200 in-wg	1800	480 V	3	21 A	23.4 A	30 A	YES	DDC	INFRARED	7.7	PLEATED	8	4 INCH	LIEBERT	PX018D21AD	850.00 lb	1, 2, 3
CRAC-2	MECHANICAL 224	MDF ROOM	BOTTOM DISCHARGE	3500 CFM	71	66.8	72.0 °F	58.7 °F	18.4 GPM	10 ftH2O	4	500 FPM	30.58	64.0 °F	2.1 GPM	1	500 FPM	ECM	DIRECT	1	0.200 in-wg	1800	480 V	3	21 A	23.4 A	30 A	YES	DDC	INFRARED	7.7	PLEATED	8	4 INCH	LIEBERT	PX018D21AD	850.00 lb	1, 2, 3

VAV BOX SCHEDULE

NOTES:
1. MANUFACTURER SHALL FURNISH UNIT WITH FLOW SENSOR AND DISCHARGE TEMPERATURE SENSOR. CONTROL CONTRACTOR SHALL PROVIDE DDC CONTROLLER AND DAMPER ACTURATOR.
2. PROVIDE DUCT TRANSITION AT UNIT WHERE INLET SIZE AND DUCT RUNOUT SIZE ARE DIFFERENT.
3. THE UNIT MAXIMUM S.P. IS THE DIFFERENCE BETWEEN THE UNIT INLET AND DISCHARGE INCLUDING REHEAT COIL.
4. UNIT SHALL BE SEISMIC CLASS C RATED WITH 1.5 COMPONENT FACTOR

									HOT WATER REHEAT COIL								NC LEVEL AT INLET S.P.	MAXIMUM ROOM NC	DISCHARGE SOUND POWER OCTAVE BAND CENTER FREQUENCY						CONTROL TYPE	POWER 120V OR 24V W/ REMOTE XFMR	WEIGHT	BASIS OF DESIGN		
UNIT TAG	SYSTEM SERVED	AREA SERVED	UNIT TYPE	UNIT INLET SIZE	MAXIMUM CFM	MINIMUM CFM	MAXIMUM S.P. AT MAXIMUM CFM	INLET S.P.	EAT	LAT	EWT	LWT	GPM	MAXIMUM WATER P.D.	NOMINAL PIPE SIZE	HEATING CFM	MBH AT HEATING CFM			125HZ	250HZ	500HZ	1000HZ	2000HZ	4000HZ				MANUFACTURER	MODEL NO.	NOTES
VAV-01-01	AHU-2-1	NORTH CORRIDOR 228	DDC	7"	500 CFM	280 CFM	0.42 in-wg	0.750 in-wg	55.0 °F	87.0 °F	130.0 °F	94.8 °F	1 GPM	0.35 Feet	3/4"	500 CFM	17.36	20	35	70	62	51	48	43	40	DDC	24V W/ REMOTE	23.00 lb	PRICE	SDV-07	1, 2, 3, 4
VAV-01-02	AHU-2-1	OFFICE 204	DDC	7"	490 CFM	100 CFM	0.41 in-wg	0.750 in-wg	55.0 °F	95.7 °F	130.0 °F	107.9 °F	1.79 GPM	0.96 Feet	3/4"	440 CFM	19.43	20	35	76	71	63	57	52	49	DDC	24V W/ REMOTE	23.00 lb	PRICE	SDV-07	1, 2, 3, 4
VAV-01-03	AHU-2-1	MECHANICAL 206	DDC	6"	300 CFM	0 CFM	0.19 in-wg	0.750 in-wg	55.0 °F	85.6 °F	130.0 °F	98.9 °F	0.33 GPM	0.02 Feet	3/4"	150 CFM	4.98	20	35	72	67	57	52	46	43	DDC	24V W/ REMOTE	20.00 lb	PRICE	SDV-06	1, 2, 3, 4
VAV-01-04	AHU-2-1	LOCKER/BREAK 205	DDC	16"	1680 CFM	575 CFM	0.41 in-wg	0.750 in-wg	55.0 °F	96.3 °F	130.0 °F	100.5 °F	4 GPM	1.07 Feet	3/4"	1300 CFM	58.25	20	35	74	69	61	58	56	54	DDC	24V W/ REMOTE	55.00 lb	PRICE	SDV-16	1, 2, 3, 4
VAV-01-05	AHU-2-1	CONTROL 209	DDC	12"	900 CFM	300 CFM	0.38 in-wg	0.750 in-wg	55.0 °F	94.5 °F	130.0 °F	99.9 °F	2.14 GPM	0.75 Feet	3/4"	740 CFM	31.71	20	35	74	69	61	58	56	54	DDC	24V W/ REMOTE	38.00 lb	PRICE	SDV-12	1, 2, 3, 4
VAV-01-06	AHU-2-1	SWITCHGEAR 212	DDC	14"	1290 CFM	430 CFM	0.27 in-wg	0.750 in-wg	55.0 °F	88.6 °F	130.0 °F	100.9 °F	1.7 GPM	0.43 Feet	3/4"	670 CFM	24.42	20	35	61	53	50	47	44	41	DDC	24V W/ REMOTE	49.00 lb	PRICE	SDV-14	1, 2, 3, 4
VAV-01-07	AHU-2-1	NORTH CORRIDOR 228	DDC	16"	2000 CFM	0 CFM	0.53 in-wg	0.750 in-wg	55.0 °F	95.2 °F	130.0 °F	109.2 °F	8.5 GPM	4.05 Feet	3/4"	2000 CFM	87.23	20	35	74	67	65	59	57	56	DDC	24V W/ REMOTE	55.00 lb	PRICE	SDV-16	1, 2, 3, 4
VAV-02-01	AHU-2-2	GENERATOR SWITCHGEAR	DDC	14"	1300 CFM	430 CFM	0.27 in-wg	0.750 in-wg	55.0 °F	86.7 °F	130.0 °F	97.8 °F	1.41 GPM	0.31 Feet	3/4"	650 CFM	22.36	20	35	61	53	50	47	44	41	DDC	24V W/ REMOTE	49.00 lb	PRICE	SDV-14	1, 2, 3, 4
VAV-02-02	AHU-2-2	GENERATOR SWITCHGEAR	DDC	14"	1300 CFM	430 CFM	0.27 in-wg	0.750 in-wg	55.0 °F	86.7 °F	130.0 °F	97.8 °F	1.41 GPM	0.31 Feet	3/4"	650 CFM	22.36	20	35	61	53	50	47	44	41	DDC	24V W/ REMOTE	49.00 lb	PRICE	SDV-14	1, 2, 3, 4
VAV-02-03	AHU-2-2	MAINTENANCE WORKROOM 207	DDC	6"	500 CFM	100 CFM	0.38 in-wg	0.750 in-wg	55.0 °F	85.2 °F	130.0 °F	105.0 °F	0.67 GPM	0.09 Feet	3/4"	250 CFM	8.19	20	35	78	73	62	56	48	45	DDC	24V W/ REMOTE	20.00 lb	PRICE	SDV-06	1, 2, 3, 4
VAV-02-04	AHU-2-2	OFFICE 203	DDC	7"	490 CFM	100 CFM	0.42 in-wg	0.750 in-wg	55.0 °F	95.7 °F	130.0 °F	109.2 °F	2 GPM	1.16 Feet	3/4"	465 CFM	20.48	20	35	76	71	63	57	52	49	DDC	24V W/ REMOTE	23.00 lb	PRICE	SDV-07	1, 2, 3, 4
VAV-02-05	AHU-2-2	OFFICE 226	DDC	7"	520 CFM	100 CFM	0.45 in-wg	0.750 in-wg	55.0 °F	94.2 °F	130.0 °F	106.8 °F	1.75 GPM	0.92 Feet	3/4"	470 CFM	19.99	20	35	76	71	63	57	52	49	DDC	24V W/ REMOTE	23.00 lb	PRICE	SDV-07	1, 2, 3, 4
VAV-02-06	AHU-2-2	MECHANICAL 224	DDC	7"	500 CFM	0 CFM	0.30 in-wg	0.750 in-wg	55.0 °F	86.2 °F	130.0 °F	101.1 °F	0.6 GPM	0.1 Feet	3/4"	250 CFM	8.46	20	35	70	62	51	48	43	40	DDC	24V W/ REMOTE	23.00 lb	PRICE	SDV-07	1, 2, 3, 4
VAV-02-07	AHU-2-2	NORTH CORRIDOR 201	DDC	16"	2000 CFM	575 CFM	0.52 in-wg	0.750 in-wg	55.0 °F	95.2 °F	130.0 °F	109.2 °F	8.5 GPM	4.05 Feet	3/4"	2000 CFM	87.23	20	35	74	67	65	59	57	56	DDC	24V W/ REMOTE	55.00 lb	PRICE	SDV-16	1, 2, 3, 4
VAV-02-08	AHU-2-2	GENERATOR CONTROL ROOM	DDC	6"	380 CFM	80 CFM	0.36 in-wg	0.750 in-wg	55.0 °F	94.9 °F	130.0 °F	96.3 °F	0.5 GPM	0.08 Feet	3/4"	190 CFM	8.23	20	35	75	70	60	54	48	44	DDC	24V W/ REMOTE	20.00 lb	PRICE	SDV-06	1, 2, 3, 4
VAV-03-01	AHU-2-4	AES SERVICE SWITCHGEAR 216	DDC	16"	1800 CFM	0 CFM	0.31 in-wg	0.750 in-wg	55.0 °F	86.5 °F	130.0 °F	98.9 °F	2 GPM	0.61 Feet	3/4"	900 CFM	30.76	20	35	61	53	53	48	46	42	DDC	24V W/ REMOTE	55.00 lb	PRICE	SDV-16	1, 2, 3, 4
VAV-03-02	AHU-2-4	AES SERVICE SWITCHGEAR 216	DDC	16"	1800 CFM	575 CFM	0.31 in-wg	0.750 in-wg	55.0 °F	86.5 °F	130.0 °F	98.8 °F	2 GPM	0.61 Feet	3/4"	900 CFM	30.76	20	35	61	53	53	48	46	42	DDC	24V W/ REMOTE	55.00 lb	PRICE	SDV-16	1, 2, 3, 4
VAV-03-03	AHU-2-4	SOUTH CORRIDOR 228	DDC	16"	2000 CFM	575 CFM	0.53 in-wg	0.750 in-wg	55.0 °F	95.2 °F	130.0 °F	109.2 °F	8.5 GPM	4.05 Feet	3/4"	2000 CFM	87.23	20	35	74	67	65	59	57	56	DDC	24V W/ REMOTE	55.00 lb	PRICE	SDV-16	1, 2, 3, 4
VAV-03-04	AHU-2-4	SOUTH CORRIDOR 228	DDC	16"	2000 CFM	0 CFM	0.53 in-wg	0.750 in-wg	55.0 °F	95.2 °F	130.0 °F	109.2 °F	8.5 GPM	4.05 Feet	3/4"	2000 CFM	87.23	20	35	74	67	65	59	57	56	DDC	24V W/ REMOTE	55.00 lb	PRICE	SDV-16	1, 2, 3, 4
VAV-03-05	AHU-2-4	SOUTH CORRIDOR 228	DDC	16"	2000 CFM	0 CFM	0.52 in-wg	0.750 in-wg	55.0 °F	85.7 °F	130.0 °F	91.5 °F	3.5 GPM	0.86 Feet	3/4"	2000 CFM	66.62	20	35	74	67	65	59	57	56	DDC	24V W/ REMOTE	55.00 lb	PRICE	SDV-16	1, 2, 3, 4

AHU ENTHALPY HEAT RECOVERY WHEEL SCHEDULE

NOTES:
1. UNIT SHALL BE SEISMIC CLASS C RATED WITH 1.5 COMPONENT FACTOR.
2. ENTHALPY WHEEL SHALL BE EQUIPPED WITH VFD PROVIDED BY THE E.C.
3. ENTHALPY WHEEL SECTION OF THE AHU SHALL BE EQUIPED WITH SA AND EA BYPASS DAMPERS.
4. ENTHALPY WHEEL SHALL BE ALUMINUM WITH 4 ANGSTROM. CERAMIC MOLECULAR SIEVE.

			SUMMER DATA											WINTER DATA											MOTOR DATA							BASIS OF DESIGN			
			SUPPLY SIDE				EXHAUST SIDE							SUPPLY SIDE				EXHAUST SIDE																		
			ENTERING			LEAVING			ENTERING			LEAVING			ENTERING			LEAVING			ENTERING			LEAVING											
UNIT TAG	SYSTEM SERVED	LOCATION	CFM	DB	WB	CFM	DB	WB	CFM	DB	WB	CFM	DB	WB	RECOVERED MBH	CFM	DB	WB	CFM	DB	WB	CFM	DB	WB	CFM	DB	WB	RECOVERED MBH	HP	VOLTS	PH	FLA	MCA	MOCP	EM. POWER	WEIGHT	MANUFACTURER	MODEL NO.	NOTES
HRW-2-1	MAU-2-1		5906 CFM	95.0 °F	76.0 °F	5570 CFM	86.8 °F	67.5 °F	6140 CFM	85.0 °F	65.0 °F	6466 CFM	86.8 °F	67.5 °F	181.77	5906 CFM	-10.0 °F	-11.0 °F	5570 CFM	42.2 °F	25.8 °F	6140 CFM	55.0 °F	30.0 °F	6466 CFM	7.5 °F	1.3 °F	327.38	1	460 V	3	2 A	2 A	15 A	YES	1539.00 lb	TRANE	7000	1, 2, 3, 4

AHU CASING SCHEDULE

NOTES:
1. UNIT SHALL BE MOUNTED ON G.C. PROVIDED EQUIPMENT PAD, SEE STRUCTURE SHEETS. COORDINATE EQUIPMENT PAD SIZES WITH G.C. MANUFACTURER TO PROVIDE 6" EQUIPMENT BASE RAIL.
2. UNIT OUTDOOR AIR AND RETURN AIR MIXING OCCUR REMOTELY FROM AHU CASING
3. UNIT RELEIF AIR OCCURS REMOTELY FROM AHU CASING.
4. UNIT ACCESS DOORS AND MAINTENANCE CLEARANCES SHALL ALL BE LOCATED ON ONE SIDE OF UNIT.
5. UNIT SHALL BE SEISMIC CLASS C RATED WITH 1.5 COMPONENT FACTOR.
6. UNIT SHALL BE EQUIPPED WITH LIGHTS IN ACCESS SECTIONS WITH DOOR WINDOWS. WIRING TO MANUFACTURER PROVIDED LIGHTING CONNECTIONS BY E.C.
7. ACCESS DOORS OVER 18" WIDE SHALL HAVE WINDOWS. WINDOWS SHALL BE THEMALLY BROKEN, DUAL PANE.

			OVERALL	AIRFLOW		OUTDOOR AIR FLOW	OVERALL	BASIS OF DESIGN		
UNIT TAG	LOCATION	SERVING	WEIGHT	MAX.	MIN.	MINIMUM	TOTAL S.P.	MANUFACTURER	MODEL NO.	NOTES
AHU-1-1		TRANSFORMER ROOM	10406.00 lb	32200 CFM	3230 CFM	0 CFM	3.540 in-wg	TRANE	CSAA066	1, 2, 3, 4, 5, 6, 7
AHU-2-1		2ND FLOOR NE CORNER	2652.00 lb	7000 CFM	1400 CFM	860 CFM	3.406 in-wg	TRANE	CSAA017	1, 2, 3, 4, 5, 6, 7
AHU-2-2		2ND FLOOR NW CORNER	2719.00 lb	7200 CFM	1440 CFM	865 CFM	3.437 in-wg	TRANE	CSAA017	1, 2, 3, 4, 5, 6, 7
AHU-2-3		2ND FLOOR SOUTH END	3155.00 lb	9600 CFM	1920 CFM	1675 CFM	3.342 in-wg	TRANE	CSAA021	1, 2, 3, 4, 5, 6, 7
AHU-2-4		LIFE SAFETY ROOM	1773.00 lb	3200 CFM	0 CFM	0 CFM	2.361 in-wg	TRANE	CSAA008	1, 2, 3, 4, 5, 6, 7
MAU-1-1		HYDRONIC BOILERS	6171.00 lb	25600 CFM	1300 CFM	0 CFM	2.396 in-wg	TRANE	CSAA050	1, 4, 5, 6, 7
MAU-1-2		STEAM BOILERS	3563.00 lb	14000 CFM	1400 CFM	0 CFM	2.040 in-wg	TRANE	CSAA030	1, 4, 5, 6, 7
MAU-2-1	MECHANICAL 206	CHILLER ROOM	4154.00 lb	5570 CFM	5570 CFM	5570 CFM	3.546 in-wg	TRANE	CSAA014	1, 4, 5, 6, 7
MAU-2-2	MECHANICAL 224	TUNNEL	1651.00 lb	1750 CFM	1750 CFM	1750 CFM	2.871 in-wg	TRANE	CSAA004	1, 4, 5, 6, 7

AHU FILTER SCHEDULE

1. UNIT SHALL BE SEISMIC CLASS C RATED WITH 1.5 COMPONENT FACTOR
2. FILTER MANUFACTURER SHALL PROVIDE FILTERS TO AHU MANUFACTURER FOR FACTORY INSTALATION.
3. FILTER MANUFACTURER AND AHU MANUFACTURER SHALL COORDINATE TO DETERMINE PRESSURE DROP FO AHU FAN FOR STATIC PRESSURE SIZING.

								QUANTITY				MINIMUM	
UNIT TAG	SYSTEM SERVED	FILTER TYPE	FILTER SERVICE	AIR FLOW	CLEAN PRESSURE DROP	DIRTY PRESSURE DROP	THICKNESS	NO. HIGH	NO. WIDE	FACE VELOCITY	MERV RATING	ASHRAE 52.1 EFFICIENCY	NOTES
F-AHU-1-1	AHU-1-1	ACTIVE	FINAL FILTER	32200 CFM	0.300 in-wg	0.700 in-wg	1"	13	3	461 FPM	13	90	1, 2, 3
F

SOUND ATTENUATORS

NOTES:

1. PERFORATED GALVANIZED LINER WITH FIBERGLASS FILL
2. UNITS ARRANGED IN ARRAY. SEE STRUCTURAL DRAWINGS FOR SUPPORT DETAILS.

UNIT TYPE TAG	LOCATION	SYSTEM SERVED	WIDTH	HEIGHT	LENGTH	CFM	VELOCITY FT/MIN	MAX. APD " W.C.	DYNAMIC INSERTION LOSS								GENERATED NOISE								BASIS OF DESIGN				
									63HZ	125HZ	250HZ	500HZ	1000HZ	2000HZ	4000HZ	8000HZ	63HZ	125HZ	250HZ	500HZ	1000HZ	2000HZ	4000HZ	8000HZ	MANUFACTURER	MODEL NO.	WEIGHT	QTY	NOTES
TYPE 1	GENERATOR EXHAUST PLENUM	GENERATOR EXHAUST	46"	43"	72"	7610 CFM	500 FPM	0.08 in-wg	7	12	20	32	30	23	16	13	29	20	15	35	42	31	23	11	PRICE	RM48/5D	299.00 lb	205	1,2
TYPE 2	ROOF MOUNTED AIR MONITORS	GENERATOR INLET	45"	48"	48"	5420 CFM	360 FPM	0.04 in-wg	9	15	27	42	36	26	17	14	49	31	18	39	44	36	25	20	PRICE	RM72/6D	424.00 lb	288	1,2

UNIT HEATER SCHEDULE

NOTES:
1. TEMPERATURE CONTROLS CONTRACTOR TO PROVIDE THERMOSTAT
2. UNIT SHALL BE SEISMIC CLASS C RATED WITH 1.5 COMPONENT FACTOR

UNIT TAG	LOCATION	TYPE	MBH	EAT	LAT	CFM	EWT	LWT	GPM	WATER P.D.	FAN DIA.	MOTOR DATA							ELECTRICAL DATA			BASIS OF DESIGN				
												HP	NO. OF SPEEDS	RPM	FLA	MCA	MOCP	VOLTS	PHASES	DISC. SW. BY	EM. POWER	CONTROL TYPE	MANUFACTURER	MODEL NO.	WEIGHT	NOTES
UH-1	GENERATOR ROOM A 220	HORIZONTAL PROPELLER	85	55.0 °F	85.0 °F	2600 CFM	130.0 °F	100.0 °F	7.86 GPM	0.6 Feet	24.38"	.333	1	1140	4.5 A	5.6 A	15 A	120 V	1	MANUFACTURER	NO	THERMOSTAT	TRANE	S-180	98.00 lb	1,2
UH-2	GENERATOR ROOM A 220	HORIZONTAL PROPELLER	85	55.0 °F	85.0 °F	2600 CFM	130.0 °F	100.0 °F	7.86 GPM	0.6 Feet	24.38"	.333	1	1140	4.5 A	5.6 A	15 A	120 V	1	MANUFACTURER	NO	THERMOSTAT	TRANE	S-180	98.00 lb	1,2
UH-3	GENERATOR ROOM B 218	HORIZONTAL PROPELLER	85	55.0 °F	85.0 °F	2600 CFM	130.0 °F	100.0 °F	7.86 GPM	0.6 Feet	24.38"	.333	1	1140	4.5 A	5.6 A	15 A	120 V	1	MANUFACTURER	NO	THERMOSTAT	TRANE	S-180	98.00 lb	1,2
UH-4	GENERATOR ROOM B 218	HORIZONTAL PROPELLER	85	55.0 °F	85.0 °F	2600 CFM	130.0 °F	100.0 °F	7.86 GPM	0.6 Feet	24.38"	.333	1	1140	4.5 A	5.6 A	15 A	120 V	1	MANUFACTURER	NO	THERMOSTAT	TRANE	S-180	98.00 lb	1,2

LOUVER SCHEDULE

NOTES:
1. LOUVER IS PART OF AN ARRAY.
2. PROVIDE BIRD SCREENS.
3. PAINTED FINISH. COLOR CHOSEN BY ARCHITECT.

LOUVER TAG	AREA SERVED	QUANTITY	ARRAY TOTAL CFM	LOUVER HEIGHT	LOUVER WIDTH	LOUVER MANUFACTURER	MAX FACE VELOCITY	LOUVER MODEL NO	NOTES
AML	AIR MONITOR	72	1314400 CFM	72 in	120 in	GREENHECK	515 FPM	ESD-635	1, 2, 3
CEL-A	CHILLER PLANT ELECTRIC ROOM	3	25,600 CFM	72 in	104 in	GREENHECK	210 FPM	ESD-635	1, 2, 3
CEL-B	CHILLER PLANT ELECTRIC ROOM	3	14,000 CFM	72 in	104 in	GREENHECK	135 FPM	ESD-635	1, 2, 3
CEL-C	CHILLER PLANT ELECTRIC ROOM	3	32,200 CFM	72 in	120 in	GREENHECK	260 FPM	ESD-635	1, 2, 3
MRL	MECHANICAL 206	3	19540 CFM	84 in	96 in	GREENHECK	200 FPM	ESD-635	1, 2, 3
BL	BOILER ROOM	6		60 in	72 in	GREENHECK		ESD-635	2, 3
GL	GENERATOR ROOMS	1	1227530 CFM	240 in	2110 in	GREENHECK	635 FPM	ESD-635	2, 3

INTAKE HOOD SCHEDULE

NOTES:
1. MANUFACTURER SHALL PROVIDE GAVANIZED BIRD SCREEN.
2. MANUFACTURER SHALL PROVIDE 24" TALL, INSULATED ROOF CURB.
3. MANUFACTURER SHALL PROVIDE WITH HINGED CURB CAP ADAPTER
4. MECHANICAL CONTRACTOR SHALL PROVIDE INSULATED BLADE, MOTORIZED CONTROL DAMPER. CONTROL CONTRACT SHALL PROVIDE DAMPER ACTUATOR.

UNIT TAG	DESCRIPTION	LOCATION	PERFORMANCE					BASIS OF DESIGN			
			CFM	PRESSURE DROP	THROAT VELOCITY	MAX. VELOCITY	THROAT AREA	MANUFACTURER	MODEL NO.	WEIGHT	NOTES
IH-1	HOODED AIR INTAKE	ROOF, AREA A	1750 CFM	0.045 in-wg	438 FPM	1200 FPM	4 ft²	GREENHECK	FGI-24X24	82.00 lb	1, 2, 3, 4
IH-2	HOODED AIR INTAKE	ROOF, AREA F	1750 CFM	0.063 in-wg	517 FPM	1200 FPM	24 ft²	GREENHECK	FGI-48X72	353.00 lb	1, 2, 3, 4

HVAC PUMPED COILS PUMP SCHEDULE

NOTES:
1. UNIT SHALL BE SEISMIC CLASS C RATED WITH 1.5 COMPONENT FACTOR

UNIT TAG	LOCATION	DESIGN CRITERIA								MOTOR DATA								ELECTRICAL				BASIS OF DESIGN		
		TYPE	FLOW	TDH	FLUID	MIN. FLUID TEMP.	MAX. FLUID TEMP.	MIN. IMPELLER DIA.	MIN. EFFICIENCY	BHP	HP	RPM	VOLTS	PH	FLA	MCA	MOCP	STARTER BY	STARTER TYPE	EM. POWER	CONTROL TYPE	MANUFACTURER	MODEL NO.	NOTES
P-1-1	1ST FLOOR MEZZANINE	INLINE	120 GPM	15 FT	HEATING HOT WATER	40.0 °F	130.0 °F	4.75	63.8%	0.703	1	1800	480 V	3	1 A	2 A	15 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	e-60 2x2x5.25	1
P-1-2	1ST FLOOR MEZZANINE	INLINE	66 GPM	15 FT	HEATING HOT WATER	40.0 °F	130.0 °F	5.4	64.2%	0.384	1	1800	480 V	3	1 A	1 A	15 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	e-60 2x2x5.25	1
P-2-1	MECHANICAL ROOM 206	INLINE	40 GPM	15 FT	HEATING HOT WATER	40.0 °F	130.0 °F	4.375	57.2%	0.268	0.33	1800	480 V	3	0 A	1 A	15 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	e-60 1.25x1.25x5.25	1
P-2-2	MECHANICAL ROOM 224	INLINE	8 GPM	10 FT	HEATING HOT WATER	40.0 °F	130.0 °F		31.3%	0.1	0.167	3300	120 V	1	2 A	3 A	15 A	E.C.	VFD	Y	DDC	BELL & GOSSETT	PL-36	1

EXHAUST FAN SCHEDULE

NOTE:
1. MECHANICAL CONTRACTOR SHALLPROVIDE INSULATED BLADE MOTORIZED CONTROL DAMPER. CONTROL CONTRACTOR SHALL PROVIDE DAMPER ACTUATOR. MANUFACTURER SHALL PROVIDE 24" CURB AND BIRD SCREEN.
2. MANUFACTURER SHALL PROVIDE WITH HINGED CURB CAP ADAPTER.
3. SPARK RESISTANT CLASS C FAN AND ROOF CURB.
4. FAN SHALL BE PROVIDED WITH PERFORMANCE BAFFLE TO MEET SELECTED FLOWRATE AND PRESSURE DROP.

UNIT TAG	AREA SERVED	FAN					NC LEVEL AT INLET S.P.	DISCHARGE SOUND POWER OCTAVE BAND CENTER FREQUENCY							MOTOR DATA						MOTOR	DISCONNECT						BASIS OF DESIGN		
		FAN TYPE	CFM	TOTAL EXTERNAL S.P.	RPM	DRIVE		125HZ	250HZ	500HZ	1000HZ	2000HZ	4000HZ	HP	VOLTS	PH	FLA	MCA	MOCP	EM. POWER	TYPE	PROVIDED BY	LOCATION	STARTER BY	STARTER TYPE	CONTROL TYPE	WEIGHT	MANUFACTURER	MODEL NO.	NOTES
EF-1-1	FUEL PUMP ROOM 103	ROOF MOUNTED DOWNBLAST	570 CFM	0.375 in-wg	1139	DIRECT	65	71	70	62	56	54	49	0.33	460 V	3	1.10 A	1.375 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA D	E.C.	VFD	DDC	67.00 lb	GREENHECK	G-099-A	1, 2, 3, 4
EF-2-1	LOCKER/BREAK 205	ROOF MOUNTED DOWNBLAST	485 CFM	0.250 in-wg	948	DIRECT	60	66	64	57	52	49	45	0.33	460 V	3	1.10 A	1.375 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA D	E.C.	VFD	DDC	67.00 lb	GREENHECK	G-099-A	1, 2, 4
EF-2-2	FUEL OIL DAY TANK A 222	ROOF MOUNTED DOWNBLAST	440 CFM	0.250 in-wg	907	DIRECT	59	65	62	56	51	49	44	0.33	460 V	3	1.10 A	1.375 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA A	E.C.	VFD	DDC	67.00 lb	GREENHECK	G-099-A	1, 2, 3, 4
EF-2-3	BATTERY ROOM 211	ROOF MOUNTED DOWNBLAST	800 CFM	0.100 in-wg	1152	DIRECT	68	71	73	63	60	60	51	0.25	460 V	3	1.10 A	1.375 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA E	E.C.	VFD	DDC	65.00 lb	GREENHECK	G-099-A	1, 2, 3, 4
EF-2-4	FUEL OIL DAY TANK B 213	ROOF MOUNTED DOWNBLAST	535 CFM	0.250 in-wg	996	DIRECT	62	68	66	59	54	51	46	0.25	460 V	3	1.10 A	1.375 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA E	E.C.	VFD	DDC	65.00 lb	GREENHECK	G-099-A	1, 2, 3, 4
EF-2-5	MAINTENANCE STORAGE ROOM 214	ROOF MOUNTED DOWNBLAST	790 CFM	0.375 in-wg	1356	DIRECT	70	74	74	66	61	60	54	0.25	460 V	3	1.10 A	1.375 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA F	E.C.	VFD	DDC	65.00 lb	GREENHECK	G-099-A	1, 2, 4
EF-2-6	GENERATOR ROOMS A AND B	ROOF MOUNTED DOWNBLAST	3590 CFM	0.250 in-wg	9	DIRECT	77	77	80	75	68	70	61	1	460 V	3	2.10 A	2.630 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA B	E.C.	VFD	DDC	124.00 lb	GREENHECK	G-180-B	1, 2, 4
EF-2-7	MSS BATTERY ROOM 229	ROOF MOUNTED DOWNBLAST	450 CFM	0.100 in-wg	745	DIRECT	56	62	58	53	49	45	39	0.25	460 V	3	1.10 A	1.375 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA C	E.C.	VFD	DDC	65.00 lb	GREENHECK	G-099-A	1, 2, 3, 4
REF-1	CHILLER PLANT 114	ROOF MOUNTED UPBLAST	6140 CFM	2.000 in-wg	932	DIRECT	85	84	88	83	77	75	73	7.5	460 V	3	11.00 A	13.250 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA D	E.C.	VFD	DCC	337.00 lb	GREENHECK	CUE-300HP-B	1, 2, 4
REF-2	CHILLER PLANT 114	ROOF MOUNTED UPBLAST	6140 CFM	2.000 in-wg	932	DIRECT	85	84	88	83	77	75	73	7.5	460 V	3	11.00 A	13.250 A	15 A	YES	LOCKING	MANUFACTURER	ROOF AREA D	E.C.	VFD	DCC	337.00 lb	GREENHECK	CUE-300HP-B	1, 2, 4

AIR COOLED CONDENSING UNIT SCHEDULE

NOTES:
1. UNIT SHALL BE SEISMIC CLASS C RATED WITH 1.5 COMPONENT FACTOR.
2. UNIT SHALL BE MOUNTED ON G.C. PROVIDED ROOF RAILS. MECHANICAL CONTRACTOR SHALL COORDINATE WITH G.C. FOR SIZING.
3. UNIT SHALL BE PROVIDED WITH MANUFACTURER MOUNTED, LOCKING DISCONNECT.

UNIT TAG	SYSTEM SERVED	LOCATION	COOLING		BTU PER HOUR	REFRIGERANT TYPE	ELECTRICAL	ELECTRICAL						BASIS OF DESIGN			
			EDB	LOW AMBIENT POINT			MCA	FLA	MOCP	VOLTS	PHASES	STARTER BY	DISC. SWITCH BY	EM. POWER	MANUFACTURER	MODEL NO.	WEIGHT	NOTES
ACCU-1	CRAC-1	ROOF AREA A	95.0 °F	-20.0 °F	58400.0 Btu/h	R-410a	1.8 A	1.4 A	15 A	460 V	3	MANUFACTURER	MANUFACTURER	YES	LIEBERT	MCS028	194.00 lb	1,2,3
ACCU-2	CRAC-2	ROOF AREA A	95.0 °F	-20.0 °F	58400.0 Btu/h	R-410a	1.8 A	1.4 A	15 A	460 V	3	MANUFACTURER	MANUFACTURER	YES	LIEBERT	MCS028	194.00 lb	1,2,3

SUPPLY GRILLE SCHEDULE

NOTES:
1. LOUVERED GRILLE, HORIZONTAL 45° BLADES, ALUMINUM, MANUFACTURERS STANDARD WHITE.
2. DRUM DIFFUSER SHALL INCLUDE FACTORY MOUNTED, OPPOSED BLADE DAMPER.
3. DRUM LOUVER EQUIPPED WITH INTEGRAL PITCH ROTATION MECHANISM.

TYPE TAG	NOMINAL FACE SIZE	BRANCH DUCT SIZE	NOMINAL AREA	MIN. CFM	MAX. CFM	MAX. NC LEVEL	MAX. CORE VELOCITY	MAX. VELOCITY PRESSURE	MAX. TOTAL PRESSURE	MANUFACTURER	MODEL NO.	NOTES
DLA	SEE PLANS	SEE PLANS	SEE PLANS	0 CFM	VARIES	15	650 FPM	0.026 in-wg	0.089 in-wg	PRICE	HCD	2, 3
DLB	SEE PLANS	SEE PLANS	SEE PLANS	0 CFM	VARIES	15	650 FPM	0.026 in-wg	0.089 in-wg	PRICE	HCD	2, 3
DLC	SEE PLANS	SEE PLANS	SEE PLANS	0 CFM	VARIES	15	650 FPM	0.026 in-wg	0.089 in-wg	PRICE	HCD	2, 3
DLD	SEE PLANS	SEE PLANS	SEE PLANS	0 CFM	VARIES	15	650 FPM	0.026 in-wg	0.089 in-wg	PRICE	HCD	2, 3
SG	SEE PLANS	SEE PLANS	SEE PLANS	0 CFM	VARIES	30	750 FPM	0.080 in-wg	0.130 in-wg	PRICE	610	1

SUPPLY DIFFUSER SCHEDULE

NOTES:
1. SQUARE CONE DIFFUSER, ALUMINUM, 1/2" FIBERGLASS WITH FOIL SCRIM VAPOR BARRIER INSULATED BACKPAN, MANUFACTURERS STANDARD WHITE.
2.. BORDER STYLE SHALL MATCH INSTLLATION LOCATION. SEE ARCHITECTURAL CEILING PLANS AND OTHER RELEVANT DRAWINGS.
3.. RADIUS OF DIFFUSION BASED ON TERMINAL HORIZONTAL VELOCITIES OF 150-100-50 FPM AT MAX CFM.

TYPE TAG	NOMINAL SIZE	NOMINAL ROUND NECK SIZE	BRANCH DUCT SIZE TO DIFFUSER	MINIMUM CFM	MAXIMUM CFM	MAX. NC LEVEL	THROW (FT) 150-100-50	MAX. NECK VELOCITY	MAX. VELOCITY PRESSURE	MAX. TOTAL PRESSURE	MANUFACTURER	MODEL NO.	TYPE	DESCRIPTION	NOTES
SDA	24"x24"	6	6	220 CFM	380 CFM	15	3-5-9	700 FPM	0.031 in-wg	0.103 in-wg	PRICE	SCD	CEILING	SQUARE CONE	1, 2, 3
SDB	24"x24"	8	8	320 CFM	500 CFM	15	4-6-11	700 FPM	0.031 in-wg	0.103 in-wg	PRICE	SCD	CEILING	SQUARE CONE	1, 2, 3
SDC	24"x24"	10	10	220 CFM	380 CFM	15	5-7-13	700 FPM	0.031 in-wg	0.103 in-wg	PRICE	SCD	CEILING	SQUARE CONE	1, 2, 3

RETURN AND EXHAUST GRILLE SCHEDULE

NOTES:
1. EGG CRATE GRILLE, 1/2"x1/2", 0° ALUMINUM CORE, MANUFACTURER'S STANDARD WHITE.
2. LOUVERED GRILLE, HORIZONTAL 45° BLADES, ALUMINUM, MANUFACTURER'S STANDARD WHITE.
3. BORDER STYLE SHALL MATCH INSTALLATION LOCATION. SEE ARCHITECTURAL CEILING PLANS AND OTHER RELEVANT DRAWINGS.

TYPE TAG	NOMINAL FACE SIZE	MIN. CORE AREA	BRANCH DUCT SIZE	MIN. CFM	MAX. CFM	MAX. NC LEVEL	MAX. CORE VELOCITY	MAX. VELOCITY PRESSURE	MAX. TOTAL PRESSURE	MANUFACTURER	MODEL NO.	NOTES
EG	SEE PLANS	SEE PLANS	SEE PLANS	0 CFM	<varies>	30	700 FPM	0.031 in-wg	0.130 in-wg	PRICE	630	2
EGA	12"x12"	0.88 Sq. Ft.	12"x12"	0 CFM	700	15	700 FPM	0.031 in-wg	0.046 in-wg	PRICE	80	1, 3
EGB	24"x24"	3.75 Sq. Ft.	24"x24"	0 CFM	1400 CFM	11	600 FPM	0.047 in-wg	0.024 in-wg	PRICE	80	1, 3
RG	SEE PLANS	SEE PLANS	SEE PLANS	0 CFM	<varies>	30	700 FPM	0.031 in-wg	0.130 in-wg	PRICE	630	2
RGB	24"x24"	3.75 Sq. Ft.	24"x24"	0 CFM	1400 CFM	11	700 FPM	0.031 in-wg	0.024 in-wg	PRICE	80	1, 3

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:35 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS


NO.	DATE	DESCRIPTION

DESIGNED BY: **AESI**
CHECKED BY: **AESI**
APPROVED BY: **Approver**
PROJECT NO.: **21-154**

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE: **HVAC SCHEDULES**

SHEET NUMBER: **H602**



CENTRAL UTILITY PLANT AIRFLOW ONE LINE

SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:35 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

HVAC ONE LINE DIAGRAMS

SHEET NUMBER

H701



BOILER ROOM AND CHILLER ELECTRICAL ROOM AIR HANDLERS

SCALE: NONE

HVAC SETPOINTS - AHU-1				
ROOM NAME	ROOM NO	SYSTEM SERVED	HEATING SETPOINT	COOLING SETPOINT

PLAN NOTES:

1. PRESSURE SWITCHES HARDWIRED TO VFD FOR HIGH STATIC LIMIT OR LOW STATIC LIMIT.
2. START/STOP INTERLOCK WITH THE FIRE ALARM SYSTEM.
3. FREEZE STAT HARDWIRED TO SUPPLY FAN VFD.

GLOBAL OUTDOOR AIR SENSOR (T-1)

GLOBAL PRESSURE SENSOR

COMBINED UNIT SEQUENCE OF OPERATIONS:

1. COMBINED AHU ECONOMIZER MODE:
   A. SEQUNCE DESCRIBES JOINT OPERATION OF AHU-1-1, MAU-1-1 AND MAU-1-2 TO RECLAIM HEATED AIR FROM CHILLER ELECTRICAL ROOM FOR BOILER COMBUSTION UP AIR DURING ECONOMIZER OPERATIONS.
   B. AHU-1-1 ECONOMIZER MODE
      a. ECONOMIZER OPERATION SHALL BE ENABLED WHEN:
         a.a. OUTSIDE AIR TEMPERATURE (T-1) IS BELOW 55°F (ADJ.).
         a.b. SUPPLY FAN STATUS IS ON.
      b. THE OUTSIDE AIR DAMPER (OAD-1) SHALL MODULATE OPEN AND THE RETURN AIR DAMPER (RAD-1) SHALL MODULATE CLOSE TO MAINTAIN COOLING COIL ENTERING TEMPERATURE (T-5) ABOVE 46°F.
      c. AHU-1-1 SUPPLY FAN VFD SHALL MODULATE TO MAINTAIN ROOM TEMPERATURE BETWEEN HEATING AND COOLING SETPOINTS.
   C. MAU-1-1 AND MAU-1-2 ECONOMIZER MODE
      a. IF AHU-1-1 ECONOMIZER MODE IS ENABLED, AHU-1-1 OUTDOOR AIR AIRFLOW MEASURING STATION (AFMS) SHALL TRACK INCOMING OUTDOOR AIR. MAU-1-1 AND MAU-1-2 OUTDOOR AIR DAMPERS SHALL MODULATE CLOSED AND RETURN AIR DAMPERS SHALL MODULATE OPEN TO TRANSFER THE OUTDOOR AIR FROM THE CHILLER ELECTRIC ROOM INTO THE BOILER ROOM FOR COMBUSTION AIR.
      b. VOLUME OF OUTDOOR AIR MEASURED BY AHU-1-1 AFMS SHALL BE PROPORTIONALLY DISTRIBUTED TO MAU-1-1 AND MAU-1-2 BASED ON MAU-1-1 AND MAU-1-2 CURRENT SUPPLY AIRFLOW RATES OVER THEIR COMBINED SUPPLY AIRFLOW RATE.

BOILER ROOM HEATING WATER MAU-1-1 SEQUENCE OF OPERATIONS:

1. GENERAL:
   A. THE AIR HANDLER HAS 4 SUPPLY AIR FANS WITH BACKDRAFT DAMPERS FROM MANUFACTURER. E.C. TO PROVIDE ONE VFD PER FAN. T.C.C. TO OPERATE EACH VFD INDEPENDENTLY AND TO DE-ENERGIZE FANS AS NEEDED TO MAXIMIZE UNIT TURNDOWN CAPABILITIES.
   B. THE VFDS SHALL BE CONTROLLED BY THE BAS AND INTERLOCKED WITH THE HHW BOILER CONTROLLERS.
   C. ALL SET POINTS SHALL BE ADJUSTABLE THROUGH THE BAS CONSOLE.
   D. ALL TEMPERATURES, AIRFLOWS AND DAMPER POSITIONS SHALL BE DISPLAYED AT THE BAS CONSOLE.
   E. THE SUPPLY AIR FAN VARIABLE FREQUENCY DRIVES SHALL HAVE HAND-OFF-AUTO SWITCHES.
      a. IN THE HAND POSITION, THE FAN SHALL RUN CONTINUOUSLY AT A CONSTANT SPEED. THE SPEED SHALL BE MANUALLY ADJUSTABLE AT THE VARIABLE FREQUENCY DRIVE CONTROL PAD. ALL TEMPERATURE AND FAN SYSTEM SAFETIES SHALL REMAIN FUNCTIONAL AS DESCRIBED BELOW.
      b. IN THE AUTOMATIC POSITION, THE BUILDING BAS SHALL CONTROL ALL FUNCTIONS AS DESCRIBED.
   F. UNIT TO OPERATE AS A SINGLE ZONE VARIABLE VOLUME UNIT TO MAINTAIN POSITIVE SPACE PRESSURE IN THE BOILER ROOM.
2. SAFETY INTERLOCKS:
   A. ON COMMAND TO STOP THE AIR HANDLER, THE SUPPLY AIR FANS SHALL BE DE-ENERGIZED, THE OUTSIDE AIR DAMPER (OAD-1) SHALL CLOSE AND THE RETURN AIR DAMPER (RAD-1) SHALL OPEN. THE CHILLED WATER CONTROL VALVE (V-CHW-1) AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL FULLY CLOSE. THE COIL PUMP (P-1-1)(UNLESS OTHERWISE NOTED) SHALL DE-ENERGIZE.
      a. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   B. WHENEVER THE FANS ARE STOPPED EITHER BY THE FIRE ALARM SYSTEM OR LOSS OF POWER, THE OUTSIDE AIR DAMPER (OAD-1) SHALL CLOSE, THE RETURN AIR DAMPER (RAD-1) SHALL CLOSE AND THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN. THE CHILLED WATER CONTROLS VALVE (V-CHW-1) AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL FULLY CLOSE. THE COIL PUMP (P-1-1)(UNLESS OTHERWISE NOTED) SHALL DE-ENERGIZE. AN ALARM SHALL BE SENT TO THE BAS.
   C. SUPPLY HIGH STATIC (P-1) AND LOW STATIC (P-2) PRESSURE LIMIT: IF THE SUPPLY AIR STATIC PRESSURE OF 4" WG POSITIVE OR 4" NEGATIVE SET POINTS ARE EXCEEDED, THE AIR HANDLER SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
      a. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   D. FREEZE PROTECTION
      a. WHEN THE OUTSIDE AIR TEMPERATURE FALLS TO BELOW 38°F (ADJUSTABLE), HEATING COIL PUMP (P-1-1) SHALL BE ENERGIZED.
      b. WHEN THE OUTSIDE AIR TEMPERATURE RISES TO ABOVE 43°F, HEATING COIL PUMP SHALL BE DE-ENERGIZED.
      c. PHYSICAL LOW LIMIT. IF THE FREEZESTAT TEMPERATURE (T-4) IS LESS THAN OR EQUAL TO 38°F:
         c.a. THE SUPPLY FAN SHALL STOP THROUGH A HARDWIRED INTERFACE BETWEEN THE FREEZE STAT (T-4) AND FAN MOTOR VFD.
         c.b. THE AIR HANDLER SHALL STOP.
         c.c. CHILLED WATER VALVE (V-CHW-1) SHALL OPEN 50%, COIL PUMP (P-1-1) SHALL REMAIN ON, AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL MODULATE TO MAINTAIN SENSOR (T-4) AT 50°F (ADJ.).
         c.d. AN ALARM SHALL BE SENT TO THE BAS.
         c.e. FREEZESTAT SHALL REQUIRE A MANUAL RESET.
      d. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   E. IF ANY FAN FAILS, AS DETERMINED BY CURRENT SENSOR, THE FAN SHALL BE DE-ENERGIZED AND AN ALARM SHALL BE SENT TO THE BAS. THE REMAINING UNIT'S FANS SHALL CONTINUE TO RUN AS DESCRIBED BELOW.
      a. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   F. SMOKE DETECTION
      a. ON DETECTION OF SMOKE IN THE RETURN AIR DUCT, THE SMOKE DETECTOR SHALL SIGNAL THE FIRE ALARM SYSTEM.
      b. THE FIRE ALARM SYSTEM, THROUGH HARD WIRING, SHALL STOP THE SUPPLY AIR FAN AS DESCRIBED ABOVE.
3. NORMAL OPERATION MODE
   A. ON COMMAND TO START MAU-1-1, THE OUTSIDE AIR DAMPER (OAD-1) AND RETURN AIR DAMPER (RAD-1) SHALL FULLY OPEN, UPON PROOF OF ALL DAMPERS OPENING, AS DETERMINED BY END POSITION SWITCHES, THE RETURN AIR DAMPER SHALL FULLY CLOSE AND THE OUTDOOR AIR DAMPER SHALL REMAIN OPEN.
   B. UPON SIGNAL FROM HEATING HOT WATER BOILER CONTROL PANEL, THE SUPPLY AIR DAMPER ASSOCIATED WITH THE SIGNALLING BOILER SHALL FULLY OPEN. UPON PROOF OF DAMPER OPENING, AS DETERMINED BY END POSITION SWITCH, THE LEAD SUPPLY FAN SHALL CYCLE ON.
      a. IF ANY SUPPLY AIR DAMPER DOES NOT FULLY OPEN, AS DETERMINED BY END POSITION SWITCH, AN ALARM SHALL BE SENT TO THE BAS.
      b. IF NO SUPPLY AIR DAMPER HAS BEEN PROVEN TO OPEN, THE UNIT SHALL SHUT DOWN AS DESCRIBED ABOVE.
      c. SUPPLY AIR DAMPERS SHALL FULLY CLOSE UPON SIGNAL FROM BOILER CONTROL PANEL OF ASSOCIATED BOILER DE-ENERGIZATION.
   C. MAU-1-1 FANS SHALL ENERGIZE, MODULATE AND DE-ENERGIZE IN RESPONSE TO BOILER ROOM PRESSURE SENSOR. MAU-1-1 FANS SHALL WORK IN CONJUNCTION WITH MAU-1-2 FAN TO MAINTAIN A POSITIVE DIFFERENTIAL PRESSURE IN THE BOILER ROOM OF +.05" W.C. (ADJ.) IN REFERENCE TO THE OUTDOOR PRESSURE.
   D. FILTERS:
      a. FILTERS SHALL BE ACTIVE UNITS AND SEND FAILURE/FAULT ALARMS TO THE BAS.
      b. A DIFFERENTIAL PRESSURE SWITCH SHALL MONITOR STATUS OF EACH FILTER BANK. AN ALARM SHALL BE ISSUED TO THE BAS WHEN THE FILTER PRESSURE EXCEEDS SETPOINT. SEE EQUIPMENT SCHEDULES FOR FINAL PRESSURE SETPOINT.
   E. HEATING MODE:
      a. HEATING MODE SHALL BE ENABLED WHENEVER:
         a.a. OUTSIDE AIR TEMPERATURE (T-1) IS LESS THAN 52°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE BAS SHALL MODULATE THE HEATING WATER CONTROL VALVE (V-HHW-1) TO MAINTAIN DISCHARGE SETPOINT (T-5) AT 55°F (T-3)(ADJ.)
   F. IF AHU-1-1 OA DAMPER IS OPEN, MAU-1-1 RETURN AIR DAMPER (RAD-1) AND OUTDOOR AIR DAMPER (OAD-1) SHALL MODULATE PER COMBINED UNIT SEQUENCE FOUND ON THIS SHEET.

BOILER ROOM STEAM MAU-1-2 SEQUENCE OF OPERATIONS:

1. GENERAL:
   A. THE AIR HANDLER HAS 1 SUPPLY AIR FAN, E.C. TO PROVIDE ONE VFD FOR THE FAN.
   B. THE VFD SHALL BE CONTROLLED BY THE BAS AND INTERLOCKED WITH THE STEAM BOILER CONTROLLERS.
   C. ALL SET POINTS SHALL BE ADJUSTABLE THROUGH THE BAS CONSOLE.
   D. ALL TEMPERATURES, AIRFLOWS AND DAMPER POSITIONS SHALL BE DISPLAYED AT THE BAS CONSOLE.
   E. THE SUPPLY AIR FAN VARIABLE FREQUENCY DRIVE SHALL HAVE A HAND-OFF-AUTO SWITCH.
      a. IN THE HAND POSITION, THE FAN SHALL RUN CONTINUOUSLY AT A CONSTANT SPEED. THE SPEED SHALL BE MANUALLY ADJUSTABLE AT THE VARIABLE FREQUENCY DRIVE CONTROL PAD. ALL TEMPERATURE AND FAN SYSTEM SAFETIES SHALL REMAIN FUNCTIONAL AS DESCRIBED BELOW.
      b. IN THE AUTOMATIC POSITION, THE BUILDING BAS SHALL CONTROL ALL FUNCTIONS AS DESCRIBED.
   F. UNIT TO OPERATE AS A SINGLE ZONE VARIABLE VOLUME UNIT TO MAINTAIN POSITIVE SPACE PRESSURE IN THE BOILER ROOM.
2. SAFETY INTERLOCKS:
   A. ON COMMAND TO STOP THE AIR HANDLER, THE SUPPLY AIR FANS SHALL BE DE-ENERGIZED, THE OUTSIDE AIR DAMPER (OAD-1) SHALL CLOSE AND THE RETURN AIR DAMPER (RAD-1) SHALL OPEN. THE CHILLED WATER CONTROL VALVE (V-CHW-1) AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL FULLY CLOSE. THE COIL PUMP (P-1-2)(UNLESS OTHERWISE NOTED) SHALL DE-ENERGIZE.
      a. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   B. WHENEVER THE FANS ARE STOPPED EITHER BY THE FIRE ALARM SYSTEM OR LOSS OF POWER, THE OUTSIDE AIR DAMPER (OAD-1) SHALL CLOSE, THE RETURN AIR DAMPER (RAD-1) SHALL CLOSE AND THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN. THE CHILLED WATER CONTROL VALVE (V-CHW-1) AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL FULLY CLOSE. THE COIL PUMP (P-1-2)(UNLESS OTHERWISE NOTED) SHALL DE-ENERGIZE. AN ALARM SHALL BE SENT TO THE BAS.
   C. SUPPLY HIGH STATIC (P-1) AND LOW STATIC (P-2) PRESSURE LIMIT: IF THE SUPPLY AIR STATIC PRESSURE OF 4" WG POSITIVE OR 4" NEGATIVE SET POINTS ARE EXCEEDED, THE AIR HANDLER SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
      a. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   D. FREEZE PROTECTION
      a. WHEN THE OUTSIDE AIR TEMPERATURE FALLS TO BELOW 38°F (ADJUSTABLE), HEATING COIL PUMP (P-1-2) SHALL BE ENERGIZED.
      b. WHEN THE OUTSIDE AIR TEMPERATURE RISES TO ABOVE 43°F, HEATING COIL PUMP SHALL BE DE-ENERGIZED.
      c. PHYSICAL LOW LIMIT: IF THE FREEZESTAT TEMPERATURE (T-4) IS LESS THAN OR EQUAL TO 38°F:
         c.a. THE SUPPLY FAN SHALL STOP THROUGH A HARDWIRED INTERFACE BETWEEN THE FREEZE STAT (T-4) AND FAN MOTOR VFD.
         c.b. THE AIR HANDLER SHALL STOP.
         c.c. CHILLED WATER VALVE (V-CHW-1) SHALL OPEN 50%, COIL PUMP (P-1-2) SHALL REMAIN ON, AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL MODULATE TO MAINTAIN SENSOR (T-4) AT 50°F (ADJ.).
         c.d. AN ALARM SHALL BE SENT TO THE BAS.
         c.e. FREEZESTAT SHALL REQUIRE A MANUAL RESET.
      d. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   E. IF THE FAN FAILS, AS DETERMINED BY CURRENT SENSOR, THE FAN SHALL BE DE-ENERGIZED AND AN ALARM SHALL BE SENT TO THE BAS.
      a. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   F. SMOKE DETECTION
      a. ON DETECTION OF SMOKE IN THE RETURN AIR DUCT, THE SMOKE DETECTOR SHALL SIGNAL THE FIRE ALARM SYSTEM.
      b. THE FIRE ALARM SYSTEM, THROUGH HARD WIRING, SHALL STOP THE SUPPLY AIR FAN AS DESCRIBED ABOVE.
3. NORMAL OPERATION MODE
   A. ON COMMAND TO START MAU-1-2, THE OUTSIDE AIR DAMPER (OAD-1) AND RETURN AIR DAMPER (RAD-1) SHALL FULLY OPEN. UPON PROOF OF ALL DAMPERS OPENING, AS DETERMINED BY END POSITION SWITCHES, THE RETURN AIR DAMPER SHALL FULLY CLOSE AND THE OUTDOOR AIR DAMPER SHALL REMAIN OPEN.
   B. UPON SIGNAL FROM STEAM BOILER CONTROL PANEL, THE SUPPLY AIR DAMPER ASSOCIATED WITH THE SIGNALLING BOILER SHALL FULLY OPEN. UPON PROOF OF DAMPER OPENING, AS DETERMINED BY END POSITION SWITCH, THE SUPPLY FAN SHALL CYCLE ON.
      a. IF ANY SUPPLY AIR DAMPER DOES NOT FULLY OPEN, AS DETERMINED BY END POSITION SWITCH, AN ALARM SHALL BE SENT TO THE BAS.
      b. IF NO SUPPLY AIR DAMPER HAS BEEN PROVEN TO OPEN, THE UNIT SHALL SHUT DOWN AS DESCRIBED ABOVE.
      c. SUPPLY AIR DAMPERS SHALL FULLY CLOSE UPON SIGNAL FROM BOILER CONTROL PANEL OF ASSOCIATED BOILER DE-ENERGIZATION.
   C. MAU-1-2 FAN SHALL MODULATE IN RESPONSE TO BOILER ROOM PRESSURE SENSOR. MAU-1-2 FAN SHALL WORK IN CONJUNCTION WITH MAU-1-1 FANS TO MAINTAIN A POSITIVE DIFFERENTIAL PRESSURE IN THE BOILER ROOM OF +.05" W.C. (ADJ.) IN REFERENCE TO THE OUTDOOR PRESSURE.
   D. FILTERS:
      a. FILTERS SHALL BE ACTIVE UNITS AND SEND FAILURE/FAULT ALARMS TO THE BAS.
      b. A DIFFERENTIAL PRESSURE SWITCH SHALL MONITOR STATUS OF EACH FILTER BANK. AN ALARM SHALL BE ISSUED TO THE BAS WHEN THE FILTER PRESSURE EXCEEDS SETPOINT. SEE EQUIPMENT SCHEDULES FOR FINAL PRESSURE SETPOINT.
   E. HEATING MODE:
      a. HEATING MODE SHALL BE ENABLED WHENEVER:
         a.a. OUTSIDE AIR TEMPERATURE (T-1) IS LESS THAN 52°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE BAS SHALL MODULATE THE HEATING WATER CONTROL VALVE (V-HHW-1) TO MAINTAIN DISCHARGE SETPOINT (T-5) AT 55°F (T-3)(ADJ.)
   F. IF AHU-1-1 OA DAMPER IS OPEN, MAU-1-2 RETURN AIR DAMPER (RAD-1) AND OUTDOOR AIR DAMPER (OAD-1) SHALL MODULATE PER COMBINED UNIT SEQUENCE FOUND ON THIS SHEET.

CHILLER ELECTRICAL ROOM AHU-1-1 SEQUENCE OF OPERATIONS:

1. GENERAL:
   A. THE AIR HANDLER HAS 4 SUPPLY AIR FANS WITH BACKDRAFT DAMPERS FROM MANUFACTURER. E.C. TO PROVIDE ONE VFD PER FAN. T.C.C. TO OPERATE EACH VFD INDEPENDENTLY AND TO DE-ENERGIZE FANS AS NEEDED TO MAXIMIZE UNIT TURNDOWN CAPABILITIES.
   B. THE VFDS SHALL BE CONTROLLED BY THE BAS.
   C. ALL SET POINTS SHALL BE ADJUSTABLE THROUGH THE BAS CONSOLE.
   D. ALL TEMPERATURES, AIRFLOWS AND DAMPER POSITIONS SHALL BE DISPLAYED AT THE BAS CONSOLE.
   E. THE SUPPLY AIR FAN VARIABLE FREQUENCY DRIVES SHALL HAVE A HAND-OFF-AUTO SWITCHES.
      a. IN THE HAND POSITION, THE FAN SHALL RUN CONTINUOUSLY AT A CONSTANT SPEED. THE SPEED SHALL BE MANUALLY ADJUSTABLE AT THE VARIABLE FREQUENCY DRIVE CONTROL PAD. ALL TEMPERATURE AND FAN SYSTEM SAFETIES SHALL REMAIN FUNCTIONAL AS DESCRIBED BELOW.
      b. IN THE AUTOMATIC POSITION, THE BUILDING BAS SHALL CONTROL ALL FUNCTIONS AS DESCRIBED.
   F. UNIT TO OPERATE AS A VARIABLE VOLUME UNIT TO MAINTAIN SPACE TEMPERATURE. IN THE CHILLER ELECTRICAL ROOM.
2. SAFETY INTERLOCKS:
   A. ON COMMAND TO STOP THE AIR HANDLER, THE SUPPLY AIR FANS SHALL BE DE-ENERGIZED, THE OUTSIDE AIR DAMPER (OAD-1) SHALL CLOSE AND THE RETURN AIR DAMPER (RAD-1) SHALL OPEN. THE CHILLED WATER CONTROL VALVE (V-CHW-1) AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL FULLY CLOSE.
   B. WHENEVER THE FANS ARE STOPPED EITHER BY THE FIRE ALARM SYSTEM OR LOSS OF POWER, THE OUTSIDE AIR DAMPER (OAD-1) SHALL CLOSE AND THE RETURN AIR DAMPER (RAD-1) SHALL OPEN. THE CHILLED WATER CONTROL VALVE (V-CHW-1) AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL FULLY CLOSE. AN ALARM SHALL BE SENT TO THE BAS.
   C. SUPPLY HIGH STATIC (P-1) AND LOW STATIC (P-2) PRESSURE LIMIT: IF THE SUPPLY AIR STATIC PRESSURE OF 4" WG POSITIVE OR 4" NEGATIVE SET POINTS ARE EXCEEDED, THE AIR HANDLER SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
      a. THE EMERGENCY OUTDOOR AIR DAMPERS (OAD-EM) SHALL OPEN IF ROOM PRESSURE BEGINS TO DROP BELOW -.05 IN. W.C. RELATIVE TO THE OUTDOOR AIR PRESSURE AND AN ALARM SHALL BE SENT TO THE BAS.
   D. FREEZE PROTECTION
      a. WHEN THE COOLING COIL ENTERING AIR TEMPERATURE (T-4) FALLS TO BELOW 43°F (ADJ.), HEATING COIL DAMPERS SHALL FULLY OPEN AND BYPASS DAMPERS SHALL FULLY CLOSE. HEATING WATER CONTROL VALVE SHALL MODULATE TO MAINTAIN TEMPERATURE (T-4) AT 50°F (ADJ.).
      b. WHEN THE COOLING COIL ENTERING AIR TEMPERATURE (T-4) RISES TO ABOVE 55°F (ADJ.), HEATING COIL DAMPERS SHALL FULLY CLOSE AND BYPASS DAMPERS SHALL FULLY OPEN.
      c. PHYSICAL LOW LIMIT: IF THE FREEZESTAT TEMPERATURE (T-4) IS LESS THAN OR EQUAL TO 38°F:
         c.a. THE SUPPLY FAN SHALL STOP THROUGH A HARDWIRED INTERFACE BETWEEN THE FREEZE STAT (T-5) AND FAN MOTOR VFD.
         c.b. THE AIR HANDLER SHALL STOP.
         c.d. AN ALARM SHALL BE SENT TO THE BAS.
         c.e. FREEZESTAT SHALL REQUIRE A MANUAL RESET.
   E. IF ANY FAN FAILS, AS DETERMINED BY CURRENT SENSOR, THE FAN SHALL BE DE-ENERGIZED AND AN ALARM SHALL BE SENT TO THE BAS. THE REMAINING UNIT'S FANS SHALL CONTINUE TO RUN AS DESCRIBED BELOW.
   F. SMOKE DETECTION
      a. ON DETECTION OF SMOKE IN THE RETURN AIR DUCT, THE SMOKE DETECTOR SHALL SIGNAL THE FIRE ALARM SYSTEM.
      b. THE FIRE ALARM SYSTEM, THROUGH HARD WIRING, SHALL STOP THE SUPPLY AIR FAN AS DESCRIBED ABOVE.
3. NORMAL OPERATION MODE:
   A. ON COMMAND TO START AHU-1-1, THE SUPPLY FANS SHALL CYCLE ON AND RUN CONTINUOUSLY. THE RETURN AIR DAMPER (RAD-1) SHALL BE FULLY OPEN AND THE OUTDOOR AIR DAMPER (OAD-1) SHALL BE FULLY CLOSED, WITH BOTH DAMPER POSITIONS CONFIRMED BY END POSITION SWITCHES. SUPPLY FANS SHALL RAMP UP AND DOWN IN RESPONSE TO CHILLER ELECTRICAL ROOM TEMPERATURE SENSOR SET AT 85°F FOR COOLING AND 55°F FOR HEATING.
   B. FILTERS:
      a. FILTERS SHALL BE ACTIVE UNITS AND SEND FAILURE/FAULT ALARMS TO THE BAS.
      b. A DIFFERENTIAL PRESSURE SWITCH SHALL MONITOR STATUS OF EACH FILTER BANK. AN ALARM SHALL BE ISSUED TO THE BAS WHEN THE FILTER PRESSURE EXCEEDS SETPOINT. SEE EQUIPMENT SCHEDULES FOR FINAL PRESSURE SETPOINT.
   C. CHILLED WATER COOLING:
      a. COOLING MODE SHALL BE ENABLED WHENEVER:
         a.a. ROOM TEMPERATURE IS GREATER THAN 85°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE BAS SHALL MODULATE THE CHILLED WATER CONTROL VALVE (V-CHW-1) TO MAINTAIN ROOM SETPOINT AT 85°F (ADJ.).
      c. ONCE THE CHILLED WATER CONTROL VALVE (V-CHW-1) IS FULLY OPEN, THE BAS SHALL MODULATE THE FAN SPEED TO MAINTAIN ROOM TEMPERATURE (ADJ.) AT 85°F (ADJ.) SETPOINT.
   D. ECONOMIZER MODE:
      a. THE ECONOMIZER CYCLE SHALL BE ENABLED PER THE COMBINED UNIT SEQUENCE FOUND ON THIS SHEET.

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:36 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 305 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 | Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023


REVISIONS		
NO.	DATE	DESCRIPTION

DESIGNED BY	AESI
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE: HVAC DIAGRAMS

SHEET NUMBER: H702



CHILLER ROOM TEMPERATURE CONTROL DIAGRAM

PLAN NOTES:

1. PRESSURE SENSORS HARDWIRED TO VFD FOR HIGH STATIC LIMIT OR LOW STATIC LIMIT. PROVIDE ANALOG CONNECTION TO DDC CONTROLS.
2. START/STOP INTERLOCK WITH THE FIRE ALARM SYSTEM.
3. FREEZE STAT HARDWIRED TO SUPPLY FAN VFD.

HVAC SETPOINTS - AHU-2-1

ROOM NAME	ROOM NO	SYSTEM SERVED	HEATING SETPOINT	COOLING SETPOINT

HVAC SETPOINTS - AHU-2-2

ROOM NAME	ROOM NO	SYSTEM SERVED	HEATING SETPOINT	COOLING SETPOINT

PLAN NOTES:

1. PRESSURE SWITCHES HARDWIRED TO VFD FOR HIGH STATIC LIMIT OR LOW STATIC LIMIT. PROVIDE PRESSURE SENSORS WITH ANALOG CONNECTION TO DDC CONTROLS AT SAME LOCATIONS.
2. START/STOP INTERLOCK WITH THE FIRE ALARM SYSTEM.
3. FREEZE STAT HARDWIRED TO SUPPLY FAN VFD.

NORTH MEZZANINE AHU TEMPERATURE CONTROL DIAGRAM

CHILLER ROOM MUA-2-1 AND REF-1 AND REF-2 SEQUENCE OF OPERATIONS:

1. GENERAL:
   - A. THE AIR HANDLER HAS ONE SUPPLY AIR FAN. E.C. TO PROVIDE ONE VFD FOR THE FAN. E.C. TO PROVIDE VFD FOR THE HEAT RECOVERY WHEEL.
   - B. ALL SET POINTS SHALL BE ADJUSTABLE THROUGH THE BAS CONSOLE.
   - C. ALL TEMPERATURES, AIRFLOWS AND DAMPER POSTIONS SHALL BE DISPLAYED AT THE BAS CONSOLE.
   - D. THE SUPPLY AIR FAN VFD SHALL HAVE A HAND-OFF-AUTO SWITCH.
     - a. IN THE HAND POSITION, THE FAN SHALL RUN CONTINUOUSLY AT A CONSTANT SPEED. THE SPEED SHALL BE MANUALLY ADJUSTABLE AT THE VARIABLE FREQUENCY DRIVE CONTROL PAD. ALL TEMPERATURE AND FAN SYSTEM SAFETIES SHALL REMAIN FUNCTIONAL AS DESCRIBED BELOW.
     - b. IN THE AUTOMATIC POSITION, THE BUILDING BAS SHALL CONTROL ALL FUNCTIONS AS DESCRIBED BELOW.
   - E. UNIT TO OPERATE AS A CONSTANT VOLUME UNIT TO MAINTAIN MAKEUP AIR VOLUME AND SPACE TEMPERATURE. TAB CONTRACTOR SHALL SET VFD SPEED.
2. SAFETY INTERLOCKS:
   - A. ON COMMAND TO STOP THE AIR HANDLER, THE SUPPLY AIR FAN SHALL BE DE-ENERGIZED, AND THE OUTSIDE AIR DAMPER (OAD-1) SHALL CLOSE. THE HEAT RECOVERY WHEEL SHALL DE-ENERGIZE AND SUPPLY AND EXHAUST BYPASS DAMPERS SHALL OPEN. THE CHILLED WATER CONTROLS VALVE (V-CHW-1) AND HEATING WATER CONTROL VAVLE (V-HHW-1) SHALL FULLY CLOSE. THE COIL PUMP (P-2-1) (UNLESS OTHERWISE NOTED) SHALL DE-ENERGIZE.
   - B. WHENEVER THE SUPPLY FAN IS STOPPED EITHER BY THE BAS, THE FIRE ALARM SYSTEM OR LOSS OF POWER, THE OUTSIDE AIR DAMPER (OAD-1) SHALL CLOSE AND THE HEAT RECOVERY WHEEL SHALL DE-ENERGIZE. THE BYPASS DAMPERS SHALL OPEN. THE CHILLED WATER CONTROLS VALVE (V-CHW-1), HEATING WATER CONTROL VAVLE (V-HHW-1) AND COIL PUMP (P-2-1)(UNLESS OTHERWISE NOTED) SHALL DE-ENERGIZE. AN ALARM SHALL BE SENT TO THE BAS.
   - C. WHENEVER BOTH EXHAUST FANS ARE STOPPED EITHER BY THE BAS, THE FIRE ALARM SYSTEM OR LOSS OF POWER, MAU-2-1 SHALL SHUT DOWN AS DESCRIBED ABOVE AND THE EXHAUST AIR DAMPERS (EAD-1 AND EAD-2) SHALL FULLY CLOSE.
   - D. SUPPLY HIGH STATIC AND LOW STATIC PRESSURE LIMIT: IF THE SUPPLY AIR STATIC PRESSURE OF 4" WG POSITIVE (P-1) OR 4" NEGATIVE (P-2) SET POINT IS EXCEEDED, THE AIR HANDLER SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
   - E. EXHAUST LOW STATIC PRESSURE LIMIT: IF THE EXHAUST AIR STATIC PRESSURE OF 3" NEGATIVE (P-3) SET POINT IS EXCEEDED, THE EXHAUST FANS SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
   - F. IF THE SUPPLY FAN FAILS, AS DETERMINED BY CURRENT SENSOR, THE FAN SHALL BE DE-ENERGIZED AND AN ALARM SHALL BE SENT TO THE BAS.
   - G. IF EITHER EXHAUST AIR FAN (REF-1 OR REF-2) FAILS, AS DETERMINED BY CURRENT SENSOR, THE FAN SHALL DE-ENERGIZED, THE ASSOCIATED EXHAUST AIR DAMPER (EAD-1 OR EAD-2) SHALL FULLY CLOSE AND AN ALARM SHALL BE SENT TO THE BAS. THE REMAINING EXHAUST FAN SHALL RE-INDEX TO MAINTAIN CONSTANT FLOW FROM THE CHILLER ROOM, SEE EQUIPMENT SCHEDULES FOR FLOW RATE.
   - H. FREEZE PROTECTION
     - a. WHEN THE OUTSIDE AIR TEMPERATURE FALLS TO BELOW 38°F (ADJUSTABLE), HEATING COIL PUMP (P-2-1) SHALL BE ENERGIZED.
     - b. WHEN THE OUTSIDE AIR TEMPERATURE RISES TO ABOVE 43°F, HEATING COIL PUMP SHALL BE DE-ENERGIZED.
     - c. PHYSICAL LOW LIMIT: IF THE FREEZESTAT TEMPERATURE (T-3) IS LESS THAN OR EQUAL TO 38°F:
       - c.a. THE SUPPLY FAN SHALL STOP THROUGH A HARDWIRED INTERFACE BETWEEN THE FREEZE STAT (T-3) AND FAN MOTOR VFD.
       - c.b. THE AIR HANDLER SHALL STOP.
       - c.c. CHILLED WATER VALVE (V-CHW-1) SHALL OPEN 50%, COIL PUMP (P-2-1) SHALL REMAIN ON, AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL MODULATE TO MAINTAIN SENSOR (T-3) AT 50°F (ADJ.).
       - c.d. AN ALARM SHALL BE SENT TO THE BAS.
       - c.e. FREEZESTAT SHALL REQUIRE A MANUAL RESET.
   - I. SMOKE DETECTION
     - a. ON DETECTION OF SMOKE IN THE RETURN AIR DUCT, THE SMOKE DETECTOR SHALL SIGNAL THE FIRE ALARM SYSTEM.
     - b. THE FIRE ALARM SYSTEM, THROUGH HARD WIRING, SHALL STOP THE SUPPLY AIR FAN AND THE EXHAUST AIR FANS REF-1 AND REF-2 AS DESCRIBED ABOVE.
3. NORMAL OPERATION MODE
   - A. ON COMMAND TO START MAU-2-1, THE OUTSIDE AIR DAMPER (OAD-1) AND EXHAUST AIR DAMPERS (EAD-1 AND EAD-2) SHALL FULLY OPEN. UPON PROOF OF ALL DAMPERS OPENING, AS DETERMINED BY END POSITION SWITCHES, THE SUPPLY FAN SHALL CYCLE ON AND SUPPLY A CONSTANT AIR VOLUME TO THE SPACE. SEE EQUIPMENT SCHEDULES FOR FLOWRATE. THE REFRIGERANT EXHAUST FANS SHALL CYCLE ON AND EXHAUST A CONSTANT AIR VOLUME FROM THE SPACE, SEE EQUIPMENT SCHEDULES FOR FLOWRATE. THE DESIGN SPEED SET POINT FOR SUPPLY FAN AND EXHAUST FANS SHALL BE DETERMINED IN ACCORDANCE WITH THE TESTING, ADJUSTING AND BALANCING (TAB) SPECIFICATIONS AND AIR FLOW MEASURING STATIONS (AFMS).
     - a. IF OUTDOOR AIR DAMPER DOES NOT FULLY OPEN, AS DETERMINED BY END POSITION SWITCH, MAU-2-1 SHALL SHUT DOWN AS DESCRIBED ABOVE AND AN ALARM SHALL BE SENT TO THE BAS.
     - b. IF EITHER EXHAUST AIR DAMPER (EAD-1 OR EAD-2) DOES NOT FULLY OPEN, AS DETERMINED BY THE END POSITION SWITCH, THEN THE ASSOCIATED FAN SHALL NOT ENERGIZE. AN ALARM SHALL BE SENT TO THE BAS. THE REMAINING FAN WITH A FULLY OPEN DAMPER SHALL INDEX TO MAINTAIN SCHEDULED EXHAUST AIRFLOW.
     - c. IF NEITHER EXHAUST AIR DAMPER (EAD-1 AND EAD-2) FULLY OPEN, AS DETERMINED BY THE END POSITION SWITCH, THEN THE EXHAUST AIR FANS SHALL NOT ENERGIZE AND A STOP SIGNAL SHALL BE SENT TO MAU-2-1. AN ALARM SHALL BE SENT TO THE BAS.
   - B. FANS REF-1 AND REF-2 SHALL RUN IN PARALLEL TO MAINTAIN FLOWRATE FROM CHILLER ROOM.
   - C. THE EXHAUST AIR DAMPERS (GEN-E&-1&2) IN THE CHILLER ROOM SHALL BE OPEN. ALL CHILLER EXHAUST AIR DAMPERS (CHILL-EAD-1 THROUGH 7) SHALL BE CLOSED.
   - D. FILTERS:
     - a. FILTERS SHALL BE ACTIVE UNITS AND SEND FAILURE/FAULT ALARMS TO THE BAS.
     - b. A DIFFERENTIAL PRESSURE SWITCH SHALL MONITOR STATUS OF EACH FILTER BANK. AN ALARM SHALL BE ISSUED TO THE BAS WHEN THE FILTER PRESSURE EXCEEDS SETPOINT. SEE EQUIPMENT SCHEDULES FOR FINAL PRESSURE SETPOINT.
   - E. CHILLED WATER COOLING:
     - a. COOLING MODE SHALL BE ENABLED WHENEVER:
       - a.a. POST-WHEEL SENSOR (T-2) IS GREATER THAN 58°F (ADJ.) AND POST WHEEL ENTHALPY IS ABOVE 28 BTU/LB (ADJ.).
       - a.b. THE SUPPLY FAN STATUS IS ON.
       - a.c. THE SPACE SETPOINT IS ABOVE 85°F (ADJ).
     - b. IF ROOM TEMPERATURE (T-7) DRIFTS ABOVE 85°F SETPOINT, THE BAS SHALL MODULATE THE CHILLED WATER CONTROL VALVE (V-CHW-1) TO MAINTAIN COIL DISCHARGE SETPOINT AT 55°F (T-3)(ADJ.). ONCE SPACE SETPOINT IS BELOW 82°F, THE BAS SHALL FULLY CLOSE THE CHILLED WATER CONTROL VALVE.
   - F. HOT WATER HEATING:
     - a. HEATING MODE SHALL BE ENABLED WHENEVER:
       - a.a. POST-WHEEL SENSOR (T-2) IS LESS THAN 45°F (ADJ.).
       - a.b. THE SUPPLY FAN STATUS IS ON.
       - a.c. THE ROOM TEMPERATURE IS LESS THAN 55°F (ADJ.).
     - b. THE BAS SHALL MODULATE THE HEATING WATER CONTROL VALVE (V-CHW-1) TO MAINTAIN DISCHARGE SETPOINT AT 60°F (T-3)(ADJ.) ONCE THE POST-WHEEL SENSOR (T-2) RISES ABOVE 48°F, THE BAS SHALL FULLY CLOSE THE HEATING WATER CONTROL VALVE.
   - G. ECONOMIZER CYCLE:
     - a. THE ECONOMIZER CYCLE SHALL BE ACTIVE WHEN:
       - a.a OUTSIDE AIR TEMPERATURE (T-1) IS BETWEEN 45°F(ADJ.) AND 58°F (ADJ.)
       - a.b. OUTSIDE AIR ENTHALPY IS BELOW 28 BTU/LB (ADJ.)
       - a.c. SUPPLY FAN STATUS IS ON.
     - b. THE HEATING WATER CONTROL VALVE (V-HHW-1) AND CHILLED WATER CONTROL VALVE (V-CHW-1) SHALL BE FULLY CLOSED. THE HEAT RECOVERY WHEEL SHALL BE DE-ENERGIZED AND SUPPLY AND EXHAUST BYPASS DAMPERS SHALL BE FULLY OPEN.
     - c. THE UNIT SHALL CONTINUE TO PROVIDE CONSTANT MAKE UP AIR TO THE SPACE. THE EXHAUST FANS (REF-1 AND REF-2) SHALL CONTINUE TO PROVIDE CONSTANT EXHAUST FROM THE SPACE. THE SPACE SETPOINT SHALL BE MAINTAINED BETWEEN 55°F AND 85°F.
     - d. IF SPACE TEMPERATURE (T-7) DRIFTS ABOVE OR BELOW SETPOINTS, UNIT SHALL RESUME HEAT RECOVERY, AS DESCRIBED BELOW, AND HEATING AND COOOLING, AS DESCRIBED ABOVE, TO MAINTAIN SPACE TEMPERATURE SETPOINTS.
   - H. HEAT RECOVERY WHEEL CONTROL:
     - a. HEAT WHEEL TO BE PROVIDED WITH INVERTER RATED MOTOR AND VFD CONTROLLER. PROGRAM IN MANUFACTURER RECOMMENDED WHEEL JOG TO GET WHEEL STARTED WHEN IT IS STOPPED.
     - b. THE DIFFERENCE IN ENTHALPY BETWEEN THE OA AND RA INPUTS IS MONITORED TO DETERMINE IF HEAT WHEEL SHALL OPERATE IN COOLING OR HEATING MODE.
     - c. CONTROL WHEEL SPEED TO MAINTAIN MIXED AIR TEMPERATURE OF 3 DEG BELOW SETPOINT IN HEATING MODE AND 3 DEG ABOVE SETPONT IN COOLING MODE. VARY SPEED OF HEAT WHEEL TO MAINTAIN ROOM TEMPERATURE SETPOINT AS 1ST STAGE OF HEATING OR COOLING BEFORE OPENING HEATING OR COOLING CONTROL VALVES AS DESCRIBED ABOVE.
     - d. IF OA ENTHALPY IS GREATER THAN RA ENTHALPY, THE WHEEL SHALL BE IN COOLING MODE AND SHALL RECEIVE A FULL 10VDC SIGNAL. DIFFERENCE IN ENTHALPY SHALL BE ADJUSTABLE BY 5%.
     - e. IF OA ENTHALPY IS LESS THAN RA ENTHALPY BY 0.5%, THE WHEEL SHALL OPERATE IN HEATING MODE. PROVIDE AN ANALOG SIGNAL FROM 0-6VDC BASED ON THE HEAT WHEEL OUTSIDE AIR DISCHARGE TEMPERATURE. IF HEAT WHEEL DISCHARGE TEMPERATURE IS ABOVE AHU SUPPLY AIR SETPOINT MINUS 3 DEG THE SIGNAL SHALL BE 0VDC. THIS SIGNAL SHALL MODULATE UP TO 6VDC AT A 5° (ADJ.) DIFFERENCE. DIFFERENCE IN ENTHALPY SHALL BE ADJUSTABLE BY 5% ABOVE OR BELOW.
     - f. FROST PROTECTION CYCLE SHALL BE INITIATED IF HEAT WHEEL DISCHARGE EA TEMPERATURE REACHES OR DROPS BELOW 5°F (ADJ). INITIAL FROST TEMPERATURE TO BE PROVIDED BY WHEEL MANUFACTURER. WHEEL SHALL CONTROL BASED ON EA TEMPERATURE TO PREVENT FROSTING UNTIL EA TEMPERATURE IS ABOVE SETPOINT.
     - g. THE HEAT WHEEL BY-PASS DAMPERS SHALL BE CLOSED WHEN THE HEAT WHEEL IS ON.
     - h. OPEN WHEEL BYPASS DAMPERS WHEN IT IS NOT IN USE.
4. REFRIGERANT MONITOR SYSTEM PURGE CYCLE
   - A. UPON SIGNAL FROM ROOM REFRIGERANT MONITOR SYSTEM (ZONE-X), THE CHILLER EXHAUST AIR DAMPER (CHILL EAD-X) ASSOCIATED WITH THE LEAK DETECTION SHALL FULLY OPEN. UPON CONFIRMATION OF OPEN CHILLER DAMPER STATUS, AS DETERMINED BY END POSITION SWITCH, BOTH GENERAL EXHAUST AIR DAMPERS (GEN-EAD-1&2) SHALL FULLY CLOSE. A VISUAL ALARM SHALL BE INDICATED IN THE ROOM NEAR THE CHILLERS, AND OUTSIDE OF EACH CHILLER ROOM DOOR. AN ALARM SHALL BE GENERATED AT BAS. IF MULTIPLE ZONES ACTIVATE UPON LEAK DETECTION ALARM, OPEN ALL DAMPERS ASSOCIATED WITH THOSE ZONES.
   - B. MAU-2-1 SHALL DEACTIVATE HEAT RECOVERY WHEEL AND OPEN BOTH WHEEL BYPASS DAMPERS.
   - C. MINIMUM RUN TIME OF EMERGENCY MODE SHALL BE 5 MINUTES. IF REFRIGERANT DETECTOR (ZONE X) IS NOT IN ALARM AFTER THAT TIME, VISUAL ALARMS SHALL BE CANCELED, GENERAL EXHAUST DAMPERS (GEN-EAD-1&2) SHALL RE-OPEN AND CHILLER EXHAUST AIR DAMPER (CHILL-EAD-X) SHALL FULLY CLOSE .

AHU-2-1, AHU-2-2 AND RF-1 SEQUENCE OF OPERATIONS:

1. GENERAL:
   - A. THE AIR HANDLERS HAVE ONE SUPPLY AIR FAN EACH, E.C. TO PROVIDE ONE VFD PER FAN.
   - B. ALL SET POINTS SHALL BE ADJUSTABLE THROUGH THE BAS CONSOLE.
   - C. ALL TEMPERATURES, AIRFLOWS, AND DAMPER POSITIONS SHALL BE DISPLAYED AT THE BAS CONSOLE.
   - D. THE SUPPLY AIR FAN VFD SHALL HAVE A HAND-OFF-AUTO SWITCH.
     - a. IN THE HAND POSITION, THE FAN SHALL RUN CONTINUOUSLY AT A CONSTANT SPEED. THE SPEED SHALL BE MANUALLY ADJUSTABLE AT THE VARIABLE FREQUENCY DRIVE CONTROL PAD. ALL TEMPERATURE AND FAN SYSTEM SAFETIES SHALL REMAIN FUNCTIONAL AS DESCRIBED BELOW.
     - b. IN THE AUTOMATIC POSITION, THE BUILDING BAS SHALL CONTROL ALL FUNCTIONS AS DESCRIBED.
   - E. AHUS TO OPERATE AS VARIABLE VOLUME UNITS TO MAINTAIN CONSTANT DUCT TEMPERATURE AND CONSTANT DUCT STATIC PRESSURE.
2. SAFETY INTERLOCKS:
   - A. WHENEVER EITHER AHU SUPPLY FAN IS STOPPED EITHER BY THE FIRE ALARM SYSTEM OR LOSS OF POWER, THE OUTDOOR AIR DAMPER (OAD-1) SHALL CLOSE, THE RELIEF AIR DAMPER (EAD-1) SHALL CLOSE, AND THE RETURN AIR DAMPER (RAD-1) SHALL OPEN. ALL VALVES SHALL FULLY CLOSE. AN ALARM SHALL BE SENT TO THE BAS.
   - B. SUPPLY HIGH STATIC AND LOW STATIC PRESSURE LIMIT: IF THE SUPPLY AIR STATIC PRESSURE OF 4" WG POSITIVE (P-1) OR 4" NEGATIVE (P-2) SET POINT IS EXCEEDED, THE ASSOCIATED AIR HANDLER SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
   - C. RELIEF LOW STATIC PRESSURE LIMIT: IF THE RELIEF AIR STATIC PRESSURE OF 3" NEGATIVE (P-3) SET POINT IS EXCEEDED, THE RELIEF FAN SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
   - D. FREEZE PROTECTION
     - a. PHYSICAL LOW LIMIT: IF THE FREEZESTAT TEMPERATURE (T-4) IS LESS THAN OR EQUAL TO 38°F:
       - a.a. THE SUPPLY FANS SHALL STOP THROUGH A HARDWIRED INTERFACE BETWEEN THE FREEZESTAT (T-4) AND THE FAN MOTOR VFD.
       - a.b. THE AIR HANDLER SHALL STOP.
       - a.c. CHILLED WATER VALVE (V-CHW-1) SHALL OPEN 50% AND THE HEATING WATER CONTROL VALVE (V-HHW-1) SHALL MODULATE TO MAINTAIN SENSOR (T-4) AT 50°F(ADJ.).
       - a.d. AN ALARM SHALL BE SENT TO THE BAS.
       - a.e. FREEZESTAT SHALL REQUIRE A MANUAL RESET.
   - E. IF A SUPPLY FAN FAILS, AS DETERMINED BY CURRENT SENSOR, THE ASSOCIATED AHU SHALL BE SHUT-DOWN AS DESCRIBED ABOVE AND AN ALARM SHALL BE SENT TO THE BAS.
   - F. IF THE RELIEF AIR FAN (RF-1) FAILS, AS DETERMINED BY CURRENT SENSOR, THE FAN SHALL BE DE-ENERGIZED, THE RELIEF AIR DAMPERS (EAD-1) SHALL REMAIN OPEN.
     - a. AN ALARM SHALL BE SENT TO THE BAS.
     - b. BOTH AHU-2-1 AND AHU-2-2 SHALL EXIT ECONOMIZER MODE.
     - c. THE OUTDOOR AIR DAMPERS (OAD-1) AND RETURN AIR DAMPERS (RAD-1) SHALL MODULATE TO MAINTAIN MINIMUM OUTDOOR AIR AND RELIEF AIR FLOWRATES AS DETERMINED BY AIRFLOW MEASURING STATIONS. SEE EQUIPMENT SCHEDULES FOR FLOWRATES.
   - G. SMOKE DETECTION
     - a. ON DETECTION OF SMOKE IN THE RETURN AIR DUCT, THE SMOKE DETECTOR SHALL SIGNAL THE FIRE ALARM SYSTEM.
     - b. THE FIRE ALARM SYSTEM THROUGH HARD WIRING SHALL STOP THE AHUS AND THE RELIEF AIR FAN (RF-1) AS DESCRIBED ABOVE.
3. UNIT SHUTDOWN
   - A. ON COMMAND FROM THE BAS TO STOP EITHER AIR HANDLER OR AN IN FIELD MANUAL FAN SHUTDOWN, THE SUPPLY AIR FAN SHALL BE DE-ENERGIZED, THE OUTDOOR AIR DAMPER (OAD-1) SHALL CLOSE, THE RELIEF AIR DAMPER (EAD-1) SHALL CLOSE, AND RETURN AIR DAMPER (RAD-1) SHALL OPEN. ALL VALVES SHALL FULLY CLOSE.
     - a. IF BOTH AHU-2-1 AND AHU-2-2 ARE COMMANDED TO STOP OR BOTH IN FIELD MANUAL FAN SHUTDOWNS ARE ACTIVATED, THE RELIEF FAN (RF-1) SHALL SHUTDOWN AS DESCRIBED BELOW.
   - B. ON COMMAND FROM THE BAS TO STOP THE RELIEF FAN OR AN IN FIELD MANUAL FAN SHUTDOWN, THE FAN SHALL BE DE-ENERGIZED, THE RELIEF AIR DAMPERS (EAD-1) SHALL REMAIN OPEN.
     - a. AN ALARM SHALL BE SENT TO THE BAS.
     - b. BOTH AHU-2-1 AND AHU-2-2 SHALL EXIT ECONOMIZER MODE.
     - c. THE OUTDOOR AIR DAMPERS (OAD-1) AND RETURN AIR DAMPERS (RAD-1) SHALL MODULATE TO MAINTAIN MINIMUM OUTDOOR AIR AND RELIEF AIR FLOWRATES AS DETERMINED BY AIRFLOW MEASURING STATIONS. SEE EQUIPMENT SCHEDULES FOR FLOWRATES.
4. NORMAL OPERATION MODE
   - A. ON COMMAND TO START EITHER OR BOTH AHU-2-1 OR AHU-2-2, THE OUTSIDE AIR DAMPER(S) (OAD-1) AND RELIEF AIR DAMPER(S) (EAD-1) SHALL FULLY OPEN. UPON PROOF OF ALL DAMPERS OPENING, AS DETERMINED BY END POSITION SWITCHES, THE SUPPLY FAN SHALL CYCLE ON AND RUN CONTINUOUSLY. THE OUTDOOR AIR DAMPER(S) (OAD-1), RETURN AIR DAMPER(S) (RAD-1) AND RELIEF AIR DAMPER(S) (EAD-1) SHALL INDEX TO MAINTAIN MINIMUM OUTDOOR AIR FLOW RATES IN ACCORDANCE WITH THE TESTING, ADJUSTING AND BALANCING (TAB) SPECIFICATIONS AND AS MEASURED BY THE AIR FLOW MEASURING STATIONS (AFMS). SEE EQUIPMENT SCHEDULES FOR FLOWRATES. SUPPLY FAN SHALL RAMP UP AND DOWN IN RESPONSE TO DUCT PRESSURE SENSOR (P-3) SET AT 2" W.C. SEE PLANS FOR LOCATION OF DUCT PRESSURE SENSORS. THE RETURN AIR DAMPER (RAD-1), RELIEF AIR DAMPER (EAD-1) AND OUTDOOR AIR DAMPER (OAD-1) SHALL CONTINUE TO MODULATE TO MAINTAIN MINIMUM OUTDOOR AIR AS SUPPLY FAN SPEED UPDATES.
     - a. IF OUTDOOR AIR DAMPER (OAD-1) DOES NOT FULLY OPEN, AS DETERMINED BY END POSITION SWITCH, A STOP SIGNAL SHALL BE SENT TO THE ASSOCIATED AHU. AN ALARM SHALL BE SENT TO THE BAS.
     - b. IF ONE OF THE RELIEF AIR DAMPERS (EAD-1) DOES NOT FULLY OPEN, AS DETERMINED BY THE END POSITION SWITCH, THEN A STOP SIGNAL SHALL BE SENT TO THE ASSOCIATED AHU. AN ALARM SHALL BE SENT TO THE BAS.
     - c. IF NEITHER RELIEF AIR DAMPER (EAD-1) FULLY OPENS, AS DETERMINED BY THE END POSITION SWITCH, THEN THE RELIEF AIR FAN SHALL NOT ENERGIZE AND A STOP SIGNAL SHALL BE SENT TO BOTH AHUS. AN ALARM SHALL BE SENT TO THE BAS.
   - B. RELIEF FAN RF-1 VFD SHALL MODULATE WITH AHU-2-1 AND AHU-2-2 SUPPLY FANS TO MAINTAIN VOLUMETRIC OFFSET FROM MIMIMUM OUTSIDE AIR AS DETERMINED BY AIRFLOW MEASURING STATION.
   - C. FILTERS:
     - a. FILTERS SHALL BE ACTIVE UNITS AND SEND FAILURE/FAULT ALARMS TO THE BAS.
     - b. A DIFFERENTIAL PRESSURE SWITCH SHALL MONITOR STATUS OF EACH FILTER BANK. AN ALARM SHALL BE ISSUED TO THE BAS WHEN THE FILTER PRESSURE EXCEEDS SETPOINT. SEE EQUIPMENT SCHEDULES FOR FINAL PRESSURE SETPOINT.
   - D. CHILLED WATER COOLING:
     - a. COOLING MODE SHALL BE ENABLED WHENEVER:
       - a.a. OUTDOOR AIR TEMPERATURE (T-1) IS GREATER THAN 58°F (ADJ.).
       - a.b. THE SUPPLY FAN STATUS IS ON.
       - a.c. OUTSIDE AIR ENTHALPY IS ABOVE 28 BTU/LB (ADJ.).
     - b. THE BAS SHALL MODULATE THE CHILLED WATER CONTROL VALVES (V-CHW-1) TO MAINTAIN COIL DISCHARGE SETPOINT (T-5) AT 55°F (ADJ.)
   - E. HOT WATER HEATING:
     - a. HEATING MODE SHALL BE ENABLED WHENEVER:
       - a.a. OUTDOOR AIR TEMPERATURE (T-1) IS LESS THAN 55°F (ADJ.).
       - a.b. THE SUPPLY FAN STATUS IS ON.
     - b. THE BAS SHALL MODULATE THE HEATING WATER CONTROL VALVES (V-HHW-1) TO MAINTAIN DISCHARGE SETPOINT (T-5) AT 55°F (ADJ.)
   - F. ECONOMIZER CYCLE:
     - a. THE ECONOMIZER CYCLE SHALL BE ACTIVE WHEN:
       - a.a OUTSIDE AIR TEMPERATURE (T-1) IS BETWEEN 45°F (ADJ.) AND 58°F (ADJ.).
       - a.b. OUTSIDE AIR ENTHALPY IS BELOW 28 BTU/LB (ADJ.)
       - a.c. SUPPLY FAN STATUS IS ON.
     - b. THE OUTSIDE AIR DAMPERS (OAD-1) SHALL FULLY OPEN, THE RETURN AIR DAMPERS (RAD-1) SHALL FULLY CLOSE AND THE RELIEF AIR DAMPERS (EAD-1) SHALL FULLY OPEN.
     - c. AHU SUPPLY FAN VFDS SHALL MODULATE TO MAINTAIN DUCT STATIC PRESSURE.
     - d. RELIEF FAN (RF-1) VFD SHALL MODULATE IN UNISON WITH THE AHU SUPPLY FANS AND MAINTAIN THE SAME OFFSET AS DURING MINIMUM OUTSIDE AIR MODE AS MEASURED BY THE AIR FLOW MEASURING STATION.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

HVAC DIAGRAMS


SHEET NUMBER

H703

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:37 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

HVAC SETPOINTS - AHU-2-3

ROOM NAME	ROOM NO	SYSTEM SERVED	HEATING SETPOINT	COOLING SETPOINT




HVAC SETPOINTS - AHU-2-4

ROOM NAME	ROOM NO	SYSTEM SERVED	HEATING SETPOINT	COOLING SETPOINT

AHU-2-4 PLAN NOTES:

1. PRESSURE SWITCHES HARDWIRED TO VFD FOR HIGH STATIC LIMIT OR LOW STATIC LIMIT. PROVIDE PRESSURE SENSORS WITH ANALOG CONNECTION TO DDC CONTROLS AT SAME LOCATIONS.
2. START/STOP INTERLOCK WITH THE FIRE ALARM SYSTEM.
3. FREEZE STAT HARDWIRED TO SUPPLY FAN VFD.


SOUTH MEZZANINE AHU TEMPERATURE CONTROL DIAGRAM



CONTINUOUS ROOM EXHAUST FAN SEQUENCE OF OPERATIONS:

1. NORMAL OPERATION
   A. UPON START SIGNAL FROM BAS, THE MOTORIZED DAMPER SHALL OPEN. UPON PROOF OF OPENING FROM THE END POSITION SWITCH, THE FAN SHALL ENERGIZE.
   B. FAN RUNS CONTINUOUSLY.
   C. UPON STOP SIGNAL FROM BAS, THE FAN SHALL DE-ENERGIZE AND THE MOTORIZED DAMPER SHALL CLOSE.
2. SAFETIES
   A. ON A FAN FAILURE AS DETERMINED BY CURRENT SENSOR, AN ALARM SHALL BE GENERATED AT THE BAS FRONT END. THE MOTORIZED DAMPER SHALL FULLY CLOSE UPON RECEIPT OF FAN FAILURE ALARM.

CONTINUOUS ROOM EXHAUST FAN CONTROL DIAGRAM



GENERATOR ROOM TEMPERATURE CONTROL DIAGRAM

AHU-2-3, AHU-2-4 AND RF-2 SEQUENCE OF OPERATIONS:

1. GENERAL:
   A. THE AIR HANDLERS HAVE ONE SUPPLY AIR FAN EACH, E.C. TO PROVIDE ONE VFD PER FAN.
   B. ALL SET POINTS SHALL BE ADJUSTABLE THROUGH THE BAS CONSOLE.
   C. ALL TEMPERATURES, AIRFLOWS, AND DAMPER POSITIONS SHALL BE DISPLAYED AT THE BAS CONSOLE.
   D. THE SUPPLY AIR FAN VFD SHALL HAVE A HAND-OFF-AUTO SWITCH.
      a. IN THE HAND POSITION, THE FAN SHALL RUN CONTINUOUSLY AT A CONSTANT SPEED. THE SPEED SHALL BE MANUALLY ADJUSTABLE AT THE VARIABLE FREQUENCY DRIVE CONTROL PAD. ALL TEMPERATURE AND FAN SYSTEM SAFETIES SHALL REMAIN FUNCTIONAL AS DESCRIBED BELOW.
      b. IN THE AUTOMATIC POSITION, THE BUILDING BAS SHALL CONTROL ALL FUNCTIONS AS DESCRIBED.
   F. AHU-2-3 TO OPERATE AS VARIABLE VOLUME UNIT TO MAINTAIN CONSTANT DUCT TEMPERATURE AND CONSTANT DUCT STATIC PRESSURE.
   G. AHU-2-4 TO OPERATE AS A SINGLE ZONE VARIABLE VOLUME UNIT TO MAINTAIN ROOM TEMPERATURE.
2. SAFETY INTERLOCKS:
   A. WHENEVER EITHER AHU SUPPLY FAN IS STOPPED EITHER BY THE FIRE ALARM SYSTEM OR LOSS OF POWER, THE OUTDOOR AIR DAMPER (OAD-1) SHALL CLOSE, THE RELIEF AIR DAMPER (EAD-1) SHALL CLOSE, AND THE RETURN AIR DAMPER (RAD-1) SHALL OPEN. ALL VALVES SHALL FULLY CLOSE. AN ALARM SHALL BE SENT TO THE BAS.
   B. SUPPLY HIGH STATIC AND LOW STATIC PRESSURE LIMIT: IF THE SUPPLY AIR STATIC PRESSURE OF 4" WG POSITIVE (P-1) OR 4" NEGATIVE (P-2) SET POINT IS EXCEEDED, THE ASSOCIATED AIR HANDLER SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
   C. RELIEF LOW STATIC PRESSURE LIMIT: IF THE RELIEF AIR STATIC PRESSURE OF 3" NEGATIVE (P-3) SET POINT IS EXCEEDED, THE RELIEF FAN SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
   D. FREEZE PROTECTION
      a. PHYSICAL LOW LIMIT: IF THE FREEZESTAT TEMPERATURE (T-4) IS LESS THAN OR EQUAL TO 38°F:
         a.a. THE SUPPLY FANS SHALL STOP THROUGH A HARDWIRED INTERFACE BETWEEN THE FREEZESTAT (T-4) AND THE FAN MOTOR VFD.
         a.b. THE AIR HANDLER SHALL STOP.
         a.c. CHILLED WATER VALVE (V-CHW-1) SHALL OPEN 50% AND THE HEATING WATER CONTROL VALVE (V-HHW-1) SHALL MODULATE TO MAINTAIN SENSOR (T-4) AT 50°F (ADJ.).
         a.d. AN ALARM SHALL BE SENT TO THE BAS.
         a.e. FREEZESTAT SHALL REQUIRE A MANUAL RESET.
   E. IF A SUPPLY FAN FAILS, AS DETERMINED BY CURRENT SENSOR, THE ASSOCIATED AHU SHALL BE SHUT-DOWN AS DESCRIBED ABOVE AND AN ALARM SHALL BE SENT TO THE BAS.
   F. IF THE RELIEF AIR FAN (RF-2) FAILS, AS DETERMINED BY CURRENT SENSOR, THE FAN SHALL BE DE-ENERGIZED, THE RELIEF AIR DAMPERS (EAD-1) SHALL REMAIN OPEN.
      a. AN ALARM SHALL BE SENT TO THE BAS.
      b. BOTH AHU-2-3 AND AHU-2-4 SHALL EXIT ECONOMIZER MODE.
      c. AHU-2-3'S OUTDOOR AIR DAMPER (OAD-1) AND RETURN AIR DAMPER (RAD-1) SHALL MODULATE TO MAINTAIN MINIMUM OUTDOOR AIR AND RELIEF AIR FLOWRATE AS DETERMINED BY AIRFLOW MEASURING STATIONS. SEE EQUIPMENT SCHEDULES FOR FLOWRATES.
   G. SMOKE DETECTION
      a. ON DETECTION OF SMOKE IN THE RETURN AIR DUCT, THE SMOKE DETECTOR SHALL SIGNAL THE FIRE ALARM SYSTEM.
      b. THE FIRE ALARM SYSTEM THROUGH HARD WIRING SHALL STOP THE AHUS AND THE RELIEF AIR FAN (RF-2) AS DESCRIBED ABOVE.
3. UNIT SHUTDOWN
   A. ON COMMAND FROM THE BAS TO STOP EITHER AIR HANDLER OR AN IN FIELD MANUAL FAN SHUTDOWN, THE SUPPLY AIR FAN SHALL BE DE-ENERGIZED, THE OUTDOOR AIR DAMPER (OAD-1) SHALL CLOSE, THE RELIEF AIR DAMPER (EAD-1) SHALL CLOSE, AND RETURN AIR DAMPER (RAD-1) SHALL OPEN. ALL VALVES SHALL FULLY CLOSE.
      a. IF BOTH AHU-2-3 AND AHU-2-4 ARE COMMANDED TO STOP OR BOTH IN FIELD MANUAL FAN SHUTDOWNS ARE ACTIVATED, THE RELIEF FAN (RF-2) SHALL SHUTDOWN AS DESCRIBED BELOW. IF AHU-2-3 IS COMMANDED OFF AND AHU-2-4 IS NOT IN ECONOMIZER MODE, RF-2 SHALL STILL SHUTDOWN AS DESCRIBED ABOVE.
   B. ON COMMAND FROM THE BAS TO STOP THE RELIEF FAN OR AN IN FIELD MANUAL FAN SHUTDOWN, THE FAN SHALL BE DE-ENERGIZED, THE RELIEF AIR DAMPERS (EAD-1) SHALL REMAIN OPEN.
      a. AN ALARM SHALL BE SENT TO THE BAS.
      b. BOTH AHU-2-3 AND AHU-2-4 SHALL EXIT ECONOMIZER MODE.
      c. AHU-2-3'S OUTDOOR AIR DAMPER (OAD-1) AND RETURN AIR DAMPER (RAD-1) SHALL MODULATE TO MAINTAIN MINIMUM OUTDOOR AIR AND RELIEF AIR FLOWRATE AS DETERMINED BY AIRFLOW MEASURING STATIONS. SEE EQUIPMENT SCHEDULES FOR FLOWRATES.
4. NORMAL OPERATION MODE
   A. ON COMMAND TO START AHU-2-3, THE OUTSIDE AIR DAMPER (OAD-1) AND RELIEF AIR DAMPER (EAD-1) SHALL FULLY OPEN. UPON PROOF OF ALL DAMPERS OPENING, AS DETERMINED BY END POSITION SWITCHES, THE SUPPLY FAN SHALL CYCLE ON AND RUN CONTINUOUSLY. THE OUTDOOR AIR DAMPER (OAD-1), RETURN AIR DAMPER (RAD-1) AND RELIEF AIR DAMPER (EAD-1) SHALL INDEX TO MAINTAIN MINIMUM OUTDOOR AIR FLOW RATE IN ACCORDANCE WITH THE TESTING, ADJUSTING AND BALANCING (TAB) SPECIFICATIONS AND AS MEASURED BY THE AIR FLOW MEASURING STATIONS. SEE EQUIPMENT SCHEDULES FOR FLOWRATES. SUPPLY FAN SHALL RAMP UP AND DOWN IN RESPONSE TO DUCT PRESSURE SENSOR (P-3) SET AT .5" W.C. SEE PLANS FOR LOCATION OF DUCT PRESSURE SENSOR. THE RETURN AIR DAMPER (RAD-1), RELIEF AIR DAMPER (EAD-1) AND OUTDOOR AIR DAMPER (OAD-1) SHALL CONTINUE TO MODULATE TO MAINTAIN MINIMUM OUTDOOR AIR AS SUPPLY FAN SPEED UPDATES.
      a. IF OUTDOOR AIR DAMPER (OAD-1) DOES NOT FULLY OPEN, AS DETERMINED BY END POSITION SWITCH, A STOP SIGNAL SHALL BE SENT TO AHU-2-3. AN ALARM SHALL BE SENT TO THE BAS.
      b. IF THE RELIEF AIR DAMPER (EAD-1) DOES NOT FULLY OPEN, AS DETERMINED BY THE END POSITION SWITCH, THEN A STOP SIGNAL SHALL BE SENT TO AHU-2-3 AND THE RELIEF AIR FAN SHALL NOT ENERGIZE. AN ALARM SHALL BE SENT TO THE BAS.
   B. ON COMMAND TO START AHU-2-4, THE SUPPLY FAN SHALL CYCLE ON AND RUN CONTINUOUSLY. THE RETURN AIR DAMPER (RAD-1) SHALL BE FULLY OPEN, OUTDOOR AIR DAMPER (OAD-1) SHALL BE FULLY CLOSED, AND RELIEF AIR DAMPER (EAD-1) SHALL BE FULLY CLOSED WITH ALL DAMPER POSITIONS CONFIRMED BY END POSITION SWITCHES. SUPPLY FAN SHALL RAMP UP AND DOWN IN RESPONSE TO ROOM TEMPERATURE SENSOR (T-6) SET AT 85°F FOR COOLING AND 55°F FOR HEATING.
      a. IF RETURN AIR DAMPER (RAD-1) IS NOT CONFIRMED AS FULLY OPEN, AS DETERMINED BY END POSITION SWITCH, A STOP SIGNAL SHALL BE SENT TO AHU-2-4. AN ALARM SHALL BE SENT TO THE BAS.
   C. RELIEF FAN RF-2 VFD SHALL MODULATE WITH AHU-2-3'S SUPPLY FAN TO MAINTAIN VOLUMETRIC OFFSET FROM MIMIMUM OUTSIDE AIR AS DETERMINED BY AIRFLOW MEASURING STATION.
   D. FILTERS:
      a. FILTERS SHALL BE ACTIVE UNITS AND SEND FAILURE/FAULT ALARMS TO THE BAS.
      b. A DIFFERENTIAL PRESSURE SWITCH SHALL MONITOR STATUS OF EACH FILTER BANK. AN ALARM SHALL BE ISSUED TO THE BAS WHEN THE FILTER PRESSURE EXCEEDS SETPOINT. SEE EQUIPMENT SCHEDULES FOR FINAL PRESSURE SETPOINT.
   E. AHU-2-3 CHILLED WATER COOLING:
      a. COOLING MODE SHALL BE ENABLED WHENEVER:
         b.a OUTDOOR AIR TEMPERATURE (T-1) IS GREATER THAN 58°F (ADJ.).
         b.b. THE SUPPLY FAN STATUS IS ON.
         b.c. OUTSIDE AIR ENTHALPY IS ABOVE 28 BTU/LB (ADJ.).
      b. FOR AHU-2-3 THE BAS SHALL MODULATE THE CHILLED WATER CONTROL VALVE (V-CHW-1) TO MAINTAIN COIL DISCHARGE SETPOINT (T-5) AT 55°F (ADJ.)
   F. AHU-2-4 CHILLED WATER COOLING:
      a. COOLING MODE SHALL BE ENABLED WHENEVER:
         a.a. ROOM TEMPERATURE (T-3)(ADJ.) IS GREATER THAN 85°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE BAS SHALL MODULATE THE CHILLED WATER CONTROL VALVE (V-CHW-1) TO MAINTAIN ROOM SETPOINT AT 85°F (T-6)(ADJ.).
      c. ONCE THE CHILLED WATER CONTROL VALVE (V-CHW-1) IS FULLY OPEN, THE BAS SHALL MODULATE THE FAN SPEED TO MAINTAIN ROOM TEMPERATURE (T-6)(ADJ.) AT 85°F (ADJ.) SETPOINT.
   G. AHU-2-3 HOT WATER HEATING:
      a. HEATING MODE SHALL BE ENABLED WHENEVER:
         a.a. OUTDOOR AIR TEMPERATURE (T-1) IS LESS THAN 55°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE BAS SHALL MODULATE THE HEATING WATER CONTROL VALVES (V-HHW-1) TO MAINTAIN DISCHARGE SETPOINT (T-5) AT 55°F (ADJ.)
   H. AHU-2-4 HOT WATER HEATING:
      a. HEATING MODE SHALL BE ENABLED WHENEVER:
         a.a. ROOM AIR TEMPERATURE (T-6) IS LESS THAN 55°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE BAS SHALL MODULATE THE HEATING WATER CONTROL VALVE (V-HHW-1) TO MAINTAIN ROOM SETPOINT AT 55°F (T-6)(ADJ.).
      c. ONCE THE HEATING WATER CONTROL VALVE (V-HHW-1) IS FULLY OPEN, THE BAS SHALL MODULATE THE FAN SPEED TO MAINTAIN ROOM TEMPERATURE (T-6)(ADJ.) AT 55°F (ADJ.) SETPOINT.
   I. AHU-2-3 ECONOMIZER CYCLE:
      a. THE ECONOMIZER CYCLE SHALL BE ACTIVE WHEN:
         a.a OUTSIDE AIR TEMPERATURE (T-1) IS BETWEEN 45°F (ADJ.) AND 58°F (ADJ.)
         a.b OUTSIDE AIR ENTHALPY IS BELOW 28 BTU/LB (ADJ.)
         a.c. SUPPLY FAN STATUS IS ON.
      b. THE OUTSIDE AIR DAMPER (OAD-1) SHALL FULLY OPEN, THE RETURN AIR DAMPER (RAD-1) SHALL FULLY CLOSE AND THE RELIEF AIR DAMPER (EAD-1) SHALL FULLY OPEN.
      c. AHU SUPPLY FAN VFD SHALL MODULATE TO MAINTAIN DUCT STATIC PRESSURE.
      d. RELIEF FAN (RF-2) VFD SHALL MODULATE IN UNISON WITH THE AHU SUPPLY FAN AND MAINTAIN THE SAME OFFSET AS DURING MINIMUM OUTSIDE AIR MODE AS MEASURED BY THE AIR FLOW MEASURING STATION.
   J. AHU-2-4 ECONOMIZER CYCLE:
      a. THE ECONOMIZER CYCLE SHALL BE ACTIVE WHEN:
         a.a OUTSIDE AIR TEMPERATURE (T-1) IS BETWEEN 55°F (ADJ.) AND 70°F (ADJ.)
         a.b OUTSIDE AIR ENTHALPY IS BELOW 28 BTU/LB (ADJ.)
         a.c. SUPPLY FAN STATUS IS ON.
      b. THE OUTSIDE AIR DAMPER (OAD-1) SHALL FULLY OPEN, THE RETURN AIR DAMPER (RAD-1) SHALL FULLY CLOSE AND THE RELIEF AIR DAMPER (EAD-1) SHALL FULLY OPEN.
      c. AHU SUPPLY FAN VFD SHALL MODULATE TO MAINTAIN ROOM TEMPERATURE BETWEEN HEATING AND COOLING SETPOINTS.
      d. RELIEF FAN (RF-2) VFD SHALL MODULATE IN UNISON WITH THE AHU SUPPLY FAN AND MAINTAIN THE FLOWRATE AS MEASURED BY THE AIR FLOW MEASURING STATION.
      e. IF ROOM SETPOINT IS NOT SATISFIED BY ECONOMIZER OPERATION, THE UNIT SHALL EXIT ECONOMIZER MODE AND RETURN TO NORMAL OPERATION.

GENERATOR ROOM SEQUENCE OF OPERATIONS:

1. GENERAL
   A. THE AIR MONITOR OUTDOOR AIR DAMPERS (OAD), GENERATOR RETURN AIR DAMPERS (RAD) AND GENERATOR EXHAUST AIR DAMPERS (EAD) SHALL HAVE NORMALLY OPEN, SPRING RETURN ACTUATORS CAPABLE OF FULLY OPENING THE DAMPERS IN 5 SECONDS AND FULLY CLOSING THE DAMPERS IN 15 SECONDS.
2. NORMAL OPERATION (GENERATORS OFF)
   A. ALL AIR MONITOR OUTDOOR AIR DAMPERS (OAD), GENERATOR RETURN AIR DAMPERS (RAD) AND GENERATOR EXHAUST AIR DAMPERS (EAD) ARE TO BE CLOSED DURING NORMAL OPERATION WHEN GENERATORS ARE OFF.
      a. IF ANY DAMPER OPENS WITHOUT AN INITIATING SIGNAL, AS DETERMINED BY END POSITION SWITCH, THEN AN ALARM SHALL BE SENT TO THE BAS.
   B. UNIT HEATERS SHALL ENERGIZE WHEN THE GENERATOR ROOM UNIT HEATER THERMOSTATS TEMPERATURE FALLS BELOW 55°F AND MODULATE HEATING WATER VALVES OPEN TO MAINTAIN ROOM SETPOINT. UNIT HEATERS SHALL DE-ENERGIZE WHEN THE GENERATOR ROOM THERMOSTAT TEMPERATURE RISES ABOVE 55°F AND MODULATE HEATING WATER VALVES FULLY CLOSED.
   C. IN ROOM GENERAL EXHAUST AND IN ROOM GENERAL OUTDOOR AIR DAMPERS SHALL BOTH BE FULLY OPEN. GENERATOR ROOM EXHAUST FAN SHALL RUN CONTINUOUSLY.
      a. ON A FAN FAILURE, AS DETERMINED BY CURRENT SENSOR, AN ALARM SHALL BE SENT TO THE BAS.
      b. IN ROOM GENERAL EXHAUST AIR AND IN ROOM GENERAL OUTDOOR AIR DAMPERS SHALL FULLY CLOSE.
2. EMERGENCY OPERATION (GENERATORS ON)(MANUALLY STARTED)
   A. IN THE EVENT OF A MANUAL GENERATOR ACTIVATION, THE BAS SHALL REMAIN POWERED ON AND THE DAMPERS SHALL REMAIN POWERED ON.
   B. UPON GENERATOR START SIGNAL, THE AIR MONITOR OUTDOOR AIR DAMPERS (OAD), GENERATOR RETURN AIR DAMPERS (RAD) AND GENERATOR EXHAUST AIR DAMPERS (EAD) ASSOCIATED WITH THE ACTIVATED GENERATOR(S) ARE TO FULLY OPEN UPON GENERATOR START SIGNAL USING SPRING ACTUATORS.
   C. ONCE THE GENERATOR(S) ARE FULLY POWERED, THE GENERATOR RADIATOR FAN SHALL INDUCE AIRFLOW THROUGH THE ROOM. THE BAS SHALL MODULATE THE GENERATOR RADIATOR PLENUM RETURN AIR DAMPERS (IN UNISON IF MULTIPLE GENERATORS) TO MAINTAIN A SPACE TEMPERATURE OF 55°F AS DETERMINED BY THE GENERATOR ROOM THERMOSTAT. IF THE ROOM IS ABOVE 55°F, THEN THE GENERATOR RETURN AIR DAMPERS SHALL BE FULLY CLOSED.
      a. IF THE GENERATOR RETURN AIR DAMPERS ARE MODULATED FULLY OPEN AND THE SPACE TEMPERATURE BEGINS TO DROP BELOW 50°F, THE BAS SHALL CLOSE AIR MONITOR OUTDOOR AIR DAMPERS, ONE DAMPER ARRAY AT A TIME UNTIL THE ROOM IS ABOVE 55°F.
      b. ONCE THE ROOM TEMPERATURE REACHES 60°F (ADJ.), THE BAS SHALL RE-OPEN AIR MONITOR OUTDOOR AIR DAMPERS ONE AT A TIME. ONCE ALL OUTDOOR AIR DAMPERS ARE OPEN, THE BAS SHALL BEGIN TO MODULATE THE RETURN AIR DAMPER CLOSED TO MAINTAIN ROOM SETPOINT.
   D. UPON GENERATOR SHUTDOWN SIGNAL, THE BAS SHALL FULLY CLOSE THE AIR MONITOR OUTDOOR AIR DAMPERS. AFTER A 30 SECOND DELAY, THE BAS SHALL FULLY CLOSE THE GENERATOR RADIATOR PLENUM RETURN AIR DAMPERS AND GENERATOR RADIATOR DISCHARGE AIR DAMPERS. THE GENERATOR ROOM SHALL RESUME NORMAL OPERATION.
3. EMERGENCY OPERATION (GENERATORS ON)(POWER FAILURE)
   A. IN THE EVENT OF A POWER FAILURE TO THE FACILTIY, THE BAS SHALL REMAIN POWERED ON UPS BACKUP POWER AND ALL DAMPERS SHALL LOSE POWER.
   B. ALL THE AIR MONITOR OUTDOOR AIR DAMPERS (OAD), GENERATOR RETURN AIR DAMPERS (RAD) AND GENERATOR EXHAUST AIR DAMPERS (EAD) SHALL FULLY OPEN FROM THE SPRING ACTUATORS.
   C. ONCE THE GENERATORS HAVE RESTORED POWER TO THE FACILITY AND ALL THE DAMPERS, THE BAS SHALL OPERATE THE GENERATOR ROOM AS DESCRIBED ABOVE IN THE EMERGENCY OPERATION (MANUALLY STARTED) SEQUENCE.

HVAC SETPOINTS - UH UNITS

ROOM NAME	ROOM NO	SYSTEM SERVED	HEATING SETPOINT	COOLING SETPOINT

OWNER
Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT
Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS


NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE
HVAC DIAGRAMS

SHEET NUMBER
H704

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:38 PM AESI Proj. No: 21-154
0 1/2" 1" 2"




PLAN NOTES:

(1) START/STOP INTERLOCK WITH THE FIRE ALARM SYSTEM.

TYPICAL BLOWER COIL UNIT CONTROL DIAGRAM

PLANT TYPICAL BLOWER COIL/FAN COIL UNIT SEQUENCE OF OPERATIONS:


1. GENERAL:
   A. ALL SET POINTS SHALL BE ADJUSTABLE THRQUGH THE BAS CONSOLE.
   B. ALL TEMPERATURES SHALL BE DISPLAYED AT THE BAS CONSOLE.
   C. THE UNIT MOUNTED SUPPLY AIR FANS SHALL BE ECM CONTROLLED AND HAVE A HAND-OFF-AUTO SWITCH
      a. IN THE HAND POSITION, THE FAN SHALL RUN CONTINUOUSLY AT A CONSTANT SPEED. ALL TEMPERATURE AND FAN SYSTEM SAFETIES SHALL REMAIN FUNCTIONAL AS DESCRIBED BELOW.
      b. IN THE AUTOMATIC POSITION, THE BUILDING DDC SYSTEM SHALL CONTROL ALL FUNCTIONS AS DESCRIBED.
   D. UNIT TO OPERATE AS A SINGLE ZONE, VARIABLE VOLUME UNIT TO MAINTAIN ROOM TEMPERATURE.
2. SAFETY INTERLOCKS:
   A. ON COMMAND TO STOP THE BLOWER COIL, THE SUPPLY AIR FAN SHALL BE DE-ENERGIZED.
   B. WHENEVER THE FAN IS STOPPED EITHER BY THE BAS, THE FIRE ALARM SYSTEM, REFRIGERANT MONITORING SYSTEM OR LOSS OF POWER, THE SUPPLY AIR FAN SHALL DE-ENERGIZE AND AN ALARM SENT TO THE BAS.
   C. IF THE FAN FAILS, THE FAN SHALL BE DE-ENERGIZED AND AN ALARM SHALL BE SENT TO THE BAS.
3. NORMAL OPERATION MODE
   A. ON COMMAND TO START, THE SUPPLY FAN SHALL CYCLE ON.
   B. CHILLED WATER COOLING:
      a. THE BAS SHALL MODULATE THE CONTROL VALVE TO MAINTAIN COIL SUPPLY AIR SETPOINT AT 55°F (ADJ.)
      b. THE BAS SHALL MODULATE ECM FAN SPEED TO MAINTAIN SPACE SETPOINT.
      c. THE COOLING MODE SHALL BE ENABLED WHENEVER:
         c.a. THE SUPPLY FAN STATUS IS ON.
         c.b. THE ROOM TEMPERATURE AS DETERMINED BY IN ROOM THERMOSTAT EXCEEDS 85°F (ADJ.)
   C. HOT WATER HEATING:
      a. THE BAS SHALL MODULATE THE CONTROL VALVE TO MAINTAIN COIL SUPPLY AIR SETPOINT AT 95°F (ADJ.)
      b. THE BAS SHALL MODULATE ECM FAN SPEED TO MAINTAIN SPACE SETPOINT.
      c. HEATING MODE SHALL BE ENABLED WHENEVER:
         c.a. THE SUPPLY FAN STATUS IS ON.
         c.b. THE ROOM TEMPERATURE AS DETERMINED BY IN ROOM THERMOSTAT DROPS BELOW 55°F (ADJ.)
   D. IF ROOM TEMPERATURE IS BETWEEN TEMPERATURE SETPOINTS, BLOW COIL UNIT SHALL SHUT DOWN AS DESCRIBED ABOVE.



VARIABLE VOLUME TERMINAL BOX WITH REHEAT CONTROL DIAGRAM

VAV BOX CONTROL SEQUENCE SEQUENCE OF OPERATIONS:

1. GENERAL
   A. ALL TERMINAL BOXES SHALL BE PRESSURE INDEPENDENT.
   B. THE ROOM TEMPERATURE SET POINT SHALL BE SET TO THE ROOM TEMPERATURE SET POINT SCHEDULE.
2. VARIABLE VOLUME REHEAT BOX CONTROL
   A. ON A CALL FOR COOLING FROM THE ROOM TEMPERATURE SENSOR, THE TERMINAL BOX DAMPER SHALL MODULATE ROOM AIRFLOW FROM MINIMUM TO MAXIMUM SCHEDULED AIRFLOWS TO MEET ROOM AIR TEMPERATURE COOLING SET POINT.
   B. WHEN THE ROOM AIR TEMPERATURE IS BETWEEN HEATING AND COOLING SET POINTS, THE TERMINAL BOX SHALL FLOW AT MINIMUM SCHEDULED AIRFLOW.
   C. ON A CALL FOR HEATING FROM THE ROOM TEMPERATURE SENSOR, THE TERMINAL BOX HEATING VALVE SHALL MODULATE OPEN TO MAINTAIN ROOM TEMPERATURE SETPOINT UNTIL DISCHARGE AIR TEMPERATURE REACHES SCHEDULED LEAVING AIR TEMPERATURE (LAT ON VAV BOX SCHEDULE) .
   D. ONCE DISCHARGE AIR TEMPERATURE REACHES SCHEDULED LEAVING AT TEMPERATURE, THE TERMINAL BOX DAMPER SHALL MODULATE FROM MINIMUM AIRFLOW TO MAINTAIN ROOM TEMPERATURE SET POINT.




PLAN NOTES:

(1) START/STOP INTERLOCK WITH THE FIRE ALARM SYSTEM.

CRAC UNIT TEMPERATURE CONTROL DIAGRAM

COMPUTER ROOM AIR CONDITIONER SEQUENCE OF OPERATIONS:

1. GENERAL:
   A. EACH COMPUTER ROOM AIR CONDITIONER (CRAC UNIT) HAS ONE SUPPLY AIR FAN WITH A FACTORY INTEGRATED VFD.
   B. ALL OUTPUT CONTROLS SHALL BE PERFORMED BY THE UNIT INTEGRATED CONTROL SYSTEM. BAS SHALL PERFORM MONITORING ONLY.
   C. ALL TEMPERATURES, AIR FLOWS AND DAMPER POSITIONS SHALL BE DISPLAYED AT THE BAS CONSOLE.
   D. CRAC UNITS TO OPERATE IN PARALLEL AS VARIABLE VOLUME UNITS TO MAINTAIN CONSTANT ROOM TEMPERATURE AND HUMIDITY.
2. SAFETY INTERLOCKS:
   A. ON COMMAND TO STOP ONE CRAC UNIT, THE UNITS SHALL PERFORM FACTORY CODED SHUTDOWN. SUPPLY AIR DAMPER (SAD-1) AND RETURN AIR DAMPER (RAD-1) SHALL REMAIN OPEN.
   B. UPON SIGNAL FROM THE MDF ROOM DEDICATED, GAS BASED FIRE ALARM SYSTEM, THE CRAC UNITS SUPPLY AIR FANS SHALL BE DE-ENERGIZED VIA HARDWIRE CONNECTION. THE CRAC UNITS SHALL PERFORM FACTORY CODED SHUTDOWN. THE SUPPLY AIR DAMPER (SAD-1) SHALL CLOSE IN 5 SECONDS AND THE RETURN AIR DAMPER (RAD-1) SHALL CLOSE IN 5 SECONDS. AN ALARM SHALL BE SENT TO THE BAS.
   C. WHENEVER EITHER FAN IS STOPPED BY LOSS OF POWER, THE SUPPLY AIR DAMPER (SAD-1) AND THE RETURN AIR DAMPER (RAD-1) SHALL REMAIN OPEN. AN ALARM SHALL BE SENT TO THE BAS.
3. NORMAL OPERATION MODE
   A. ON COMMAND TO START, THE CRAC UNITS SHALL PERFORM FACTORY CODED START UP. THE UNITS SHALL RUN CONTINUOUSLY TO MAINTAIN TEMPERATURE AND HUMIDITY SETPOINT.
   B. BOTH UNITS SHALL RUN IN PARALLEL. IF ONE UNIT FAN, DISCHARGE TEMPERATURE OR DISCHARGE HUMIDITY BEGINS TO FAIL, THE UNIT SHALL BE SHUTDOWN AND THE REMAINING UNIT SHALL CONTINUE TO MAINTAIN ROOM TEMPERATURE AND HUMIDITY SETPOINTS. THE RETURN AIR DAMPER ASSOCIATED WITH THE SHUTDOWN UNIT (RAD-2 OR RAD-3) SHALL FULLY CLOSE. AN ALARM SHALL BE GENERATED AT THE BAS.
   C. CHILLED WATER AND DX COOLING:
      a. COOLING MODE SHALL BE ENABLED WHENEVER:
         a.a. ROOM TEMPERATURE (T-1) IS GREATER THAN 72°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE CRAC UNIT INTERNAL CONTROLS SHALL MODULATE THE CHILLED WATER CONTROL VALVE (V-CHW-1) TO MAINTAIN ROOM COOLING SETPOINT.
      c. IF THE CHILLED WATER COIL IS UNABLE TO MAINTAIN DISCHARGE TEMPERATURE REQUIRED TO MEET ROOM SETPOINT, THE CHILLED WATER VALVE (V-CHW-1) SHALL FULLY CLOSE. THE ROOF MOUNTED ACCU SHALL ENERGIZE AND THE DX COOLING VALVE (V-DX-1) SHALL MODULATE TO MAINTAIN ROOM COOLING SETPOINT.
         c.a. THE CHILLED WATER CONTROL VALVE SHALL MODULATE OPEN TO MAINTAIN ROOM COOLING SETPOINT IN ADDITION TO DX COOLING IF THE DX COOLING VALVE (V-DX-1) IS FULLY OPENED.
   C. HOT WATER HEATING:
      a. HEATING MODE SHALL BE ENABLED WHENEVER:
         a.a. ROOM TEMPERATURE (T-1) IS LESS THAN 68°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE CRAC UNIT INTERNAL CONTROLS SHALL MODULATE THE HEATING WATER CONTROL VALVE (V-HHW-1) TO MAINTAIN ROOM HEATING SETPOINT.
   D. HUMIDIFICATION:
      a. THE CRAC UNIT HUMIDIFIERS SHALL BE ENABLED WHENEVER:
         a.a. ROOM HUMIDITY IS BELOW 35%RH.
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE CRAC UNIT INTERNAL CONTROLS SHALL MODULATE THE INFRARED HUMIDIFIER AND RO MAKE UP WATER VALVE (V-RO-1) TO MAINTAIN ROOM HUMIDITY SETPOINT.



PLAN NOTES:

(1) PRESSURE SWITCHES HARDWIRED TO VFD FOR HIGH STATIC LIMIT OR LOW STATIC LIMIT. PROVIDE PRESSURE SENSORS WITH ANALOG CONNECTION TO DDC CONTROLS AT SAME LOCATIONS.

(2) FREEZE STAT HARDWIRED TO SUPPLY FAN VFD.

TUNNEL MAKE UP AIR UNIT TEMPERATURE CONTROL DIAGRAM

MAU-2-2 TUNNEL VENTILATION SEQUENCE OF OPERATIONS:

1. GENERAL:
   A. THE AIR HANDLER HAS ONE SUPPLY AIR FAN, E.C. TO PROVIDE VFD FOR THE FAN.
   B. ALL SET POINTS SHALL BE ADJUSTABLE THROUGH THE BAS CONSOLE.
   C. ALL TEMPERATURES, AIRFLOWS, AND DAMPER POSITIONS SHALL BE DISPLAYED AT THE BAS CONSOLE.
   D. THE SUPPLY AIR FAN VFD SHALL HAVE A HAND-OFF-AUTO SWITCH.
      a. IN THE HAND POSITION, THE FAN SHALL RUN CONTINUOUSLY AT A CONSTANT SPEED. THE SPEED SHALL BE MANUALLY ADJUSTABLE AT THE VARIABLE FREQUENCY DRIVE CONTROL PAD. ALL TEMPERATURE AND FAN SYSTEM SAFETIES SHALL REMAIN FUNCTIONAL AS DESCRIBED BELOW.
      b. IN THE AUTOMATIC POSITION, THE BUILDING BAS SHALL CONTROL ALL FUNCTIONS AS DESCRIBED.
   E. UNIT TO OPERATE AS A SINGLE ZONE CONSTANT VOLUME UNIT TO MAINTAIN TUNNEL VENTILATION REQUIREMENT AND TEMPERATURE SETPOINTS.
2. SAFETY INTERLOCKS:
   A. WHENEVER THE AHU SUPPLY FAN IS STOPPED BY A LOSS OF POWER, THE INLET HOOD DAMPER SHALL CLOSE. AN ALARM SHALL BE SENT TO THE BAS.
   B. SUPPLY HIGH STATIC AND LOW STATIC PRESSURE LIMIT: IF THE SUPPLY AIR STATIC PRESSURE OF 4" WG POSITIVE (P-1) OR 4" NEGATIVE (P-2) SET POINT IS EXCEEDED, THE UNIT SHALL BE COMMANDED TO STOP AND AN ALARM SENT TO THE BAS CONSOLE.
   C. FREEZE PROTECTION
      a. WHEN THE OUTSIDE AIR TEMPERATURE FALLS TO BELOW 38°F (ADJUSTABLE), HEATING COIL PUMP (P-2-2) SHALL BE ENERGIZED.
      b. WHEN THE OUTSIDE AIR TEMPERATURE RISES TO ABOVE 43°F, HEATING COIL PUMP SHALL BE DE-ENERGIZED.
      c. PHYSICAL LOW LIMIT: IF THE FREEZESTAT TEMPERATURE (T-2) IS LESS THAN OR EQUAL TO 38°F:
         c.a. THE SUPPLY FAN SHALL STOP THROUGH A HARDWIRED INTERFACE BETWEEN THE FREEZE STAT (T-2) AND FAN MOTOR VFD.
         c.b. THE AIR HANDLER SHALL STOP.
         c.c. CHILLED WATER VALVE (V-CHW-1) SHALL OPEN 50%, COIL PUMP (P-2-2) SHALL REMAIN ON, AND HEATING WATER CONTROL VALVE (V-HHW-1) SHALL MODULATE TO MAINTAIN SENSOR (T-2) AT 50°F.
         c.d. AN ALARM SHALL BE SENT TO THE BAS.
         c.e. FREEZESTAT SHALL REQUIRE A MANUAL RESET.
   D. IF THE SUPPLY FAN FAILS, AS DETERMINED BY CURRENT SENSOR, THE AHU SHALL BE SHUT-DOWN AS DESCRIBED ABOVE AND AN ALARM SHALL BE SENT TO THE BAS.
3. UNIT SHUTDOWN
   A. ON COMMAND FROM THE BAS TO STOP THE AIR HANDLER OR AN IN FIELD MANUAL FAN SHUTDOWN, THE SUPPLY AIR FAN SHALL BE DE-ENERGIZED AND THE AIR INLET HOOD DAMPER SHALL CLOSE. ALL VALVES SHALL FULLY CLOSE AND THE HEATING COIL PUMP (P-2-2) SHALL BE DE-ENERGIZED.
4. NORMAL OPERATION MODE
   A. ON COMMAND TO START MAU-2-2, THE AIR INLET HOOD DAMPER SHALL FULLY OPEN, AS CONFIRMED BY END POSITION SWITCH.THE SUPPLY FAN SHALL CYCLE ON AND RUN CONTINUOUSLY. SUPPLY FAN SHALL PROVIDE CONSTANT AIR VOLUME TO UTILITY TUNNEL AS MEASURED BY AIR FLOW MEASURING STATION (AFMS).
      a. IF AIR INLET HOOD DAMPER IS NOT CONFIRMED AS FULLY OPEN, AS DETERMINED BY END POSITION SWITCH, A STOP SIGNAL SHALL BE SENT TO MAU-2-2. AN ALARM SHALL BE SENT TO THE BAS.
   B. FILTERS:
      a. FILTERS SHALL BE ACTIVE UNITS AND SEND FAILURE/FAULT ALARMS TO THE BAS.
      b. A DIFFERENTIAL PRESSURE SWITCH SHALL MONITOR STATUS OF EACH FILTER BANK. AN ALARM SHALL BE ISSUED TO THE BAS WHEN THE FILTER PRESSURE EXCEEDS SETPOINT. SEE EQUIPMENT SCHEDULES FOR FINAL PRESSURE SETPOINT.
   C. CHILLED WATER COOLING:
      a. COOLING MODE SHALL BE ENABLED WHENEVER:
         a.a. TUNNEL TEMPERATURE (T-4)(ADJ.) IS GREATER THAN 85°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE BAS SHALL MODULATE THE CHILLED WATER CONTROL VALVE (V-CHW-1) TO MAINTAIN TUNNEL TEMPERATURE (T-4) (ADJ.) BELOW 85°F (ADJ.) SETPOINT.
   D. HOT WATER HEATING:
      a. HEATING MODE SHALL BE ENABLED WHENEVER:
         a.a. TUNNEL TEMPERATURE (T-4) IS LESS THAN 55°F (ADJ.).
         a.b. THE SUPPLY FAN STATUS IS ON.
      b. THE BAS SHALL MODULATE THE HEATING WATER CONTROL VALVES (V-HHW-1&2) TO MAINTAIN TUNNEL TEMPERATURE (T-4)(ADJ.) ABOVE 55°F (ADJ.) SETPOINT.
         LEAVING AIR TEMPERATURE.
   E. DE-HUMIDIFICATION MODE:
      a. IF TUNNEL SENSOR (T-4) DETECTS A HUMIDITY HIGHER THAN 60%RH (ADJ.) THE UNIT SHALL MODULATE THE CHILLED WATER CONTROL VALVE (V-CHW-1) AND RE-HEAT CONTROL VALVE (V-HHW-2) AS NEEDED TO DISCHARGE 50% RH AIR UNTIL TUNNEL RELATIVE HUMIDITY (T-4) HAS DROPPED BELOW 55%RH (ADJ.).

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	AESI
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

HVAC DIAGRAMS

SHEET NUMBER

H705

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:02:38 PM AESI Proj. No: 21-154

NOTE: ALL SYMBOL DESCRIPTIONS ARE SUBJECT TO MODIFICATION ON THE DRAWINGS. ALL SYMBOLS NOT NECESSARILY USED ON THIS PROJECT.

GENERAL SYMBOLS:

- POINT OF CONNECTION
- PLAN NOTE
- REVISION
- DETAIL BUBBLE
- SECTION BUBBLE

VALVES & FITTINGS:

- GATE VALVE
- BALANCING VALVE
- BALL VALVE
- BUTTERFLY VALVE
- CHECK VALVE
- GLOBE VALVE
- CONTROL VALVE
- PRESSURE RELIEF, ANGLE TYPE VALVE
- REDUCED PRESSURE BACK FLOW PREVENTER
- INDICATED FLOW DIRECTION
- PIPE TURN 90°
- LINE BREAK
- PIPE ELBOW UP (RISER)
- PIPE ELBOW DOWN OR DROP
- PIPE TEE DOWN
- CAP OR PLUG
- REDUCER, CONCENTRIC
- REDUCER, ECCENTRIC
- FLANGES
- UNION
- METER
- FD FLOOR DRAIN
- CO FLOOR CLEANOUT
- GAUGE
- THERMOMETER
- T STEAM TRAP
- P PRESSURE SENSOR
- INLINE PUMP

PIPING DESIGNATIONS:

- NEW PIPING
- PIPE SLOPES IN DIRECTION OF ARROW
- CW DOMESTIC COLD WATER
- HW DOMESTIC HOT WATER
- HWR DOMESTIC HOT WATER RETURN
- 140°F DOMESTIC HOT WATER 140°F
- 140°F DOMESTIC HOT WATER 140°F RETURN
- W WASTE PIPING
- ST STORM PIPING
- SANITARY VENT
- D INDIRECT DRAIN
- AW ACID WASTE
- AV ACID VENT
- DI DEIONIZED WATER
- RODI REVERSE OSMOSIS DEIONIZED WATER
- LS LAWN SPRINKLER
- G GAS
- FOS FUEL OIL SUPPLY
- FOR FUEL OIL RETURN
- FOV FUEL OIL VENT
- VAC VACUUM
- CA COMPRESSED AIR
- PD PUMPED DISCHARGE
- BR BRINE WATER
- PIPE BELOW FLOOR
- SCW SOFT COLD WATER

PLUMBING ABBREVIATIONS:

AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AHU	AIR HANDLING UNIT
AD	ACCESS DOOR
ADA	AMERICANS WITH DISABILITIES ACT
AV	ACID VENT
AW	ACID WASTE
BDD	BACK DRAFT DAMPER
BFP	BACKFLOW PREVENTER
BHP	BRAKE HORSEPOWER
BLDG	BUILDING
BOD	BOTTOM OF DUCT
BOP	BOTTOM OF PIPE
BOS	BOTTOM OF STEEL
BR	BRINE WATER
BRP	BRINE PUMP
BRT	BRINE TANK
BTU	BRITISH THERMAL UNIT
CA	COMPRESSED AIR
CO	CLEANOUT
CS	CUP SINK
CSS	CLINIC SERVICE SINK
CTRL	CONTROL
CW	DOMESTIC COLD WATER
D	CONDENSATE/DRAIN
DB	DRY BULB
DBP	DOMESTIC BOOSTER PUMP
DCV	DOUBLE CHECK VALVE
DD	DECK DRAIN
DET	DOMESTIC EXPANSION TANK
DIA	DIAMETER
DN	DOWN
DWH	DOMESTIC WATER HEATER
DWRP	DOMESTIC HOT WATER RECIRCULATION PUMP
DWS	DOMESTIC WATER SOFTER
EC	ELECTRICAL CONTRACTOR
ECO	EXTERIOR CLEANOUT
EW	EMERGENCY EYE/FACE WASH
EL	ELEVATION
ESEW	EMERGENCY SHOWER EYE/FACE WASH
ETMV	EMERGENCY THERMOSTATIC MIXING VALVE
EXIST	EXISTING
FCO	FLOOR CLEANOUT
FD	FLOOR DRAIN
FLA	FULL LOAD AMPS
FM	FLOW METER
FS	FLOOR SINK
GPR	GAS PRESSURE REGULATOR
HB	HOSE BIBB
HKSP	HOUSEKEEPING
HW	DOMESTIC HOT WATER
HWR	DOMESTIC HOT WATER RETURN
IE	INVERT ELEVATION
L	LAVATORY
MB	MOP BASIN
MC	MECHANICAL CONTROLLER
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
ORD	OVERFLOW ROOF DRAIN
OS	OIL SEPARATOR
PC	PLUMBING CONTRACTOR
PIV	POST INDICATING VALVE
PSIA	POUNDS PER SQUARE INCH ABSOLUTE
PSIG	POUNDS PER SQUARE INCH GAUGE
PT	PRESSURE TANK
RD	ROOF DRAIN
RH	ROOF HYDRANT
RO	REVERSE OSMOSIS
RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
SAN	SANITARY
SCW	SOFTENED COLD WATER
SH	SHOWER
SI	SEDIMENT INTERCEPTOR
SK	SINK
SP	SUMP PUMP
SS	STAINLESS STEEL
ST	STORM WATER
SVB	SHUT-OFF VALVE BOX
TD	TRENCH DRAIN
TMV	THEROSTATIC MIXING VALVE
TW	TEPID WATER
TYP	TYPICAL
UR	URINAL
US	UTILITY SINK
V	SANITARY VENT
VFD	VARIABLE FREQUENCY DRIVE
VTR	VENT THROUGH ROOF
W	WASTE
WC	WATER CLOSET
WH	WALL HYDRANT

GENERAL NOTES:

A. VERIFY CONDITIONS IN THE FIELD PRIOR TO BUILDING AND BEFORE BEGINNING WORK.

B. REVIEW THE WORK OF OTHER TRADES, COORDINATE AND -PLAN WORK WITH THE OTHER TRADES AND OWNER. ADJUST AS A RESULT OF COORDINATION.

C. STORE EQUIPMENT AND COMPONENTS IN A CLEAN, DRY LOCATION UNTIL READY FOR INSTALLATION. PROTECT FROM WEATHER, DIRT, WATER, AND CONSTRUCTION DEBRIS, ETC. AT ALL TIMES. ANY DAMAGED EQUIPMENT OR COMPONENTS SHALL BE RESTORED AS NEW OR REPLACED.

D. DRAWINGS SHOW THE INTENDED ARRANGEMENT AND ROUTING OF ALL PIPING, EQUIPMENT, AND APPURTENANCES. THEY SHALL BE FOLLOWED AS CLOSELY AS ACTUAL BUILDING CONSTRUCTION AND WORK OF OTHER TRADES WILL PERMIT.

E. CLEAN ALL EQUIPMENT TO PRESENT A "LIKE NEW" CONDITION AT PROJECT COMPLETION.

F. OFFSET PIPING AROUND ELECTRICAL PANELS TO PROVIDE CLEARANCES AS REQUIRED BY THE NATIONAL ELECTRICAL CODE.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: EPW	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

PLUMBING SYMBOLS AND ABBREVIATIONS

SHEET NUMBER

P001

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:22 PM AESI Proj. No: 21-154
0 1/2" 1" 2"




LOWER LEVEL PLUMBING PLAN
Scale: 3/32" = 1'-0"

GENERAL NOTES:

A. SEE SHEET P001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
B. ALL SANITARY WASTE PIPING TO BE 4" UNLESS OTHERWISE NOTED.

(#) PLAN NOTES:

1. 8" ST FROM ABOVE.
2. 4" ST FROM ABOVE.
3. 4" ST UP TO FLOOR CLEANOUT (FCO).
4. 4" ST UP TO EXTERIOR CLEANOUT (ECO).
5. 4" W UP TO EXTERIOR CLEANOUT (ECO).
6. 6" W WITH P-TRAP UP TO FLOOR DRAIN (FD).
7. 4" W WITH P-TRAP UP TO FLOOR DRAIN (FD).
8. 4" W UP TO FLOOR CLEANOUT (FCO).
9. 10" INCOMING DOMESTIC COLD WATER UP.
10. 4" DRAIN FROM FLOOR DRAIN (FD) TO TERMINATE INTO FIRE PUMP WATER STORAGE TANK.
11. 4" W UP.
12. 3" V UP.
13. 4" V UP ALONG WALL ABOVE.
14. 2" W UP TO ESEW-1.
15. 8" W WITH P-TRAP UP TO FLOOR DRAIN (FD).
16. 4" W UP IN CHASE ABOVE.
17. 2" V UP IN WALL ABOVE.
18. 2" W WITH P-TRAP UP TO FLOOR DRAIN (FD).
19. 3" W WITH P-TRAP UP TO MOP BASIN (MB).
20. 2" CW FROM ABOVE.
21. 2" BRINE WATER UP.
22. INVERT ELEVATION OF 4" INLET AND OUTLET TO OS-1 IS -2'-0" BFF.
23. 2" W UP.
24. 3" PD TO CONNECT INTO THE TOP OF THE 8"W.
25. 3" W UP TO SS-1.
26. SEE DETAIL 1/P501.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:27 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: EPW	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


LOWER LEVEL PLUMBING PLAN

SHEET NUMBER

P302



FIRST FLOOR PLUMBING PLAN
Scale: 3/32" = 1'-0"




FIRST FLOOR MEZZANINE PLUMBING PLAN
Scale: 3/32" = 1'-0"

GENERAL NOTES:

A. SEE SHEET P001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
B. ALL SANITARY WASTE PIPING TO BE 4" UNLESS OTHERWISE NOTED.

PLAN NOTES:

1. 3' X 3' X 2' CONCRETE DRAINAGE PIT WITH GRATE (BY OTHERS). FLOOR DRAIN (FD) AT BOTTOM OF PIT, SEE DRAINAGE PIT DETAIL 2/P501.
2. TO COOLING TOWER MAKE-UP. SEE SHEET M701.
3. INCOMING GAS SERVICE REDUCED TO 5 PSI. SEE SITE/CIVIL DRAWINGS FOR CONTINUATION. PC TO PROVIDE GAS PRESSURE REGULATOR IF GAS PRESSURE PROVIDED BY GAS COMPANY EXCEEDS 5 PSI. TOTAL GAS LOAD CONNECTED IS 165,728,000 BTUH WITH A FUTURE TOTAL CONNECTED GAS LOAD OF 205,728,000 BTUH. TOTAL DEVELOPED LENGTH IS 200 FT WITH FUTURE LENGTH OF 300 FT. SEE DETAIL 8/P501.
4. 8" ST DOWN. PROVIDE CLEANOUT AT BASE OF STORM RISER.
5. PIPE BELOW MEZZANINE.
6. 4" W FROM ABOVE AND DOWN ALONG WALL.
7. HOT WATER BALANCING VALVE STATION. SEE DETAIL 4/P501. BALANCE TO 2.0 GPM.
8. 3" CW TO HEATING HOT WATER MAKE-UP. SEE SHEET M710.
9. 2 1/2" CW TO CARBON FILTER SYSTEM FOR RO MAKE-UP. SEE SHEET M709.
10. 1" CW UP IN WALL ABOVE.
11. 3/4" CW DROP IN WALL.
12. 3/4" CW DROP ALONG COLUMN.
13. 3/4" CW UP IN WALL ABOVE.
14. 4" ST UP TO DECK DRAIN (DD).
15. 1" CW UP.
16. 1" CW FROM BELOW.
17. 8" ST UP AND DOWN ALONG WALL. PROVIDE CLEANOUT AT BASE OF STORM RISER.
18. 8" ST FROM ABOVE.
19. 4" ST DOWN ALONG COLUMN. PROVIDE CLEANOUT AT BASE OF STORM RISER.
20. 4" W WITH P-TRAP UP TO FLOOR DRAIN (FD).
21. 8" ST UP AND DOWN ALONG COLUMN. PROVIDE CLEANOUT AT BASE OF STORM RISER.
22. 4" W DOWN ALONG WALL.
23. 2" W WITH P-TRAP UP TO FLOOR DRAIN (FD).
24. 3" W WITH P-TRAP UP TO MOP BASIN (MB). 3/4" CW AND 3/4" HW UP IN WALL ABOVE. INSTALL SHUT-OFF VALVES AND CHECK VALVES ON WATER PIPES BEFORE UP IN WALL ABOVE.
25. 4" V UP IN WALL ABOVE.
26. 1 1/2" CW AND 3/4" HW DROP IN CHASE. PROVIDE WHA-A ON COLD WATER PIPE BEFORE WATER CLOSET CONNECTION.
27. 4" W DOWN. 2" V RISE.
28. 2" V UP.
29. 2" V FROM BELOW FLOOR IN WALL.
30. 3/4" CW AND 3/4" HW DROP IN WALL. INSTALL SHUT-OFF VALVES AND CHECK VALVES ON WATER PIPES BEFORE DROP IN WALL. 3" W DOWN FROM MOP BASIN (MB).
31. 2" W WITH P-TRAP UP TO SHOWER (SH) DRAIN.
32. 3" V FROM BELOW FLOOR RISE ALONG WALL..
33. 4" W UP IN CHASE ABOVE.
34. 4" V UP IN CHASE ABOVE.
35. 4" ST DOWN ALONG WALL. PROVIDE CLEANOUT AT BASE OF STORM RISER.
36. 3" CW TO CHILLED WATER MAKE-UP. SEE SHEET M703.
37. 1/2" CW AND 1/2" HW UP IN WALL ABOVE.
38. 2" CW AND 3/4" HW UP IN CHASE ABOVE.
39. INCOMING 10" DOMESTIC COLD WATER FROM BELOW.
40. 4" W DOWN ALONG COLUMN.
41. 3/4" CW AND 3/4" HW UP IN WALL ABOVE. 3" W FROM WALL ABOVE.
42. 2" CW DOWN BELOW FLOOR SLAB.
43. 2" BRINE WATER (BR) FROM BELOW FLOOR SLAB.
44. 1" CW AND 1" HW DROP TO ETMV-1. 1 1/4" TW TO ESEW-1. 2" DOWN AND 1 1/2" V RISE. SEE DETAIL 3/P501.
45. 1" CW AND 1" HW DROP ETMV-1. 1 1/4" TW TO ESEW-2.
46. 4" V FROM BELOW FLOOR SLAB ALONG WALL.
47. 4" W FROM ABOVE.
48. 2" W FROM ABOVE.
49. 3/4" CW DROP IN WALL. 1 1/2" V RISE. 2" W DOWN. PROVIDE WHA-A ON COLD WATER PIPE BEFORE URINAL CONNECTION.
50. 6" W COOLING TOWER DRAIN FROM ABOVE.
51. 6" W DROP ALONG WALL AND TO DRAINAGE PIT.
52. 6" W COOLING TOWER DRAIN FROM ABOVE AND DOWN.
53. 3/4" CW DROP ALONG WALL.
54. VALVE AND CAP 6" G (5 PSI) FOR FUTURE.
55. 3" G (5 PSI) DROP TO HEATING HOT WATER BOILER GAS TRAIN AND GAS PRESSURE REGULATOR (PROVIDED WITH BOILER). INSTALL DIRT LEG. GAS LOAD IS 10,000,000 BTUH. SEE DETAIL 8/P502.
56. 4" G (5 PSI) DROP TO STEAM BOILER GAS TRAIN AND GAS PRESSURE REGULATOR (PROVIDED WITH STEAM BOILER). INSTALL DIRT LEG. GAS LOAD IS 28,576,000 BTUH. SEE DETAIL 8/P502.
57. FIRST FLOOR MEZZANINE (ABOVE). SEE FIRST FLOOR MEZZANINE PLAN THIS SHEET.
58. 3/4" CW AND 3/4" HW DOWN IN WALL TO SS-1. 3" W DOWN, 1-1/2"V RISE.
59. SEE DETAIL 5/P501.
60. SEE DETAIL 6/P501.
61. SEE DETAIL 7/P501.
62. SEE DETAIL 9/P501.
63. SEE SHEET P701 FOR DETAIL AND DIAGRAM.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:35 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS		
NO.	DATE	DESCRIPTION


DESIGNED BY	CERTIFICATION
EPW	PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY	
AESI	
APPROVED BY	
Approver	
PROJECT NO.	
21-154	

SHEET TITLE


FIRST FLOOR PLUMBING PLAN

SHEET NUMBER


P303



SECOND FLOOR PLUMBING PLAN
Scale: 3/32" = 1'-0"



SECOND FLOOR MEZZANINE 1 PLUMBING PLAN
Scale: 3/32" = 1'-0"




SECOND FLOOR MEZZANINE 2 PLUMBING PLAN
Scale: 3/32" = 1'-0"

GENERAL NOTES:

A. SEE SHEET P001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
B. ALL SANITARY WASTE PIPING TO BE 4" UNLESS OTHERWISE NOTED.

(#) PLAN NOTES:

1. 1" CW FROM BELOW IN WALL.
2. 1" CW UP TO RH-1. 1" D FROM RH-1.
3. 3/4" CW DROP IN WALL TO HB-1.
4. 3/4" CW FROM BELOW IN WALL.
5. 1" DRAIN LINE FROM RH-1 DOWN ALONG WALL AND TERMINATE INTO FLOOR DRAIN (FD) BELOW WITH AIR GAP.
6. 3/4" CW DROP ALONG COLUMN.
7. 1" DRAIN LINE DOWN IN WALL.
8. 1" DRAIN LINE FROM ABOVE IN WALL.
9. 1" DRAIN LINE DROP ALONG WALL AND TERMINATE INTO FLOOR DRAIN (FD) WITH AIR GAP.
10. 8" ST DOWN ALONG WALL.
11. 6" ST UP TO ROOF DRAIN (RD).
12. 6" ST UP TO OVERFLOW ROOF DRAIN (ORD).
13. 8" ST DOWN ALONG COLUMN.
14. 4" ST UP TO DECK DRAIN (DD).
15. 8" ST DOWN.
16. PIPE BELOW MEZZANINE.
17. 4" V UP AND DOWN IN WALL.
18. 3/4" CW AND 3/4" HW FROM BELOW IN WALL. 3" W DOWN FROM MOP BASIN (MB).
19. 2" V FROM BELOW IN WALL.
20. 2" V UP IN CORNER.
21. 3/4" CW AND 3/4" HW FROM BELOW IN WALL. 3" W DOWN ALONG WALL. 2" V RISE.
22. 4" V FROM BELOW IN CHASE.
23. 1" CW UP AND DOWN IN WALL.
24. 8" ST UP AND DOWN ALONG COLUMN.
25. 2" V FROM BELOW IN CORNER. 4" V UP. 4"VTR.
26. 4"V UP. 4"VTR.
27. 1/2" CW AND 1/2" HW FROM BELOW IN WALL.
28. 4" W DOWN. 2" V RISE.
29. 2" CW AND 3/4" HW FROM BELOW IN CHASE. PROVIDE WHA-B ON COLD WATER PIPE BEFORE LAST WATER CLOSET CONNECTION.
30. 4" W WITH P-TRAP UP TO FLOOR DRAIN (FD).
31. 4" W DOWN ALONG WALL.
32. 3/4" CW FROM BELOW IN WALL. 1 1/2" RISE. 2" DOWN.
33. 4" W FROM COOLING TOWER DRAIN. SEE SHEET M701 FOR CONTINUATION.
34. 6" W DROP.
35. 6" W DOWN ALONG COLUMN.
36. 1" DRAIN LINE FROM ABOVE, ALONG WALL AND TERMINATE INTO FLOOR DRAIN (FD) WITH AIR GAP.
37. 1-1/2" V RISE AND 2" W DOWN IN WALL.
38. SECOND FLOOR MEZZANINE 1 (ABOVE). SEE SECOND FLOOR MEZZANINE 1 PLAN THIS SHEET.
39. SECOND FLOOR MEZZANINE 2 (ABOVE). SEE SECOND FLOOR MEZZANINE 2 PLAN THIS SHEET.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:40 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: EPW	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PLUMBING PLAN

SHEET NUMBER

P304




ROOF PLUMBING PLAN
Scale: 3/32" = 1'-0"

GENERAL NOTES:

A. SEE SHEET P001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.

(#) PLAN NOTES:

1. 1" CW FROM BELOW TO RH-1.
2. SEE DETAIL 10/P501.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:42 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: EPW	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF PLUMBING PLAN

SHEET NUMBER


P305

GENERAL NOTES:


A. SEE SHEET P001 FOR SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.
B. ALL SANITARY WASTE PIPING TO BE 4" UNLESS OTHERWISE NOTED.

(#) PLAN NOTES:

1. 4"W WITH P-TRAP UP TO FLOOR DRAIN (FD).
2. 4"W UP TO FLOOR CLEANOUT (FCO).
3. 4"W FROM BOTTOM OF CONCRETE TRENCH (BY OTHERS).
4. 6"W INTO PIT AT - BELOW TUNNEL FLOOR AT THIS POINT.
5. CONCRETE PIT (BY OTHERS).
6. SEE DETAIL 7/P502.



2 **TUNNEL PLUMBING FLOOR PLAN**
Scale: 3/32" = 1'-0"



1 **TUNNEL PLUMBING UNDERSLAB PLAN**
Scale: 3/32" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY: EPW	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

TUNNEL PLUMBING PLAN


SHEET NUMBER

P306


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:43 PM AESI Proj. No: 21-154




7 P501 **FLOOR DRAIN DETAIL**
Scale: NONE




8 P501 **GAS PIPING DIAGRAM**
Scale: NONE




3 P501 **EMERGENCY SHOWER EYE/FACE WASH ESEW-1 DETAIL**
Scale: NONE




1 P501 **BRINE TANK PIPING DETAILS**
Scale: NOT TO SCALE




2 P501 **DRAINAGE PIT DETAIL**
Scale: NONE




9 P501 **HOT WATER RECIRCULATING PUMP DETAIL**
Scale: NONE




5 P501 **EXTERIOR CLEANOUT DETAIL**
Scale: NONE



10 P501 **PLUMBING VENT DETAIL**
Scale: NONE



6 P501 **FLOOR CLEANOUT DETAIL**
Scale: NONE



4 P501 **HOT WATER BALANCING VALVE STATION DETAIL**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:43 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION


DESIGNED BY: EPW	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


PLUMBING DETAILS

SHEET NUMBER


P501




8 / P502 **GAS TRAIN DETAIL**
Scale: NONE



4 / P502 **ROOF DRAIN DETAIL**
Scale: NONE




1 / P502 **PIPE HANGER (6 INCH & SMALLER) DETAIL**
Scale: NONE




NOTE:
1. SEE FLOOR PLANS FOR TRENCH DRAIN LENGTHS AND NUMBER OF TD-1's THAT WILL BE REQUIRED.
2. THERE WILL BE (2) TD-2's.


7 / P502 **TUNNEL DUPLEX SUMP PUMP DETAIL**
Scale: 12" = 1'-0"




5 / P502 **TYPICAL CLEANOUT FOR STORM RISER DETAIL**
Scale: NONE



6 / P502 **WALL PENETRATION DETAIL**
Scale: NONE



2 / P502 **PIPE HANGER (8 INCH & LARGER) DETAIL**
Scale: NONE



3 / P502 **PIPE JOINT RESTRAINT (6 INCH & LARGER) DETAIL**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:44 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	CERTIFICATION
EPW	PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY	
AESI	
APPROVED BY	
Approver	
PROJECT NO.	
21-154	

SHEET TITLE

PLUMBING DETAILS

SHEET NUMBER

P502

DRAINAGE FIXTURE SCHEDULE

TAG NO.	LOCATION	IPS SIZE	STRAINER	MFR.	MODEL	REMARKS
FD-1	FINISHED AREAS ON GRADE	2"	NICKEL BRONZE, ROUND	J. R. SMITH	2041-A-NB	FLOOR DRAIN: C.I. BODY, 5" ADJUSTABLE NICKEL BRONZE STRAINER, INTEGRAL P-TRAP AND CLEANOUT. PROVIDE SURE SEAL TRAP SEAL IN DRAIN.
FD-2	FINISHED AREAS ABOVE GRADE	2"	NICKEL BRONZE, ROUND	J. R. SMITH	2005Y-A-NB	FLOOR DRAIN: C.I. BODY, 5" ADJUSTABLE NICKEL BRONZE STRAINER, PROVIDE DEEP SEAL P-TRAP WITH BOTTOM CLEANOUT. PROVIDE SURE SEAL TRAP SEAL IN DRAIN.
FD-3	MECHANICAL & PLUMBING EQUIPMENT & GENERAL BUILDING AREAS	4"	1/2 NICKEL BRONZE, SQUARE WITH DOME BOTTOM STRAINER	J. R. SMITH	2635Y-F-C-12-NB	FLOOR DRAIN: C.I. BODY, ACID RESISTANT INTERIOR COATING, SEDIMENT BUCKET AND 1/2 NICKEL BRONZE GRATE. PROVIDE WITH DEEP SEAL P-TRAP. PROVIDE SURE SEAL TRAP SEAL IN DRAIN.
FD-4	INCOMING DOMESTIC WATER FOR BFP-1 AND BFP-2, COOLING TOWER & HEATING HOT WATER SIDE STREAM FILTERS	6"	1/2 NICKEL BRONZE, SQUARE WITH DOME BOTTOM STRAINER	J. R. SMITH	2635Y-F-C-12-NB	FLOOR DRAIN: C.I. BODY, ACID RESISTANT INTERIOR COATING, SEDIMENT BUCKET AND 1/2 NICKEL BRONZE GRATE. PROVIDE WITH DEEP SEAL P-TRAP. PROVIDE SURE SEAL TRAP SEAL IN DRAIN.
FD-5	DRAINAGE PIT	6"	ROUND, LESS GRATE	J. R. SMITH	2143C	FLOOR DRAIN: C.I. BODY AND FLASHING COLLAR, ACID RESISTANT INTERIOR COATING, LESS GRATE. PROVIDE WITH DEEP SEAL P-TRAP.
FD-6	DRAINAGE PITS	8"	ROUND, LESS GRATE	J. R. SMITH	2143C	FLOOR DRAIN: C.I. BODY AND FLASHING COLLAR, ACID RESISTANT INTERIOR COATING, LESS GRATE. PROVIDE WITH DEEP SEAL P-TRAP.
TD-1	TUNNEL RAMP	N/A	12" WIDE, BLACK DUCTILE IRON	NEENAH FOUNDRY	R-4990-CX	TRENCH DRAIN GRATES AND FRAMES: HEAVY DUTY, UNBOLTED, TYPE A GRATES, TYPE B FRAMES, 24" LONG X 12" WIDE X 1-1/2" THICK.
TD-2	TUNNEL RAMP PIT	N/A	51" WIDE, BLACK DUCTILE IRON	NEENAH FOUNDRY	R-4990-OX	TRENCH DRAIN GRATES AND FRAMES: HEAVY DUTY, UNBOLTED, TYPE A GRATES, TYPE B FRAMES, 24" LONG X 51" WIDE X 2" THICK.
RD-1	ROOF	6"	C.I. DOME	J. R. SMITH	1015Y-R-C-CID	ROOF DRAIN: C.I. BODY, ADJUSTABLE EXTENSION SLEEVE, FLASHING CLAMP AND GRAVEL STOP, SUMP RECEIVER, UNDERDECK CLAMP, C.I. DOME.
ORD-1	ROOF	6"	C.I. DOME	J. R. SMITH	1045Y-R-C-CID	OVERFLOW ROOF DRAIN: C.I. BODY, ADJUSTABLE EXTENSION SLEEVE, FLASHING CLAMP AND 2" WATER DAM, SUMP RECEIVER, UNDERDECK CLAMP, C.I. DOME.
DD-1	ROOF	4"	C.I. ROUND	J. R. SMITH	1450Y-R-C-M	DECK DRAIN: C.I. BODY, FLASHING CLAMP WITH SEEPAGE OPENINGS, SUMP RECEIVER, UNDERDECK CLAMP, DUCTILE IRON GRATE.
FCO	FINISHED AREAS ON GRADE	4"	NICKEL BRONZE, ROUND	J. R. SMITH	4021S	FLOOR CLEANOUT: C.I. BODY, ROUND ADJUSTABLE SCORIATED SECURED NICKEL BRONZE TOP, BRONZE PLUG, FLANGE WITH FLASHING CLAMP.
ECO	OUTSIDE AT GRADE	4"	C.I. ROUND	J. R. SMITH	4251S	EXTERIOR CLEANOUT: C.I. BODY, DOUBLE FLANGE HOUSING, HEAVY DUTY SECURED SCORIATED CAST IRON COVER, LIFTING DEVICE, GASKET SEAL, BRONZE PLUG.

WATER HAMMER ARRESTER SCHEDULE

MARK	IPS SIZE	FIXTURE UNIT RATING	PRESSURE RATING	J.R. SMITH MOD. NO.	WADE MOD. NO.	ZURN MOD. NO.	REMARKS
WHA-A	3/4"	1 TO 11	150 PSIG	5005	W-5	100	P.D.I. CERTIFIED
WHA-B	1"	12 TO 32	150 PSIG	5010	W-10	200	P.D.I. CERTIFIED
WHA-C	1"	33 TO 60	150 PSIG	5020	W-20	300	P.D.I. CERTIFIED
WHA-D	1"	61 TO 113	150 PSIG	5030	W-50	400	P.D.I. CERTIFIED
WHA-E	1"	114 TO 154	150 PSIG	5040	W-75	500	P.D.I. CERTIFIED

PLUMBING EQUIPMENT SCHEDULE

TAG NO.	DESCRIPTION	PIPE CONNECTIONS				PERFORMANCE				MFG.	MODEL #	NOTES
		WASTE	VENT	CW	HW	GPM	P.D.	AMPS/Hp	VOLTS/HZ/PH			
BFP-1 BFP-2	REDUCED PRESSURE ZONE ASSEMBLY BACKFLOW PREVENTERS	3"	N/A	8"	N/A	1000	12 PSIG	N/A	N/A	WATTS	8" LF909-OSY-S-FDA	MAIN SUPPLY: PROVIDE STRAINER AND AIR GAP DRAIN FITTING. INSTALL STRAINER UPSTREAM OF BFP AND DOWNSTREAM OF ISOLATION VALVE (TYPICAL). ROUTE DRAIN LINE FROM AIR GAP TO NEAREST FLOOR DRAIN.
BFP-3 BFP-4	REDUCED PRESSURE ZONE ASSEMBLY BACKFLOW PREVENTERS	3"	N/A	8"	N/A	800	13 PSIG	N/A	N/A	WATTS	6" LF909-OSY-S-FDA	HYDRONIC MAKE-UP: PROVIDE STRAINER AND AIR GAP DRAIN FITTING. INSTALL STRAINER UPSTREAM OF BFP AND DOWNSTREAM OF ISOLATION VALVE (TYPICAL). ROUTE DRAIN LINE FROM AIR GAP TO NEAREST DRAINAGE PIT/FLOOR DRAIN.
FM-1 FM-2	INCOMING DOMESTIC WATER FLOW METERS	N/A	N/A	6"	N/A	1000	N/A	N/A	N/A	ENDRESS + HAUSER	PROMAG	MAIN SUPPLIES, ELECTROMAGNETIC TYPE, CONNECT TO BMS AND SETUP TO RECORD HOURLY DATA.
FM-3	COOLING TOWER MAKE-UP WATER FLOW METER	N/A	N/A	4"	N/A	800	N/A	N/A	N/A	ENDRESS + HAUSER	PROMAG	COOLING TOWER MAKE-UP, ELECTROMAGNETIC TYPE, CONNECT TO BMS AND SETUP TO RECORD HOURLY DATA.
FM-4	CHILLED WATER MAKE-UP WATER FLOW METER	N/A	N/A	2"	N/A	30	N/A	N/A	N/A	ENDRESS + HAUSER	PROMAG	CHILLED WATER MAKE-UP, ELECTROMAGNETIC TYPE, CONNECT TO BMS AND SETUP TO RECORD HOURLY DATA.
FM-5	DOMESTIC HOT WATER MAKE-UP WATER FLOW METER	N/A	N/A	2"	N/A	30	N/A	N/A	N/A	ENDRESS + HAUSER	PROMAG	DOMESTIC HOT WATER MAKE-UP, ELECTROMAGNETIC TYPE, CONNECT TO BMS AND SETUP TO RECORD HOURLY DATA.
FM-6	RO MAKE-UP WATER FLOW METER	N/A	N/A	2 1/2"	N/A	70	N/A	N/A	N/A	ENDRESS + HAUSER	PROMAG	RO MAKE-UP, ELECTROMAGNETIC TYPE, CONNECT TO BMS AND SETUP TO RECORD HOURLY DATA.
FM-7	HEATING HOT WATER MAKE-UP WATER FLOW METER	N/A	N/A	3"	N/A	30	N/A	N/A	N/A	ENDRESS + HAUSER	PROMAG	HEATING HOT WATER MAKE-UP, ELECTROMAGNETIC TYPE, CONNECT TO BMS AND SETUP TO RECORD HOURLY DATA.
DWH-1	DOMESTIC WATER HEATER	FD	N/A	1 1/2"	1 1/2"	SEE NOTES	N/A	21.6 AMPS	480/60/3	BOCK	CE119-3D	DIGITAL ELECTRIC STORAGE WATER HEATER: 18.0 KW, 119 GALLON CAPACITY, GLASS LINED, UNIT CAPABLE OF HEATING 72 GPH FROM 40 DEG F TO 140 DEG F.
DET-1	DOMESTIC HOT WATER EXPANSION TANK	N/A	N/A	1"	N/A	N/A	N/A	N/A	N/A	AMTROL	ST-12C-DD	AMTROL THERM-X-TROL THERMAL EXPANSION TANK. ASME CONSTRUCTED, 6.4 GALLON TANK VOLUME AND NON-FERROUS MATERIALS.
TMV-1	THERMOSTATIC MIXING VALVE	N/A	N/A	1"	1" HW, 1 1/4" TW	28	5 PSIG	N/A	N/A	LAWLER	802 UNIT 86008	THERMOSTATIC MIXING VALVE, ALL BRONZE CONSTRUCTION WITH THERMOMETER, SHUT-OFF VALVES AND UNIONS. SET POINT OF 110 DEG F.
ETMV-1	EMERGENCY THERMOSTATIC MIXING VALVE	N/A	N/A	1"	1" HW, 1 1/4" TW	35	10 PSIG	N/A	N/A	LAWLER	911	EMERGENCY SAFETY SHOWER AND EYEWASH THERMOSTATIC MIXING VALVE, ROUGH CHROME PLATED FINISH WITH THERMOMETER, SHUT-OFF VALVES, CHECK VALVES AND UNIONS.
DWS-1 DWS-2	DOMESTIC WATER SOFTENERS	6"	N/A	8"	N/A	NORM: 700 GPM MAX: 1,000 GPM	NORM: 15 PSID MAX: 25 PSID	3 AMPS	120/60/1	NANCREDE ENGINEERING	NECO MHC-3600-8	DUPLEX WATER SOFTENER SYSTEM WITH BRINE DAY TANK WATER METER ON DEMAND REGENERATION UNIT, ELECTRONIC CONTROLS.
DBP-1	DOMESTIC WATER BOOSTER PUMP	N/A	N/A	10"	N/A	250 EACH	+55 PSI	15 HP EACH	460/60/3	TIGERFLOW	SERIES ES-3000-H-VFD MODEL QESH-15EB-C-S8-CC-P-VFD	QUADRAPLEX BOOSTER PUMP PACKAGE, VARIABLE SPEED DRIVE, SKID MOUNTED. PROVIDE WITH BAS INTERFACE CAPABILITY.
BRT-1	BRINE TANK	N/A	8"	1"	2" BRINE	N/A	N/A	N/A	N/A	NANCREDE ENGINEERING	NEDW1026	13,000 GALLON UNDERGROUND DOUBLE WALL BRINE TANK, 10' X 26'. WITH WATER LEVEL ULTRASONIC CONTROLLER, SALT LEVEL INDICATOR AND CONCENTRATOR MONITOR, INTERNAL FIBERGLASS LADDER, DUST BAG HOUSING, NSF 61 LABEL, 12" GRAVEL BED, H25 RATED TRAFFIC COVERS, AND CONCRETE ANCHOR SYSTEM
BRP-1 BRP-2	DUPLEX BRINE PUMPS	N/A	N/A	2" BRINE	N/A	25	30 PSIG	2 HP EACH	460/60/3	FINISH THOMPSON	DB15	POLYPROPYLENE MAG DRIVE PUMPS, DUPLEX BASE MOUNTED PUMPS WITH CONTROL PANEL.
PT-1	PRESSURE TANK	N/A	N/A	1"	N/A	N/A	N/A	N/A	N/A	TIGERFLOW	TF-185-E	185 GALLON, BLADDER TYPE EXPANSION TANK; REMOVABLE BUTYL BLADDER
SP-1	DUPLEX SUMP PUMPS	2" EACH	N/A	N/A	N/A	109	40' TDH	2 HP EACH	460/60/3	ZOELLER	4189	DOUBLE SEAL PUMPS, Z-RAIL SYSTEM, DUPLEX PUMPS CONTROL/ALARM PANEL, FLOAT TREE WITH FLOATS.
OS-1	OIL SEPARATOR	4"	3"	N/A	N/A	75	N/A	N/A	N/A	STRIEM	OS-75-4M-C24-HP-SR24	110 GALLON LIQUID CAPACITY; OIL: 93 GAL.; SAND: 11 GAL.; H2O RATED PICKABLE CAST IRON COVER, PROVIDE RISER HEIGHT AS REQUIRED TO BE FLUSH WITH FINISH FLOOR.
DWRP-1	DOMESTIC HOT WATER RECIRCULATION PUMP	N/A	N/A	N/A	1"	4	20' TDH	1.02 AMPS	115/60/1	BELL AND GOSSETT	ECOCIRC 20-18	STAINLESS STEEL CONSTRUCTION, PROVIDE STRAP ON AQUASTAT TO START AND STOP PUMP ON 10 DEGREE TEMPERATURE VARIATION IN RETURN MAIN.

PLUMBING FIXTURE SCHEDULE

TAG NO.	DESCRIPTION (LOCATION)	PIPE ROUGH-IN CONNECTIONS					PERFORMANCE	MFG.	MODEL #	MOUNTING HEIGHT	NOTES
		WASTE	VENT	CW	HW	TW	GPM				
WC-1	WATER CLOSET - ADA: (TOILET 111, TOILET/SHOWER 205A, TOILET/CHANGING 205B)	4"	2"	1"	N/A	N/A	1.28 (GPF)	AMERICAN STANDARD SLOAN	AFWALL MILLENNIUM FLOWISE 2257.101 ROYAL 111-1.28	16-1/2" AFF TO RIM	WATER CLOSET: ADA MOUNTING HEIGHT, WHITE ELONGATED VITREOUS CHINA BOWL, WALL MOUNTED, 1 1/2" TOP SPUD. FLUSH VALVE: CHROME PLATED BRASS, 1.28 GPF MANUAL FLUSH VALVE, CHROME ESCUTCHEON PLATE, VACUUM BREAKER, SWEAT SOLDER ADAPTER, WATERSENSE LISTED. SEAT: BEMIS 2155SSCT COMMERCIAL, ANTI-MICROBIAL SURFACE PLASTIC SEAT WITH SELF SUSTAINING/CHECK TYPE HINGES AND SS HARDWARE, WHITE. CARRIER: J.R. SMITH 100 SERIES.
UR-1	URINAL - ADA: (TOILET 111, TOILET/SHOWER 205A, TOILET/CHANGING 205B)	2"	1 1/2"	3/4"	N/A	N/A	1 GALLON EVERY 72 HOURS	SLOAN	HYB-1000	17" AFF TO LIP	URINAL: ADA MOUNTING HEIGHT, HYBRID URINAL WITH JETRINSE SOLUTION TECHNOLOGY, VITREOUS CHINA, WHITE. AUTOMATIC CLEANING FLUSH EVERY 72 HOURS. WATERFREE NORMAL OPERATION. 6V LITHIUM BATTERY POWERED. WATERSENSE LISTED. CARRIER: J.R. SMITH 600 SERIES.
L-1	LAVATORY - ADA: (TOILET 111, TOILET/SHOWER 205A, TOILER/CHANGING 205B)	2"	1 1/2"	1/2"	1/2"	N/A	0.35	AMERICAN STANDARD CHICAGO FAUCET	LUCERNE 0355.027 420-T45E39VPABCP	34" AFF TO RIM	LAVATORY: ADA MOUNTING HEIGHT, WALL-HUNG, VITREOUS CHINA, WHITE, 20 1/2" X 18 1/4", FAUCET HOLES ON 4" CENTERS. FAUCET: DECK MOUNTED, POLISHED CHROME, 4" CENTERS, MANUAL FAUCET, 0.35 GPM FLOW AERATOR, WATERSENSE LISTED. DRAIN: CHROME PLATED OFFSET GRID STRAINER, CHROME PLATED, 17 GA BRASS, P-TRAP TAIL PIECE, EXTENSION AND BOX ESCUTCHEON. SUPPLIES: CHICAGO FAUCET 1017 SOFT SUPPLY TUBES AND LOOSE KEY ANGLE STOP VALVES, CHROME PLATED. INSULATION: TRUBRO HOT WATER, COLD WATER AND DRAIN INSULATION KIT. CARRIER: J.R. SMITH 700 SERIES.
SH-1	SHOWER - ADA: (TOILET/SHOWER 205A)	2"	N/A	1/2"	1/2"	N/A	1.5 / 1.5	AQUATIC CHICAGO FAUCET	1363BFSCST SH-PB1-11-031	SHOWER VALVE 42" AFF, DIVERTER VALVE 54" AFF, SHOWER HEAD 75" AFF	SHOWER: 36"W x 36"D x 75 1/8"H INTERIOR, ACRYLIC SURFACE, WHITE FINISH, CENTER DRAIN, L-SHAPED GRAB BAR, FOLD-UP SEAT, CURTAIN ROD AND CURTAIN, CENTER BRASS DRAIN, SOAP DISH, VINYL FLEXIBLE WATER DAM. SHOWER VALVE: PRESSURE BALANCED, BRASS BODY CONSTRUCTION WITH 1.5 GPM ADJUSTABLE FLOW SHOWER HEAD AND 1.5 GPM HAND SPRAY, 24" WALL MOUNTED SLIDE BAR, 59" STAINLESS STEEL HOSE AND PUASE CONTROL, INLINE VACUUM BREAKER, DIVERTER VALVE. WATERSENSE LISTED. DRAIN: BRASS TO FIT DRAIN OPENING, CHROME, STAINLESS-STEEL STRAINER, DEEP SEAL P-TRAP.
SK-1	SINK: (LOCKER/BREAK 205)	2"	1 1/2"	1/2"	1/2"	N/A	1.5	JUST CHICAGO FAUCET	DLN-1933-A-GR 201-AG8AE35-317VAB	UNDERMOUNT	SINK: 304 STAINLESS STEEL, 18 GA, DOUBLE BOWL, UNDERCOATED, DIMENSIONS - OVERALL 33" X 19" X 8", BOWLS 14" X 14" X 8", (3) HOLES - 4" CENTERS, CENTER DRAINS. FAUCET: DECK MOUNTED, 8" CENTER, CERAMIC CARTRIDGE, 8" SWING SPOUT, 4" WRIST BLADES, 1.5 GPM LAMINAR FLOW, CHROME PLATED, WATERSENSE LISTED. DRAIN: LKS8 DRAIN FITTING, 2" PVC TAIL PIECE, PVC P-TRAP AND ARM AND ESCUTCHEON, CHROME PLATED. SUPPLIES: CHICAGO FAUCET 1017 SOFT SUPPLY TUBES AND LOOSE KEY ANGLE STOP VALVES, CHROME PLATED.
MB-1	MOP BASIN: (JANITOR 115 & JANITOR/STORAGE 223)	3"	1 1/2"	1/2"	1/2"	N/A	FULL	FIAT CHICAGO FAUCET	TSB3000 897-RCF	FLOOR MOUNTED	MOP BASIN: ONE PIECE PRECAST TERRAZZO, 24"X24"X12" HIGH WITH 6" DROP FRONT, SS CAPS ON ALL CURBS, SS WALL GUARDS, SS STRAINER, 3" WASTE PIPE, WALL MOUNTED MOP BRACKET, WALL MOUNTED HOSE BRACKET WITH HOSE. SILICONE SEALANT. FAUCET: CHROME PLATED, QUARTER TURN, LEVER HANDLES, BRACING ROD, INTEGRAL STOP VALVES, VACUUM BREAKER.
SS-1	SERVICE SINK: (MAINTENANCE WORKROOM 207)	3"	1 1/2"	1/2"	1/2"	N/A	FULL	AMERICAN STANDARD CHICAGO FAUCET	AKRON 7695.008 305-VBXKCCP	26-1/4" AFF TO RIM	SERVICE SINK: ENAMELED CAST IRON WITH SUPPLIED WALL HANGER AND RIM GUARD. FAUCET: 3" BRASS SPOUT, INTEGRAL CHECK STOPS, CERAMIC DISC VALVE CARTRIDGES, VACUUM BREAKER, CHROME PLATED. DRAIN: TRAP STANDARD 7708.030, 3" CAST IRON P-TRAP STANDARD TO WALL AND STRAINER. STOP VALVES: CHICAGO FAUCET 1017 STOPS AND SUPPLY TUBES, ESCUTCHEONS, CHROME PLATED.
HB-1	HOSE BIBB: (INDOOR)	N/A	N/A	3/4"	N/A	N/A	FULL	WOODFORD	26-BR	24" AFF	HOSE BIBB: 3/4" INLET, 3/4" HOSE CONNEECTION, ROUGH BRASS FINISH, STEEL WHEEL HANDLE, TWO INDEPENDENT CHECK VALVES, BACKFLOW PREVENTER.
WH-1	WALL HYDRANT: (OUTDOOR)	N/A	N/A	3/4"	N/A	N/A	FULL	WOODFORD	B67-CH	24" ABOVE EXT. GRADE	WALL HYDRANT: 3/4" INLET, 3/4" HOSE CONNECTION, CHROME FINISH, DOUBLE CHECK BACKFLOW PREVENTER, AUTOMATIC DRAINING, BRASS BODY, LOCKABLE COVER, FREEZELESS, REMOVABLE KEY, ANGLED HOSE CONNECTION, WALL CLAMP, .
RH-1	ROOF HYDRANT: (ROOF)	1"	N/A	1"	N/A	N/A	FULL	WOODFORD	RHY2-1-MS	30" ABOVE ROOF	ROOF HYDRANT: DUAL CHECK BACKFLOW PREVENTER, 3/4" HOSE CONNECTION, ASSE 1052 LISTED, 1" NPT FEMALE INLET CONNECTION, 1 1/4" U.S. MADE GALVANIZED PIPE CASING, 1/8" NPT DRAIN HOLE, UNDER DECK FLANGE, MOUNTING BOLTS, AUTOMATIC DRAINING WHEN SHUT OFF.
ESEW-1	EMERGENCY SHOWER EYE/FACE WASH: (RECEIVING 105)	2"	1 1/2"	1"	1"	1 1/4"	20 SHOWER HEAD; 3.2 FACE/EYE WASH	GUARDIAN	GBF1909	FLOOR MOUNTED	EMERGENCY SHOWER & FACE/EYE WASH: COMBINATION UNIT. SHOWER: ABS PLASTIC DRENCH SHOWER, STAY OPEN FULL PORT BALL VALVE WITH PULL ROD. FACE/EYE WASH: ABS PLASTIC BOWL RECEPTOR, STAINLESS STEEL PUSH FLAG, LAMINAR FLOW, FACE WASH. DRAIN (FACE/EYE WASH): 1 1/2" BRASS P-TRAP, CHROME PLATED. PIPING: 1 1/2" HOT DIPPED GALVANIZED. ETMV-1: PROVIDE ETMV-1 AT ESEW-1 LOCATION.
ESEW-2	EMERGENCY SHOWER EYE/FACE WASH: (SERVICE YARD - OUTDOOR)	N/A	N/A	1"	1"	1 1/4"	20 SHOWER HEAD; 3.2 FACE/EYE WASH	GUARDIAN	GFR35007-TL	FLOOR MOUNTED	EMERGENCY SHOWER & FACE/EYE WASH: COMBINATION UNIT, ELECTRIC HEAT-TRACED 120V, ALARM HORN, LIGHT AND REMOTE SENSING CAPABILITY. SHOWER: ABS PLASTIC DRENCH SHOWER, STAY OPEN FULL PORT BALL VALVE WITH PULL ROD. FACE/EYE WASH: STAINLESS STEEL PUSH FLAG, LAMINAR FLOW, FACE WASH. DRAIN (FACE/EYE WASH): NONE. PIPING: 1 1/2" HOT DIPPED GALVANIZED. ETMV-1: PROVIDE ETMV-1 AT ESEW-2 LOCATION. INSTALL ETMV-1 IN NON-FREEZING ENVIRONMENT (INSIDE BUILDING).

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:46 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: EPW
CHECKED BY: AESI
APPROVED BY: Approver
PROJECT NO.: 21-154
CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

PLUMBING SCHEDULES

SHEET NUMBER

P601



1 **DOMESTIC WATER DIAGRAM**
Scale: 12" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:46 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: EPW	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


PLUMBING DIAGRAMS

SHEET NUMBER

P701

GENERAL NOTES:

A. THE ISOMETRIC DIAGRAM IS A 3-D CAMERA VIEW OF THE BUILDING SANITARY, WASTE AND VENT PIPING. SOME PIPING AND FITTINGS MAY APPEAR HIDDEN OR OUT OF PERSPECTIVE DUE TO THE ANGLE OF THE VIEW.
B. CHANGES IN DIRECTION FOR DRAINAGE AND VENT PIPING SHALL BE MADE USING APPROPRIATE 45-DEGREE WYES, HALF WYES, OR LONG SWEEP QUARTER BENDS MAY BE USED ON VERTICAL STACKS OF DRAINAGE LINES WHERE THE CHANGE IN DIRECTION OF FLOW IS FROM HORIZONTAL TO VERTICAL, EXCEPT USE LONG TURN TEES WHERE TWO FIXTURES ARE INSTALLED BACK TO BACK AND HAVE A COMMON DRAIN. NO CHANGE IN DIRECTION OF FLOW GREATER THAN 90 DEGREES SHALL BE MADE.
C. WHERE DIFFERENT SIZES OF DRAINAGE PIPES AND FITTINGS ARE CONNECTED, USE PROPER SIZE STANDARD INCREASERS AND REDUCERS. REDUCTION OF THE SIZE OF DRAINAGE PIPING IN THE DIRECTION OF FLOW IS PROHIBITED.
D. INSTALL BUILDING DRAINS PITCHED DOWN AT MINIMUM SLOPE OF 1/4" PER FOOT (2222 PERCENT) FOR PIPING 2" AND SMALLER AND 1/8 INCH PER FOOT (1 PERCENT) FOR PIPING LARGER THAN 2" UNLESS OTHERWISE NOTED ON THE DRAWINGS.
E. VENT AND BRANCH VENT PIPING SHALL BE GRADED OR SLOPED AND CONNECTED AS TO DRAIN BACK TO THE DRAINAGE PIPING BY GRAVITY.
F. ALL WASTE AND VENT PIPE SIZES MAY NOT BE INDICATED ON THIS DRAWING. REFER TO FLOOR PLANS AND UNDER FLOOR PLANS FOR ADDITIONAL SIZES AND INFORMATION.
G. WHERE PIPES PASS THROUGH FIRE RATED WALLS, PARTITIONS, CEILINGS AND FLOORS, MAINTAIN THE FIRE RATED INTEGRITY. REFER TO DIVISION 7 FOR SPECIAL SEALERS AND MATERIALS. REFER TO BUILDING CODE SUMMARY AND LIFE SAFETY PLANS FOR FIRE RATED ASSEMBLIES.
H. ALL SANITARY WASTE PIPING TO BE 4" UNLESS OTHERWISE NOTED.



1 **WASTE AND VENT ISOMETRIC**
Scale:

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:29:50 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: EPW	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: ---	
PROJECT NO.: 21-154	

SHEET TITLE

PLUMBING WASTE & VENT ISOMETRIC

SHEET NUMBER

P801

NOTE: ALL SYMBOL DESCRIPTIONS ARE SUBJECT TO MODIFICATION ON THE DRAWINGS. ALL SYMBOLS NOT NECESSARILY USED ON THIS PROJECT.

GENERAL SYMBOLS:

- POINT OF CONNECTION
- POINT OF REMOVAL
- PLAN NOTE
- REVISION
- DETAIL BUBBLE
- SECTION BUBBLE

VALVES & FITTINGS:

- GATE VALVE
- BALL VALVE
- BUTTERFLY VALVE
- CHECK VALVE
- GLOBE VALVE
- CONTROL VALVE
- 2 1/2" VALVE AND HOSE CONNECTION
- AIR VENT
- PRESSURE RELIEF VALVE
- PRESSURE REGULATING VALVE
- REDUCED PRESSURE BACK FLOW PREVENTER
- INDICATED FLOW DIRECTION
- PIPE TURN 90°
- LINE BREAK
- PIPE ELBOW UP (RISER)
- PIPE ELBOW DOWN
- PIPE TEE DOWN
- CAP OR PLUG
- REDUCER, CONCENTRIC
- REDUCER, ECCENTRIC
- FLANGES
- UNION
- METER
- FD FLOOR DRAIN
- GAUGE
- THERMOMETER
- PRESSURE SENSOR
- JOCKEY PUMP

DRAWING ABBREVIATIONS:

AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AD	ACCESS DOOR
BHP	BRAKE HORSEPOWER
BLDG	BUILDING
BOD	BOTTOM OF DUCT
BOP	BOTTOM OF PIPE
BOS	BOTTOM OF STEEL
BTU	BRITISH THERMAL UNIT
CW	DOMESTIC COLD WATER
DCV	DOUBLE CHECK VALVE
DIA	DIAMETER
DN	DOWN
DCVA	DOUBLE CHECK VALVE ASSEMBLY
FD	FLOOR DRAIN
EL	ELEVATION
EXIST	EXISTING
FCO	FLOOR CLEANOUT
FLA	FULL LOAD AMPS
HKSP	HOUSEKEEPING
HW	DOMESTIC HOT WATER
HWR	DOMESTIC HOT WATER RETURN
IE	INVERT ELEVATION
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
NG	NITROGEN GENERATOR
PA	PRE-ACTION
PIV	POST INDICATING VALVE
PSIA	POUNDS PER SQUARE INCH ABSOLUTE
PSIG	POUNDS PER SQUARE INCH GAUGE

FIRE PROTECTION PIPING SYMBOLS

(WITHIN THE BUILDING)

- F — FIRE PROTECTION
- PA — PRE-ACTION
- FDP — FIRE DRY PIPE
- FPV — FIRE WATER STORAGE TANK VENT
- FIRE DEPARTMENT SIAMESE CONNECTION (FREE STANDING)
- FIRE DEPARTMENT SIAMESE CONNECTION (WALL MOUNTED)
- FS — FLOW SWITCH
- TS — ZONE CONTROL VALVE WITH TAMPER SWITCH
- SIGHT GLASS
- P — PRESSURE GAUGE
- PA — DOUBLE INTERLOCK PRE-ACTION VALVE
- FIRE PUMP TEST METER

HYDRANT FLOW TEST DATA

ADDRESS OF TEST: 15TH STREET AND MISSOURI STREET
LOCATION OF TEST: 2ND HYDRANT EAST OF MISSOURI STREET ON 15TH STREET
DATE OF TEST: JULY 29, 2021 AT 8:00 AM

FLOW HYDRANT NUMBER: 155
FLOW HYDRANT MAIN SIZE (IN.): 8
NOZZLES: 1
NOZZLE SIZE (IN.): 2.5
FLOW RATE (GPM): 1090

PRESSURE HYDRANT NUMBER: 154
PRESSURE HYRANT MAIN SIZE (IN.): 8
STATIC PRESSURE (PSI): 58
RESIDUAL PRESSURE (PSI): 56
ESTIMATED FLOW AT 20 PSI (GPM): 5,345

FIRE PROTECTION GENERAL NOTES:

1. THE CUP BUILDING WILL SUPPLY FIRE PROTECTION WATER TO THE CUP BUILDING, THE SOUTH SUPPORT BUILDING AND THE MEDICAL CENTER BUILDING. THE CONTRACTOR WILL BE REQUIRED TO DESIGN AND INSTALL THE FIRE PROTECTION SYSTEM FOR THE CUP BUILDING AND THE TUNNEL TO THE HAND-OFF POINTS FOR BOTH THE MEDICAL CENTER BUILDING AND THE SOUTH SUPPORT BUILDING.
2. THE ENTIRE CUP BUILDING WILL BE A FULLY SPRINKLED. FIRE PROTECTION CONTRACTOR SHALL DESIGN THE COMPLETE SYSTEM ACCORDING TO THE CRITERIA OUTLINED ON THE DRAWINGS, SPECIFICATIONS, FM, N.F.P.A. 13, 14, 20 AND 22. THE ENTIRE BUILDING SHALL BE PROTECTED BY A WET-PIPE OR A DRY-PIPE SPRINKLER SYSTEM. THE MDF ROOM WILL HAVE A CLEAN AGENT FIRE PROTECTION SYSTEM, IT WILL ALSO HAVE A SECONDARY DRY-PIPE SPRINKLER SYSTEM.
3. THE 10" FIRE PROTECTION SERVICE TO THE MEDICAL CENTER BUILDING SHALL HAVE THE CAPACITY OF 290 PSI @ 1000 GPM AT THE HAND-OFF POINT IN THE TUNNEL.
4. FIRE PROTECTION CONTRACTOR SHALL PREPARE ALL DRAWINGS AND APPLICATIONS REQUIRED TO OBTAIN APPROVAL OF THE SYSTEM BY OWNERS INSURANCE UNDERWRITER, STATE AND LOCAL AUTHORITIES HAVING JURISDICTION. ALL DRAWINGS TO BE SUBMITTED DURING CONSTRUCTION.
5. FIRE PROTECTION CONTRACTOR SHALL SUBMIT DRAWINGS WITH ALL SPRINKLER HEAD LOCATIONS. ALL SPRINKLER HEADS TO BE LAID OUT NEATLY WITHIN THE CEILING SYSTEMS AND BE COORDINATED WITH ALL BULKHEADS, CEILINGS AND STRUCTURE. REFERENCE ARCHITECTURAL DRAWINGS FOR CEILING PLANS.
6. ALL PIPING, SIZES, ZONES AND SPRINKLER MAINS SHOWN ON DRAWINGS ARE FOR BIDDING AND DESIGN INTENT ONLY. FIRE PROTECTION CONTRACTOR IS RESPONSIBLE FOR PROPER COVERAGE AND CAPACITY OF THE SPRINKLER SYSTEM.
7. ALL MATERIALS, WHERE APPLICABLE SHALL BE U.L. LISTED AND FACTORY MUTUAL APPROVED FOR THE USE IN AUTOMATIC SPRINKLER SYSTEMS.
8. DO NOT PLACE SPRINKLER HEAD WITHIN THE ELEVATOR OR THE ELEVATOR EQUIPMENT ROOM.
9. SPRINKLER PIPING SHALL NOT BE ROUTED THRU TECHNOLOGY ROOMS, USE SIDEWALL SPRINKLER HEADS WITH GUARDS TO SERVE THE ROOM.
10. SPRINKLER SYSTEM DESIGN SHALL BE APPOVED BY AUTHORITIES HAVING JURISDITION.
    a. MARGIN OF SAFETY FOR AVAILABLE WATER FLOW AND PRESSURE: 10 PERCENT, INCLUDING LOSSES THROUGH WATER SERVICE PIPING, VALVES AND BACKFLOW PREVENTERS.
    b. SPRINKLER OCCUPANCY HAZARD CLASSIFICATIONS:
        1) OFFICES, LOUNGES, SEPARATED DINING AREAS, TOILET ROOMS, COORIDORS: LIGHT HAZARD. DENSITY: 0.10 GPM SQ. FT. AREA: 1500 SQ. FT. HOSE DEMAND: 250 GPM. MAXIMUM PROTECTION AREA PER SPRINKLER HEAD: 196 SQ. FT. WITH FINISHED ACT CEILING TILES, 225 SQ. FT. WITH FINISHED GWB CEILINGS.
        5) MECHANICAL, ELECTRICAL, CLASSES I TO IV COMMODITIES STORAGE UP TO 200 SQ. FT., WORKSHOP AND UTILITY AREAS: ORDINARY HAZARD GROUP 2. DENSITY: 0.20 GPM SQ. FT. AREA: 2500 SQ. FT. HOSE DEMAND; 250 GPM. MAXIMUM PROTECTION AREA PER SPRINKLER HEAD: 130 SQ. FT.
        9) STORAGE AND RECEIVING AREAS: EXTRA HAZARD GROUP 2 AND NFPA 13 STORAGE CRITERIA. DENSITY: REFER TO FM DATA SHEET 8-9, AREA: 500 SQ. FT. HOSE DEMAND: 100 GPM. MAXIMUM PROTECTION AREA PER SPRINKLER HEAD: 11.2
        10) FUEL OIL STORAGE: EXTRA HAZARD GROUP 2. DENSITY: 0.40 GPM SQ. FT. AREA: 2500 SQ. FT. HOSE DEMAND: 500 GPM. MAXIMUM PROTECTION AREA PER SPRINKLER HEAD: 100 SQ. FT.
        13) GENERATOR ROOMS: EXTRA HAZARD GROUP 1. DENSITY: 0.30 GPM SQ. FT. AREA: 2500 SQ. FT. HOSE DEMAND: 500 GPM. MAXIMUM PROTECTION AREA PER SPRINKLER HEAD: 100 SQ. FT.
11. MAXIMUM PROTECTION AREA PER SPRINKLER: ACCORDING TO UL LISTING.
12. ALL SYSTEMS SHALL BE DESIGNED TO MEET THE REQUIREMENTS OF A FACILITY LOCATED IN A SEISMIC DESIGN CATEGORY C, RISK/OCCUPANCY CATEGORY IV AREA.
13. EACH DRY-PIPE SYSTEM SHALL BE EQUIPPED WITH A NITROGEN INJECTION POINTS AND NITROGEN MONITORING VENTS.
14. EACH PRE-ACTION SYSTEM SHALL HAVE A NITROGEN GENERATOR TO MAINTAIN A NITROGEN ATMOSPHERE WITHIN THE PIPING SYSTEM.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: MLP	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AES	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRE PROTECTION SYMBOLS AND ABBREVIATIONS

SHEET NUMBER

FP001

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:31:45 PM AES Proj. No: 21-154



1 / FP301 LOWER LEVEL FIRE PROTECTION PLAN


Scale: 3/32" = 1'-0"

GENERAL NOTES:

A. SEE DRAWING FP001 FOR ADDITIONAL GENERAL NOTES.

PLAN NOTES:

1. 10" FIRE PROTECTION PIPING IN TUNNEL. 10" FIRE PROTECTION SHALL BE INSTALLED TO THE SOUTH SUPPORT BUILDING AND TO THE HAND-OFF POINT IN THE TUNNEL TO SERVE THE MEDICAL CENTER BUILDING.
2. 10" FIRE PROTECTION PIPING UP.
3. FIRE PROTECTION PIPING UP.
4. FIRE PROTECTION SYSTEM SERVING THE TUNNEL. SEE TUNNEL DRAWINGS UT101.2 MECHANICAL - FIRE PROTECTION AND UT102.2 FIRE PROTECTION FOR HAND-OFF POINTS AT SOUTH SUPPORT BUILDING (SSB) AND THE MEDICAL CENTER BUILDING.
5. SEE SITE UTILITY DRAWINGS FOR CONTINUATION.
6. FIRE PROTECTION WATER STORAGE TANK. TANK SHALL BE 42'-0" LONG x 26'-5 3/4" WIDE x 9'-11" USABLE WATER DEPTH = 11,037 CUBIC FEET. 11,037 CUBIC FEET x 7.481 GALLONS PER CUBIC FOOT = 82,567 GALLONS OF USABLE WATER.
7. 10" WATER SUPPLY UP.
8. 10" FIRE PUMP WATER TEST RETURN TO TANK UP.
9. 6" TANK VENT UP.
10. FIRE PUMP (FP-1).
11. 2" FIRE RISER DRAIN DROP ROUTE THROUGH THE TUNNEL AND DROP AT TRENCH DRAIN, APPROXIMATELY 150'-0".
12. FLOOR CONTROL VALVE ASSEMBLY. SEE SPRINKLER SYSTEM FLOOR CONTROL VALVE DETAIL 2/FP501.
13. EARLY SUPPRESSION, FAST RESPONSE (ESFR) TYPE SPRINKER HEADS SHALL BE UTILIZED THROUGHOUT THE TUNNEL. SEE TUNNEL DRAWINGS UT101.2 MECHANICAL - FIRE PROTECTION AND UT102.2 FIRE PROTECTION FOR HAND-OFF POINTS AT SOUTH SUPPORT BUILDING (SSB) AND THE MEDICAL CENTER BUILDING.
14. TANK ACCESS WITH LADDER.
15. 2 1/2" VALVE AND HOSE CONNECTION ON THE INTERMEDIATE STAIR LANDING BETWEEN THE LOWER LEVEL AND FIRST FLOORS. FIRE DEPARTMENT HOSE CONNECTION AND VALVE (TYPICAL).
16. 8" TANK OVERFLOW UP.
17. PIPE SLEEVE THROUGH EXTERIOR FOUNDATION.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:31:47 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: MLP	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AES	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

LOWER LEVEL FIRE PROTECTION PLAN


SHEET NUMBER

FP301



FIRST FLOOR FIRE PROTECTION PLAN

Scale: 3/32" = 1'-0"



FIRST FLOOR MEZZANINE FIRE PROTECTION PLAN


Scale: 1/8" = 1'-0"

GENERAL NOTES:

A. SEE DRAWING FP001 FOR ADDITIONAL GENERAL NOTES.

PLAN NOTES:

1. FLOOR CONTROL VALVE ASSEMBLY. SEE SPRINKLER SYSTEM FLOOR CONTROL VALVE DETAIL 2/FP501.
2. 6" FIRE WATER STORAGE TANK VENT UP TO SECOND FLOOR.
3. 2" FIRE RISER DRAIN DOWN. 2" FIRE RISER DRAIN EXIT BUILDING AT 18" A.F.G. AND TURN DOWN AT 45 DEGREE.
4. 2" FIRE RISER DRAIN.
5. 2" FIRE RISER DRAIN UP.
6. STANDPIPE DRAIN.
7. PRESSURE GAUGE.
8. 10" FIRE PROTECTION SERVICE.
9. FIRE RISER DOWN TO LOWER LEVEL AND UP TO SECOND FLOOR. FIRE RISER SHALL HAVE A 2 1/2" VALVE AND HOSE CONNECTION ON THE INTERMEDIATE STAIR LANDING BETWEEN THE FIRST AND SECOND FLOORS. FIRE DEPARTMENT HOSE CONNECTION AND VALVE.
10. 10" FIRE PROTECTION DOWN INTO TUNNEL TO SERVE THE SOUTH SERVICE BUILDING AND THE HOSPITAL.
11. CHECK VALVE.
12. CLASS 1 MANUAL WET-STANDPIPE FIRE RISER UP. INSTALL DRAIN VALVE AT THE BASE OF THE RISER. FIRE RISER SHALL HAVE A 2 1/2" VALVE AND HOSE CONNECTION ON THE INTERMEDIATE STAIR LANDING BETWEEN THE FIRST AND SECOND FLOORS.
13. DOUBLE INTERLOCK PRE-ACTION SYSTEM RISER, SERVING THE CHILLER PLANT ELECTRICAL ROOM.
14. NITROGEN GENERATOR SERVING THE PRE-ACTION SYSTEM FOR THE CHILLER PLANT ELECTRICAL ROOM.
15. FIRE DEPARTMENT HOSE CONNECTION AND VALVE. HOSE CONNECTION LOCATED ON INTERMEDIATE FLOOR LANDING.
16. PRE-ACTION SYSTEM CONTROL PANEL.
17. FIRE PROTECTION UP TO MEZZANINE.
18. FIRE PROTECTION DOWN.
19. FLOW SWITCH.
20. GATE VALVE WITH TAMPER SWITCH.
21. THE ELEVATOR ENCLOSURE HAS A 2-HOUR FIRE RATING AND WILL NOT REQUIRE A SPRINKLER SYSTEM TO BE INSTALLED.



KEY PLAN

SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:31:50 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: MLP	CERTIFICATION
CHECKED BY: AES	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


FIRST FLOOR FIRE PROTECTION PLAN

SHEET NUMBER


FP302



1 FP303 SECOND FLOOR FIRE PROTECTION PLAN
Scale: 3/32" = 1'-0"



2 FP303 SECOND FLOOR MEZZANINE 1 FIRE PROTECTION PLAN
Scale: 1/8" = 1'-0"




3 FP303 SECOND FLOOR MEZZANINE 2 FIRE PROTECTION PLAN
Scale: 1/8" = 1'-0"

GENERAL NOTES:

A. SEE DRAWING FP001 FOR ADDTIONAL GENERAL NOTES.

PLAN NOTES CONTINUED:

1. WET-PIPE FIRE PROTECTION SYSTEM SERVING FUEL OIL DAY TANK ROOM AND MAINTENANCE STORAGE ROOM.
2. FIRE PROTECTION RISER UP AND DOWN. FIRE RISER SHALL HAVE A 2 1/2" VALVE AND HOSE CONNECTION ON THE INTERMEDIATE STAIR LANDINGS. FIRE DEPARTMENT HOSE CONNECTION AND VALVE.
3. MDF ROOM SHALL BE PROTECTED WITH A NOVEC-1230 CLEAN AGENT FIRE SUPPRESSION SYSTEM WITH SECONDARY DOUBLE INTERLOCK PRE-ACTION SYSTEM.
4. FIRE PROTECTION UP TO ROOF STANDPIPE HOSE CONNECTION.
5. DOUBLE INTERLOCK PRE-ACTION SYSTEM RISER, SERVING MDF DATA ROOM.
6. DOUBLE INTERLOCK PRE-ACTION SYSTEM RISER, SERVING SWITCHGEAR ROOM, CUP EMERGENCY ELECTRICAL ROOM AES SERVICE SWITCHGEAR ROOM.
7. NITROGEN GENERATOR SERVING THE PRE-ACTION SYSTEM FOR THE ELECTRICAL ROOMS.
8. DOUBLE INTERLOCK PRE-ACTION SYSTEM RISER, SERVING GENERATOR ROOM A, GENERATOR ROOM B AND GENERATOR SWITCHGEAR ROOM.
9. NITROGEN GENERATOR SERVING THE GENERATOR ROOMS.
10. NITROGEN GENERATOR SERVING THE PRE-ACTION SYSTEM FOR MDF ROOM.
11. 650# NOVEC CYLINDER, SECURED TO WALL.
12. NOVEC MANUAL RELEASE.
13. NOVEC DISABLE SWITCH.
14. NOVEC PHOTOELECTRIC SMOKE DETECTOR.
15. NOVEC HORN/STROBE.
16. NOVEC BELL.
17. NOVEC PIPING SYSTEM.
18. NOVEC DISCHARGE NOZZLE.
19. PRE-ACTION SYSTEM CONTROL PANEL.
20. PRE-ACTION SYSTEM SERVING THE GENERATOR CONTROL ROOM.
21. PRE-ACTION SYSTEM PIPING DROP.
22. WET-PIPE FIRE PROTECTION SYSTEM SERVING MAINTENANCE WORKROOM.
23. WET-PIPE FIRE PROTECTION SYSTEM DROP.
24. WET-PIPE FIRE PROTECTION SYSTEM SERVING THE MEZZANINE.
25. WET-PIPE FIRE PROTECTION UP TO ELEVATOR VESTIBULE.
26. 2" FIRE RISER DRAIN UP AND DOWN.
27. FLOOR CONTROL VALVE ASSEMBLY. SEE SPRINKLER SYSTEM FLOOR CONTROL VALVE DETAIL 2/FP501.
28. 6" FIRE WATER STORAGE TANK VENT DOWN.
29. 2" FIRE RISER DRAIN.
30. 2" FIRE RISER DRAIN UP.
31. PRE-ACTION FIRE PROTECTION SYSTEM UP TO EMERGENCY GENERATOR INTAKE MONITOR ROOM 302.
32. 6" FIRE WATER STORAGE TANK VENT UP THRU ROOF.
33. 2 1/2" VALVE AND HOSE CONNECTION ON THE INTERMEDIATE STAIR LANDING BETWEEN THE SECOND FLOOR AND THE ROOF. FIRE DEPARTMENT HOSE CONNECTION AND VALVE.
34. WET-PIPE FIRE PROTECTION SYSTEM UP TO SERVE THE UPPER LEVEL OF THE STAIRS.
35. THE ELEVATOR ENCLOSURE HAS A 2-HOUR FIRE RATING AND WILL NOT REQUIRE A SPRINKLER SYSTEM TO BE INSTALLED.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:31:56 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: MLP	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AES	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR FIRE RPOTECTION PLAN

SHEET NUMBER

FP303



ROOF FIRE PROTECTION PLAN

1 / FP304 Scale: 3/32" = 1'-0"

GENERAL NOTES:

A. SEE DRAWING FP001 FOR ADDTIONAL GENERAL NOTES.

PLAN NOTES:

1. 4" STANDPIPE DOWN.
2. POST INDICATING VALVE.
3. 2 1/2" HOSE CONNECTION AND VALVE.
4. FIRE PROTECTION DOWN.
5. FIRE PROTECTION DRAIN PIPING DOWN.
6. FLOOR CONTROL VALVE ASSEMBLY. SEE SPRINKLER SYSTEM FLOOR CONTROL VALVE DETAIL 1/FP501.
7. FIRE PROTECTION SERVING THE VESTIBULE.
8. FIRE PROTECTION SERVING THE TOP OF THE STAIR TOWER.
9. PRE-ACTION FIRE PROTECTION SYSTEM SERVING THE EMERGENCY GENERATOR INTAKE MONITOR SPACE.
10. PRE-ACTION FIRE PROTECTION SYSTEM DOWN.
11. 6" FIRE WATER STORAGE TANK VENT THRU ROOF. INSTALL INSECT SCREEN ON VENT OPENING.
12. THE ELEVATOR AND ELEVATOR EQUIPMENT ROOM ENCLOSURE HAS A 2-HOUR FIRE RATING AND WILL NOT REQUIRE A SPRINKLER SYSTEM TO BE INSTALLED.

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:31:57 PM AES| Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: MLP	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AES	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF FIRE PROTECTION PLAN

SHEET NUMBER

FP304



1 FP401 **01-First-FirePro-New - Callout 1**
Scale: 1/4" = 1'-0"

GENERAL NOTES:

A. SEE DRAWING FP001 FOR ADDITIONAL GENERAL NOTES.

(#) PLAN NOTES:

1. FIRE WATER STORAGE TANK ACCESS DOOR.
2. WALL MOUNTED FIRE DEPARTMENT CONNECTION.
3. WALL MOUNTED FIRE PUMP TEST HEADER.
4. 8" FIRE PROTECTION WATER TANK VENT. TURN VENT DOWN AND TERMINATE 2'-6" ABOVE FINISHED GRADE WITH AN INSECT SCREEN.
5. FIRE PUMP (FP-2) CONTROL PANEL. SEE "E" SERIES DRAWINGS FOR INFORMATION ON CONTROL PANEL.
6. JOCKEY PUMP CONTROL PANELS. SEE "E" SERIES DRAWINGS FOR INFORMATION ON CONTROL PANEL.
7. FIRE PUMP (FP-1) CONTROL PANEL. SEE "E" SERIES DRAWINGS FOR INFORMATION ON CONTROL PANEL.
8. 10" FIRE PROTECTION TO SERVE THE SOUTH SERVICE BUILDING AND THE MEDICAL CENTER BUILDING.
9. 10" WATER DROP TO FIRE PROTECTION WATER STORAGE TANK.
10. 6" FIRE WATER STORAGE TANK VENT DOWN.
11. FIRE PROTECTION PIPING SERVING THE FIRST FLOOR.
12. FIRE PROTECTION PIPING SERVING ALL OTHER FLOORS AND THE STANDPIPE SYSTEM.
13. 4" HIGH CONCRETE HOUSE KEEPING PAD.
14. 2'-0" HIGH CONCRETE BASE.
15. SEE FIRE RISER PIPING DIAGRAM ON DRAWING FP701.
16. SEE FIRE RISER DIAGRAM 3/FP501.
17. 10" FIRE WATER SERVICE.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: MLP	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AES	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ENLARGED FIRE PROTECTION PLANS


SHEET NUMBER

FP401


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:31:59 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

FIRE PROTECTION EQUIPMENT SCHEDULE


MARK	EQUIPMENT	LOCATION	CAPACITY	MANUFACTURER AND MODEL NUMBER	ELECTRICAL LOADS						REMARKS
					HP	WATTS	VOLTS	AMPS	PHASE	RPM	
FP-1	FIRE PUMP - VERTICAL TURBINE	FIRE PUMP ROOM - 108	1000 GPM AT 295 PSI	APEX PUMPING EQUIPMENT MODEL No. FP12CHC	250		460		3	1770	BRONZE FITTED VERTICAL TURBINE FIRE PUMP
FP-2	FIRE PUMP - HORIZONTAL SPLIT CASE	FIRE PUMP ROOM - 108	1000 GPM AT 245 PSI	ARMSTRONG MODEL No. HSC 6 x 5 x 12MF	350		460		3	3600	BRONZE FITTED SPLIT CASE PUMP WITH PACKING, STEEL BASE, COUPLING, GUARD
JP-1	JOCKEY PUMP	FIRE PUMP ROOM - 108	10 GPM AT 305 PSI	ARMSTRONG MODEL No. 4700-VMS-01:29B	3		460		3	3450	BRONZE FITTED SPLIT PUMP WITH MECHANICAL PACKING, S.S. SHAFT, O.D.P. CLOSE COUPLED MOTOR AND AROSS THE LINE CONTROLLER
JP-2	JOCKEY PUMP	FIRE PUMP ROOM - 108	10 GPM AT 305 PSI	ARMSTRONG MODEL No. 4700-VMS-01:29B	3		460		3	3450	BRONZE FITTED SPLIT PUMP WITH MECHANICAL PACKING, S.S. SHAFT, O.D.P. CLOSE COUPLED MOTOR AND AROSS THE LINE CONTROLLER
DCVA-1	DOUBLE CHECK VALVE ASSEMBLY	CHILLER PLANT ROOM - 114	1000 GPM @ 2.5 PSI DROP	WILKENS MODEL No. 10" - 350-FSC-OSY	–	–	–	–	–	–	INSTALL BACKFLOW PREVENTER AT 3'-0" A.F.F.
DCVA-2	DOUBLE CHECK VALVE ASSEMBLY	CHILLER PLANT ROOM - 114	1000 GPM @ 2.5 PSI DROP	WILKENS MODEL No. 10" - 350-FSC-OSY	–	–	–	–	–	–	INSTALL BACKFLOW PREVENTER AT 3'-0" A.F.F.
NG-1	NITROGEN GENERATOR	BOILER PLANT ROOM 109	–	ENGINEERED CORROSION SOLUTIONS MODEL No. PGEN -3(3E)	–	–	120	6	1	–	SERVING THE PRE-ACTION FIRE PROTECTION SYSTEM IN THE CHILLER PLAT ELECTRICAL ROOM 113
NG-2	NITROGEN GENERATOR	MECHANICAL ROOM 224	–	ENGINEERED CORROSION SOLUTIONS MODEL No. PGEN -5(5E)	–	–	120	6	1	–	SERVING THE PRE-ACTION FIRE PROTECTION SYSTEM IN GENERATOR CONTROL ROOM 208, GENERATOR SWITCHGEAR ROOM 210, CONTROL ROOM 211, GENERATOR ROOM A 220, GENERATOR ROOM B 218, GENERATOR EXHAUST PLENUM1 ROOM 221, AND GENERATOR EXHAUST PLENUM 2 ROOM 219
NG-3	NITROGEN GENERATOR	MECHANICAL ROOM 206	–	ENGINEERED CORROSION SOLUTIONS MODEL No. PGEN -3(3E)	–	–	120	6	1	–	SERVING THE PRE-ACTION FIRE PROTECTION SYSTEM IN 15KW SWITCHGEAR ROOM 212, CUP EMERGENCY ELECTRICAL ROOM 215, AND AES SERVICE SWITCHGEAR ROOM 216
NG-4	NITROGEN GENERATOR	MECHANICAL ROOM 224	–	ENGINEERED CORROSION SOLUTIONS MODEL No. PGEN -3(3E)	–	–	120	6	1	–	SERVING THE PRE-ACTION FIRE PROTECTION SYSTEM IN THE MDF DATA ROOM 225
CACP-1	CLEAN AGENT CONTROL PANEL	MECHANICAL ROOM 224	–	CHEETAH Xi 50 CONTROL PANEL	–	–	120	5.25	1	–	SERVING THE CLEAN AGENT FIRE PROTECTION SYSTEM IN THE MDF DATA ROOM 225




5 FP501 **FIRE PROTECTION PIPE HANGER 8 INCH AND LARGER DETAIL**
Scale: NONE




3 FP501 **FIRE RISER DIAGRAM**
Scale: None



6 FP501 **PIPE SLEEVE DETAIL**
Scale: NONE



4 FP501 **FIRE PROTECTION PIPE HANGER 6 INCH AND SMALLER DETAIL**
Scale: NONE



2 FP501 **SPRINKLER SYSTEM FLOOR CONTROL VALVE DETAIL**
Scale: None

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:32:00 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: MLP	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AES	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRE PROTECTION SCHEDULES AND DETAILS

SHEET NUMBER

FP501



1 FP701 **FIRE RISER PIPING DIAGRAM**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 1:32:00 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: MLP	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AES	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRE PROTECTION DIAGRAMS

SHEET NUMBER

FP701

NOTE: ALL SYMBOL DESCRIPTIONS ARE SUBJECT TO MODIFICATION ON THE DRAWINGS. ALL SYMBOLS NOT NECESSARILY USED ON THIS PROJECT.

RACEWAY SYMBOLS:

- CONDUIT
- CONDUIT CONCEALED UNDER FLOOR OR BELOW GRADE
- UNDERGROUND CONDUIT STUBBED OUT 5'-0" FROM BUILDING OR WALKWAY LINE, CAPPED AND MARKED
- (2) PHASE CONDUCTORS, (2) NEUTRAL CONDUCTORS, (1) GROUND; B#5,7 — HOME RUN TO PANEL "B" FOR CIRCUITS #5 & 7 WITH NEUTRAL AND GROUND
- CONDUIT UP/DOWN
- JUNCTION BOX CONCEALED ABOVE ACCESSIBLE CEILING AREA

RECEPTACLE SYMBOLS:

- 20 AMP DUPLEX GROUNDING RECEPTACLE +20" AFF UNLESS OTHERWISE NOTED
- 20 AMP DUPLEX GROUNDING RECEPTACLE, EMERGENCY POWER
- 20 AMP DUPLEX GROUNDING RECEPTACLE, SPLIT WIRED
- 20 AMP DUPLEX GROUNDING RECEPTACLE, GROUND FAULT INTERRUPTING CIRCUIT
- 20 AMP DUPLEX GROUNDING RECEPTACLE, EMERGENCY POWER, GROUND FAULT INTERRUPTING CIRCUIT
- 20 AMP DOUBLE DUPLEX GROUNDING RECEPTACLE IN TWO GANG OUTLET BOX
- 20 AMP DOUBLE DUPLEX GROUNDING RECEPTACLE, EMERGENCY POWER
- 20 AMP DOUBLE DUPLEX GROUNDING RECEPTACLE, GROUND FAULT INTERRUPTING CIRCUIT
- 20 AMP DOUBLE DUPLEX GROUNDING RECEPTACLE, EMERGENCY POWER, GROUND FAULT INTERRUPTING CIRCUIT
- SPECIAL RECEPTACLE. SEE DRAWING FOR NEMA TYPE
- SPECIAL RECEPTACLE. SEE DRAWING FOR NEMA TYPE
- FLOOR DUPLEX RECEPTACLE OUTLET. SEE DRAWING FOR TYPE
- CEILING DUPLEX RECEPTACLE OUTLET. SEE DRAWING FOR TYPE
- SURFACE MULTI-OUTLET RACEWAY WITH RECEPTACLES 24" ON CENTER UNLESS OTHERWISE NOTED

LIGHTING CONTROL SYMBOLS:

- $\$^{3}_{4}$ — 20 AMP POLE TOGGLE SWITCH 48" AFF. INSTALL MULTIPLE SWITCHES UNDER COMMON COVER PLATE. SUBSCRIPT AT SWITCH SYMBOL INDICATES THE FOLLOWING:
  TOP: 2 - DOUBLE POLE, 3 - THREE WAY, D - DIMMER, LV - LOW-VOLTAGE PUSH BUTTON TYPE TOGGLE SWITCH; 4 - FOUR WAY, P - PILOT LIGHT, LC - LIGHT CONTROLLER; M - MOMENTARY, K - KEY OPERATED, BLANK - SINGLE POLE
  BOTTOM: a,b,c,d, ETC. - IDENTIFICATION OF CONTROLLED DEVICE
- OCCUPANCY SENSOR SWITCH, CEILING MOUNTED
- OCCUPANCY SENSOR SWITCH, WALL MOUNTED
- DAYLIGHT SENSOR SWITCH, CEILING MOUNTED
- DAYLIGHT SENSOR SWITCH, WALL MOUNTED
- RC — LIGHTING ROOM CONTROLLER
- R — LIGHTING ISOLATED RELAY

POWER/MOTOR CONTROL SYMBOLS:

- PANELBOARD OR EQUIPMENT CABINET AS INDICATED
- MOTOR, NUMBER INDICATES HP
- $\$^{T}_{P}$ — MANUAL MOTOR STARTER WITH THERMAL OVERLOADS AND PILOT LIGHT, 48" AFF
- SAFETY (DISCONNECT) SWITCH, INSTALL AT 60" AFF. "F" INDICATES FUSE SIZE, BLANK INDICATES NON-FUSED, "X" INDICATES AMPERAGE RATING
- COMBINATION STARTER: SEE SCHEDULE.

LIGHTING SYMBOLS:

- a/b; F# — LIGHTING FIXTURE, "a/b" INDICATES SWITCHING, "F#" INDICATES TYPE
- LIGHTING FIXTURE WITH LAMPS ON NORMAL AND EMERGENCY CIRCUIT, PROVIDE SEPARATE EMERGENCY LAMP BALLASTS AS SPECIFIED
- ALWAYS ON NIGHT LIGHT
- a/F# — ROUND LIGHTING FIXTURE, "a" INDICATES SWITCHING, "F#" INDICATES TYPE
- a/F# — WALL MOUNTED LIGHTING FIXTURE, "a" INDICATES SWITCHING, "F#" INDICATES TYPE
- SINGLE ARM LIGHTING STANDARD, POLE MOUNTED LUMINAIRE AND POLE SUPPORT BASE
- DOUBLE ARM LIGHTING STANDARD, POLE MOUNTED LUMINAIRE AND POLE SUPPORT BASE
- LIGHTING FIXTURE ON LIGHTING TRACK, CEILING MOUNTED
- SINGLE FACE EXIT SIGN. ARROW INDICATES DIRECTIONAL ARROW ON EXIT SIGN FACE
- EXIT SIGN, WALL MOUNTED 8'-0" AFF UNLESS OTHERWISE NOTED
- EMERGENCY BATTERY UNIT WITH TWO HEADS, WALL MOUNTED 8'-0" AFF UNLESS OTHERWISE NOTED

FIRE ALARM SYMBOLS:

- FACP — FIRE ALARM CONTROL PANEL
- FAAP — FIRE ALARM ANNUNCIATOR PANEL
- NAC — NOTIFICATION ALARM CIRCUIT
- F — FIRE ALARM MANUAL PULL STATION, 48" AFF
- F — FIRE ALARM MANUAL PULL STATION, AUDIO-VISUAL INDICATING DEVICE CENTERED ABOVE THE PULL STATION, 48" AFF AND +80" AFF; LIGHT OUTPUT 75 cd UNLESS OTHERWISE NOTED
- V — FIRE ALARM VISUAL ONLY INDICATING DEVICE, +80" AFF; LIGHT OUTPUT 75 cd UNLESS OTHERWISE NOTED
- CEILING: AV — WALL: AV — FIRE ALARM AUDIO/VISUAL INDICATING DEVICE, WALL MOUNT +80" AFF; LIGHT OUTPUT 75 cd UNLESS OTHERWISE NOTED
- V — V — FIRE ALARM VISUAL ONLY INDICATING DEVICE, WALL MOUNT +80" AFF; LIGHT OUTPUT 75 cd UNLESS OTHERWISE NOTED
- A — A — FIRE ALARM AUDIO HORN INDICATING DEVICE, WALL MOUNT +80" AFF
- BELL
- SD — AREA SMOKE DETECTOR
- HD — AREA HEAT DETECTOR
- FS — FLOW SWITCH, FIRE ALARM
- TS — TAMPER SWITCH, FIRE ALARM
- DS — DOOR SWITCH, FIRE ALARM
- AS — AIR DUCT SMOKE DETECTOR MOUNTED ON AIR DUCT
- LA — LOW AIR
- PS — PRESSURE SWITCH
- DOOR HOLD

TELECOMMUNICATION SYMBOLS:

- X — DATA OUTLET IN TWO GANG BOX WITH SINGLE GANG OPENING, "X" INDICATES NUMBER OF DATA JACKS
- X — FLOOR OUTLET, DATA OUTLET CONSISTS OF (2) DATA OUTLETS UNLESS OTHERWISE NOTED, EACH ALPHA CHARACTER "X" INDICATES NUMBER OF UNIQUE DATA JACKS
- AC-X — CEILING MOUNTED OUTLET, DATA OUTLET CONSISTS OF (2) DATA OUTLETS, UNLESS OTHERWISE NOTED, EACH ALPHA CHARACTER "X" INDICATES NUMBER OF UNIQUE DATA JACKS
- AP-X — CEILING MOUNTED WIRELESS ACCESS POINT OUTLET, DATA OUTLET CONSISTS OF (2) DATA OUTLETS, UNLESS OTHERWISE NOTED, EACH ALPHA CHARACTER "X" INDICATES NUMBER OF UNIQUE DATA JACKS
- SURFACE DATA/TELECOM RACEWAY
- S — CEILING MOUNTED SPEAKER
- S — PAGING HORN TYPE SPEAKER
- TV — TELEVISION/VIDEO OUTLET IN TWO GANG BOX WITH SINGLE GANG OPENING

SECURITY/ACCESS CONTROL SYMBOLS

- CR — CARD READER, WALL MOUNT +48" AFF
- KP — KEYPAD
- PB — PANIC BUTTON
- RX — REQUEST TO EXIT
- DS — DOOR STATUS
- ES — ELECTRIC STRIKE
- ML — MAG LOCK
- AA — AUDIBLE ALARM
- VI — VIDEO INTERCOM DOOR STATION
- VS — VIDEO INTERCOM MASTER STATION

DIAGRAM SYMBOLS:

- GROUND ROD (SINGLE LINE DIAGRAM)
- GROUND ROD (PLAN DRAWING)
- LIGHTNING ROD
- EXOTHERMIC WELDED CONNECTION.
- T — TRANSFORMER, 480V PRIMARY, 120/208 VOLT SECONDARY, 3 PHASE, 4 WIRE UNLESS OTHERWISE NOTED
- CURRENT & VOLTAGE TRANSFORMERS AS REQUIRED (REFER TO SPECIFICATIONS)
- AM — AMMETER, (REFER TO SPECIFICATIONS)
- VM — VOLTMETER, (REFER TO SPECIFICATIONS)
- FUSE
- 30A 3P — CIRCUIT BREAKER (C.B.)
- PUSHBUTTON, NORMALLY OPEN
- PUSHBUTTON, NORMALLY CLOSED
- LEVEL SWITCH, NORMALLY OPEN
- LEVEL SWITCH, NORMALLY CLOSED
- LIMIT SWITCH, NORMALLY OPEN
- LIMIT SWITCH, NORMALLY OPEN
- PRESSURE SWITCH, NORMALLY OPEN
- PRESSURE SWITCH, NORMALLY CLOSED
- FLOW SWITCH, NORMALLY OPEN
- FLOW SWITCH, NORMALLY CLOSED
- ON-DELAY TIMING CONTACT, NORMALLY OPEN
- ON-DELAY TIMING CONTACT, NORMALLY CLOSED
- OFF-DELAY TIMING CONTACT, NORMALLY OPEN
- OFF-DELAY TIMING CONTACT, NORMALLY CLOSED
- TEMPERATURE SWITCH, NORMALLY OPEN
- TEMPERATURE SWITCH, NORMALLY CLOSED
- RELAY CONTACT, NORMALLY OPEN
- RELAY CONTACT, NORMALLY CLOSED
- SOLENOID VALVE (WIRING DIAGRAM)
- R — PUSH-TO-TEST PILOT LIGHT
- XXXX / XXXX; X / X — 2-POSITION SELECTOR SWITCH
- OFF; HAND / AUTO; X / X — 3-POSITION SELECTOR SWITCH
- TERMINAL BLOCK
- CONTROL TRANSFORMER
- CONTROL TRANSFORMER

GENERAL SYMBOLS:

- NEW
- EXISTING
- DEMOLITION
- FUTURE
- POINT OF CONNECTION
- POINT OF REMOVAL
- # — PLAN NOTE
- # — DEMOLITION NOTE
- X / X — DETAIL OR SECTION MARKER

ELECTRICAL ABBREVIATIONS:

#/C	MULTI-CONDUCTOR CABLE
1/C	SINGLE CONDUCTOR CABLE
20AF	20 AMP FUSES
3P	3 POLE
A, AMP	AMPERE
ACCU	AIR COOLED CONDENSING UNIT
AFF	ABOVE FINISHED FLOOR. MOUNTING HEIGHTS FROM FINISHED FLOOR TO TOP OF BOX.
AHU	AIR HANDLING UNIT
CH	CABINET HEATER
E	EXISTING EQUIPMENT TO BE REUSED
EF	EXHAUST FAN
FCU	FAN COIL UNIT
GFI	GROUND FAULT INTERRUPTER
GND	GROUND
HP	HORSEPOWER
IG	ISOLATED GROUND
KVA	KILOVOLT AMPERES
KW	KILOWATT
NL	NIGHT LIGHT ON UNSWITCHED CIRCUIT
OL	OVERLOAD
PROVIDE	FURNISH, INSTALL AND CONNECT.
RTU	ROOF TOP UNIT
UH	UNIT HEATER
UON	UNLESS OTHERWISE NOTED
V	VOLTS
WC	WATER COOLER
WG	WIRE GUARD
WP	WEATHERPROOF

GENERAL FIRE ALARM NOTES:

1. MANUAL PULL STATIONS AT EXIT DOORS SHALL BE INSTALLED WITHIN 5'-0" OF THE DOOR. OPERABLE PART OF EACH MANUAL PULL STATION SHALL BE INSTALLED BETWEEN 42" AND 48" ABOVE FINISHED FLOOR TO MEET ADA REQUIREMENTS.
2. FIRE RATED DOORS WITH HOLDS SHALL RELEASE UPON AN ALARM FROM SMOKE DETECTOR ON EITHER SIDE OF THE DOOR, OR OTHER ALARM INITIATION.
3. SMOKE DETECTOR SHALL BE INSTALLED 5'-0" OR LESS IN FRONT OF FACP AND CENTER OF THE DOORS WHICH CONTAIN HOLDERS.
4. SMOKE DETECTORS SHALL NOT BE INSTALLED WITHIN 3'-0" OF AN AIR DIFFUSER OR RETURN GRILL.
5. SMOKE DETECTORS IN ELEVATOR LOBBIES MUST BE INSTALLED WITHIN 21'-0" OF THE CENTERLINE OF THE ELEVATOR.
6. FIRE ALARM DESIGN SHALL CONTAIN NO MORE THAN 70% LOAD ON EACH PANEL AND LOOP LEAVING 30% AVAILABLE FOR FUTURE CAPACITY PER CIRCUIT.
7. CONTRACTOR MAY UTILIZE OPEN FIRE ALARM CABLING OR ARMORED FIRE ALARM CABLING WHEN INSTALLING CONDUCTORS ABOVE ACCESSIBLE CEILINGS AND BEHIND ACCESSIBLE CHASES. FIRE ALARM CABLING SHALL BE INSTALLED IN RACEWAY ABOVE INACCESSIBLE CEILINGS AND BEHIND INACCESSIBLE CHASES AND WALLS. IN ALL OPEN PUBLIC SPACES, FIRE ALARM CABLING SHALL BE INSTALLED IN RACEWAY (SURFACE RACEWAY) AND RACEWAY SHALL BE PAINTED TO MATCH WALLS/CEILING SURFACE ON WHICH THE RACEWAY IS INSTALLED.
8. OPEN FIRE ALARM CABLING NOT INSTALLED IN RACEWAY SHALL BE PLENUM RATED, NO EXCEPTION.
9. CONTRACTOR SHALL ADJUST DEVICE LOCATIONS BY UP TO 30" FROM WHAT IS SHOWN TO AVOID OBSTRUCTIONS.
10. CONTRACTOR SHALL PROVIDE "SURFACE MOUNT ADAPTER SKIRTS" FOR ALL SURFACE MOUNTED DEVICES. "SKIRTS" ARE NOT REQUIRED FOR SURFACE MOUNTED DEVICES INSTALLED IN MECHANICAL OR ELECTRICAL ROOMS.

GENERAL ELECTRICAL NOTES:

1. ALL WORK SHOWN IS NEW AND BY THE ELECTRICAL TRADES, UNLESS OTHERWISE NOTED.
2. ALL ELECTRICAL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70-2020).
3. ALL FIRE ALARM WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF NATIONAL FIRE ALARM CODE (NFPA 72) AS ADOPTED BY THE STATE INCLUDING ALL AMENDMENTS.
4. THIS CONTRACTOR SHALL REVIEW THE COMPLETE SET OF DRAWINGS AND SPECIFICATIONS AND INCLUDE WORK FROM OTHER DIVISIONS THAT AFFECT HIS WORK IN HIS BID.
5. EACH CONTRACTOR SHALL FIELD VERIFY ALL EXISTING APPLICABLE CONDITIONS AND DIMENSIONS SHOWN ON THE DRAWINGS, AS PERTAINS TO THE INTENT OF THESE DRAWINGS. CONTRACTOR SHALL BRING TO THE ATTENTION OF THE ENGINEER AND DESIGNER ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF ANY WORK AFFECTED BY OR RELATED TO SUCH DISCREPANCY. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH OR CAUSED BY THAT CONTRACTOR'S FAILURE TO COMPLY WITH THIS REQUIREMENT.
6. UNLESS OTHERWISE NOTED ON THE DRAWINGS, ALL CUTTING AND PATCHING REQUIRED FOR THE ELECTRICAL, SECURITY, AND FIRE ALARM INSTALLATION SHALL BE PERFORMED BY THE APPROPRIATE TRADE AND PAID FOR BY THIS CONTRACTOR. ALL CUTTING AND PATCHING SHALL BE IN ACCORDANCE WITH THE APPLICABLE ARCHITECTURAL DETAILS/NOTES.
7. ALL FIRESTOPPING SHALL BE PROVIDED UNDER DIVISION 26050 3.2, "FIRESTOPPING", AND BY DIVISION 7 SPECIFICATIONS.
8. VERIFY EXACT LOCATION OF OUTLETS ABOVE COUNTERS, IN CASEWORK OR EQUIPMENT PRIOR TO ROUGH IN.
9. COORDINATE INSTALLATION OF DEVICES AND WIRING WITH LIGHTING, HVAC, PIPING, AND STRUCTURAL MEMBERS.
10. GFCI CIRCUIT SHALL BE INSTALLED SUCH THAT GFCI RECEPTACLE SHALL ONLY TRIP ITSELF AND DOES NOT TRIP OR DISCONNECT POWER ON ANY OTHER RECEPTACLE.
11. LOW-VOLTAGE CONDUIT SHALL NOT CONTAIN MORE THAN 270° IN BENDS BETWEEN FLOOR BOXES, PROJECTOR BOXES, CAMERA BOXES, A/V EQUIPMENT RACKS, FIRE ALARM DEVICE BOXES, FIRE ALARM PANELS, SECURITY DEVICE BOXES, AND SECURITY PANELS. PROVIDE PULL BOXES IN RACEWAYS THAT CONTAIN MORE THAN 270° IN BENDS. PROVIDE A MINIMUM OF ONE (1) PULL BOX FOR EVERY 100 FEET OF RACEWAY.
12. CONTRACTOR SHALL PROVIDE MINIMUM 200 LB TENSION PULL STRING IN ALL EMPTY/FUTURE USE RACEWAYS.
13. ALL CONDUIT ROUTED IN AND THROUGH CONCRETE AND/OR BUILDING STRUCTURAL WALLS SHALL BE RIGID METAL CONDUIT, UNLESS OTHERWISE NOTED.
14. WHEN NEW WALL AND FLOOR FINISHES ARE SHOWN, REMOVE ALL COVERPLATES AND REINSTALL AFTER NEW FINISHES HAVE BEEN COMPLETED.
15. ALL CONDUIT AND DEVICES SHALL BE PROVIDED WITH OWNER APPROVED HANGERS CONFORMING TO STANDARDS OUTLINED. IN GENERAL ALL HANGERS SHALL BE ANCHORED FROM THE SIDE OF THE STRUCTURE AND NOT FROM THE BOTTOM.
16. TURN OVER ALL KEYS TO OWNER AT COMPLETION OF PROJECT.
17. FIRE STOP ALL WALL AND FLOOR PENETRATIONS WHETHER SURFACE IS RATED OR NOT.
18. DEVICE LOCATIONS AND RACEWAY ROUTING SHOWN IS DIAGRAMMATIC. CONTRACTOR SHALL VERIFY ALL CONDITIONS PRIOR TO STARTING CONSTRUCTION.

XXXX
- NUMBER: 1,2,3, ETC.
- VOLTAGE: L-208/120V, H-480/277V
- CRITICALITY: N-NORMAL POWER, UPS - UNINTERUPABLE POWER SUPPLY
- FLOOR: T-TUNNEL, B-BASEMENT, 1-FIRST FLOOR, 2-SECOND FLOOR, R-ROOF

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL SYMBOLS AND ABBREVIATIONS

SHEET NUMBER

E001

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:19:47 PM AESI Proj. No: 21-154



GENERAL NOTES:


1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE NOTED.
4. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. SEE STAIRS #1 CROSS SHEET E501.

LOWER LEVEL LIGHTING PLAN- AREA A

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:27:31 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

LOWER LEVEL LIGHTING PLAN - AREA A

SHEET NUMBER

EL301





LOWER LEVEL PHOTOMETRIC PLAN AREA-A

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:27:32 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

LOWER LEVEL PHOTOMETRIC PLAN - AREA A

SHEET NUMBER

EL301LT



GENERAL NOTES:


1. GENERAL NOTES FOR INDIVIDUAL SHEETS.
2. NEXT LINE OF NOTES HAVE NO SPACING BETWEEN LINES.

(#) PLAN NOTES:

1. PLAN NOTES FOR INDIVIDUAL SHEETS.
2. NEXT LINE OF NOTES HAVE NO SPACING BETWEEN LINES.

LOWER LEVEL LIGHTING PLAN- AREA D

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE


LOWER LEVEL LIGHTING PLAN - AREA D

SHEET NUMBER

EL303

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:27:34 PM AESI Proj. No: 21-154




FIRST FLOOR LIGHTING PLAN - AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE 4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 15'-0" AFF.
2. INSTALL LIGHT FIXTURE SHOWN THIS LOCATION ON TWO DIFFRENT LANDING.
3. SEE STAIRS #1 CROSS SHEET ES01.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION
CHECKED BY: MB	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR LIGHTING PLAN - AREA A

SHEET NUMBER

EL304

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:27:39 PM AESI Proj No: 21-154



FISRT FLOOR PHOTOMETRIC PLAN AREA-A

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:27:40 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PHOTOMETRIC PLAN - AREA A

SHEET NUMBER

EL304LT



FIRST FLOOR LIGHTING PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE NOTED.
4. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
5. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
6. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
7. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
8. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
9. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 15'-0" AFF, TYPICAL.
2. COORDINATE SWITCH LOCATION WITH PLACEMENT OF DOOR.
3. LIGHT FIXTURE WILL BE HANGING OFF A PICCE OF UNISTRUT MOUNTED IN TRAPEZE.
4. SEE ONE LINE DIAGRAM AT SHEET EP708.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:27:49 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DAG	CERTIFICATION
CHECKED BY: MB	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR LIGHTING PLAN - AREA B

SHEET NUMBER

EL305



FISRT FLOOR PHOTOMETRIC PLAN AREA-B

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:27:50 PM AESI Proj. No.: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ESL-SPECTRUM	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PHOTOMETRIC PLAN - AREA B

SHEET NUMBER

EL305LT




FIRST FLOOR LIGHTING PLAN - AREA C
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 15'-0" AFF, TYPICAL.
2. LIGHT FIXTURE SHALL BE MOUNTED AT 9'-0" AFF.
3. INSTALL LIGHT FIXTURE SHOWN THIS LOCATION ON TWO DIFFRENT LANDING.
4. SEE STAIRS #2 CROSS SHEET E501.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR LIGHTING PLAN - AREA C

SHEET NUMBER

EL306

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:27:59 PM AESI Proj. No.: 21-154
0 1/2" 1" 2"



FISRT FLOOR PHOTOMETRIC PLAN AREA-C

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:00 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PHOTOMETRIC PLAN - AREA C

SHEET NUMBER

EL306LT



FIRST FLOOR LIGHTING PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURE SHALL BE MOUNTED AT 9'-0" AFF.
2. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 15'-0" AFF.
3. ADD SWITCH SOR SERVICE YARD.



KEY PLAN

SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE


FIRST FLOOR LIGHTING PLAN - AREA D

SHEET NUMBER

EL307

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:04 PM AESI Proj. No: 21-154

0 1/2" 1" 2"



FISRT FLOOR PHOTOMETRIC PLAN AREA-D
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:05 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PHOTOMETRIC PLAN - AREA D

SHEET NUMBER

EL307LT



FIRST FLOOR LIGHTING PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE 4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 15'-0" AFF.
2. LIGHT FIXTURE SHALL BE MOUNTED AT 9'-0" AFF.
3. LIGHT FIXTURE WILL BE HANGING OFF A PICCE OF UNISTRUT MOUNTED IN TRAPEZE.



KEY PLAN
SCALE: NONE

OWNER
Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT
Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS


NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE
FIRST FLOOR LIGHTING PLAN - AREA E

SHEET NUMBER
EL308

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:09 PM AESI Proj. No: 21-154



FISRT FLOOR PHOTOMETRIC PLAN AREA-E

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:11 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PHOTOMETRIC PLAN - AREA E

SHEET NUMBER

EL308LT



GENERAL NOTES:


1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 15'-0" AFF.
2. LIGHT FIXTURE WILL BE HANGING OFF A PICCE OF UNISTRUT MOUNTED IN TRAPEZE.

FIRST FLOOR LIGHTING PLAN - AREA F

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR LIGHTING PLAN - AREA F

SHEET NUMBER

EL309

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:14 PM AESI Proj. No.: 21-154



FISRT FLOOR PHOTOMETRIC PLAN AREA-F

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:15 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PHOTOMETRIC PLAN - AREA F

SHEET NUMBER

EL309LT



GENERAL NOTES:


1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE NOTED.
4. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
5. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
6. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
7. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
8. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
9. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURE SHALL BE MOUNTED AT 9'-0" AFF.
2. ADD SWITCH FOR SERVICE YARD.

FIRST FLOOR LIGHTING PLAN - AREA G

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR LIGHTING PLAN - AREA G

SHEET NUMBER

EL310

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:17 PM AESI Proj No: 21-154



FISRT FLOOR PHOTOMETRIC PLAN AREA-G

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:18 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR PHOTOMETRIC PLAN - AREA G

SHEET NUMBER


EL310LT

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.


(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 10'-0" AFF.
2. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 8'-0" AFF.
3. INSTALL LIGHT FIXTURE SHOWN THIS LOCATION ON TWO DIFFRENT LANDING.
4. SEE STAIRS #1 CROSS SHEET E501.



SECOND FLOOR LIGHTING PLAN - AREA A

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR LIGHTING PLAN - AREA A

SHEET NUMBER

EL311

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:25 PM AESI Proj. No: 21-154



SECOND FLOOR PHOTOMETRIC PLAN AREA-A

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:27 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PHOTOMETRIC PLAN - AREA A

SHEET NUMBER

EL311LT



SECOND FLOOR LIGHTING PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE 4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 10'-0" AFF.
2. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 8'-0" AFF.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:40 PM AESI Proj. No.: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR LIGHTING PLAN - AREA B

SHEET NUMBER

EL312



SECOND FLOOR PHOTOMETRIC PLAN AREA-B

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:42 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PHOTOMETRIC PLAN - AREA B

SHEET NUMBER

EL312LT



SECOND FLOOR LIGHTING PLAN - AREA C


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 10'-0" AFF.
2. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 8'-0" AFF.
3. INSTALL LIGHT FIXTURE SHOWN THIS LOCATION ON TWO DIFFRENT LANDING.
4. SEE STAIRS #2 CROSS SHEET E501.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
87?0 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR LIGHTING PLAN - AREA C

SHEET NUMBER

EL313

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:47 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



SECOND FLOOR PHOTOMETRIC PLAN AREA-C

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:28:49 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PHOTOMETRIC PLAN - AREA C

SHEET NUMBER

EL313LT



SECOND FLOOR LIGHTING PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.
11.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 10'-0" AFF.
2. LIGHT FIXTURE WILL BE HANGING OFF A PICCE OF UNISTRUT MOUNTED IN TRAPEZE



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100, Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR LIGHTING PLAN - AREA D

SHEET NUMBER

EL314

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:29:00 PM AESI Proj. No.: 21-154



SECOND FLOOR PHOTOMETRIC PLAN AREA-D

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:29:00 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PHOTOMETRIC PLAN - AREA D

SHEET NUMBER

EL314LT



SECOND FLOOR LIGHTING PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE NOTED.
4. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
5. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
6. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
7. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
8. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
9. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.
10.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 10'-0" AFF.
2. NOT USED.
3. SEE HOMRUNS CONTINUE AT SHEET EL 316.
4. SEE HOMRUNS CONTINUE AT SHEET EL 314.
5. SEE HOMRUNS CONTINUE AT SHEET EL 312.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:29:04 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR LIGHTING PLAN - AREA E

SHEET NUMBER

EL315



SECOND FLOOR PHOTOMETRIC PLAN AREA-E

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:29:05 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PHOTOMETRIC PLAN - AREA E

SHEET NUMBER

EL315LT



SECOND FLOOR LIGHTING PLAN - AREA F


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 10'-0" AFF.
2. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 8'-0" AFF.
3. SEE ONE LINE DIAGRAM AT SHEET EP708.
4. LIGHTING INVERTER WITH 480/277 V ,20KVA FOR EMERGENCY LIGHTING PANELS 1LSUPSH1 AND 2LSUPSH1.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE


SECOND FLOOR LIGHTING PLAN - AREA F

SHEET NUMBER

EL316

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:29:09 PM AESI Proj. No: 21-154



SECOND FLOOR PHOTOMETRIC PLAN AREA-F

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:29:10 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR PHOTOMETRIC PLAN - AREA F

SHEET NUMBER

EL316LT




ROOF LIGHTING PLAN - AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE NOTED.
4. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
5. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
6. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
7. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
8. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. COORDINATE SWITCH LOCATION WITH PLACEMENT OF DOOR.
2. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 16'-0" AFF.
3. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 9'-0" AFF.
4. SEE STAIRS #1 CROSS SHEET ES01.
5. COORDINATE SWITCH LOCATION WITH PLACEMENT OF DOOR FOR OUT DOOR LIGHTING.
6. COORDINATE SWITCH LOCATION WITH PLACEMENT OF DOOR , AND PROVIDE 4 HOURS TIMER FOR POLE LIGHT FIXTURES.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF LIGHTING PLAN - AREA A

SHEET NUMBER

EL317

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:29:14 PM AESI Proj. No: 21-154



ROOF PHOTOMETRIC PLAN AREA-A

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:30:02 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF PHOTOMETRIC PLAN - AREA A

SHEET NUMBER

EL317LT



ROOF LIGHTING PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULEEL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE NOTED.
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 16'-0" AFF.



KEY PLAN

SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:30:07 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF LIGHTING PLAN - AREA B

SHEET NUMBER

EL318



ROOF PHOTOMETRIC PLAN AREA-B

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:31:38 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF PHOTOMETRIC PLAN - AREA B

SHEET NUMBER

EL318LT




ROOF LIGHTING PLAN - AREA C
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. COORDINATE SWITCH LOCATION WITH PLACEMENT OF DOOR.
2. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 16'-0" AFF.
3. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT9'-0" AFF.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE


ROOF LIGHTING PLAN - AREA C

SHEET NUMBER

EL319

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:31:40 PM AESI Proj. No: 21-154



ROOF PHOTOMETRIC PLAN AREA-C

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:13 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF PHOTOMETRIC PLAN - AREA C

SHEET NUMBER

EL319LT



ROOF LIGHTING PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. LIGHT SWITCH SHALL BE MOUNTED AT TOP OF PLATFORM NEAR STAIRS.
2. LIGHT FIXTURES IN THIS AREA / ROOM SHALL BE MOUNTED AT 8'-0" AFF.
3. POLE LIGHT FIXTURES IN THIS AREA SHALL BE MOUNTED AT 25'-0" OF COOLING TOWER, AND PIECE OF CONDUIT THAT FIXTURE MOUNTS ONLY FOR ONE FIXTURE PER CONDUIT.
4. LIGHT SWITCH FOR COOLING TOWER SHALL BE MOUNTED AT COOLING TOWER STAIR.
5. LIGHT FIXTURES IN THIS AREA SHALL BE MOUNTED AT 7'-6" STRUCTURE CRANE RAIL.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF LIGHTING PLAN - AREA D

SHEET NUMBER

EL320

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:16 PM AESI Proj No: 21-154
0 1/2" 1" 2"



ROOF PHOTOMETRIC PLAN AREA-D

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:22:21 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF PHOTOMETRIC PLAN - AREA D

SHEET NUMBER

EL320LT



ROOF LIGHTING PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. POLE LIGHT FIXTURES IN THIS AREA SHALL BE MOUNTED AT 25'-0" OF COOLING TOWER , AND PIECE OF CONDUIT THAT FIXTURE MOUNTS ONLY FOR ONE FIXTURE PER CONDUIT.
2. LIGHT FIXTURES IN THIS AREA SHALL BE MOUNTED AT 7'-6" STRUCTURE CRANE RAIL.



KEY PLAN

SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:23 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF LIGHTING PLAN - AREA E

SHEET NUMBER

EL321



ROOF PHOTOMETRIC PLAN AREA-E

Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:28 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF PHOTOMETRIC PLAN - AREA E

SHEET NUMBER

EL321LT



ROOF LIGHTING PLAN - AREA F

Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE EL601.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.

(#) PLAN NOTES:

1. POLE LIGHT FIXTURES IN THIS AREA SHALL BE MOUNTED AT 25'-0" OF COOLING TOWER, AND PIECE OF CONDUIT THAT FIXTURE MOUNTS ONLY FOR ONE FIXTURE PER CONDUIT.
2. LIGHT FIXTURES IN THIS AREA SHALL BE MOUNTED AT 7'-6" STRUCTURE CRANE RAIL.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF LIGHTING PLAN - AREA F

SHEET NUMBER


EL322



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:22:31 PM AESI Proj. No: 21-154



ROOF PHOTOMETRIC PLAN AREA-F

Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:35 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: SPE	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF PHOTOMETRIC PLAN - AREA F


SHEET NUMBER

EL322LT






1 **FIRST FLOOR MEZZANINE 1 LIGHTING PLAN**
Scale: 1/4" = 1'-0"



3 **SECOND FLOOR MEZZANINE 2 LIGHTING PLAN**
Scale: 1/4" = 1'-0"

5 **FIRST FLOOR MEZZANINE 1 LIGHTING PLAN**
Scale: 1/4" = 1'-0"



2 **SECOND FLOOR MEZZANINE 1 LIGHTING PLAN**
Scale: 1/4" = 1'-0"

PLAN NOTES:

1. CONNECT CIRCUIT TO LOWER LEVEL AT FIRE PUMP ROOM 108

GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AS ADOPTED BY STATE INCLUDING ALL AMENDMENTS.
2. PROVIDE LIGHT FIXTURE AS SPECIFIED ON LIGHT FIXTURE SCHEDULE.
3. ALL LIGHTING CIRCUITS TO CONSIST OF (2) #12 AWG, #12 GND UNLESS OTHERWISE
4. NOTED.
5. ALL LIGHTING CIRCUITS EXCEEDING 75 FEET IN LENGTH SHALL CONSIST OF (2) #10 AWG, #10 GND UNLESS OTHERWISE NOTED.
6. PROVIDE ALL POWER PACKS AS REQUIRED LIGHTING CONTROL DEVICES AND POWER SUPPLIES FOR LOW VOLTAGE LIGHTING FIXTURES AS REQUIRED.
7. CEILING MOUNTED EXIT SIGN IN ROOMS WITH OPEN CEILINGS SHALL BE PENDANT MOUNTED, TOP OF FIXTURE SHALL ALIGN WITH BOTTOM OF PENDANT LIGHT FIXTURE.
8. ALL EXPOSED CONDUIT TO BE RIGID GALVANIZED STEEL (RGS).
9. SEAL ALL PENETRATIONS IN FULL HEIGHT WALLS.
10. PROVIDE ADDITIONAL TRAPEZE SUPPORTS FOR LIGHT FIXTURES AS REQUIRED UNDER DUCTWORK AND OTHER UTILITIES.
11.

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT
Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.3912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS


NO.	DATE	DESCRIPTION

DESIGNED BY **DAG**	CERTIFICATION
CHECKED BY **MB**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **SPE**	
PROJECT NO. **21-154**	


SHEET TITLE
LIGHTING MEZZAINE PLAN

SHEET NUMBER
EL401


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:40 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



1 STAIRS #1
Scale: 1/4" = 1'-0"



2 STAIRS #2
Scale: 1/4" = 1'-0"



3 CORRIDOR 227
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:41 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 | Fishers, IN 46038 | 317.818.1912 | cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

LIGHTING DETAILS

SHEET NUMBER

EL501

LIGHTING FIXTURE SCHEDULE

NOTES:
1. ALL LUMENS AND WATTS IN LIGHT FIXTURE SCHEDULE ARE FOR ESL SPECTRUM LIGHT FIXTURES ONLY.
2. X

TYPE TAG	DESCRIPTION	MOUNTING	LAMPS			CRI	LAMPS		MANUFACTURERS	ROOMS #	NOTES
			TYPE	LUMENS	TEMPERATURE		WATTS	VOLTS			
F1a	LINEAR HIGH BAY - EXTRUDED ALUMINUM HOUSING, WIDE DISTRIBUTION, POLYCARDONATE LENS, 0-10V DIMMING	CABLE	LED	12100 lm	3500 K	80	72 W	277 V	1--COLUMBIA LIGHTING ECH1-835-L12-DW-ED-U-PM-ODS-F5C012 2--LITHONIA LIGTHING CPHB-12000LM-SEF-GCL-WD-MVOLT-GZ10- 35K-80CRI-DWH 3--METALUX OHB-12-SE-W-UNV-L835-CD-X-U-X	201-224-227	1
F1a-90	LINEAR HIGH BAY - EXTRUDED ALUMINUM HOUSING, WIDE DISTRIBUTION, POLYCARDONATE LENS, 0-10V DIMMING	CABLE	LED	9100 lm	3500 K	90	53 W	277 V	1--COLUMBIA LIGHTING ECH1-935-L09-DW-ED-U-PM-ODS-F5C012 2--LITHONIA LIGHTING CPHB-9000LM-SEF-GCL-WD-MVOLT-GZ10-35K-90CRI-DWH 3--METALUX OHB-9-SE-W-UNV-L935-CD-X-U-X	207-208	1
F1b	LINEAR HIGH BAY - EXTRUDED ALUMINUM HOUSING, WIDE DISTRIBUTION, POLYCARDONATE LENS, 0-10V DIMMING	CABLE	LED	15101 lm	3500 K	80	94 W	277 V	1--COLUMBIA LIGHTING ECH1-835-L15-DW-ED-U-PM-ODS-F5C012 2--LITHONIA LIGHTING L CPHB-15000LM-SEF-GCL-WD-MVOLT-GZ10-35K-80CRI-DWH 3--METALUX OHB-15-SE-W-UNV-L835-CD-X-U-X	102-105-108-109-113 -114-210-211-212-22 0-226	1
F1c	LINEAR HIGH BAY - EXTRUDED ALUMINUM HOUSING, WIDE DISTRIBUTION, POLYCARDONATE LENS, 0-10V DIMMING	CABLE	LED	9100 lm	3500 K	80	53 W	277 V	1--COLUMBIA LIGHTING ECH1-835-L09-DW-ED-U-PM-ODS-F5C012 2--LITHONIA LIGHTING CPHB-9000LM-SEF-GCL-WD-MVOLT-GZ10-35K-80CRI-DWH 3--METALUX OHB-9-SE-W-UNV-L835-CD-X-U-X	215	1
F2a	2X4 TROFFER - DIE-FORMED CODE GAUGE COLD ROLLED STEEL HOUSING, ACRYLIC LENS, 0-10V DIMMING	LAY-IN GRID	LED	3492 lm	3500 K	90	27 W	277 V	1--COLUMBIA LIGHTING LCAT24-9-35-VW-G-R-ED-U 2--LITHONIA LIGHTING ENVX 2X4-HRG-3000LM-90CRI-35K-MIN1- ZT-MVOLT 3--METALUX 24-G-R-X-LD5-34-X-UNV-L935-X-CD-1--U-SK-24-WT	101-112-203-204-205 -209	1
F4a	LINEAR HAZARDOUS RATED-CLASS I(FLAMMABLE VAPORS, GASES & LIQUIDS)-DIV 2- GROUP D	CABLE	LED	8692 lm	3500 K	70	62 W	277 V	1--SPECGRADE LED ARIA-60-35K-120-V01-GR-PM-VDIM 2--LITHONIA LIGHTING HJHL42-040-50-35K-U-HJUB 3--METALUX 4-SRL-LD5-60SL-LW-UNV-L835-CD-1-SVPD2-U	103-222	1
F5c	LINEAR STAIRWELL - DIE-CAST STEEL, FROSTED ACRYLIC LENS, WIDE DISTRIBUTION. INTEGRAL OCCUPANCY SENSOR, UNOCCUPIED STATE DIM LUMINARE TO 50% OUTPUT, OCCUPIED STATE LUMINARIE RETURNS TO 100% OUTPUT, 0-10V DIMMING	PENDANT	LED	4556 lm	3500 K	80	40 W	277 V	1--COLUMBIA LIGHTING ESL4-35ML-FAW-EDU-NXOS 2--LITHONIA LIGHTING ESL-4-35-ML-FA-W-ED-NXOS 3--METALUX 4NWS3C3-UNV-HIGH-3500K	106-110-202-217-227	1
F6	LINEAR GENERATOR ROOM- 2" APETURE WALL MOUNTED, EXTRUDED ALUMINUM BODY, FLUSH FROSTED LENS, INTEGRAL OCCUPANCY SENSOR, UNOCCUPIED STATE DIM LUMINARE TO 50% OUTPUT, OCCUPIED STATE LUMINARIE RETURNS TO 100% OUTPUT, 0-10V DIMMING	WALL	LED	5037 lm	3500 K	80	60 W	277 V	1--COLUMBIA LIGHTING LXEM-2-35-HL-RFA-ED-U-XE45MB 2--LITHONIA LIGHTING CSVT-L48-5000LM-MVOLT-35K-80CRI 3--METALUX 2VT2-LD5-3-DR-W-UNV-L835-CD1-WL-U	304-305	1
F7	EXTERIOR WALLPACK - DIE-CAST ALUMINUM HOUSING, POWDER PAINT BLACK MATTE FINISH, FLOSTED ACYLIC DIFFUSER, ZERO UPLIGHT	WALL	LED	4012 lm	3000 K	<varies>	35 W	277 V	1--HUBBELL LIGHTING LNC3-24L3K-050-3-U-BLT LNC2-48L-35-4K7-4W-UNV 2--LITHONIA LIGHTING WDGE1 -P2-30K-80CRI-VW-MVOLT 3--METALUX McGRAW-IST-SA1-F-830-U-T4w-BK--X	EXTERIOR	1
F8	VAPOR TIGHT JELLY JAR - DIE-CAST ALUMINUM HOUSING WITH REMOVABLE CAST ALUMINUM GUARD, FROSTED GLASS GLOBE, WALL MOUNT TO SURFACE J-BOX	WALL	LED	2332 lm	3500 K	80	16 W	277 V	1--SPECGTADELED TAURUS-C TAUC-20-35K-120-V01-GRWM-VDIM-R1 2--LITHONIA LIGHTING AVP-20L2-U-HIF-G-W-35 3--PHOENIX VA-W-17LED-WW--FGC	219-221	1
F9a	LINEAR UTILITY - CODE-GAUGE STEEL CONSTRUCTION, FROSTED ACRYLIC LENS, WIDE DISTRIBUTION, 0-10V DIMMING	CHAIN	LED	4613 lm	3500 K	80	40 W	277 V	1--COLUMBIA LIGHTING MPS4-35ML-CW-EDU CSHC 2--LITHONIA LIGHTING CLX-L48-4000LM-SEF-FDL-MVOLT-GZ10-35K-80CRI-WH 3--METALUX 4-SNLED-LD5-49SL-LN-UNV-X-L835-CD-1-U	115-223-224-225	1
F9b	LINEAR UTILITY - CODE-GAUGE STEEL CONSTRUCTION, FROSTED ACRYLIC LENS, WIDE DISTRIBUTION, 0-10V DIMMING	CHAIN	LED	5831 lm	3500 K	80	50 W	277 V	1--COLUMBIA LIGHITNG MPS4-35HL-CW-EDU-CSHC 2--LITHONIA LIGHTING CLX-L48-5000LM-SEF-FDL-MVOLT-GZ10-35K-80CRI-WH 3--METALUX 4-SNLED-LD5-46SL-LN-UNV-X-L835-CD-1-U	214-223	1
F9c	LINEAR UTILITY - CODE-GAUGE STEEL CONSTRUCTION, FROSTED ACRYLIC LENS, WIDE DISTRIBUTION, 0-10V DIMMING	CHAIN	LED	8045 lm	3500 K	80	67 W	277 V	1--COLUMBIA LIGHITNG MPS4-35XL-CW-EDU-CSHC 2--LITHONIA LIGHTING CLX-L48-7000LM-SEF-FDL-MVOLT-GZ10-35K-80CRI-WH 3--METALUX 4-SNLED-LD5-74HL-LN-UNV-X-L835-CD-1-U	225	1
F10a	6" RECESSED DOWNLIGHT - COLD-ROLLED STEEL HOUSING, WIDE DISTRIBUTION DIFFUSED LENS, WET LOCATION RATED, WHITE TRIM COLOR	RECESSED	LED	984 lm	3500 K	80	10 W	277 V	1--ALPHABET LIGHITNG NU6-RD-SW-13LM-35K-80-HE70-UNV-DIM10-NC-WH-WH 2--LITHONIA LIGHTING LDN6-35/10-L06WR-MVOLT-GZ10 3--HOLO COMMERCIAL HC6-10-D010+IM6-3040-835	111-205A-205B	1
F11	LINEAR STAIRWELL - 4" APETURE WALL MOUNTED, EXTRUDED ALUMINUM BODY, FLUSH FROSTED LENS, INTEGRAL OCCUPANCY SENSOR, UNOCCUPIED STATE DIM LUMINARE TO 50% OUTPUT, OCCUPIED STATE LUMINARIE RETURNS TO 100% OUTPUT, 0-10V DIMMING	SURFACE	LED	2882 lm	3500 K	80	19 W	277 V	1--FINELITE HP-4-WW-D-4-H-835-F-96LG-277-SC-FC-10%-FM-FE-SW-OBO 2--LITHONIA LIGHTING S4LS-LLP-4FT-MSL4-80CRI-35K-700LMF-MIN1-MVOLT-WHT-XT -APD 3--LUMENWERX V1A4S-D-ARO2-FH-SW--80-X-35K-X-UNV-D1-1-DRC-W	106-110-202-217-301 -227	1
F12	LINEAR HIGH PERFORMANCE- 2" APETURE WALL MOUNTED, EXTRUDED ALUMINUM BODY, FLUSH FROSTED LENS, INTEGRAL OCCUPANCY SENSOR, UNOCCUPIED STATE DIM LUMINARE TO 50% OUTPUT, OCCUPIED STATE LUMINARIE RETURNS TO 100% OUTPUT, 0-10V DIMMING	SURFACE	LED	2882 lm	3500 K	80	16 W	277 V	1--FINELITE HP-2-WM-ID-2FT-S-B-835 2--LITHONIA LIGHTING S2WID-LLP-MSL2-80CRI-35K-400LMF-I80CRI-I35K-I400LMF-SC T-MIN10-FLL-MVOLT-WHTT 3--STARTEK-BEAM BEAMDI-2-500-750-WD-BW-35K-80-PW-ACW05-U-1C-DT1	205A-205B	1
F13	LED FLOOD LIGHTING WITH DIE-CASTHOUSING WITH HIDDEN VERTICAL HEAT FINES WITH BLACK COLOR	POLE	LED	22653 lm	3000 K	70	178 W	277 V	1-- BEACON VP-F-2-264L-175-3K7-W 2--LITHIONIA RSXF2LED-P4-30K-MFL-MVOLT-IS-DDBXD 3--COOPER- McGRAW-EDITION GLEON-SA3-D-830-U-T4W-ADJA-BK	EXTERIOR	1
F14	LED FLOOD LIGHTING WITH DIE-CASTHOUSING WITH HIDDEN VERTICAL HEAT FINES WITH BLACK COLOR	LAY-IN GRID	LED	22653 lm	3000 K	70	178 W	277 V	1-- BEACON VP-F-2-264L-175-3K7-W-T-TRUNNION 2--LITHIONIA RSXF2LED-P4-30K-MFL-MVOLT-IS-DDBXD 3--COOPER- McGRAW-EDITION GLEON-SA3-D-830-U-T4W-ADJA-BK	EXTERIOR-302-303	1
FX	EXIT SIGN - DIE-CAST ALUMINUM CONSTRUCTION, WHITE FINISH WITH RED LETTERS, UNIVERSAL MOUNTING	WALL/SURFACE/CEILING/PENDANT	LED	0 lm	0 K		4 W	277 V	1--DUAL-LITE SE*RW-I 2--LITHONIA LIGHTING LE-S-W-1-R 3--SURE-LITES CX-7-1-WH-SD-R	EXIT SIGN	1
P1	ELEVATOR LIGHT FIXTURE	SURFACE	LED	7643 lm	3500 K	80	62 W	277 V	1--COLUMBIA LIGHTING LXEM4-35-VL-RFA-ED-U 2--LITHONIA LIGHTING CSVT-L48-6000LM-MVOLT-35K-80CRI 3--LUMENWERX 4VT3-LD5-6-G-UNV-L835-CD1-U	ELEVATOR PIT	1

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:42 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: DAG	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: MB	
APPROVED BY: SPE	
PROJECT NO.: 21-154	

SHEET TITLE

LIGHTING SCHEDULES

SHEET NUMBER

EL601

PANELBOARD SCHEDULE

Branch Panel...	1LSH1		**New/Exist:**	NEW		**Location:**	CHILLER PLANT 114			**Project Name:**	Central Utility Plant								
SPD:	Yes		**Main:**	MCB		**Mounting:**	Surface			**Project No.**	Project Number								
Voltage	480/277 Wye		**Amp:**	225 A		**Kaic Rating:**	65			**Date**	February 10, 2023								
Feed From:			**Enclosure:**	Type 1		**Feeder:**	SEE SINGLE LINE DIAGRAM				Applied Engineering Services (317) 810-4141								
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**		**B (KVA)**		**C (KVA)**		**Load...**	**Type**	**Rating**	**Pole**	**Load Name**		**Ckt**	
1	LTG-BOILER PLANT MEZZ. (109)	1	20 A		Lighting	0.58	0.00					--		20 A	1	Spare		2	
3	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		4	
5	LTG- VEST. (101)	1	20 A		Lighting					0.31	0.00	--		20 A	1	Spare		6	
7	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		8	
9	LTG- CHILLER PLANT (114)	1	20 A		Lighting			1.61	0.00			--		20 A	1	Spare		10	
11	LTG- CHILLER PLANT (114)	1	20 A		Lighting					1.41	0.00	--		20 A	1	Spare		12	
13	LTG- FIRE PUMP ROOM (108)	1	20 A		Lighting	0.47	0.00					--		20 A	1	Spare		14	
15	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		16	
17	LTG- CHILLER PLANT ELECTRICAL RM...	1	20 A		Lighting					0.85	0.00	--		20 A	1	Spare		18	
19	LTG- CHILLER PLANT ELECTRICAL RM...	1	20 A		Lighting	0.85	0.00					--		20 A	1	Spare		20	
21	LTG- CHILLER PLANT ELECTRICAL RM...	1	20 A		Lighting			0.39	0.00			--		20 A	1	Spare		22	
23	LTG- BOILER PLANT (109)	1	20 A		Lighting					1.53	0.00	--		20 A	1	Spare		24	
25	LTG- CONTROL (112)	1	20 A		Lighting	0.10	0.00					--		20 A	1	Spare		26	
27	LTG- BOILER PLANT (109)	1	20 A		Lighting			1.14	0.00			--		20 A	1	Spare		28	
29	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		30	
31	LTG- SERVICE YARD	1	20 A		Lighting	0.39	0.00					--		20 A	1	Spare		32	
33	LTG- OUTSIDE	1	20 A		Lighting			0.11	0.00			--		20 A	1	Spare		34	
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		36	
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		38	
39	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		40	
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		42	
						2.39 kVA		**3.2 kVA**		**4.1 kVA**									

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)	9.73	1.00	9.73	Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	9.73		9.73		

PANELBOARD SCHEDULE

Branch Panel...	2LSH2		**New/Exist:**	NEW		**Location:**	15KW SWITCHGEAR 212			**Project Name:**	Central Utility Plant								
SPD:	YES		**Main:**	MCB		**Mounting:**	Surface			**Project No.**	Project Number								
Voltage	480/277 Wye		**Amp:**	225 A		**Kaic Rating:**	65			**Date**	February 10, 2023								
Feed From:			**Enclosure:**	Type 1		**Feeder:**	SEE SINGLE LINE DIAGRAM				Applied Engineering Services (317) 810-4141								
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**		**B (KVA)**		**C (KVA)**		**Load...**	**Type**	**Rating**	**Pole**	**Load Name**		**Ckt**	
1	LTG- LOCKER / BREAK RM (205)	1	20 A		Lighting	0.46	0.00					--		20 A	1	Spare		2	
3	LTG- OFFICE (203)	1	20 A		Lighting			0.11	0.00			--		20 A	1	Spare		4	
5	LTG- OFFICE (226)	1	20 A		Lighting					0.27	0.00	--		20 A	1	Spare		6	
7	LTG- GANITOR / STORAGE (223)	1	20 A		Lighting	0.48	0.00					--		20 A	1	Spare		8	
9	LTG- FUEL OIL DAY TANKS A (222)	1	20 A		Lighting			0.25	0.00			--		20 A	1	Spare		10	
11	LTG- MECHANICAL (206)	1	20 A		Lighting					0.47	0.00	--		20 A	1	Spare		12	
13	LTG- CONTROL ROOM (209)	1	20 A		Lighting	0.22	0.00					--		20 A	1	Spare		14	
15	LTG- MAINTENANCE STORAGE (214)	1	20 A		Lighting			0.45	0.00			--		20 A	1	Spare		16	
17	LTG-GENERATOR EXHAUST PLENUM 2...	1	20 A		Lighting					0.13	0.00	--		20 A	1	Spare		18	
19	LTG- GENERATOR CONTROL . MEZZ (208)	1	20 A		Lighting	0.29	0.00					--		20 A	1	Spare		20	
21	LTG- MAINTENANCE STRORAGE . MEZZ...	1	20 A		Lighting			0.50	0.00			--		20 A	1	Spare		22	
23	LTG- INTAKE MONITORE RM (302)	1	20 A		Other					1.43	0.00	--		20 A	1	Spare		24	
25	LTG- OUTSIDE EMERG. GENERATOR (302)	1	20 A		Lighting	0.18	0.00					--		20 A	1	Spare		26	
27	LTG- POLE LIGHT- ROOF TOP	1	20 A		Lighting			0.71	0.00			--		20 A	1	Spare		28	
29	LTG- POLE LIGHT- ROOF TOP	1	20 A		Lighting					0.71	0.00	--		20 A	1	Spare		30	
31	LTG- VESTIBLUE (304)	1	20 A		Lighting	0.16	0.00					--		20 A	1	Spare		32	
33	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		34	
35	LTG- COOLING TOWER LIGHT	1	20 A		Other					1.43	0.00	--		20 A	1	Spare		36	
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		38	
39	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		40	
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		42	
						1.80 kVA		**2.0 kVA**		**4.4 kVA**									

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)	5.40	1.00	5.40	Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)	2.85	0.80	2.28		
Total Load (KVA)	8.26		7.69		

PANELBOARD SCHEDULE

Branch Panel...	1LSUPSH1		**New/Exist:**	NEW		**Location:**	CHILLER PLANT 114			**Project Name:**	Central Utility Plant								
SPD:	Yes		**Main:**	MLO		**Mounting:**	Surface			**Project No.**	Project Number								
Voltage	480/277 Wye		**Amp:**	100 A		**Kaic Rating:**	65			**Date**	February 10, 2023								
Feed From:			**Enclosure:**	Type 1		**Feeder:**	SEE SINGLE LINE DIAGRAM				Applied Engineering Services (317) 810-4141								
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**		**B (KVA)**		**C (KVA)**		**Load...**	**Type**	**Rating**	**Pole**	**Load Name**		**Ckt**	
1	LTG- STAIR #1 (001)	1	20 A		Lighting	1.04	0.00					--		20 A	1	Spare		2	
3	LTG- STAIR #1 (106)	1	20 A		Lighting			0.10	0.00			--		20 A	1	Spare		4	
5	LTG- RECEIVING (105)	1	20 A		Lighting					1.70	0.00	--		20 A	1	Spare		6	
7	LTG- STAIR #2 (110)	1	20 A		Lighting	0.11	0.00					--		20 A	1	Spare		8	
9	LTG- ELEVATOR LIGHT	1	20 A		Lighting			0.12	0.00			--		20 A	1	Spare		10	
11	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		12	
13	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		14	
15	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		16	
17	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		18	
19	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		20	
21	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		22	
23	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		24	
25	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		26	
27	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		28	
29	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		30	
31	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		32	
33	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		34	
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		36	
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		38	
39	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		40	
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		42	
						1.15 kVA		**0.2 kVA**		**1.7 kVA**									

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)	3.07	1.00	3.07	Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	3.07		3.07		

PANELBOARD SCHEDULE

Branch Panel...	2LSUPSH1		**New/Exist:**	NEW		**Location:**	15KW SWITCHGEAR 212			**Project Name:**	Central Utility Plant								
SPD:	Yes		**Main:**	MLO		**Mounting:**	Surface			**Project No.**	Project Number								
Voltage	480/277 Wye		**Amp:**	100 A		**Kaic Rating:**	65			**Date**	February 10, 2023								
Feed From:			**Enclosure:**	Type 1		**Feeder:**	SEE SINGLE LINE DIAGRAM				Applied Engineering Services (317) 810-4141								
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**		**B (KVA)**		**C (KVA)**		**Load...**	**Type**	**Rating**	**Pole**	**Load Name**		**Ckt**	
1	LTG- STAIR #1 (202)	1	20 A		Lighting	0.08	0.00					--		20 A	1	Spare		2	
3	LTG- CORRIDOR (227)	1	20 A		Lighting			1.48	0.00			--		20 A	1	Spare		4	
5	LTG- STAIR #2 (217)	1	20 A		Lighting					0.08	0.00	--		20 A	1	Spare		6	
7	LTG- STAIR #1 (301)	1	20 A		Lighting	0.12	0.00					--		20 A	1	Spare		8	
9	LTG- CUP EMERGENCY ELECT. RM (215)	1	20 A		Lighting			0.38	0.00			--		20 A	1	Spare		10	
11	LTG-15KW SWITCHGEAR (212)	1	20 A		Lighting					1.80	0.00	--		20 A	1	Spare		12	
13	LTG- AES SERVICE SWITCHGEAR (216)	1	20 A		Lighting	0.95	0.00					--		20 A	1	Spare		14	
15	LTG- GENERATOR ROOM B (218)	1	20 A		Lighting			1.51	0.00			--		20 A	1	Spare		16	
17	LTG- GENERATOR ROOM A (220)	1	20 A		Lighting					1.32	0.00	--		20 A	1	Spare		18	
19	LTG- GENERATOR CONTROL (208)	1	20 A		Lighting	0.32	0.00					--		20 A	1	Spare		20	
21	LTG- CONTROL (211)	1	20 A		Lighting			1.23	0.00			--		20 A	1	Spare		22	
23	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		24	
25	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		26	
27	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		28	
29	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		30	
31	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		32	
33	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		34	
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		36	
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		38	
39	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		40	
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		42	
						1.47 kVA		**4.6 kVA**		**3.2 kVA**									

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)	9.26	1.00	9.26	Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	9.26		9.26		

ASHRAE STANDARD 90.1-2019 USING 9.6 SPACE BY SPACE METHOD

Key Plan Area	Rooms Name	Room #	Window Dimensions/ Top of Window Elevation	Primary Slide Lighted Area	Requires Day Light Control	Note for Lighting Control	# of Light Fixtures Day Lighting Control Required	Light Fixture For Day Light	Wattage Per Fixture For Day Light	Requires Occupancy Sensor	Note for r Occupancy Sensor	Light Fixtures	Wattage Per Fixture	Total Light Fixtures in the Room	Total Wattage in the Room	Room Square footage (SF)	Lighting Power Density(LPD) (W/FT^2)	Total Wattage Allowed	Pass /Fail
D	Vestibiule	101	16' H X12'W / 16'	256	YES	9.4.1.1 a,d,e	2	F2a	27	YES	9.4.1.1 g	F2a	27	2	54	195	0.45	93.6	Pass
D	Entry	102	No Window	No Window	NO	9.4.1.1 a,d	-	-	-	NO	9.4.1.1 g	F1b	94	2	188	265	0.48	127.2	Pass
D	Fuel Pump Room	103	4' H X 20'-0"W / 16'	432	YES	9.4.1.1 a,e	-	-	-	NO	9.4.1.1 h	F4a	62	4	248	614	0.76	466.64	Pass
	Elevator Shaft	-	No Window	No Window	NO	9.4.1.1 a	-	-	-	NO	9.4.1.1 h	-	-	-	-	-	-	-	-
A	Receiving	105	No Window	No Window	NO	9.4.1.1 a	-	-	-	YES	9.4.1.1 h	F1b	94	6	564	1410	0.49	690.9	Pass
A	Stair # 1	106	No Window	No Window	NO	9.4.1.1 a,c,d	-	-	-	YES	9.4.1.1 g	F11 & F5c	19/40	2 & 2	118	329	0.49	161.21	Pass
A,B	Water Pump Room	107	4' H X 26' W / 16'	480	YES	9.4.1.1 a,b,e	-	-	-	NO	9.4.1.1 h	F1b	94	10	940	3634	0.76	2685.84	Pass
B	Fire Pump Room	108	4' H X 26' W / 16'	480	YES	9.4.1.1 a,b,e	1	F1b	94	NO	9.4.1.1 h	F1b	94	3 & 2	470	730	0.76	554.8	Pass
B,C,E,F	Boiler Plant Room	109	4' H X 26' W / 16'	480	YES	9.4.1.1 a,b,e	-	-	-	NO	9.4.1.1 h	F1b/F1a	94/72	28 & 8	3208	10221	0.76	7767.96	Pass
C	Stair # 2	110	4' H X 21'-9" W / 16' & 30' H X7'-6" W / 30'	446 & 270	YES	9.4.1.1 a,c,d,e	1	F5c	40	YES	9.4.1.1 g	F11 & F5c	19/40	1 & 2	118	255	0.49	144.55	Pass
B	Toilet	111	No Window	No Window	NO	9.4.1.1 a,d	-	-	-	YES	9.4.1.1 h	F10a/F12	10/16	2 &1	36	67	0.63	42.21	Pass
B	Control Room	112	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 a	F2a	27	1	27	188	0.76	142.88	Pass
E,F	Chiller Plant Electrical Room	113	4' H X 126' & 207' W / 16'	480 & 384	YES	9.4.1.1 a,b,e	2	F1b	94	NO	9.4.1.1 h	F1b	94	22	2068	6970	0.76	5297.2	Pass
A,D,E	Chiller Plant Room	114	4' H X 26' W / 16'	480	YES	9.4.1.1 a,b,e	1	F1b	94	NO	9.4.1.1 h	F1b	94	32	3008	12391	0.76	9417.16	Pass
B	Janitor Room	115	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	YES	9.4.1.1 h	F9a	40	1	40	36	0.38	13.68	Fail
D	Elevator Room	116	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	P1	62	2	124	102	0.65	66.3	-
A,D	Corridor Room	201	21' H X 8' W / 21'	192	NO	9.4.1.1 a,b,e	1	F1a	72	YES	9.4.1.1 g	F1a	72	6	432	1841	0.76	1399.16	Pass
A	Stair #1	202	No Window	No Window	NO	9.4.1.1 a,c,d	-	-	-	YES	9.4.1.1 g	F11 & F5c	19/40	2 & 2	118	337	0.49	165.13	Pass
A	Office	203	21' H X 8' W /21'	252	YES	9.4.1.1 a,c,d,e	4	F2a	27	YES	9.4.1.1 h	F2a	27	4	108	232	0.74	171.68	Pass
A,D	Office	204	21' H X 8' W /21'	252	YES	9.4.1.1 a,c,d,e	4	F2a	27	YES	9.4.1.1 h	F2a	27	4	108	214	0.74	158.36	Pass
D	Isolen/Break Room	205	21' H X 8' W /21'	252	YES	9.4.1.1 a,d,e	4	F2a	27	YES	9.4.1.1 h	F2a	27	9	243	701	0.74	518.74	Pass
D	Toilet/ Shower	205A	No Window	No Window	NO	9.4.1.1 a,d	-	-	-	YES	9.4.1.1 h	F10a/F12	10/16	3 &1	46	75	0.63	47.25	Pass
D	Toilet/ Changing	205B	No Window	No Window	NO	9.4.1.1 a,d	-	-	-	YES	9.4.1.1 h	F10a/F12	10/16	2 &1	46	57	0.63	35.91	Pass
D	Mechanical Room	206	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	YES	9.4.1.1 h	F1b	94	5	470	739	0.76	561.64	Pass
A,D	Maintenanance Work Rm.	207	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	YES	9.4.1.1 h	F1a-90	53	4	212	561	0.76	426.36	Pass
A,D	Generator Control Room	208	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 a	F1a-90/F1a	53/72	2 & 4	394	444	0.76	337.44	Pass
D	Control Room	209	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 a	F2a	27	8	216	786	0.76	597.36	Pass
A,B,D,E	Generator Switchgear Room	210	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 a	F1b	94	9	846	2417	0.76	1836.92	Pass
A,D,E	Control Room	211	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F1b	94	5	470	843	0.76	640.68	Pass
E,F	15Kw Switchgear Room	212	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F1b	94	19	1786	4719	0.76	3586.44	Pass
A,E	Fuel Oil Day Tanks B Room	213	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F4a/F1a	62/72	4 & 4	536	617	0.76	468.92	Pass
F	Maintenanance Storage Room	214	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F9b/F1a	50/72	4 & 2	344	455	0.63	286.65	Pass
F	Cup Emergency Electrical Room	215	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F1c	53	7	371	1475	0.76	1121	Pass
C,F	AES Service Switchgear Room	216	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F1b	94	10	940	2519	0.76	1914.44	Pass
C	Stair #2	217	25' H X 27' W / 27'	837	YES	9.4.1.1 a,c,d,e	2	F5c	40	NO	9.4.1.1 g	F5c	40	2	80	319	0.76	242.44	Pass
A,B,C	Generator Room B	218	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F1b	72	16	1152	4641	0.76	3527.16	Pass
A,B,C	Generator Exhaust Plenum 2	219	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F8	16	4	64	1091	0.76	829.16	Pass
A,B	Generator Room A	220	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F1b	72	14	1008	4259	0.76	3236.84	Pass
A	Generator Exhaust Plenum 1	221	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F8	16	4	64	1112	0.76	845.12	Pass
A	Fuel Oil Day Tanks A Room	222	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F4a	62	4	248	443	0.76	336.68	Pass
A	Janitor / Storage Room	223	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	YES	9.4.1.1 h	F9a	40	1	40	204	0.38	77.52	Pass
A	Mechanical Room	224	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F1a & F9a	72/40	5 & 2	368	824	0.43	354.32	Pass
A	MDF Data Room	225	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	F9a	50	4	200	321	0.74	237.54	Pass
A	Office	226	21' H X 8' W / 21'	252	YES	9.4.1.1 a,c,d,e	4	F2a	27	YES	9.4.1.1 h	F2a	27	4	108	229	0.74	169.46	Pass
D,E,F	Corridor	227	No Window	No Window	NO	9.4.1.1 a,c	-	-	-	YES	9.4.1.1 g	F1a,F5C,F11	72/40/19	13 & 1 & 2	1014	3220	0.41	1320.2	Pass
C,F	Corridor	228	21'H X 8' W / 21'	252	YES	9.4.1.1 a,c,e	2	F1a	72	YES	9.4.1.1 g	F1a	72	3	216	841	0.41	385.81	Pass
A,B	Emergency Generator Intake Monitor 1	302	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	P1	62	4	248	2263	0.76	1719.88	Pass
B,C	Emergency Generator Intake Monitor 2	303	No Window	No Window	NO	9.4.1.1 a,b	-	-	-	NO	9.4.1.1 h	P1	62	4	248	2259	0.76	1716.84	Pass
A	Stair #1	001	No Window	No Window	NO	9.4.1.1 a,c,d	-	-	-	YES	9.4.1.1 g	F9b	50	2	100	227	0.49	111.23	Pass
A	Utility Tunnel	002	No Window	No Window	NO	9.4.1.1 a,b,d	-	-	-	YES	9.4.1.1 g	F9b & F9c	50/67	2 &14	1038	3697	0.41	1515.77	PASS
														Total Wattage=	25093		Total Wattage=	58572.18	

9.4.1.1 Interior Lighting Controls:
For each space in the building, all of lighting control functions indicated in Table 9.6.1, for the appropriate space type in first column, and as described below, shall be implemented.
9.4.1.1 a Local Control: There shall be one or more manual lighting controls in space that controls all of lighting in the space. Each control device shall control an area (1) no larger than 2500 ft^2 if the space is <= 10000 ft^2 and (2) no larger than 10000 ft^2 otherwise.
9.4.1.1 b Restricted to manual ON: None of lighting shall be automatically turned on.
9.4.1.1 c Restricted to partial automatic ON: No more than 50% of the lighting power for the general lighting shall be allowed to be automatically turned on, and none of the remaining lighting shall be automatically turned on.
9.4.1.1 d Bilevel lighting control: The general lighting in space shall be controlled so as to provide at least one intermediate step in lighting power or continuous dimming in addition to full ON and full OFF. At least one intermediate step shall be between 30% and 70% (inclusive) of full lighting power.
9.4.1.1 e Automatic daylight responsive controls for sidelighting: In any space where the combined input power of all general lighting completely or partially withtin the primary sidelighted areas is 150 W or greater, the general lighting in primary sidelighted areas shall be controlled by photocontrols.
9.4.1.1 g Automatic partial OFF (Full OFF complies): The general lighting power in the space shall be automatically reduced by atleast 50% within 20 minutes of all occupants leaving the space.
9.4.1.1 h Automatic full OFF: All lighting, including lighting connected to emergency circuits, shall be automatically shut off within 20 minutes of all occupants leaving the space. A control device meeting the requirment shall controll no more than 5000 ft^2.

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:32:43 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT


Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.bi



LOWER LEVEL SYSTEMS PLAN- AREA A


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. SEE DRAWINGS UT101.3 AND UT102.3 FOR ADDITIONAL TUNNEL DRAWINGS.
3. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
4. COORDINATE CARD READER INSTALLATION WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLY.
5. ROUTE ALL CABLING FOR LOW VOLTAGE SYSTEMS TO THE FIRST FLOOR OF THE CUP IN CONDUIT. ALL CABLING CAN THEN BE TRANSITIONED TO J-HOOKS WITH THE EXCEPTION OF FIRE ALARM CABLING.

(#) PLAN NOTES:

1. (16) 4" CONDUITS UP TO MDF ROOM. CONDUITS ARE FROM THE AAHC AND SSB BUILDINGS.
2. (8) 4" CONDUITS UP TO MDF ROOM. CONDUITS ARE FROM IUH SITE DUCTBANK.
3. TUNNEL SPRINKLER RISER TAMPER AND FLOW SWITCHES.
4. INSTALL CAMERA AT 96" AFF. CAMERA SHALL BE TYPE "B" AS NOTED IN THE 282300 SPECIFICATION.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION
CHECKED BY: KH	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


LOWER LEVEL SYSTEMS PLAN - AREA A

SHEET NUMBER

ES301

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:10 PM AESI Proj No: 21-154



GENERAL NOTES:


1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.

(#) PLAN NOTES:

1. (8) 4" CONDUITS UP TO 2ND FLOOR MDF ROOM. CONDUITS ARE FROM THE VENDOR SITE DUCTBANK. SEE DRAWING ES307 FOR CONDUIT CONTINUATION TO 2ND FLOOR MDF ROOM AND SITE PLAN DRAWING FOR CONTINUATION TO THE SITE VENDOR DUCTBANK.

LOWER LEVEL SYSTEMS PLAN- AREA D

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:10 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

LOWER LEVEL SYSTEMS PLAN - AREA D

SHEET NUMBER

ES303



FIRST FLOOR SYSTEMS PLAN - AREA A


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. ALL LOW VOLTAGE CABLING ON THE FIRST FLOOR SHALL BE ROUTED IN J-HOOKS WITH THE EXCEPTION OF FIRE ALARM CABLING, WHICH SHALL BE INSTALLED IN CONDUIT.

(#) PLAN NOTES:

1. MULTI-SENSOR PoE CAMERA (4 SENSORS). CAMERA SHALL BE TYPE "C" AS NOTED IN 282300 SPECIFICATION. PENDENT MOUNTED TO SIDE OF BUILDING. DATA JACK SHALL BE IN WEATHER PROOF ENCLOSURE.
2. (4) 4" COMMUNICATION CONDUITS. (1) CONDUIT WILL BE UTILIZED FOR THE FIRE ALARM COMMUNICATION NETWORK CABLING ROUTED THROUGH THE TUNNEL TO THE SSB FIRE ALARM PANEL. (3) CONDUITS WILL BE SPARES FOR ADDITIONAL FUTURE COMMUNICATIONS SYSTEMS.
3. (8) 4" C UP TO MDF ROOM. CONDUITS ARE FROM THE SITE VENDOR DUCTBANK. SEE DRAWING ES311 FOR CONTINUATION IN 2ND FLOOR MDF ROOM.
4. (16) 4" IIS CONDUITS UP TO MDF ROOM FROM THE TUNNEL. SEE DRAWING ES301 FOR CONTINUATION TO TUNNEL AND DRAWING ES311 FOR CONTINUATION IN 2ND FLOOR MDF ROOM.
5. (8) 4" C UP TO MDF ROOM. CONDUITS ARE FROM THE SITE IUH DUCTBANK. SEE DRAWING ES311 FOR CONTINUATION IN 2ND FLOOR MDF ROOM AND DRAWING ES301 TO SITE IUH DUCTBANK.
6. CAMERA SHALL BE TYPE "A" AS NOTED IN 282300 SPECIFICATION.
7. (3)4" SLEEVES IN CEILING UP TO MDF ROOM.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR SYSTEMS PLAN - AREA A

SHEET NUMBER

ES304

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:11 PM AESI Proj. No: 21-154



FIRST FLOOR SYSTEMS PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG. CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. (3) FLOW AND (16) TAMPER SWITCHES FOR FIRE PROTECTION ZONES.
2. FP-1 FIRE PUMP MONITORING POINTS. SEE POINTS TO BE MONITORED ON DRAWING ES701.
3. FP-2 FIRE PUMP MONITORING POINTS. SEE POINTS TO BE MONITORED ON DRAWING ES701.
4. JOCKEY PUMP JP-1 MONITORING POINTS. SEE POINTS TO BE MONITORED ON DRAWING ES701.
5. ALARM BELL.
6. CAMERA SHALL BE TYPE "A" AS NOTED IN 282300 SPECIFICATION.
7. JOCKEY PUMP JP-2 MONITORING POINTS. SEE POINTS TO BE MONITORED ON DRAWING ES701.
8. ACCESS CONTROL PANEL CONNECTED TO MAIN SECURITY PANEL IN THE 2ND FLOOR CONTROL ROOM.
9. NAC PANEL FOR FIRE ALARM SYSTEM.
10. MONITOR BY OTHERS. COORDINATE DATA OUTLET AND HDMI CABLE CONDUIT WITH ARCHITECTURAL PLAN.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:11 PM AESI Proj No: 21-154
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR SYSTEMS PLAN - AREA B

SHEET NUMBER

ES305



GENERAL NOTES:


1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. TAMPER AND FLOW SWITCH FOR SPRINKLER RISER.
2. MULTI-SENSOR PoE CAMERA (4 SENSORS). CAMERA SHALL BE TYPE "C" AS NOTED IN 282300 SPECIFICATION. PENDENT MOUNTED TO SIDE OF BUILDING. DATA JACK LOCATED INSIDE BUILDING. INSTALL 1" CONDUIT THROUGH WALL TO A 4 SQUARE BACK BOX ON EXTERIOR FOR PATCH CORD TO BE INSTALLED FOR CAMERA. SEAL CONDUIT TO MAKE WEATHERPROOF.
3. CAMERA SHALL BE TYPE "B" AS NOTED IN 282300 SPECIFICATION. DATA JACK TO BE LOCATED INSIDE BUILDING. INSTALL 1" CONDUIT THROUGH WALL TO A 4 SQUARE BACK BOX ON EXTERIOR FOR PATCH CORD TO BE INSTALLED FOR CAMERA. SEAL CONDUIT TO MAKE WEATHERPROOF.

FIRST FLOOR SYSTEMS PLAN - AREA C

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


FIRST FLOOR SYSTEMS PLAN - AREA C

SHEET NUMBER

ES306

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:13 PM AESI Proj. No: 21-154

0 1/2" 1" 2"



FIRST FLOOR SYSTEMS PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.

(#) PLAN NOTES:

1. FIRE ALARM ANNUNCIATOR PANEL.
2. MULTI-SENSOR PoE CAMERA (4 SENSORS). CAMERA SHALL BE A TYPE "C" AS NOTED IN 282300 SPECIFICATION. PENDENT MOUNT TO SIDE OF BUILDING. DATA JACK LOCATED INSIDE BUILDING. INSTALL 1" CONDUIT THROUGH WALL TO A 4 SQUARE BACK BOX ON EXTERIOR FOR PATCH CORD TO BE INSTALLED FOR CAMERA. SEAL CONDUIT TO MAKE WEATHERPROOF.
3. (6) 4" CONDUITS TO THE SITE VENDOR DUCTBANK. SEE SITE PLAN FOR CONTINUATION OF CONDUITS TO VENDOR DUCTBANK.
4. 36"X36"X16" PULL BOX.
5. CAMERA SHALL BE TYPE "B" AS NOTED IN 282300 SPECIFICATION. DATA JACK LOCATED INSIDE BUILDING. INSTALL 1" CONDUIT THROUGH WALL TO A 4 SQUARE BACK BOX ON EXTERIOR FOR PATCH CORD TO BE INSTALLED FOR CAMERA. SEAL CONDUIT TO MAKE WEATHERPROOF.
6. CAMERA SHALL BE TYPE "A" AS NOTED IN 282300 SPECIFICATION.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR SYSTEMS PLAN - AREA D

SHEET NUMBER

ES307

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:38:15 PM AESI Proj. No: 21-154



FIRST FLOOR SYSTEMS PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. (2) VALVE TAMPER SWITCHES FOR FIRE PROTECTION BACK FLOW PREVENTERS.
2. CAMERA SHALL BE TYPE "A" AS NOTED IN 282300 SPECIFICATION.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:17 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR SYSTEMS PLAN - AREA E

SHEET NUMBER

ES308



FIRST FLOOR SYSTEMS PLAN - AREA F


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. FIRE ALARM MONITORING POINTS FOR THE ELECTRIC ROOM PRE-ACTION SYSTEM. MONITORING POINTS INCLUDE LOW AIR, TROUBLE AND ALARM SIGNAL.
2. MULTI-SENSOR PoE CAMERA (4 SENSOR). CAMERA SHALL BE A TYPE "C" AS NOTED IN 282300 SPECIFICATION. PENDENT MOUNT TO SIDE OF BUILDING. DATA JACK INSIDE BUILDING. INSTALL 1" CONDUIT THROUGH WALL TO A 4 SQUARE BACK BOX ON EXTERIOR FOR PATCH CORD TO BE INSTALLED FOR CAMERA. SEAL CONDUIT TO MAKE WEATHERPROOF.
3. (4) 4" CONDUITS ROUTED TO JCI BUILDING FROM 2ND FLOOR MDF ROOM. SEE CONDUIT CONTINUATION TO 2ND FLOOR ON DRAWING ES316 AND ON SITE PLAN DRAWING FOR DUCTBANK TO JCI BUILDING.
4. CAMERA SHALL BE TYPE "A" AS NOTED IN 282300 SPECIFICATION.



KEY PLAN

SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


FIRST FLOOR SYSTEMS PLAN - AREA F

SHEET NUMBER

ES309

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:18 PM AESI Proj. No: 21-154




GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A WESCO UTG20 CABLE. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. VIDEO INTERCOM STATION CONNECTED TO A BASE STATION IN THE CONTROL ROOMS.
2. CAMERA SHALL BE TYPE "A" AS NOTED IN 282300 SPECIFICATION. INSTALL DATA JACK IN WEATHER PROOF ENCLOSURE.
3. CAMERA SHALL BE MULTISENSOR (4 SENSORS) TYPE "C" AS NOTED IN 282300 SPECIFICATION. PENDENT MOUNT TO SIDE OF FENCE. INSTALL DATA JACK IN WEATHER PROOF ENCLOSURE.

FIRST FLOOR SYSTEMS PLAN - AREA
Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:19 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Seahorse Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ML	CERTIFICATION
CHECKED BY: KH	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR SYSTEMS PLAN - AREA G

SHEET NUMBER

ES310



SECOND FLOOR SYSTEMS PLAN - AREA A

Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. ALL LOW VOLTAGE CABLING ON THE SECOND FLOOR CAN BE ROUTED IN J-HOOKS WITH THE EXCEPTION OF FIRE ALARM CABLING, WHICH SHALL BE INSTALLED IN CONDUIT.

(#) PLAN NOTES:

1. FIRE ALARM MONITORING POINTS FOR THE MDF ROOM FIRE SUPPRESSION SYSTEM (INOVEC 1200).
2. (8) 4" C FROM THE IUH DUCTBANK SYSTEM. SEE SITE PLAN FOR ROUTING OF CONDUITS TO SENATE AVE.
3. (2) DUCT DETECTORS AND (2) RELAY SHUTDOWNS FOR (2) MDF CRAC UNITS. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATIONS.
4. PRE-ACTION SYSTEM MONITORING POINTS - LOW AIR, TROUBLE, AND ALARM.
5. TAMPER AND FLOW SWITCH FOR SPRINKLER RISER.
6. (4) 4" C ROUTED TO JCI BLDG.
7. CAMERA SHALL BE A TYPE "A" AS NOTED IN 282300 SPECIFICATION.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadrow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR SYSTEMS PLAN - AREA A


SHEET NUMBER

ES311



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:21 PM AESI Proj No: 21-154



SECOND FLOOR SYSTEMS PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. CAMERA SHALL BE A TYPE "A" AS NOTED IN 282300 SPECIFICATION.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:26:23 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ML	CERTIFICATION
CHECKED BY: KH	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR SYSTEMS PLAN - AREA B

SHEET NUMBER

ES312



SECOND FLOOR SYSTEMS PLAN - AREA C


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. CAMERA SHALL BE A TYPE "A" AS NOTED IN 282300 SPECIFICATION.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION
CHECKED BY: KH	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


SECOND FLOOR SYSTEMS PLAN - AREA C

SHEET NUMBER

ES313

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:38:24 PM AESI Proj. No: 21-154




SECOND FLOOR SYSTEMS PLAN - AREA D
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.

(#) PLAN NOTES:

1. FIRE ALARM CONTROL PANEL. TELECOM JACK FOR DACT. ALL CABLING SHALL BE IN CONDUIT TO THE FACP.
2. ACCESS CONTROL SECURITY PANEL. ALL CABLING SHALL BE IN CONDUIT FROM PANEL TO ABOVE CEILING.
3. VIDEO INTERCOM BASE STATION THAT WILL SIT ON CONTROL WORKSTATION DESK. INTERCOM WILL COMMUNICATE WITH GATE INTERCOM.
4. PRE-ACTION SYSTEM MONITORING POINTS - LOW AIR, TROUBLE, AND ALARM.
5. BAS COMPUTER DATA JACK IN FLOOR BOX BELOW CONTROL WORK STATION. SEE ELECTRICAL DRAWINGS FOR FLOOR BOX DETAIL.
6. 36"x36"x12" PULL BOX.
7. (4) 4" C ROUTED TO JCI BLDG.
8. INSTALL 1-1/2" CONDUIT FROM SHELF AT 48" AFF TO THE BACK OF THE MONITOR ON ADJACENT NORTH WALL. INSTALL SINGLE GANG BOX ON EACH END OF CONDUIT WITH GROMMETTED COVERPLATE THAT WILL ALLOW A HDMI CONNECTOR THROUGH THE GROMMETTED HOLE.
9. MONITOR BY OTHERS. COORDINATE DATA OUTLET AND HDMI CABLE CONDUIT WITH ARCHITECTURAL PLAN.
10. DUCT DETECTOR AND FIRE ALARM SHUTDOWN RELAY FOR MAU-2-1. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATION.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadylane Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION
CHECKED BY: KH	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR SYSTEMS PLAN - AREA D

SHEET NUMBER

ES314

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:38:27 PM AESI Proj. No: 21-154



SECOND FLOOR SYSTEMS PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. (4) 4" C ROUTED TO JCI BLDG.
2. 36"x36"x12" PULL BOX.
3. FIRE ALARM DEVICE ON MEZZANINE LEVEL. SEE ES402 FOR EXACT LOCATION.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:38:29 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR SYSTEMS PLAN - AREA E

SHEET NUMBER

ES315



SECOND FLOOR SYSTEMS PLAN - AREA F


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. (4) 4" C ROUTED FROM 2ND FLOOR MDF ROOM TO JCI BLDG. SEE DRAWING ES307 FOR CONTINUATION OF CONDUITS TO 1ST FLOOR.
2. 36"x36"x12" PULL BOX.
3. (4) 4" C ROUTED TO 2ND FLOOR MDF ROOM.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadyknoll Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION
CHECKED BY: KH	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


SECOND FLOOR SYSTEMS PLAN - AREA F

SHEET NUMBER

ES316

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:30 PM AESI Proj No: 21-154




ROOF SYSTEMS PLAN - AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. CAMERAS SHALL BE INSTALLED AT 10' AFF OR GRADE UNLESS OTHERWISE NOTED.
3. COORDINATE CARD READER INSTALLATIONS WITH ARCHITECTURAL DOOR SCHEDULE AND POWER PLANS FOR DOOR POWER SUPPLIES.
4. ALL LOW VOLTAGE CABLING ON THE ROOF FLOOR SHALL BE ROUTED IN CONDUIT DOWN TO THE 2ND FLOOR.

(#) PLAN NOTES:

1. WEATHER PROOF NOTIFICATION DEVICE.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION
CHECKED BY: KH	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ROOF SYSTEMS PLAN - AREA A

SHEET NUMBER

ES317

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:38:31 PM AESI Proj. No: 21-154




GENERAL NOTES:

1. SEE E001 FOR ADDITIONAL GENERAL NOTES.

(#) PLAN NOTES:

1. TAMPER SWITCH FOR ROOF PIV. COORDINATE LOCATION WITH FIRE PROTECTION DRAWINGS.

ROOF SYSTEMS PLAN - AREA C
Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF SYSTEMS PLAN - AREA C

SHEET NUMBER

ES319

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:33 PM AESI Proj. No: 21-154



ROOF SYSTEMS PLAN - AREA D
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.
2. THE CONTRACTOR SHALL VERIFY ROUTING OF DATA CABLE TO DEVICES FROM THE 2ND FLOOR MDF ROOM. FOR ALL CABLE LENGTHS GREATER THAN 90 METERS UTILIZE A UTG CABLE PER DIV 27 SPECIFICATIONS. AREAS OF POSSIBLE LENGTHS OVER 90 METERS ARE COLUMN B6 - B10 SOUTH TO COLUMN A10 - F10.

(#) PLAN NOTES:

1. CAMERA MOUNTED AT TOP OF ELEVATOR SHAFT TO VIEW COOLING TOWERS. CAMERA SHALL BE A TYPE "A" AS NOTED IN 282300 SPECIFICATION. INSTALL DATA JACKS IN WEATHER PROOF ENCLOSURE.
2. CARD READER IN ELEVATOR CAR TO ALLOW ROOF ACCESS.
3. PRIMARY, SECONDARY AND FIREMAN'S HAT ELEVATOR FIRE RELAYS LOCATED NEAR OR IN ELEVATOR CONTROLLER.
4. ELEVATOR PHONE OUTLET.
5. FLOW AND TAMPER SWITCHES FOR SPRINKLER SYSTEM.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadybrook Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF SYSTEMS PLAN - AREA D

SHEET NUMBER


ES320




KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:38:34 PM AESI Proj. No: 21-154




2 **EAST ELEVATION - MDF 225**
Scale: 1/4" = 1'-0"




1 **ENLARGED SYSTEMS PLAN - MDF 225**
Scale: 3/8" = 1'-0"

PLAN NOTES:


1. (8) 4" C FROM THE VENDOR DUCTBANK SYSTEM.
2. (8) 4" C FROM THE IUH DUCTBANK SYSTEM.
3. (16) 4" C FROM THE TUNNEL.
4. (2) 4 POST RACKS AND (4) 2 POST RACKS TO BE INSTALLED FOR ELECTRONICS.
5. 2"X12" RUNWAY CABLE TRAY.
6. TMGB TELECOM GROUNDING BUS. SEE ES501 FOR GROUNDING DETAILS.
7. MDF ROOM WRAPPED IN PLYWOOD FROM 6" AFF TO 8'6" AFF.
8. (4) 4" C FROM JCI BUILDING.
9. (3) 4"SLEEVES FOR 1ST FLOOR DATA CABLING.
10. (3) 4" SLEEVES FOR 2ND FLOOR AND ROOF DATA CABLING.
11. PoE CAMERA WITH VIEW AT THE ENTRY DOOR. CAMERA SHALL BE A TYPE "B" AS NOTED IN 282300 SPECIFICATION.
12. 2"x18" RUNWAY CABLE TRAY.
13. 2"x24" RUNWAY CABLE TRAY.



3 **SOUTH ELEVATION - MDF 225**
Scale: 1/4" = 1'-0"



4 **WEST ELEVATION - MDF 225**
Scale: 1/4" = 1'-0"



5 **NORTH ELEVATION - MDF 225**
Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ENLARGED SYSTEMS PLANS

SHEET NUMBER

ES401

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:38:40 PM AESI Proj No: 21-154
0 1/2" 1" 2"




GENERAL NOTES:

1. SEE DRAWING E001 FOR ADDITIONAL GENERAL NOTES.


(#) PLAN NOTES:

1. DUCT DETECTOR AND AHU-2-1 FIRE ALARM SHUTDOWN RELAY. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATION.
2. DUCT DETECTOR AND AHU-2-2 FIRE ALARM SHUTDOWN RELAY. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATION.
3. DUCT DETECTOR AND AHU-2-3 FIRE ALARM SHUTDOWN RELAY. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATION.
4. DUCT DETECTOR AND MAU-1-1 FIRE ALARM SHUTDOWN RELAY. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATION.
5. DUCT DETECTOR AND MAU-1-2 FIRE ALARM SHUTDOWN RELAY. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATION.
6. DUCT DETECTOR AND AHU-1-1 FIRE ALARM SHUTDOWN RELAY. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATION.
7. DUCT DETECTOR AND AHU-2-4 FIRE ALARM SHUTDOWN RELAY. SEE MECHANICAL HVAC DRAWINGS FOR EXACT DUCT DETECTOR LOCATION.
8. TAMPER AND FLOW SWITCH FOR SPRINKLER ON MEZZANINE.

1 FIRST FLOOR MEZZANINE SYSTEMS PLAN
Scale: 1/4" = 1'-0"



2 SECOND FLOOR MEZZANINE 1 SYSTEMS PLAN
Scale: 1/4" = 1'-0"



3 SECOND FLOOR MEZZANINE 2 SYSTEMS PLAN
Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY: ML
CHECKED BY: KH
APPROVED BY: Approver
PROJECT NO.: 21-154

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION


SHEET TITLE

MEZZANINE SYSTEMS PLANS


SHEET NUMBER

ES402

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:38:43 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



2 TELECOM GROUNDING DETAIL
Scale: NONE



TELECOM ROOM GROUNDING DETAIL NOTES:

1 TYP. SECTIONS OF 3/4" FIRE RATED PLYWOOD TERMINAL BOARDS MOUNTED TO WALLS

2 TYP. SECTIONS OF 12" LADDER CABLE TRAY MOUNTED TO PLYWOOD TERMINAL BOARD WITH SHELF BRACKETS

3 TYP. CABLE RUNWAY "L" BRACKET, ATTACHED TO CABLE TRAY

4 TYP. DATA EQUIPMENT FRAME

5 TYP. TELECOMMUNICATIONS MAIN GROUNDING BUSBAR (TMGB) 1/4" X 4" X 20" COMPRISED OF 1/4" AND 3/8" STUD HOLES WITH BUSBAR INSULATORS. CPI 40153-020.

6 TYP. 1" EMT CONDUIT WITH BONDING CONDUCTOR FOR TELECOMMUNICATIONS (BCT) FROM BUILDING MAIN ELECTRICAL SERVICE GROUND CONNECTION POINT. ATTACH TO "TMGB" USING TWO HOLE (5/8" SPACING) LONG BARREL COMPRESSION LUGS WITH TWO INDENTS

7 TYP. #2 "THHN" GREEN COMMON BONDING NETWORK CONDUCTOR (CBN). CONNECT TO "TMGB" USING TWO HOLE (5/8" SPACING) LONG BARREL COMPRESSION LUGS WITH TWO INDENTS.

8 TYP. ATTACH "CBN" TO TERMINAL BOARD USING NYLON CABLE TIE MOUNT WITH #10 SCREW AND CABLE TIE.

9 ATTACH "CBN" TO "L" BRACKETS USING NYLON CABLE TIE MOUNT WITH 10/24 BOLT AND CABLE TIE.

10 TYP. #6 "THHN" GREEN BONDING JUMPER FROM "CBN" TO CABLE TRAY. ATTACH TO CABLE TRAY USING TWO HOLE (5/8" SPACING) LONG BARREL COMPRESSION LUGS WITH TWO INDENTS MOUNTED TO SIDE OF TRAY USING 1/4-20 BOLTS. SCRAPE PAINT FROM SIDE OF TRAY PRIOR TO INSTALLATION. ATTACH TO "CBN" USING "HTAP" CABLE SPLICE WITH CLEAR PLASTIC COVERS.

11 TYP. #6 "THHN" GREEN BONDING JUMPER FROM "CBN" TO EQUIPMENT FRAME. ATTACH TO FRAME USING TWO HOLE (5/8" SPACING) LONG BARREL COMPRESSION LUGS WITH TWO INDENTS MOUNTED TO EQUIPMENT FRAME USING 1/4-20 BOLTS. ATTACH TO "CBN" USING "HTAP" CABLE SPLICE WITH CLEAR PLASTIC COVER.

1 MDF GROUNDING
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Stockbow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY: ML
CHECKED BY: KH
APPROVED BY: Approver
PROJECT NO.: 21-154
CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
SYSTEMS DETAILS

SHEET NUMBER
ES501

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:43 PM AESI Proj. No: 21-154

DATA DEVICE SCHEDULE

ROOM NO.	JACK I.D.	DATA QTY.	TV QTY.	VOICE QTY.	DISTRIBUTED FROM	NOTES
	CUP1-23	2	0	0	MDF 225	WAP
	CUP2-17	2	0	0	MDF 225	WAP
	CUP2-01	2	0	0	MDF 225	WAP
	A/B	2	0	0	MDF 225	CAMERA
	A/B	2	0	0	MDF 225	CAMERA
	A/B	2	0	0	MDF 225	CAMERA
	CUP2-04	2	0	0	MDF 225	WAP
	A/B	2	0	0	MDF 225	CAMERA
	AP-A/B	2	0	0	MDF 225	WAP
	AP-C/D	2	0	0	MDF 225	WAP
	AP-E/F	2	0	0	MDF 225	WAP
	AP-A/B	2	0	0	MDF 225	WAP
	AP-A/B	2	0	0	MDF 225	WAP
	A/B	2	0	0	MDF 225	ELEVATOR PHONE
	AC-A	2	0	0	MDF 225	CAMERA
	C/D	2	0	0	MDF 225	MONITOR
101	C/D	2	0	0	MDF 225	CAMERA
103	A/B	2	0	0	MDF 225	CAMERA
103	CUP1-03	2	0	0	MDF 225	WAP
104	A/B	2	0	0	MDF 225	CAMERA
105	CUP1-01	2	0	0	MDF 225	WAP
105	CUP1-22	2	0	0	MDF 225	WAP
105						
105	A/B	2	0	0	MDF 225	
105	CUP1-16	2	0	0	MDF 225	WAP
105						
109	CUP1-14	2	0	0	MDF 225	WAP
109	CUP1-15	2	0	0	MDF 225	WAP
109	A/B	2	0	0	MDF 225	CAMERA
109	C/D	2	0	0	MDF 225	CAMERA
109	A/B	2	0	0	MDF 225	CAMERA
109	E/F	2	0	0	MDF 225	CAMERA
109	CUP1-13	2	0	0	MDF 225	WAP
109	CUP1-24	2	0	0	MDF 225	WAP
109	CUP1-21	2	0	0	MDF 225	WAP
110	A/B	2	0	0	MDF 225	CAMERA
112	A/B	2	0	0	MDF 225	
112	G/H	2	0	0	MDF 225	MONITOR
112	CUP1-20	2	0	0	MDF 225	WAP
112	C/D	2	0	0	MDF 225	
112	E/F	2	0	0	MDF 225	
113	CUP1-08	2	0	0	MDF 225	WAP
113	CUP1-12	2	0	0	MDF 225	WAP
113	A/B	2	0	0	MDF 225	CAMERA
113	CUP1-09	2	0	0	MDF 225	WAP
113	CUP1-17	2	0	0	MDF 225	WAP
113	CUP1-11	2	0	0	MDF 225	WAP
113	CUP1-19	2	0	0	MDF 225	WAP
113	CUP1-18	2	0	0	MDF 225	WAP
113	CUP1-10	2	0	0	MDF 225	WAP
114	CUP1-06	2	0	0	MDF 225	WAP
114	CUP1-05	2	0	0	MDF 225	WAP
114	CUP1-02	2	0	0	MDF 225	WAP
114	CUP1-07	2	0	0	MDF 225	WAP
114	E/F	2	0	0	MDF 225	CAMERA
114	C/D	2	0	0	MDF 225	CAMERA
114	A/B	2	0	0	MDF 225	CAMERA
114	G/H	2	0	0	MDF 225	CAMERA
114						
114	CUP1-04	2	0	0	MDF 225	WAP
114	A/B	2	0	0	MDF 225	
201						
203	CUP2-06	2	0	0	MDF 225	WAP
203	A/B	2	0	0	MDF 225	
204	A/B	2	0	0	MDF 225	
205	A/B	2	0	0	MDF 225	WALL PHONE
206	CUP2-16	2	0	0	MDF 225	WAP
207-2	CUP3-01	2	0	0	MDF 225	WAP
208	A/B	2	0	0	MDF 225	
209	I/J	2	0	0	MDF 225	FIRE ALARM PANEL
209	G/H	2	0	0	MDF 225	SECURITY PANEL
209	K/L/M/N	4	0	0	MDF 225	
209	C/D	2	0	0	MDF 225	TV
209	A/B	2	0	0	MDF 225	
209	E/F	2	0	0	MDF 225	
210	CUP2-15	2	0	0	MDF 225	WAP
212	AP-E/F	2	0	0	MDF 225	WAP
212	CUP2-10	2	0	0	MDF 225	WAP
212	CUP2-09	2	0	0	MDF 225	WAP
215						
216	CUP2-12	2	0	0	MDF 225	WAP
216	CUP2-13	2	0	0	MDF 225	WAP
218	CUP2-18	2	0	0	MDF 225	WAP
218	A/B	2	0	0	MDF 225	CAMERA
218	C/D	2	0	0	MDF 225	CAMERA
220	CUP2-03	2	0	0	MDF 225	WAP
220	CUP2-08	2	0	0	MDF 225	WAP
220	CUP2-07	2	0	0	MDF 225	WAP
220	A/B	2	0	0	MDF 225	CAMERA
220	C/D	2	0	0	MDF 225	CAMERA
222	CUP2-05	2	0	0	MDF 225	WAP
225						
225						
225						
225						
225						
225						
225	A/B	2	0	0	MDF 225	CAMERA
225						
225						
225						
225						
226	A/B	2	0	0	MDF 225	
226	CUP2-02	2	0	0	MDF 225	WAP
227	CUP2-14	2	0	0	MDF 225	WAP
227	CUP2-19	2	0	0	MDF 225	WAP
227						

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION
CHECKED BY: KH	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SYSTEMS SCHEDULES

SHEET NUMBER

ES601

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:44 PM AESI Proj No: 21-154



1 **FIRE ALARM RISER**
Scale: NONE

GENERAL NOTES:


1. SEE SYMBOLS SHEET FOR FIRE ALARM SYMBOLS AND ABBREVIATIONS AND GENERAL NOTES.
2. SEE FLOOR PLANS FOR DEVICE QUANTITIES AND LOCATIONS.
3. FIRE PUMP RUNNING SHALL INITIATE A FIRE ALARM SIGNAL.
4. SYNCHRONIZE ALL STROBE IN FIELD OF VIEW.


(#) PLAN NOTES:

1. PROGRAM FACP TO RING EXTERNAL ALARM BELL WHEN ANY FLOW SWITCH HAS BEEN ACTIVATED. ALARM BELL TO BE MOUNTED ABOVE FIRE DEPARTMENT SIAMESE CONNECTION ON THE EXTERIOR OF THE BUILDING. ALARM BELL FURNISHED BY DIVISION 21 AND INSTALLED BY THE ELECTRICAL CONTRACTOR.
2. ELEVATOR RECALL CONSISTS OF:
   - 2.1. RECALL CAR TO PRIMARY FLOOR.
   - 2.2. RECALL CAR TO SECONDARY FLOOR
   - 2.3. FIREMAN'S WARNING (FIREMAN'S HAT)
3. MONITORING OF (2) FIRE PUMPS SHALL INCLUDE:
   - 3.1. FIRE PUMP LOSS OF POWER.
   - 3.2. FIRE PUMP LOSS OF PHASE/PHASE REVERSAL.
   - 3.3. FIRE PUMP RUNNING.
   - 3.4. FIRE PUMP ON EMERGENCY.
4. MONITORING OF (2) JOCKEY PUMPS SHALL INCLUDE
   - 4.1. LOSS OF POWER
   - 4.2. LOW SYSTEM PRESSURE

CABLING LEGEND (THIS DETAIL)	
1	NEW CAT 6A PLENUM UTP CABLE (BY DIVISION 27)
2	NEW CAT 6A PATCH CABLE (BY DIVISION 27)
3	NEW FIBER CABLING (BY OWNER)
4	NEW OSP FIBER OPTIC CABLE
5	EXISTING CABLING

SYMBOL LEGEND (THIS DETAIL)	
V	DATA JACK WITHIN BACK BOX
	CAMERA LOCATION







CABLING LEGEND (THIS DETAIL)	
1	NEW COMPOSITE CABLING
2	NEW CAT 6A PATCH CABLE
3	NEW RS-485 CABLE

SYMBOL LEGEND (THIS DETAIL)	
	DATA LOCATION
CR	CARD READER
EH	ELECTRONIC LOCKING HARDWARE

3 **SECURITY SYSTEM FUNCTIONAL DIAGRAM**
Scale: NONE





2 **MDF RISER DISTRIBUTION DIAGRAM**
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: ML	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: KH	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SYSTEMS DIAGRAMS

SHEET NUMBER

ES701

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 12:36:44 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP606 FOR SCHEDULES.
3. SEE DRAWING SERIES EP701 FOR DIAGRAMS.

(#) PLAN NOTES:

1. UP TO DRAWING EP304..
2. SEE DRAWING EP515 FOR SECTION.

LOWER LEVEL 13,200V POWER PLAN- AREA A

Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

LOWER LEVEL 13,200V POWER PLAN - AREA A

SHEET NUMBER

EP301



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:55:11 PM AESI Proj. No: 21-154

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP606 FOR SCHEDULES.
3. SEE DRAWING SERIES EP701 FOR DIAGRAMS.

(#) PLAN NOTES:

1. UP TO DRAWING EP306.
2. SEE DRAWING EP515 FOR SECTION.



LOWER LEVEL 13,200V POWER PLAN- AREA C

Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

LOWER LEVEL 13,200V POWER PLAN - AREA C

SHEET NUMBER

EP303

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:56:12 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



FIRST FLOOR 13,200V POWER PLAN - AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP509 AND EP510 FOR DETAILS.
3. SEE DRAWING SERIES EP606 FOR SCHEDULES.
4. SEE DRAWING SERIES EP706 FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRICAL CONNECTION FOR CH-4. SEE MEDIUM VOLTAGE CABLE SCHEDULE ON E606 FOR DETAILS.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 13,200V POWER PLAN - AREA A


SHEET NUMBER

EP304



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:56:16 PM AESI Proj No: 21-154
0 1/2" 1" 2"



FIRST FLOOR 13,200V POWER PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP509 FOR DETAILS.
3. SEE DRAWING SERIES EP606 FOR SCHEDULES.
4. SEE DRAWING SERIES EP706 FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRICAL CONNECTION FOR CH-5. SEE MEDIUM VOLTAGE CABLE SCHEDULE ON E606 FOR DETAILS.
2. PROVIDE ELECTRICAL CONNECTION FOR CH-6. SEE MEDIUM VOLTAGE CABLE SCHEDULE ON E606 FOR DETAILS.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:56:23 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 13,200V POWER PLAN - AREA B

SHEET NUMBER

EP305



GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP510 FOR DETAILS.
3. SEE DRAWING SERIES EP606 FOR SCHEDULES.
4. SEE DRAWING SERIES EP701 AND EP702 FOR DIAGRAMS.

(#) PLAN NOTES:

1. INSTALL UTILITY FURNISHED METERING CABINET. COORDINATE LOCATION WITH UTILITY. PROVIDE 2"C TO POWER CHASE FOR CT CABLING.

FIRST FLOOR 13,200V POWER PLAN - AREA C

Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 13,200V POWER PLAN - AREA C

SHEET NUMBER


EP306



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:55:32 PM AESI Proj. No: 21-154



GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP509 FOR DETAILS.
3. SEE DRAWING SERIES EP606 FOR SCHEDULES.
4. SEE DRAWING SERIES EP707 FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRICAL CONNECTION FOR CH-1. SEE MEDIUM VOLTAGE CABLE SCHEDULE ON E606 FOR DETAILS.

FIRST FLOOR 13,200V POWER PLAN - AREA D

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:56:35 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 13,200V POWER PLAN - AREA D

SHEET NUMBER

EP307



FIRST FLOOR 13,200V POWER PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP509 FOR DETAILS.
3. SEE DRAWING SERIES EP606 FOR SCHEDULES.
4. SEE DRAWING SERIES EP707 FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE UNIT SUBSTATION USS-MECH-1. SEE EP504 AND EP704 FOR DETAILS.
2. PROVIDE UNIT SUBSTATION USS-MECH-2. SEE EP504 AND EP705 FOR DETAILS.
3. PROVIDE 4" HOUSEKEEPING PAD. SEE STRUCTURAL DRAWINGS FOR DETAILS.
4. PROVIDE ELECTRICAL CONNECTION FOR CH-4. SEE MEDIUM VOLTAGE CABLE SCHEDULE ON E606 FOR DETAILS.
5. PROVIDE ELECTRICAL CONNECTION FOR CH-6. SEE MEDIUM VOLTAGE CABLE SCHEDULE ON E606 FOR DETAILS.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:56:39 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadrone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 13,200V POWER PLAN - AREA E

SHEET NUMBER

EP308



FIRST FLOOR 13,200V POWER PLAN - AREA F


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP510 FOR DETAILS.
3. SEE DRAWING SERIES EP606 FOR SCHEDULES.
4. SEE DRAWING SERIES EP706 AND EP707 FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE UNIT SUBSTATION USS-CH-1. SEE EP503 AND EP706 FOR DETAILS.
2. PROVIDE UNIT SUBSTATION USS-CH-2. SEE EP503 AND EP707 FOR DETAILS.
3. PROVIDE 4" HOUSEKEEPING PAD. SEE STRUCTURAL DRAWINGS FOR DETAILS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR 13,200V POWER PLAN - AREA F

SHEET NUMBER

EP309

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:56:41 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



SECOND FLOOR 13,200V POWER PLAN - AREA A


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. INSTALL EG-1. PROVIDE ELECTRICAL CONNECTION FOR EG-1. PROVIDE CONTROLS CONNECTIONS FOR EG-1. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR1.
2. INSTALL EG-2. PROVIDE ELECTRICAL CONNECTION FOR EG-2. PROVIDE CONTROLS CONNECTIONS FOR EG-2. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR2.
3. PROVIDE MEDIUM VOLTAGE PULL BOX. 5'-6" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.
4. PROVIDE MEDIUM VOLTAGE PULL BOX. 6'-0" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadylane Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR 13,200V POWER PLAN - AREA A

SHEET NUMBER

EP311

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:56:56 PM AESI Proj No: 21-154



SECOND FLOOR 13,200V POWER PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. INSTALL EG-3. PROVIDE ELECTRICAL CONNECTION FOR EG-3. PROVIDE CONTROLS CONNECTIONS FOR EG-3. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR3.
2. INSTALL EG-4. PROVIDE ELECTRICAL CONNECTION FOR EG-4. PROVIDE CONTROLS CONNECTIONS FOR EG-4. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR4.
3. INSTALL EG-5. PROVIDE ELECTRICAL CONNECTION FOR EG-5. PROVIDE CONTROLS CONNECTIONS FOR EG-5. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR5.
4. INSTALL EG-6. PROVIDE ELECTRICAL CONNECTION FOR EG-6. PROVIDE CONTROLS CONNECTIONS FOR EG-6. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR6.
5. INSTALL EG-7. PROVIDE ELECTRICAL CONNECTION FOR EG-7. PROVIDE CONTROLS CONNECTIONS FOR EG-7. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR7.
6. INSTALL EG-8. PROVIDE ELECTRICAL CONNECTION FOR EG-8. PROVIDE CONTROLS CONNECTIONS FOR EG-8. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR8.
7. INSTALL EG-9. PROVIDE ELECTRICAL CONNECTION FOR EG-9. PROVIDE CONTROLS CONNECTIONS FOR EG-9. (2) 1"C, (20)TWISTED SHIELDED PAIR EACH AND (1)2"C, (4)#10 & (1)#10GND FOR CTS. INSTALL NGR9.
8. SEE EP315 FOR NOTES ON SWITCHGEAR PS.
9. PROVIDE MEDIUM VOLTAGE PULL BOX. 5'-6" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.
10. PROVIDE MEDIUM VOLTAGE PULL BOX. 6'-0" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.
11. PROVIDE MEDIUM VOLTAGE PULL BOX. 6'-6" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.
12. PROVIDE MEDIUM VOLTAGE PULL BOX. 4'-6" X 4'-6"" X 2'-0", NEMA 1, BOLTED COVER FACING DOWN.
13. PROVIDE MEDIUM VOLTAGE PULL BOX. 5'-0" X 5'-0" X 2'-0", NEMA 1, BOLTED COVER FACING DOWN.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:57:00 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadowview Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR 13,200V POWER PLAN - AREA B

SHEET NUMBER

EP312



GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. INSTALL MAIN SERVICE SWITCHGEAR MSS. SEE EP502 AND EP702 FOR DETAILS.
2. PROVIDE 4" HOUSEKEEPING PAD. SEE STRUCTURAL DRAWINGS FOR DETAILS.
3. PROVIDE DC BATTERY SYSTEM FOR SWITCHGEAR POWER. SEE DETAILS ON EP708.
4. PROVIDE DC PANELBOARD 2DCN3.
5. PROVIDE DC PANELBOARD 2DCN4.

SECOND FLOOR 13,200V POWER PLAN - AREA C

Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Seahorse Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR 13,200V POWER PLAN - AREA C


SHEET NUMBER

EP313



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:57:04 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



SECOND FLOOR 13,200V POWER PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE MEDIUM VOLTAGE PULL BOX. 5'-6" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.
2. PROVIDE MEDIUM VOLTAGE PULL BOX. 6'-0" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.
3. PROVIDE MEDIUM VOLTAGE PULL BOX. 6'-6" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE


SECOND FLOOR 13,200V POWER PLAN - AREA D

SHEET NUMBER

EP314

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:57:09 PM AESI Proj. No: 21-154


MATCHLINE - SEE EP314
MATCHLINE - SEE EP316
MATCHLINE - SEE EP312
F.E.C.
HMI DASHBOARD
CORRIDOR
247
CONTROL
211
SWITCHGEAR DC BATTERY CHARGER
BATTERY RACK 400A FUSED DISCONNECT SWITCH
BATTERY RACK
2DCN2
2DCN1
GENERATOR SWITCHGEAR
210
15kV SWITCHGEAR
212
FUEL OIL DAY TANKS B
213
MV-ATS-IUH-EQ-A
MV-ATS-IUH-EQ-B
MV-ATS-IUH-OS-A
MV-ATS-IUH-OS-B
MV-ATS-CUP-MECH-A
MV-ATS-CUP-MECH-B
MV-ATS-CUP-CH-A
MV-ATS-CUP-CH-B
FRONT
PT/F1
E1/E2
PT/AUX
N1/N2
F2
F3/F4
3' - 0" TYP.
7' - 7"
TYP.
0' - 7 1/2"
7' - 7"
3' - 0" TYP.
PS
G1
G2
G3
G4
G5
F1/F2
F3/F4
F5/F6
F7/F8
F9/F10
PTS/BUS
TIE/PTS
F11/F12
F13/F14
F15/F16
F17/F18
F19/F20
G6
G7
G8
G9
G10
EP503
EP508
EP507
EP505
EP504
EP506
EP509
EP510
EP511
EP512
EP513
EP514
EP515
EP516
EP517
EP518
EP519
EP520
EP521
EP522
EP523
EP524
EP525
EP526
EP527
EP528
EP529
EP530
EP531
EP532
EP533
EP534
EP535
EP536
EP537
EP538
EP539
EP540
EP541
EP542
EP543
EP544
EP545
EP546
EP547
EP548
EP549
EP550
EP551
EP552
EP553
EP554
EP555
EP556
EP557
EP558
EP559
EP560
EP561
EP562
EP563
EP564
EP565
EP566
EP567
EP568
EP569
EP570
EP571
EP572
EP573
EP574
EP575
EP576
EP577
EP578
EP579
EP580
EP581
EP582
EP583
EP584
EP585
EP586
EP587
EP588
EP589
EP590
EP591
EP592
EP593
EP594
EP595
EP596
EP597
EP598
EP599
EP5100
EP5101
EP5102
EP5103
EP5104
EP5105
EP5106
EP5107
EP5108
EP5109
EP5110
EP5111
EP5112
EP5113
EP5114
EP5115
EP5116
EP5117
EP5118
EP5119
EP5120
EP5121
EP5122
EP5123
EP5124
EP5125
EP5126
EP5127
EP5128
EP5129
EP5130
EP5131
EP5132
EP5133
EP5134
EP5135
EP5136
EP5137
EP5138
EP5139
EP5140
EP5141
EP5142
EP5143
EP5144
EP5145
EP5146
EP5147
EP5148
EP5149
EP5150
EP5151
EP5152
EP5153
EP5154
EP5155
EP5156
EP5157
EP5158
EP5159
EP5160
EP5161
EP5162
EP5163
EP5164
EP5165
EP5166
EP5167
EP5168
EP5169
EP5170
EP5171
EP5172
EP5173
EP5174
EP5175
EP5176
EP5177
EP5178
EP5179
EP5180
EP5181
EP5182
EP5183
EP5184
EP5185
EP5186
EP5187
EP5188
EP5189
EP5190
EP5191
EP5192
EP5193
EP5194
EP5195
EP5196
EP5197
EP5198
EP5199
EP5200
EP5201
EP5202
EP5203
EP5204
EP5205
EP5206
EP5207
EP5208
EP5209
EP5210
EP5211
EP5212
EP5213
EP5214
EP5215
EP5216
EP5217
EP5218
EP5219
EP5220
EP5221
EP5222
EP5223
EP5224
EP5225
EP5226
EP5227
EP5228
EP5229
EP5230
EP5231
EP5232
EP5233
EP5234
EP5235
EP5236
EP5237
EP5238
EP5239
EP5240
EP5241
EP5242
EP5243
EP5244
EP5245
EP5246
EP5247
EP5248
EP5249
EP5250
EP5251
EP5252
EP5253
EP5254
EP5255
EP5256
EP5257
EP5258
EP5259
EP5260
EP5261
EP5262
EP5263
EP5264
EP5265
EP5266
EP5267
EP5268
EP5269
EP5270
EP5271
EP5272
EP5273
EP5274
EP5275
EP5276
EP5277
EP5278
EP5279
EP5280
EP5281
EP5282
EP5283
EP5284
EP5285
EP5286
EP5287
EP5288
EP5289
EP5290
EP5291
EP5292
EP5293
EP5294
EP5295
EP5296
EP5297
EP5298
EP5299
EP5300
EP5301
EP5302
EP5303
EP5304
EP5305
EP5306
EP5307
EP5308
EP5309
EP5310
EP5311
EP5312
EP5313
EP5314
EP5315
EP5316
EP5317
EP5318
EP5319
EP5320
EP5321
EP5322
EP5323
EP5324
EP5325
EP5326
EP5327
EP5328
EP5329
EP5330
EP5331
EP5332
EP5333
EP5334
EP5335
EP5336
EP5337
EP5338
EP5339
EP5340
EP5341
EP5342
EP5343
EP5344
EP5345
EP5346
EP5347
EP5348
EP5349
EP5350
EP5351
EP5352
EP5353
EP5354
EP5355
EP5356
EP5357
EP5358
EP5359
EP5360
EP5361
EP5362
EP5363
EP5364
EP5365
EP5366
EP5367
EP5368
EP5369
EP5370
EP5371
EP5372
EP5373
EP5374
EP5375
EP5376
EP5377
EP5378
EP5379
EP5380
EP5381
EP5382
EP5383
EP5384
EP5385
EP5386
EP5387
EP5388
EP5389
EP5390
EP5391
EP5392
EP5393
EP5394
EP5395
EP5396
EP5397
EP5398
EP5399
EP5400
EP5401
EP5402
EP5403
EP5404
EP5405
EP5406
EP5407
EP5408
EP5409
EP5410
EP5411
EP5412
EP5413
EP5414
EP5415
EP5416
EP5417
EP5418
EP5419
EP5420
EP5421
EP5422
EP5423
EP5424
EP5425
EP5426
EP5427
EP5428
EP5429
EP5430
EP5431
EP5432
EP5433
EP5434
EP5435
EP5436
EP5437
EP5438
EP5439
EP5440
EP5441
EP5442
EP5443
EP5444
EP5445
EP5446
EP5447
EP5448
EP5449
EP5450
EP5451
EP5452
EP5453
EP5454
EP5455
EP5456
EP5457
EP5458
EP5459
EP5460
EP5461
EP5462
EP5463
EP5464
EP5465
EP5466
EP5467
EP5468
EP5469
EP5470
EP5471
EP5472
EP5473
EP5474
EP5475
EP5476
EP5477
EP5478
EP5479
EP5480
EP5481
EP5482
EP5483
EP5484
EP5485
EP5486
EP5487
EP5488
EP5489
EP5490
EP5491
EP5492
EP5493
EP5494
EP5495
EP5496
EP5497
EP5498
EP5499
EP5500
EP5501
EP5502
EP5503
EP5504
EP5505
EP5506
EP5507
EP5508
EP5509
EP5510
EP5511
EP5512
EP5513
EP5514
EP5515
EP5516
EP5517
EP5518
EP5519
EP5520
EP5521
EP5522
EP5523
EP5524
EP5525
EP5526
EP5527
EP5528
EP5529
EP5530
EP5531
EP5532
EP5533
EP5534
EP5535
EP5536
EP5537
EP5538
EP5539
EP5540
EP5541
EP5542
EP5543
EP5544
EP5545
EP5546
EP5547
EP5548
EP5549
EP5550
EP5551
EP5552
EP5553
EP5554
EP5555
EP5556
EP5557
EP5558
EP5559
EP5560
EP5561
EP5562
EP5563
EP5564
EP5565
EP5566
EP5567
EP5568
EP5569
EP5570
EP5571
EP5572
EP5573
EP5574
EP5575
EP5576
EP5577
EP5578
EP5579
EP5580
EP5581
EP5582
EP5583
EP5584
EP5585
EP5586
EP5587
EP5588
EP5589
EP5590
EP5591
EP5592
EP5593
EP5594
EP5595
EP5596
EP5597
EP5598
EP5599
EP5600
EP5601
EP5602
EP5603
EP5604
EP5605
EP5606
EP5607
EP5608
EP5609
EP5610
EP5611
EP5612
EP5613
EP5614
EP5615
EP5616
EP5617
EP5618
EP5619
EP5620
EP5621
EP5622
EP5623
EP5624
EP5625
EP5626
EP5627
EP5628
EP5629
EP5630
EP5631
EP5632
EP5633
EP5634
EP5635
EP5636
EP5637
EP5638
EP5639
EP5640
EP5641
EP5642
EP5643
EP5644
EP5645
EP5646
EP5647
EP5648
EP5649
EP5650
EP5651
EP5652
EP5653
EP5654
EP5655
EP5656
EP5657
EP5658
EP5659
EP5660
EP5661
EP5662
EP5663
EP5664
EP5665
EP5666
EP5667
EP5668
EP5669
EP5670
EP5671
EP5672
EP5673
EP5674
EP5675
EP5676
EP5677
EP5678
EP5679
EP5680
EP5681
EP5682
EP5683
EP5684
EP5685
EP5686
EP5687
EP5688
EP5689
EP5690
EP5691
EP5692
EP5693
EP5694
EP5695
EP5696
EP5697
EP5698
EP5699
EP5700
EP5701
EP5702
EP5703
EP5704
EP5705
EP5706
EP5707
EP5708
EP5709
EP5710
EP5711
EP5712
EP5713
EP5714
EP5715
EP5716
EP5717
EP5718
EP5719
EP5720
EP5721
EP5722
EP5723
EP5724
EP5725
EP5726
EP5727
EP5728
EP5729
EP5730
EP5731
EP5732
EP5733
EP5734
EP5735
EP5736
EP5737
EP5738
EP5739
EP5740
EP5741
EP5742
EP5743
EP5744
EP5745
EP5746
EP5747
EP5748
EP5749
EP5750
EP5751
EP5752
EP5753
EP5754
EP5755
EP5756
EP5757
EP5758
EP5759
EP5760
EP5761
EP5762
EP5763
EP5764
EP5765
EP5766
EP5767
EP5768
EP5769
EP5770
EP5771
EP5772
EP5773
EP5774
EP5775
EP5776
EP5777
EP5778
EP5779
EP5780
EP5781
EP5782
EP5783
EP5784
EP5785
EP5786
EP5787
EP5788
EP5789
EP5790
EP5791
EP5792
EP5793
EP5794
EP5795
EP5796
EP5797
EP5798
EP5799
EP5800
EP5801
EP5802
EP5803
EP5804
EP5805
EP5806
EP5807
EP5808
EP5809
EP5810
EP5811
EP5812
EP5813
EP5814
EP5815
EP5816
EP5817
EP5818
EP5819
EP5820
EP5821
EP5822
EP5823
EP5824
EP5825
EP5826
EP5827
EP5828
EP5829
EP5830
EP5831
EP5832
EP5833
EP5834
EP5835
EP5836
EP5837
EP5838
EP5839
EP5840
EP5841
EP5842
EP5843
EP5844
EP5845
EP5846
EP5847
EP5848
EP5849
EP5850
EP5851
EP5852
EP5853
EP5854
EP5855
EP5856
EP5857
EP5858
EP5859
EP5860
EP5861
EP5862
EP5863
EP5864
EP5865
EP5866
EP5867
EP5868
EP5869
EP5870
EP5871
EP5872
EP5873
EP5874
EP5875
EP5876
EP5877
EP5878
EP5879
EP5880
EP5881
EP5882
EP5883
EP5884
EP5885
EP5886
EP5887
EP5888
EP5889
EP5890
EP5891
EP5892
EP5893
EP5894
EP5895
EP5896
EP5897
EP5898
EP5899
EP5900
EP5901
EP5902
EP5903
EP5904
EP5905
EP5906
EP5907
EP5908
EP5909
EP5910
EP5911
EP5912
EP5913
EP5914
EP5915
EP5916
EP5917
EP5918
EP5919
EP5920
EP5921
EP5922
EP5923
EP5924
EP5925
EP5926
EP5927
EP5928
EP5929
EP5930
EP5931
EP5932
EP5933
EP5934
EP5935
EP5936
EP5937
EP5938
EP5939
EP5940
EP5941
EP5942
EP5943
EP5944
EP5945
EP5946
EP5947
EP5948
EP5949
EP5950
EP5951
EP5952
EP5953
EP5954
EP5955
EP5956
EP5957
EP5958
EP5959
EP5960
EP5961
EP5962
EP5963
EP5964
EP5965
EP5966
EP5967
EP5968
EP5969
EP5970
EP5971
EP5972
EP5973
EP5974
EP5975
EP5976
EP5977
EP5978
EP5979
EP5980
EP5981
EP5982
EP5983
EP5984
EP5985
EP5986
EP5987
EP5988
EP5989
EP5990
EP5991
EP5992
EP5993
EP5994
EP5995
EP5996
EP5997
EP5998
EP5999
EP6000
EP6001
EP6002
EP6003
EP6004
EP6005
EP6006
EP6007
EP6008
EP6009
EP6010
EP6011
EP6012
EP6013
EP6014
EP6015
EP6016
EP6017
EP6018
EP6019
EP6020
EP6021
EP6022
EP6023
EP6024
EP6025
EP6026
EP6027
EP6028
EP6029
EP6030
EP6031
EP6032
EP6033
EP6034
EP6035
EP6036
EP6037
EP6038
EP6039
EP6040
EP6041
EP6042
EP6043
EP6044
EP6045
EP6046
EP6047
EP6048
EP6049
EP6050
EP6051
EP6052
EP6053
EP6054
EP6055
EP6056
EP6057
EP6058
EP6059
EP6060
EP6061
EP6062
EP6063
EP6064
EP6065
EP6066
EP6067
EP6068
EP6069
EP6070
EP6071
EP6072
EP6073
EP6074
EP6075
EP6076
EP6077
EP6078
EP6079
EP6080
EP6081
EP6082
EP6083
EP6084
EP6085
EP6086
EP6087
EP6088
EP6089
EP6090
EP6091
EP6092
EP6093
EP6094
EP6095
EP6096
EP6097
EP6098
EP6099
EP6100
EP6101
EP6102
EP6103
EP6104
EP6105
EP6106
EP6107
EP6108
EP6109
EP6110
EP6111
EP6112
EP6113
EP6114
EP6115
EP6116
EP6117
EP6118
EP6119
EP6120
EP6121
EP6122
EP6123
EP6124
EP6125
EP6126
EP6127
EP6128
EP6129
EP6130
EP6131
EP6132
EP6133
EP6134
EP6135
EP6136
EP6137
EP6138
EP6139
EP6140
EP6141
EP6142
EP6143
EP6144
EP6145
EP6146
EP6147
EP6148
EP6149
EP6150
EP6151
EP6152
EP6153
EP6154
EP6155
EP6156
EP6157
EP6158
EP6159
EP6160
EP6161
EP6162
EP6163
EP6164
EP6165
EP6166
EP6167
EP6168
EP6169
EP6170
EP6171
EP6172
EP6173
EP6174
EP6175
EP6176
EP6177
EP6178
EP6179
EP6180
EP6181
EP6182
EP6183
EP6184
EP6185
EP6186
EP6187
EP6188
EP6189
EP6190
EP6191
EP6192
EP6193
EP6194
EP6195
EP6196
EP6197
EP6198
EP6199
EP6200
EP6201
EP6202
EP6203
EP6204
EP6205
EP6206
EP6207
EP6208
EP6209
EP6210
EP6211
EP6212
EP6213
EP6214
EP6215
EP6216
EP6217
EP6218
EP6219
EP6220
EP6221
EP6222
EP6223
EP6224
EP6225
EP6226
EP6227
EP6228
EP6229
EP6230
EP6231
EP6232
EP6233
EP6234
EP6235
EP6236
EP6237
EP6238
EP6239
EP6240
EP6241
EP6242
EP6243
EP6244
EP6245
EP6246
EP6247
EP6248
EP6249
EP6250
EP6251
EP6252
EP6253
EP6254
EP6255
EP6256
EP6257
EP6258
EP6259
EP6260
EP6261
EP6262
EP6263
EP6264
EP6265
EP6266
EP6267
EP6268
EP6269
EP6270
EP6271
EP6272
EP6273
EP6274
EP6275
EP6276
EP6277
EP6278
EP6279
EP6280
EP6281
EP6282
EP6283
EP6284
EP6285
EP6286
EP6287
EP6288
EP6289
EP6290
EP6291
EP6292
EP6293
EP6294
EP6295
EP6296
EP6297
EP6298
EP6299
EP6300
EP6301
EP6302
EP6303
EP6304
EP6305
EP6306
EP6307
EP6308
EP6309
EP6310
EP6311
EP6312
EP6313
EP6314
EP6315
EP6316
EP6317
EP6318
EP6319
EP6320
EP6321
EP6322
EP6323
EP6324
EP6325
EP6326
EP6327
EP6328
EP6329
EP6330
EP6331
EP6332
EP6333
EP6334
EP6335
EP6336
EP6337
EP6338
EP6339
EP6340
EP6341
EP6342
EP6343
EP6344
EP6345
EP6346
EP6347
EP6348
EP6349
EP6350
EP6351
EP6352
EP6353
EP6354
EP6355
EP6356
EP6357
EP6358
EP6359
EP6360
EP6361
EP6362
EP6363
EP6364
EP6365
EP6366
EP6367
EP6368
EP6369
EP6370
EP6371
EP6372
EP6373
EP6374
EP6375
EP6376
EP6377
EP6378
EP6379
EP6380
EP6381
EP6382
EP6383
EP6384
EP6385
EP6386
EP6387
EP6388
EP6389
EP6390
EP6391
EP6392
EP6393
EP6394
EP6395
EP6396
EP6397
EP6398
EP6399
EP6400
EP6401
EP6402
EP6403
EP6404
EP6405
EP6406
EP6407
EP6408
EP6409
EP6410
EP6411
EP6412
EP6413
EP6414
EP6415
EP6416
EP6417
EP6418
EP6419
EP6420
EP6421
EP6422
EP6423
EP6424
EP6425
EP6426
EP6427
EP6428
EP6429
EP6430
EP6431
EP6432
EP6433
EP6434
EP6435
EP6436
EP6437
EP6438
EP6439
EP6440
EP6441
EP6442
EP6443
EP6444
EP6445
EP6446
EP6447
EP6448
EP6449
EP6450
EP6451
EP6452
EP6453
EP6454
EP6455
EP6456
EP6457
EP6458
EP6459
EP6460
EP6461
EP6462
EP6463
EP6464
EP6465
EP6466
EP6467
EP6468
EP6469
EP6470
EP6471
EP6472
EP6473
EP6474
EP6475
EP6476
EP6477
EP6478
EP6479
EP6480
EP6481
EP6482
EP6483
EP6484
EP6485
EP6486
EP6487
EP6488
EP6489
EP6490
EP6491
EP6492
EP6493
EP6494
EP6495
EP6496
EP6497
EP6498
EP6499
EP6500
EP6501
EP6502
EP6503
EP6504
EP6505
EP6506
EP6507
EP6508
EP6509
EP6510
EP6511
EP6512
EP6513
EP6514
EP6515
EP6516
EP6517
EP6518
EP6519
EP6520
EP6521
EP6522
EP6523
EP6524
EP6525
EP6526
EP6527
EP6528
EP6529
EP6530
EP6531
EP6532
EP6533
EP6534
EP6535
EP6536
EP6537
EP6538
EP6539
EP6540
EP6541
EP6542
EP6543
EP6544
EP6545
EP6546
EP6547
EP6548
EP6549
EP6550
EP6551
EP6552
EP6553
EP6554
EP6555
EP6556
EP6557
EP6558
EP6559
EP6560
EP6561
EP6562
EP6563
EP6564
EP6565
EP6566
EP6567
EP6568
EP6569
EP6570
EP6571
EP6572
EP6573
EP6574
EP6575
EP6576
EP6577
EP6578
EP6579
EP6580
EP6581
EP6582
EP6583
EP6584
EP6585
EP6586
EP6587
EP6588
EP6589
EP6590
EP6591
EP6592
EP6593
EP6594
EP6595
EP6596
EP6597
EP6598
EP6599
EP6600
EP6601
EP6602
EP6603
EP6604
EP6605
EP6606
EP6607
EP6608
EP6609
EP6610
EP6611
EP6612
EP6613
EP6614
EP6615
EP6616
EP6617
EP6618
EP6619
EP6620
EP6621
EP6622
EP6623
EP6624
EP6625
EP6626
EP6627
EP6628
EP6629
EP6630
EP6631
EP6632
EP6633
EP6634
EP6635
EP6636
EP6637
EP6638
EP6639
EP6640
EP6641
EP6642
EP6643
EP6644
EP6645
EP6646
EP6647
EP6648
EP6649
EP6650
EP6651
EP6652
EP6653
EP6654
EP6655
EP6656
EP6657
EP6658
EP6659
EP6660
EP6661
EP6662
EP6663
EP6664
EP6665
EP6666
EP6667
EP6668
EP6669
EP6670
EP6671
EP6672
EP6673
EP6674
EP6675
EP6676
EP6677
EP6678
EP6679
EP6680
EP6681
EP6682
EP6683
EP6684
EP6685
EP6686
EP6687
EP6688
EP6689
EP6690
EP6691
EP6692
EP6693
EP6694
EP6695
EP6696
EP6697
EP6698
EP6699
EP6700
EP6701
EP6702
EP6703
EP6704
EP6705
EP6706
EP6707
EP6708
EP6709
EP6710
EP6711
EP6712
EP6713
EP6714
EP6715
EP6716
EP6717
EP6718
EP6719
EP6720
EP6721
EP6722
EP6723
EP6724
EP6725
EP6726
EP6727
EP6728
EP6729
EP6730
EP6731
EP6732
EP6733
EP6734
EP6735
EP6736
EP6737
EP6738
EP6739
EP6740
EP6741
EP6742
EP6743
EP6744
EP6745
EP6746
EP6747
EP6748
EP6749
EP6750
EP6751
EP6752
EP6753
EP6754
EP6755
EP6756
EP6757
EP6758
EP6759
EP6760
EP6761
EP6762
EP6763
EP6764
EP6765
EP6766
EP6767
EP6768
EP6769
EP6770
EP6771
EP6772
EP6773
EP6774
EP6775
EP6776
EP6777
EP6778
EP6779
EP6780
EP6781
EP6782
EP6783
EP6784
EP6785
EP6786
EP6787
EP6788
EP6789
EP6790
EP6791
EP6792
EP6793
EP6794
EP6795
EP6796
EP6797
EP6798
EP6799
EP6800
EP6801
EP6802
EP6803
EP6804
EP6805
EP6806
EP6807
EP6808
EP6809
EP6810
EP6811
EP6812
EP6813
EP6814
EP6815
EP6816
EP6817
EP6818
EP6819
EP6820
EP6821
EP6822
EP6823
EP6824
EP6825
EP6826
EP6827
EP6828
EP6829
EP6830
EP6831
EP6832
EP6833
EP6834
EP6835
EP6836
EP6837
EP6838
EP6839
EP6840
EP6841
EP6842
EP6843
EP6844
EP6845
EP6846
EP6847
EP6848
EP6849
EP6850
EP6851
EP6852
EP6853
EP6854
EP6855
EP6856
EP6857
EP6858
EP6859
EP6860
EP6861
EP6862
EP6863
EP6864
EP6865
EP6866
EP6867
EP6868
EP6869
EP6870
EP6871
EP6872
EP6873
EP6874
EP6875
EP6876
EP6877
EP6878
EP6879
EP6880
EP6881
EP6882
EP6883
EP6884
EP6885
EP6886
EP6887
EP6888
EP6889
EP6890
EP6891
EP6892
EP6893
EP6894
EP6895
EP6896
EP6897
EP6898
EP6899
EP6900
EP6901
EP6902
EP6903
EP6904
EP6905
EP6906
EP6907
EP6908
EP6909
EP6910
EP6911
EP6912
EP6913
EP6914
EP6915
EP6916
EP6917
EP6918
EP6919
EP6920
EP6921
EP6922
EP6923
EP6924
EP6925
EP6926
EP6927
EP6928
EP6929
EP6930
EP6931
EP6932
EP6933
EP6934
EP6935
EP6936
EP6937
EP6938
EP6939
EP6940
EP6941
EP6942
EP6943
EP6944
EP6945
EP6946
EP6947
EP6948
EP6949
EP6950
EP6951
EP6952
EP6953
EP6954
EP6955
EP6956
EP6957
EP6958
EP6959
EP6960
EP6961
EP6962
EP6963
EP6964
EP6965
EP6966
EP6967
EP6968
EP6969
EP6970
EP6971
EP6972
EP6973
EP6974
EP6975
EP6976
EP6977
EP6978
EP6979
EP6980
EP6981
EP6982
EP6983
EP6984
EP6985
EP6986
EP6987
EP6988
EP6989
EP6990
EP6991
EP6992
EP6993
EP6994
EP6995
EP6996
EP6997
EP6998
EP6999
EP7000
EP7001
EP7002
EP7003
EP7004
EP7005
EP7006
EP7007
EP7008
EP7009
EP7010
EP7011
EP7012
EP7013
EP7014
EP7015
EP7016
EP7017
EP7018
EP7019
EP7020
EP7021
EP7022
EP7023
EP7024
EP7025
EP7026
EP7027
EP7028
EP7029
EP7030
EP7031
EP7032
EP7033
EP7034
EP7035
EP7036
EP7037
EP7038
EP7039
EP7040
EP7041
EP7042
EP7043
EP7044
EP7045
EP7046
EP7047
EP7048
EP7049
EP7050
EP7051
EP7052
EP7053
EP7054
EP7055
EP7056
EP7057
EP7058
EP7059
EP7060
EP7061
EP7062
EP7063
EP7064
EP7065
EP7066
EP7067
EP7068
EP7069
EP7070
EP7071
EP7072
EP7073
EP7074
EP7075
EP7076
EP7077
EP7078
EP7079
EP7080
EP7081
EP7082
EP7083
EP7084
EP7085
EP7086
EP7087
EP7088
EP7089
EP7090
EP7091
EP7092
EP7093
EP7094
EP7095
EP7096
EP7097
EP7098
EP7099
EP7100
EP7101
EP7102
EP7103
EP7104
EP7105
EP7106
EP7107
EP7108
EP7109
EP7110
EP7111
EP7112
EP7113
EP7114
EP7115
EP7116
EP7117
EP7118
EP7119
EP7120
EP7121
EP7122
EP7123
EP7124
EP7125
EP7126
EP7127
EP7128
EP7129
EP7130
EP7131
EP7132
EP7133
EP7134
EP7135
EP7136
EP7137
EP7138
EP7139
EP7140
EP7141
EP7142
EP7143
EP7144
EP7145
EP7146
EP7147
EP7148
EP7149
EP7150
EP7151
EP7152
EP7153
EP7154
EP7155
EP7156
EP7157
EP7158
EP7159
EP7160
EP7161
EP7162
EP7163
EP7164
EP7165
EP7166
EP7167
EP7168
EP7169
EP7170
EP7171
EP7172
EP7173
EP7174
EP7175
EP7176
EP7177
EP7178
EP7179
EP7180
EP7181
EP7182
EP7183
EP7184
EP7185
EP7186
EP7187
EP7188
EP7189
EP7190
EP7191
EP7192
EP7193
EP7194
EP7195
EP7196
EP7197
EP7198
EP7199
EP7200
EP7201
EP7202
EP7203
EP7204
EP7205
EP7206
EP7207
EP7208
EP7209
EP7210
EP7211
EP7212
EP7213
EP7214
EP7215
EP7216
EP7217
EP7218
EP7219
EP7220
EP7221
EP7222
EP7223
EP7224
EP7225
EP7226
EP7227
EP7228
EP7229
EP7230
EP7231
EP7232
EP7233
EP7234
EP7235
EP7236
EP7237
EP7238
EP7239
EP7240
EP7241
EP7242
EP7243
EP7244
EP7245
EP7246
EP7247
EP7248
EP7249
EP7250
EP7251
EP7252
EP7253
EP7254
EP7255
EP7256
EP7257
EP7258
EP7259
EP7260
EP7261
EP7262
EP7263
EP7264
EP7265
EP7266
EP7267
EP7268
EP7269
EP7270
EP7271
EP7272
EP7273
EP7274
EP7275
EP7276
EP7277
EP7278
EP7279
EP7280
EP7281
EP7282
EP7283
EP7284
EP7285
EP7286
EP7287
EP7288
EP7289
EP7290
EP7291
EP7292
EP7293
EP7294
EP7295
EP7296
EP7297
EP7298
EP7299
EP7300
EP7301
EP7302
EP7303
EP7304
EP7305
EP7306
EP7307
EP7308
EP7309
EP7310
EP7311
EP7312
EP7313
EP7314
EP7315
EP7316
EP7317
EP7318
EP7319
EP7320
EP7321
EP7322
EP7323
EP7324
EP7325
EP7326
EP7327
EP7328
EP7329
EP7330
EP7331
EP7332
EP7333
EP7334
EP7335
EP7336
EP7337
EP7338
EP7339
EP7340
EP7341
EP7342
EP7343
EP7344
EP7345
EP7346
EP7347
EP7348
EP7349
EP7350
EP7351
EP7352
EP7353
EP7354
EP7355
EP7356
EP7357
EP7358
EP7359
EP7360
EP7361
EP7362
EP7363
EP7364
EP7365
EP7366
EP7367
EP7368
EP7369
EP7370
EP7371
EP7372
EP7373
EP7374
EP7375
EP7376
EP7377
EP7378
EP7379
EP7380
EP7381
EP7382
EP7383
EP7384
EP7385
EP7386
EP7387
EP7388
EP7389
EP7390
EP7391
EP7392
EP7393
EP7394
EP7395
EP7396
EP7397
EP7398
EP7399
EP7400
EP7401
EP7402
EP7403
EP7404
EP7405
EP7406
EP7407
EP7408
EP7409
EP7410
EP7411
EP7412
EP7413
EP7414
EP7415
EP7416
EP7417
EP7418
EP7419
EP7420
EP7421
EP7422
EP7423
EP7424
EP7425
EP7426
EP7427
EP7428
EP7429
EP7430
EP7431
EP7432
EP7433
EP7434
EP7435
EP7436
EP7437
EP7438
EP7439
EP7440
EP7441
EP7442
EP7443
EP7444
EP7445
EP7446
EP7447
EP7448
EP7449
EP7450
EP7451
EP7452
EP7453
EP7454
EP7455
EP7456
EP7457
EP7458
EP7459
EP7460
EP7461
EP7462
EP7463
EP7464
EP7465
EP7466
EP7467
EP7468
EP7469
EP7470
EP7471
EP7472
EP7473
EP7474
EP7475
EP7476
EP7477
EP7478
EP7479
EP7480
EP7481
EP7482
EP7483
EP7484
EP7485
EP7486
EP7487
EP7488
EP7489
EP7490
EP7491
EP7492
EP7493
EP7494
EP7495
EP7496
EP7497
EP7498
EP7499
EP7500
EP7501
EP7502
EP7503
EP7504
EP7505
EP7506
EP7507
EP7508
EP7509
EP7510
EP7511
EP7512
EP7513
EP7514
EP7515
EP7516
EP7517
EP7518
EP7519
EP7520
EP7521
EP7522
EP7523
EP7524
EP7525
EP7526
EP7527
EP7528
EP7529
EP7530
EP7531
EP7532
EP7533
EP7534
EP7535
EP7536
EP7537
EP7538
EP7539
EP7540
EP7541
EP7542
EP7543
EP7544
EP7545
EP7546
EP7547
EP7548
EP7549
EP7550
EP7551
EP7552
EP7553
EP7554
EP7555
EP7556
EP7557
EP7558
EP7559
EP7560
EP7561
EP7562
EP7563
EP7564
EP7565
EP7566
EP7567
EP7568
EP7569
EP7570
EP7571
EP7572
EP7573
EP7574
EP7575
EP7576
EP7577
EP7578
EP7579
EP7580
EP7581
EP7582
EP7583
EP7584
EP7585
EP7586
EP7587
EP7588
EP7589
EP7590
EP7591
EP7592
EP7593
EP7594
EP7595
EP7596
EP7597
EP7598
EP7599
EP7600
EP7601
EP7602
EP7603
EP7604
EP7605
EP7606
EP7607
EP7608
EP7609
EP7610
EP7611
EP7612
EP7613
EP7614
EP7615
EP7616
EP7617
EP7618
EP7619
EP7620
EP7621
EP7622
EP7623
EP7624
EP7625
EP7626
EP7627
EP7628
EP7629
EP7630
EP7631
EP7632
EP7633
EP7634
EP7635
EP7636
EP7637
EP7638
EP7639
EP7640
EP7641
EP7642
EP7643
EP7644
EP7645
EP7646
EP7647
EP7648
EP7649
EP7650
EP7651
EP7652
EP7653
EP7654
EP7655
EP7656
EP7657
EP7658
EP7659
EP7660
EP7661
EP7662
EP7663
EP7664
EP7665
EP7666
EP7667
EP7668
EP7669
EP7670
EP7671
EP7672
EP7673
EP7674
EP7675
EP7676
EP7677
EP7678
EP7679
EP7680
EP7681
EP7682
EP7683
EP7684
EP7685
EP7686
EP7687
EP7688
EP7689
EP7690
EP7691
EP7692
EP7693
EP7694
EP7695
EP7696
EP7697
EP7698
EP7699
EP7700
EP7701
EP7702
EP7703
EP7704
EP7705
EP7706
EP7707
EP7708
EP7709
EP7710
EP7711
EP7712
EP7713
EP7714
EP7715
EP7716
EP7717
EP7718
EP7719
EP7720
EP7721
EP7722
EP7723
EP7724
EP7725
EP7726
EP7727
EP7728
EP7729
EP7730
EP7731
EP7732
EP7733
EP7734
EP7735
EP7736
EP7737
EP7738
EP7739
EP7740
EP7741
EP7742
EP7743
EP7744
EP7745
EP7746
EP7747
EP7748
EP7749
EP7750
EP7751
EP7752
EP7753
EP7754
EP7755
EP7756
EP7757
EP7758
EP7759
EP7760
EP7761
EP7762
EP7763
EP7764
EP7765
EP7766
EP7767
EP7768
EP7769
EP7770
EP7771
EP7772
EP7773
EP7774
EP7775
EP7776
EP7777
EP7778
EP7779
EP7780
EP7781
EP7782
EP7783
EP7784
EP7785
EP7786
EP7787
EP7788
EP7789
EP7790
EP7791
EP7792
EP7793
EP7794
EP7795
EP7796
EP7797
EP7798
EP7799
EP7800
EP7801
EP7802
EP7803
EP7804
EP7805
EP7806
EP7807
EP7808
EP7809
EP7810
EP7811
EP7812
EP7813
EP7814
EP7815
EP7816
EP7817
EP7818
EP7819
EP7820
EP7821
EP7822
EP7823
EP7824
EP7825
EP7826
EP7827
EP7828
EP7829
EP7830
EP7831
EP7832
EP7833
EP7834
EP7835
EP7836
EP7837
EP7838
EP7839
EP7840
EP7841
EP7842
EP7843
EP7844
EP7845
EP7846
EP7847
EP7848
EP7849
EP7850
EP7851
EP7852
EP7853
EP7854
EP7855
EP7856
EP7857
EP7858
EP7859
EP7860
EP7861
EP7862
EP7863
EP7864
EP7865
EP7866
EP7867
EP7868
EP7869
EP7870
EP7871
EP7872
EP7873
EP7874
EP7875
EP7876
EP7877
EP7878
EP7879
EP7880
EP7881
EP7882
EP7883
EP7884
EP7885
EP7886
EP7887
EP7888
EP7889
EP7890
EP7891
EP7892
EP7893
EP7894
EP7895
EP7896
EP7897
EP7898
EP7899
EP7900
EP7901
EP7902
EP7903
EP7904
EP7905
EP7906
EP7907
EP7908
EP7909
EP7910
EP7911
EP7912
EP7913
EP7914
EP7915
EP7916
EP7917
EP7918
EP7919
EP7920
EP7921
EP7922
EP7923
EP7924
EP7925
EP7926
EP7927
EP7928
EP7929
EP7930
EP7931
EP7932
EP7933
EP7934
EP7935
EP7936
EP7937
EP7938
EP7939
EP7940
EP7941
EP7942
EP7943
EP7944
EP7945
EP7946
EP7947
EP7948
EP7949
EP7950
EP7951
EP7952
EP7953
EP7954
EP7955
EP7956
EP7957
EP7958
EP7959
EP7960
EP7961
EP7962
EP7963
EP7964
EP7965
EP7966
EP7967
EP7968
EP7969
EP7970
EP7971
EP7972
EP7973
EP7974
EP7975
EP7976
EP7977
EP7978
EP7979
EP7980
EP7981
EP7982
EP7983
EP7984
EP7985
EP7986
EP7987
EP7988
EP7989
EP7990
EP7991
EP7992
EP7993
EP7994
EP7995
EP7996
EP7997
EP7998
EP7999
EP8000
EP8001
EP8002
EP8003
EP8004
EP8005
EP8006
EP8007
EP8008
EP8009
EP8010
EP8011
EP8012
EP8013
EP8014
EP8015
EP8016
EP8017
EP8018
EP8019
EP8020
EP8021
EP8022
EP8023
EP8024
EP8025
EP8026
EP8027
EP8028
EP8029
EP8030
EP8031
EP8032
EP8033
EP8034
EP8035
EP8036
EP8037
EP8038
EP8039
EP8040
EP8041
EP8042
EP8043
EP8044
EP8045
EP8046
EP8047
EP8048
EP8049
EP8050
EP8051
EP8052
EP8053
EP8054
EP8055
EP8056
EP8057
EP8058
EP8059
EP8060
EP8061
EP8062
EP8063
EP8064
EP8065
EP8066
EP8067
EP8068
EP8069
EP8070
EP8071
EP8072
EP8073
EP8074
EP8075
EP8076
EP8077
EP8078
EP8079
EP8080
EP8081
EP8082
EP8083
EP8084
EP8085
EP8086
EP8087
EP8088
EP8089
EP8090
EP8091
EP8092
EP8093
EP8094
EP8095
EP8096
EP8097
EP8098
EP8099
EP8100
EP8101
EP8102



SECOND FLOOR 13,200V POWER PLAN - AREA F


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. SEE DRAWING EP313 FOR CONTINUATION ON MSS.
2. SEE DRAWING EP315 FOR CONTINUATION ON MC-ATS-CUP-CH-B.
3. INSTALL EMERGENCY SERVICE SWITCHGEAR ESS. SEE EP504 AND EP708 FOR DETAILS.
4. PROVIDE MEDIUM VOLTAGE PULL BOX. 5'-6" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.
5. PROVIDE MEDIUM VOLTAGE PULL BOX. 6'-0" X 1'-0" X 1'-0", NEMA 1, BOLTED COVER FACING DOWN.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shelborne Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


SECOND FLOOR 13,200V POWER PLAN - AREA F

SHEET NUMBER

EP316

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:57:21 PM AESI Proj. No.: 21-154

0 1/2" 1" 2"



GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. INSTALL 15KV LOAD BANK. PROVIDE MEDIUM VOLTAGE CABLE AND TERMINATIONS AT LOAD BANK. COORDINATE EXACT TERMINATION POINT WITH LOAD BANK SUBMITTALS.
2. 3MW, 13.2KV LOAD BANK, TRANSFORMER-LESS TYPE WITH 480V CONTROL/FAN PANEL.

ROOF 13,200V POWER PLAN - AREA C

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF 13,200V POWER PLAN - AREA C

SHEET NUMBER

EP319

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:57:27 PM AESI Proj. No: 21-154




FIRST FLOOR 480V POWER PLAN - AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRICAL CONNECTION FOR HRC-5.
2. PROVIDE VFD-CHWP-3. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
3. PROVIDE VFD-CP-9. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
4. PROVIDE 1NH4. SEE SCHEDULE ON EP602 FOR DETAILS.
5. PROVIDE T-1NL3. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 1NL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
6. PROVIDE VFD-CHW-SS-FLTR-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
7. PROVIDE VFD-HRCWP-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
8. PROVIDE VFD-HRCWP-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
9. PROVIDE VFD-HRCWP-3. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
10. PROVIDE VFD-HRHHWP-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
11. PROVIDE VFD-HRHHWP-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
12. PROVIDE VFD-HRHHWP-3. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
13. PROVIDE ELECTRICAL CONNECTION FOR DBP-2 SKID CONTROL PANEL.
14. PROVIDE SW-BRP-1,2. 30A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK +54"AFF.
15. PROVIDE VFD-CHWP-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
16. PROVIDE VFD-CHWP-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
17. PROVIDE SW-DWH-1. 30A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK +54"AFF.
18. PROVIDE T-1EQL1. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 1EQL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
9575 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Seahorse Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR 480V POWER PLAN - AREA A

SHEET NUMBER

EP334

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:57:40 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



FIRST FLOOR 480V POWER PLAN - AREA B


Scale: 1/4" = 1'-0"

PLAN NOTES:

1. PROVIDE 1NH3. SEE SCHEDULE ON EP602 FOR DETAILS.
2. PROVIDE T-1NL2. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 1NL2. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
3. PROVIDE ELECTRICAL CONNECTION FOR HHWB-1.
4. PROVIDE ELECTRICAL CONNECTION FOR HHWB-2.
5. PROVIDE ELECTRICAL CONNECTION FOR HHWB-3.
6. PROVIDE ELECTRICAL CONNECTION FOR HHWB-4.
7. PROVIDE ELECTRICAL CONNECTION FOR HHWB-5.
8. PROVIDE ELECTRICAL CONNECTION FOR HHWB-6.
9. PROVIDE ELECTRICAL CONNECTION FOR HHWB-7.
10. PROVIDE ELECTRICAL CONNECTION FOR HHWB-8.
11. PROVIDE FP-2 CONTROL PANEL/ATS. SEE MECHANICAL DRAWINGS FOR DETAILS.
12. PROVIDE JP-1 CONTROL PANEL/ATS. SEE MECHANICAL DRAWINGS FOR DETAILS.
13. PROVIDE JP-2 CONTROL PANEL/ATS. SEE MECHANICAL DRAWINGS FOR DETAILS.
14. PROVIDE VFD-CHWP-4. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
15. PROVIDE VFD-CHWP-5. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
16. PROVIDE VFD-CHWP-6. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
17. PROVIDE VFD-CHWP-7. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
18. PROVIDE VFD-HHW-FLTR-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
19. PROVIDE VFD-HHWP-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
20. PROVIDE VFD-HHWP-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
21. PROVIDE VFD-HHWP-3. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
22. PROVIDE VFD-HHWP-4. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
23. PROVIDE VFD-HHWP-5. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
24. PROVIDE VFD-HHWP-6. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
25. PROVIDE ELECTRICAL CONNECTION FOR DBP-1 SKID CONTROL PANEL.
26. PROVIDE FP-1 CONTROL PANEL/ATS. SEE MECHANICAL DRAWINGS FOR DETAILS.
27. PROVIDE 1LSH1. SEE SCHEDULE ON EL602.
28. PROVIDE 1LSUPSH1. SEE SCHEDULE ON EL602.

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadylane Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	AESI
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION


SHEET TITLE

FIRST FLOOR 480V POWER PLAN - AREA B

SHEET NUMBER

EP335

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:57:49 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



FIRST FLOOR 480V POWER PLAN - AREA C


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE 1NH1. SEE SCHEDULE ON EP602 FOR DETAILS.
2. PROVIDE T-1NL1. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 1NL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
3. PROVIDE ELECTRICAL CONNECTION FOR SB-1.
4. PROVIDE ELECTRICAL CONNECTION FOR SB-2.
5. PROVIDE ELECTRICAL CONNECTION FOR SB-3.
6. PROVIDE ELECTRICAL CONNECTION FOR CONDENSATE RETURN PUMP CONTROL PANEL 1.
7. PROVIDE ELECTRICAL CONNECTION FOR CONDENSATE RETURN PUMP CONTROL PANEL 2.
8. PROVIDE ELECTRICAL CONNECTION FOR DA FEED PUMP CONTROL PANEL.
9. PROVIDE SW-RO-CIP-PUMP SKID. 30A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK AT +54"AFF.
10. PROVIDE SW-RO-SYSTEM PUMP. 30A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK AT +54"AFF.
11. PROVIDE SW-ROP SKID. 30A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK AT +54"AFF.
12. PROVIDE 1NH2. SEE SCHEDULE ON EP602 FOR DETAILS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shelborne Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR 480V POWER PLAN - AREA C

SHEET NUMBER

EP336

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:57:58 PM AESI Proj. No: 21-154



FIRST FLOOR 480V POWER PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRICAL CONNECTION FOR HRC-1.
2. PROVIDE ELECTRICAL CONNECTION FOR HRC-2.
3. PROVIDE ELECTRICAL CONNECTION FOR HRC-3.
4. PROVIDE ELECTRICAL CONNECTION FOR HRC-4.
5. NOT USED.
6. PROVIDE VFD-FO-FILTER-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
7. PROVIDE VFD-FO-FILTER-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
8. PROVIDE ELECTRICAL CONNECTION FOR FO-P-1-CONTROL PANEL.
9. PROVIDE ELECTRICAL CONNECTION FOR FO-P-2-CONTROL PANEL.
10. PROVIDE ELECTRICAL CONNECTION FOR FO-P-3-CONTROL PANEL.
11. PROVIDE ELECTRICAL CONNECTION FOR FO-P-4-CONTROL PANEL.
12. PROVIDE WELDING OUTLET. MOUNT TO COLUMN AT +54"AFF.
13. PROVIDE CONDUIT SEAL OFF WITHIN 1'-0" OF PENETRATION THROUGH WALL TO FUEL OIL PUMP ROOM 103. TYPICAL FOR ALL CONDUIT PENETRATIONS.
14. PROVIDE VFD-CTP-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
15. PROVIDE VFD-CTP-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:03 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 480V POWER PLAN - AREA D

SHEET NUMBER

EP337



FIRST FLOOR 480V POWER PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. NONE.
2. NONE.
3. PROVIDE VFD-CTP-3. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
4. PROVIDE VFD-CTP-4. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
5. PROVIDE VFD-CTP-5. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
6. PROVIDE VFD-CTP-6. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
7. PROVIDE VFD-CTP-FILTER. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:08 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shorthorne Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 480V POWER PLAN - AREA E

SHEET NUMBER


EP338

GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. NOT USED.



FIRST FLOOR 480V POWER PLAN - AREA F
Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

FIRST FLOOR 480V POWER PLAN - AREA F

SHEET NUMBER

EP339

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:11 PM AESI Proj No: 21-154



SECOND FLOOR 480V POWER PLAN - AREA A


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE 2NH2. SEE SCHEDULE ON EP602 FOR DETAILS.
2. PROVIDE T-2NL2. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 2NL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
3. PROVIDE SW-CRAC-1. 30A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK +54"AFF.
4. PROVIDE SW-CRAC-2. 30A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK +54"AFF.
5. PROVIDE VFD-MAU-2-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
6. PROVIDE VFD-EF-2-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
7. PROVIDE UH-1 SWITCH. 120V, 1 POLE, MOTOR RATED, LOCKING, NEMA 1.
8. PROVIDE VFD-EF-2-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
9. PROVIDE VFD-P-2-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR 480V POWER PLAN - AREA A

SHEET NUMBER

EP341

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:23 PM AESI Proj No: 21-154
0 1/2" 1" 2"



SECOND FLOOR 480V POWER PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE VFD-EF-2-6. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:27 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadetree Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR 480V POWER PLAN - AREA B

SHEET NUMBER

EP342



GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE (2) DC BATTERY CHARGERS FOR MSS.
2. PROVIDE VFD-EF-2-7. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.

SECOND FLOOR 480V POWER PLAN - AREA C

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR 480V POWER PLAN - AREA C

SHEET NUMBER

EP343

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:29 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



SECOND FLOOR 480V POWER PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE VFD-REF-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
2. PROVIDE VFD-EF-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
3. PROVIDE VFD-EF-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
4. PROVIDE MAU-2-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
5. PROVIDE VFD-CT-BASIN-SWPR-FLTR-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
6. PROVIDE VFD-CT-BASIN-SWPR-FLTR-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
7. PROVIDE VFD-REF-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
8. PROVIDE VFD-P-2-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
9. PROVIDE VFD-HRW-2-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR 480V POWER PLAN - AREA D

SHEET NUMBER

EP344

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:34 PM AESI Proj. No: 21-154



SECOND FLOOR 480V POWER PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE VFD-CT-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
2. PROVIDE VFD-CT-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
3. PROVIDE VFD-CT-3. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
4. PROVIDE VFD-CT-4. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
5. PROVIDE VFD-CT-5. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
6. PROVIDE VFD-CT-6. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
7. PROVIDE VFD-RF-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
8. PROVIDE VFD-EF-2-3. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
9. PROVIDE VFD-EF-2-4. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
10. PROVIDE VFD-EF-2-5. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:42 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadyknoll Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR 480V POWER PLAN - AREA E

SHEET NUMBER

EP345



SECOND FLOOR 480V POWER PLAN - AREA F


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ATS-LS1. SEE SCHEDULE ON EP601 FOR DETAILS.
2. PROVIDE ATS-EL1. SEE SCHEDULE ON EP601 FOR DETAILS.
3. PROVIDE ATS-EQ1. SEE SCHEDULE ON EP601 FOR DETAILS.
4. PROVIDE ATS-GEN1. SEE SCHEDULE ON EP601 FOR DETAILS.
5. PROVIDE 2EQUPS1. SEE SCHEDULE ON EP601.
6. PROVIDE 2LSH1. SEE SCHEDULE ON EP605.
7. PROVIDE 2ELH1. SEE SCHEDULE ON EP604.
8. PROVIDE 2EQH1. SEE SCHEDULE ON EP604.
9. PROVIDE 2GENH1. SEE SCHEDULE ON EP605.
10. PROVIDE 2NH1. SEE SCHEDULE ON EP602.
11. PROVIDE TRANSFORMER T-2LN1. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 2LNL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
12. PROVIDE TRANSFORMER T-GENL1. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 2GENL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
13. PROVIDE 2GENUPS1. SEE SCHEDULE ON EP601.
14. PROVIDE 2GENUPSH1. SEE SCHEDULE ON EP605.
15. PROVIDE TRANSFORMER T-2GENUPSL1. 480V/208-120V, 75KVA.
16. PROVIDE T-2ELL1. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 2ELL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
17. PROVIDE 2EQUPSH1. SEE SCHEDULE ON EP604.
18. PROVIDE TRANSFORMER T-2EQUPSL1. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 2EQUPSL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
19. PROVIDE VFD-RF-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STAINLESS STEEL STRUT RACK AT +54"AFF.
20. PROVIDE T-2EQL1. 480V/208-120V, 75KVA. PROVIDE CIRCUIT TO 2EQL1. COPPER: (1)2"C, (4)#4/0 & (1)#4GND. ALLUMINUM: (1)2-1/2"C, (4)300KCMIL & (1)#4GND.
21. PROVIDE 2LSH2. SEE SCHEDULE ON EL602.
22. PROVIDE 2LSUPSH1. SEE SCHEDULE ON EL602.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:45 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Seahorse Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR 480V POWER PLAN - AREA F

SHEET NUMBER

EP346



ROOF 480V POWER PLAN - AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRICAL CONNECTION TO EF-2-2. VFD-EF-2-2 IS LOCATED IN CORRIDOR 201.
2. PROVIDE ACCU-1 SWITCH. 480V, 30A, 3 POLE, HEAVY DUTY, NEMA 4X. MOUNT ON STRUT RACK AT +54"AFF.
3. PROVIDE ACCU-2 SWITCH. 480V, 30A, 3 POLE, HEAVY DUTY, NEMA 4X. MOUNT ON STRUT RACK AT +54"AFF.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadrone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF 480V POWER PLAN - AREA A


SHEET NUMBER

EP347



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:47 PM AESI Proj No: 21-154
0 1/2" 1" 2"



ROOF 480V POWER PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRICAL CONNECTION TO EF-2-6. VFD-EF-2-6 IS LOCATED IN GENERATOR ROOM 220.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:48 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadylane Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF 480V POWER PLAN - AREA B

SHEET NUMBER

EP348



ROOF 480V POWER PLAN - AREA D


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE CT-1 FAN DISCONNECT SWITCH. 400A, 3 POLE, NON FUSED, NEMA 4X, HEAVY DUTY DISCONNECT. MOUNT ON STRUT RACK AT +54"AFF.
2. PROVIDE ELECTRICAL CONNECTION TO EF-1-1. VFD-EF-1-1 IS LOCATED IN MECHANICAL 206.
3. PROVIDE ELECTRICAL CONNECTION TO EF-2-1. VFD-EF-2-1 IS LOCATED IN MECHANICAL 206.
4. PROVIDE ELECTRICAL CONNECTION TO REF-1. VFD-REF-1 IS LOCATED IN MECHANICAL 206.
5. PROVIDE ELECTRICAL CONNECTION TO REF-2. VFD-REF-2 IS LOCATED IN MECHANICAL 206.
6. PROVIDE ELECTRICAL CONNECTION TO RF-1. VFD-RF-1 IS LOCATED IN 15KV SWITCHGEAR 212.
7. INSTALL BASIN HEATER CONTROL PANEL. MOUNT ON STRUT RACK AT +54"AFF.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ROOF 480V POWER PLAN - AREA D

SHEET NUMBER

EP350

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:52 PM AESI Proj. No: 21-154

0 1/2" 1" 2"



ROOF 480V POWER PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE CT-2 FAN DISCONNECT SWITCH. 400A, 3 POLE, NON FUSED, NEMA 4X, HEAVY DUTY DISCONNECT. MOUNT ON STRUT RACK AT +54"AFF.
2. PROVIDE CT-3 FAN DISCONNECT SWITCH. 400A, 3 POLE, NON FUSED, NEMA 4X, HEAVY DUTY DISCONNECT. MOUNT ON STRUT RACK AT +54"AFF.
3. PROVIDE CT-4 FAN DISCONNECT SWITCH. 400A, 3 POLE, NON FUSED, NEMA 4X, HEAVY DUTY DISCONNECT. MOUNT ON STRUT RACK AT +54"AFF.
4. PROVIDE CT-5 FAN DISCONNECT SWITCH. 400A, 3 POLE, NON FUSED, NEMA 4X, HEAVY DUTY DISCONNECT. MOUNT ON STRUT RACK AT +54"AFF.
5. PROVIDE ELECTRICAL CONNECTION TO EF-2-3. VFD-EF-2-3 IS LOCATED IN 15KV SWITCHGEAR 212.
6. PROVIDE ELECTRICAL CONNECTION TO EF-2-4. VFD-EF-2-4 IS LOCATED IN 15KV SWITCHGEAR 212.
7. PROVIDE ELECTRICAL CONNECTION TO EF-2-5. VFD-EF-2-5 IS LOCATED IN 15KV SWITCHGEAR 212.
8. INSTALL BASIN HEATER CONTROL PANEL. MOUNT ON STRUT RACK AT +54"AFF.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:54 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF 480V POWER PLAN - AREA E

SHEET NUMBER

EP351



ROOF 480V POWER PLAN - AREA F

Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE CT-1 FAN DISCONNECT SWITCH. 400A, 3 POLE, NON FUSED, NEMA 4X, HEAVY DUTY DISCONNECT. MOUNT ON STRUT RACK AT +54"AFF.
2. PROVIDE ELECTRICAL CONNECTION TO RF-2. VFD-RF-2 IS LOCATED IN 15KV SWITCHGEAR 212.
3. PROVIDE ELECTRICAL CONNECTION TO EF-2-5. VFD-EF-2-5 IS LOCATED IN 15KV SWITCHGEAR 212.
4. INSTALL BASIN HEATER CONTROL PANEL. MOUNT ON STRUT RACK AT +54"AFF.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF 480V POWER PLAN - AREA F


SHEET NUMBER

EP352



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:55 PM AESI Proj No: 21-154
0 1/2" 1" 2"




LOWER LEVEL 208V POWER PLAN- AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

LOWER LEVEL 208V POWER PLAN - AREA A

SHEET NUMBER

EP361

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:56 PM AESI Proj. No: 21-154



GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE RECEPTACLE IN SURFACE MOUNTED BOX IN ELEVATOR PIT. MOUNT RECEPTACLE -16" TO LOWER LEVEL 1.

LOWER LEVEL 208V POWER PLAN- AREA D

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


LOWER LEVEL 208V POWER PLAN - AREA D

SHEET NUMBER

EP363

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:58:59 PM AESI Proj. No: 21-154



FIRST FLOOR 208V POWER PLAN - AREA A
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE 1NL3. SEE SCHEDULE ON EP602 FOR DETAILS.
2. NOT USED.
3. PROVIDE HEAT TRACE CONTROLLER HC-31. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)#10GND. MOUNT ON WALL +54"AFF.
4. PROVIDE ELECTRICAL CONNECTIONS FOR DWS-2.
5. PROVIDE VFD-DWRP-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON WALL AT +54"AFF.
6. PROVIDE 1EQL1. SEE SCHEDULE ON EP606 FOR DETAILS.
7. PROVIDE HEAT TRACE CONTROLLER HC-32. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)#10GND. MOUNT ON WALL +54"AFF.
8. PROVIDE HEAT TRACE CONTROLLER HC-33. 3/4"C, (2)#10, (1)#10GND. MOUNT ON WALL +54"AFF.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 208V POWER PLAN - AREA A

SHEET NUMBER


EP364



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:03 PM AESI Proj No: 21-154

0 1/2" 1" 2"



FIRST FLOOR 208V POWER PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE 1NL2. SEE SCHEDULE ON EP603 FOR DETAILS.
2. NOT USED.
3. NOT USED.
4. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.
5. PROVIDE ELECTRICAL CONNECTIONS FOR DWS-1.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:10 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 208V POWER PLAN - AREA B

SHEET NUMBER

EP365



FIRST FLOOR 208V POWER PLAN - AREA C


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE 1NL1. SEE SCHEDULE ON EP603 FOR DETAILS.
2. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadylane Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


FIRST FLOOR 208V POWER PLAN - AREA C

SHEET NUMBER

EP366

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:19 PM AESI Proj. No: 21-154



FIRST FLOOR 208V POWER PLAN - AREA D

Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE CLASS 1 DIV 1 RATED RECEPTACLE ASSEMBLY.
2. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.
3. PROVIDE POWER FOR OVERHEAD DOOR OPERATOR. PROVIDE 208V, 2 POLE, 30A DISCONNECT SWITCH AT +54"AFF. WIRE DOOR PER MANUFACTURER'S REQUIREMENTS. MOUNT DOOR CONTROLS NEXT TO DISCONNECT SWITCH.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 208V POWER PLAN - AREA D

SHEET NUMBER


EP367



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:23 PM AESI Proj. No: 21-154

0 1/2" 1" 2"



FIRST FLOOR 208V POWER PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE POWER FOR OVERHEAD DOOR OPERATOR. PROVIDE 208V, 2 POLE, 30A DISCONNECT SWITCH AT +54"AFF. WIRE DOOR PER MANUFACTURER'S REQUIREMENTS. MOUNT DOOR CONTROLS NEXT TO DISCONNECT SWITCH.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:26 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 208V POWER PLAN - AREA E

SHEET NUMBER

EP368



GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.
2. PROVIDE POWER FOR OVERHEAD DOOR OPERATOR. PROVIDE 208V, 2 POLE, 30A DISCONNECT SWITCH AT +54"AFF. WIRE DOOR PER MANUFACTURER'S REQUIREMENTS. MOUNT DOOR CONTROLS NEXT TO DISCONNECT SWITCH.

FIRST FLOOR 208V POWER PLAN - AREA F

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR 208V POWER PLAN - AREA F

SHEET NUMBER

EP369


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:29 PM AESI Proj. No: 21-154

GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. NOT USED.



FIRST FLOOR 208V POWER PLAN - AREA G
Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


FIRST FLOOR 208V POWER PLAN - AREA G

SHEET NUMBER

EP370

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:31 PM AESI Proj. No: 21-154

0 1/2" 1" 2"



SECOND FLOOR 208V POWER PLAN - AREA A


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE 2NL2. SEE SCHEDULE ON EP603 FOR DETAILS.
2. PROVIDE 120V, 1 POLE, LOCKABLE, MOTOR RATED SWITCH FOR UH-1.
3. PROVIDE CLASS 1 DIV. I RATED RECEPTACLE ASSEMBLY.
4. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadylane Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SECOND FLOOR 208V POWER PLAN - AREA A

SHEET NUMBER

EP371

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:40 PM AESI Proj No: 21-154



SECOND FLOOR 208V POWER PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. NOT USED.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:43 PM AESI Proj. No.: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadetree Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR 208V POWER PLAN - AREA B

SHEET NUMBER

EP372



SECOND FLOOR 208V POWER PLAN - AREA C


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE 120V, 1 POLE, LOCKABLE, MOTOR RATED SWITCH FOR UH-4.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


SECOND FLOOR 208V POWER PLAN - AREA C

SHEET NUMBER

EP373

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:46 PM AESI Proj. No: 21-154

0 1/2" 1" 2"




SECOND FLOOR 208V POWER PLAN - AREA D
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.
2. PROVIDE SWITCHED RECEPTACLE AND SWITCH FOR DISPOSER. LOCATE RECEPTACLE IN CASEWORK.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


SECOND FLOOR 208V POWER PLAN - AREA D

SHEET NUMBER

EP374

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:51 PM AESI Proj. No: 21-154

0 1/2" 1" 2"



SECOND FLOOR 208V POWER PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EPS## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.
2. PROVIDE CLASS 1 DIV. I RATED RECEPTACLE ASSEMBLY.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 2:59:58 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR 208V POWER PLAN - AREA E

SHEET NUMBER

EP375



SECOND FLOOR 208V POWER PLAN - AREA F


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE 2NL1. SEE SCHEDULE ON EP603 FOR DETAILS.
2. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.
3. PROVIDE 2GENL1. SEE SCHEDULE ON EP605 FOR DETAILS.
4. PROVIDE 2GENUPSL1. SEE SCHEDULE ON EP605 FOR DETAILS.
5. PROVIDE 2EQUPSL1. SEE SCHEDULE ON EP604 FOR DETAILS.
6. PROVIDE 2ELL1. SEE SCHEDULE ON EP604 FOR DETAILS.
7. PROVIDE 2GENUPSL2. SEE SCHEDULE ON EP605 FOR DETAILS.
8. PROVIDE 2EQL1. SEE SCHEDULE ON EP604 FOR DETAILS.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:01 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadybrook Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR 208V POWER PLAN - AREA F

SHEET NUMBER

EP376



ROOF 208V POWER PLAN - AREA A


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF 208V POWER PLAN - AREA A

SHEET NUMBER

EP377

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:03 PM AESI Proj. No: 21-154



ROOF 208V POWER PLAN - AREA B


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. NOT USED.



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:06 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF 208V POWER PLAN - AREA B

SHEET NUMBER

EP378




ROOF 208V POWER PLAN - AREA C
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. NOT USED.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF 208V POWER PLAN - AREA C

SHEET NUMBER

EP379

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:08 PM AESI Proj. No: 21-154



ROOF 208V POWER PLAN - AREA D
Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE HEAT TRACE CONTROLLER, HC-1. SEE SCHEDULE ON EP608 AND SPECIFICATIONS FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF 208V POWER PLAN - AREA D

SHEET NUMBER


EP380



KEY PLAN
SCALE: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:10 PM AESI Proj. No: 21-154



ROOF 208V POWER PLAN - AREA E


Scale: 1/4" = 1'-0"

GENERAL NOTES:

1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE HEAT TRACE CONTROLLER HC-1. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)# 10GND. MOUNT ON STRUT RACK +54"AFF.
2. PROVIDE HEAT TRACE CONTROLLER HC-2. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)# 10GND. MOUNT ON STRUT RACK +54"AFF.
3. PROVIDE HEAT TRACE CONTROLLER HC-3. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)# 10GND. MOUNT ON STRUT RACK +54"AFF.
4. PROVIDE HEAT TRACE CONTROLLER HC-4. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)# 10GND. MOUNT ON STRUT RACK +54"AFF.
5. PROVIDE HEAT TRACE CONTROLLER HC-5. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
6. PROVIDE HEAT TRACE CONTROLLER HC-6. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
7. PROVIDE HEAT TRACE CONTROLLER HC-7. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
8. PROVIDE HEAT TRACE CONTROLLER HC-8. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
9. PROVIDE HEAT TRACE CONTROLLER HC-9. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
10. PROVIDE HEAT TRACE CONTROLLER HC-10. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
11. PROVIDE HEAT TRACE CONTROLLER HC-11. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
12. PROVIDE HEAT TRACE CONTROLLER HC-12. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
13. PROVIDE HEAT TRACE CONTROLLER HC-13. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
14. PROVIDE HEAT TRACE CONTROLLER HC-14. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
15. PROVIDE HEAT TRACE CONTROLLER HC-15. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
16. PROVIDE HEAT TRACE CONTROLLER HC-16. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
17. PROVIDE HEAT TRACE CONTROLLER HC-17. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
18. PROVIDE HEAT TRACE CONTROLLER HC-18. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
19. PROVIDE HEAT TRACE CONTROLLER HC-19. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
20. PROVIDE HEAT TRACE CONTROLLER HC-20. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
21. PROVIDE HEAT TRACE CONTROLLER HC-21. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
22. PROVIDE HEAT TRACE CONTROLLER HC-22. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
23. PROVIDE HEAT TRACE CONTROLLER HC-23. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
24. PROVIDE HEAT TRACE CONTROLLER HC-24. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
25. PROVIDE HEAT TRACE CONTROLLER HC-25. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
26. PROVIDE HEAT TRACE CONTROLLER HC-26. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
27. PROVIDE HEAT TRACE CONTROLLER HC-27. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
28. PROVIDE HEAT TRACE CONTROLLER HC-28. 3/4"C, (3)#10 (2 PHASE + NEUTRAL), (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
29. PROVIDE HEAT TRACE CONTROLLER HC-29. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.
30. PROVIDE HEAT TRACE CONTROLLER HC-30. 3/4"C, (2)#10, (1)#10GND. MOUNT ON STRUT RACK +54"AFF.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:13 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4140 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ROOF 208V POWER PLAN - AREA E

SHEET NUMBER

EP381



GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. NOT USED.

ROOF 208V POWER PLAN - AREA F

Scale: 1/4" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ROOF 208V POWER PLAN - AREA F

SHEET NUMBER

EP382

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:15 PM AESI Proj. No: 21-154



LOWER LEVEL GROUNDING ELECTRODE SYSTEM PLAN- OVERALL

Scale: 3/32" = 1'-0"

GENERAL NOTES:

1. CONTRACTOR SHALL PROVIDE ALL MATERIAL AND LABOR NECESSARY TO INSTALL GROUNDING ELECTRODE SYSTEM AS INDICATED. THE GROUNDING RING CABLE SHALL BE INSTALLED MINIMUM OF 36" BELOW FINISHED GRADE. WHERE GROUNDING RING CABLE RUNS THROUGH CONCRETE PAD, CONTRACTOR SHALL LAY CABLE ON PAD REBAR AND MESH AND CONNECT CABLES TO CHANNEL STEEL LEVELING RAILS IN THE PAD AS INDICATED. INSTALLATION OF THE GROUNDING RING CABLE THROUGH CONCRETE FOUNDATION / PAD SHALL BE COORDINATED WITH THE FORMING AND CONCRETE POUR.
2. REFER TO DRAWING EP501 FOR GROUNDING DETAILS.
3. PROVIDE EXOTHERMIC WELD CONNECTIONS TO THE GROUNDING ELECTRODE SYSTEM UNLESS OTHERWISE NOTED FOR BURIED CONNECTIONS. BURNDY HYGROUND COMPRESSION CONNECTORS ARE ACCEPTABLE.
4. PROVIDE 1" PVC SCHEDULE 40 CONDUIT SLEEVE FOR ALL SLAB, FOUNDATION AND WALL PENETRATIONS.
5. PROVIDE A GROUNDING ELECTRODE SYSTEM CONNECTION TO WATER PIPES AND METAL PIPES PER THE NEC AT THE FIRST ACCESSIBLE POINT OF BUILDING ENTRY
6. PROVIDE A CLEAN AREA, REMOVE PAINT AND RUST DOWN TO BARE METAL BEFORE BONDING TO ALL METAL AND STEEL STRUCTURES.
7. PROVIDE A GROUNDING ELECTRODE SYSTEM CONNECTION TO EQUIPMENT WHERE SHOWN.
8. INSTALL ALL GROUNDING ELECTRODE SYSTEM CONDUCTORS WITH SLACK AND USE LARGE RADIUS BENDS TO AVOID DAMAGE.
9. INSTALLATION OF GROUND TO EQUIPMENT SHALL BE IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
10. ALL GROUNDING ELECTRODE SYSTEM CONDUCTOR WHIPS SHALL BE MINIMUM 3'-0" LONG ABOVE FINISHED FLOOR OR FINISHED GRADE UNLESS OTHERWISE NOTED.
11. BOND LIGHTNING PROTECTION SYSTEM DOWN CONDUCTOR TO GROUNDING ELECTRODE SYSTEM RING WHERE SHOWN. LIGHTNING PROTECTION SYSTEM MAIN CONDUCTOR ABOVE GRADE IS ALUMINUM, TRANSITION TO COPPER BELOW GRADE.

(#) PLAN NOTES:

1. PROVIDE #4/0 BARE COPPER GROUNDING ELECTRODE CONDUCTOR, DIRECT BURIED FOR GROUNDING ELECTRODE RING. CONNECT TO GROUNDING RODS, AND OTHER GROUNDING ELECTRODE SYSTEMS VIA EXOTHERMIC WELDS
2. PROVIDE 10'-0" x 3/4" DIA. GROUNDING ROD. DRIVE INTO THE GROUND OUTSIDE FOUNDATION PERIMETER AND 3'-0" MINIMUM BELOW FINISHED GRADE.
3. EXOTHERMIC WELD CONNECTION. TYPICAL FOR GROUNDING RING TO GROUND ROD.
4. PROVIDE GROUND TEST WELL AT THIS LOCATION. CONNECTIONS TO GROUND ROD SHALL BE MECHANICAL ONLY TO SUPPORT TESTING.
5. PROVIDE #4/0 BARE COPPER GROUNDING CONDUCTOR AND CONNECT TO FOUNDATION STEEL REBAR. EXTEND 3'-0" OF GROUND CABLE ABOVE FINISHED FLOOR AND CONNECT TO BUILDING COLUMN STEEL VIA EXOTHERMIC WELD. SEE COLUMN GROUNDING DETAIL '2' ON DRAWING EP501.
6. PROVIDE #4/0 BARE COPPER GROUNDING CONDUCTOR AND CONNECT TO SLAB ON GRADE STEEL REBAR. CONNECT TO FOUNDATION STEEL.
7. PROVIDE #4/0 BARE COPPER LIGHTNING PROTECTION DOWN CONDUCTOR. EXOTHERMIC WELD TO GROUND ELECTRODE.
8. PROVIDE #3/0 BARE COPPER GROUNDING CONDUCTOR. TAP TO FUEL TANK GROUNDING POINT. PROVIDE TANK CONNECTION PER MANUFACTURER RECOMMENDATION.
9. PROVIDE #4/0 BARE COPPER GROUNDING ELECTRODE CONDUCTOR TO 2ND FLOOR MAIN GROUNDING BUS BAR.
10. PROVIDE #4/0 BARE COPPER GROUNDING ELECTRODE CONDUCTOR TO SERVICE ENTRANCE WATER LINES.
11. PROVIDE #4/0 BARE COPPER GROUNDING ELECTRODE CONDUCTOR TO 1ST FLOOR SUBSTATION ELECTRICAL ROOM AND CONNECT TO GROUNDING BUS BAR.
12. PROVIDE #4/0 BARE COPPER GROUNDING ELECTRODE CONDUCTOR TO 2ND FLOOR MDF ROOM AND CONNECT TO GROUNDING BUS BAR.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

LOWER LEVEL GROUNDING PLAN - OVERALL

SHEET NUMBER

EP391

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:18 PM AESI Proj No: 21-154



FIRST FLOOR GROUNDING PLAN - OVERALL


Scale: 3/32" = 1'-0"

GENERAL NOTES:

1. GROUNDING CONDUCTOR ROUTED UNDER SLAB TO EQUIPMENT CONNECTION POINT. USE 1" SLEEVE THROUGH SLAB.
2. SEE SHEET EP391 FOR GENERAL NOTES.

(#) PLAN NOTES:

1. #2 BARE COPPER GROUNDING CONDUCTOR CONNECTION TO PUMP FRAME. CONNECTION PER MANUFACTURER REQUIREMENTS. EXOTHERMIC WELD TO STEEL COLUMN. MECHANICAL CONNECTION AT THE PUMP FRAME.
2. #1/0 BARE COPPER GROUNDING CONDUCTOR. PROVIDE CONNECTION TO CHILLER FRAME PER MANUFACTURER REQUIREMENTS. EXOTHERMIC WELD TO STEEL COLUMN.
3. #4/0 BARE COPPER GROUNDING CONDUCTOR CONNECTION TO INCOMING WATER PIPE. EXOTHERMIC WELD TO GROUNDING ELECTRODE RING. CONNECTION TO PIPE SHALL BE MECHANICAL AND ABOVE SLAB FOR VISUAL INSPECTION. SEE SHEET EP391 FOR CONTINUATION.
4. PROVIDE 24"L x 4"W x 1/2"D SAFETY GROUND BAR WITH STANDOFFS FOR MOUNTING. EXOTHERMIC WELD BAR WHIP TO STEEL COLUMN.
5. #3/0 BARE COPPER GROUNDING CONDUCTOR CONNECTION SUBSTATIONS AND SWITCHBOARD GROUND BUS. USE MECHANICAL CONNECTION AT GEAR AND GROUND BAR.
6. BARE COPPER GROUND BAR, GBA, 96"L x 4"W x 1/2"D WITH STANDOFFS FOR WALL MOUNTING. EXOTHERMIC WELD BAR WHIP TO STEEL COLUMN. PROVIDE #4/0 BARE COPPER CONDUCTOR TO GROUNDING ELECTRODE RING. AND EXOTHERMIC WELD. SEE SHEET EP391 FOR CONTINUATION.
7. LIGHTNING PROTECTION SYSTEM DOWN CONDUCTOR. ALUMINUM #4/0 FROM ROOF. PROVIDE BI-METAL CONNECTOR, CONNECTED TO STEEL COLUMN. TRANSITION TO COPPER #4/0 TO BELOW GRADE AND CONNECTION TO GROUNDING ELECTRODE. SEE SHEET EP391 FOR CONTINUATION.
8. PROVIDE CONCRETE ENCLOSED ELECTRODE. PROVIDE 20 FEET OF 1/2"Ø ROD OR 20 FEET OF #4 AWG COPPER CONNECTED TO SLAB STEEL REBAR AND MESH. PLACE SO 3' OF CONCRETE MINIMUM COVER AROUND ELECTRODE.



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:00:40 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadetree Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

FIRST FLOOR GROUNDING PLAN - OVERALL

SHEET NUMBER

EP392



SECOND FLOOR GROUNDING PLAN - OVERALL


Scale: 3/32" = 1'-0"

GENERAL NOTES:

1. GROUNDING CONDUCTOR ROUTED UNDER SLAB TO EQUIPMENT CONNECTION POINT. USE 1" SLEEVE THROUGH SLAB.
2. SEE SHEET EP391 FOR GENERAL NOTES.

(#) PLAN NOTES:

1. PROVIDE 24"L x 4"W x1/2"D SAFETY GROUNDING BAR WITH STANDOFFS FOR MOUNTING. EXOTHERMIC WELD BAR WHIP TO STEEL COLUMN. FOR SWITCHGEAR MAINTENANCE GROUNDING.
2. #3/0 COPPER GROUNDING CONDUCTOR CONNECTION TO SWITCHGEAR AND GENERATOR EQUIPMENT. MECHANICAL CONNECTION AT GEAR. MECHANICAL CONNECTION TO GROUND BAR. ROUTE IN 1"C. SLEEVE WHERE REQUIRED.
3. PROVIDE 96"L x 4"W x 1/2"D GROUNDING BAR WITH STAND OFFS FOR MOUNTING. EXOTHERMIC WELD BAR WHIP TO STEEL COLUMN.
4. PROVIDE 48"L x 4"W x 1/2"D GROUND BAR WITH STAND OFFS FOR MOUNTING. EXOTHERMIC WELD BAR WHIP TO STEEL COLUMN.
5. PROVIDE CONCRETE ENCASED ELECTRODE. PROVIDE 20 FEET OF 1/2" DIAMETER ROD OR 20 FEET OF #4 AWG COPPER CONNECTED TO SLAB STEEL REBAR AND MESH. PLACE SO 3" OF CONCRETE MINIMUM COVER AROUND ELECTRODE.
6. PROVIDE #4/0 BARE COPPER GROUNDING ELECTRODE CONDUCTOR. ROUTE BELOW GRADE AND CONNECT TO GROUNDING ELECTRODE ROD. SEE SHEET EP391 FOR CONTINUATION.



KEY PLAN

SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:08 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 335 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadview Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SECOND FLOOR GROUNDING PLAN - OVERALL

SHEET NUMBER

EP393



ROOF LIGHTNING PROTECTION PLAN - OVERALL

Scale: 3/32" = 1'-0"


LIGHTNING PROTECTION SYSTEM - 2020 NFPA 780, TABLE 4.1.1.1.2			
CLASS II MATERIAL REQUIREMENTS			
TYPE OF CONDUCTOR	PARAMETER	COPPER	ALUMINUM
AIR TERMINAL, SOLID	DIAMETER	1/2"	5/8"
MAIN CONDUCTOR CABLE	SIZE EACH STRAND	15 AWG	13 AWG
	WEIGHT PER LENGTH	375 LB / 1000 FT	190 LB / 1000 FT
	CROSS SECTION AREA	115,000 CIR....	192,000 CIR....
BONDING CONDUCTOR CABLE	SIZE EACH STRAND	17 AWG	14 AWG
	CROSS SECTION AREA	26,240 CIR. MILS	41,100 CIR. MILS
NOTES			
1. BASIS OF DESIGN IS CLASS II ALUMINUM MATERIAL.			
2. ALTERNATE IS CLASS II COPPER MATERIAL.			

GENERAL NOTES:

1. LIGHTNING PROTECTION. CONTRACTOR SHALL PROVIDE A MASTER LABELED SYSTEM. SEE SPECIFICATION 264113.
2. SEE SHEET EP391 FOR GENERAL NOTES.
3. LIGHTNING RODS AND CONNECTION CONDUCTOR WILL BE PLACED ON TOP OF SCREEN WALL.

(#) PLAN NOTES:

1. MAIN LIGHTNING PROTECTION CONDUCTOR. TYPICAL FOR ALL CONDUCTORS ON THIS DRAWING. SEE SCHEDULE ON THIS SHEET.
2. 24" SOLID 5/8"Ø AIR TERMINAL. TYPICAL FOR ALL AIR TERMINALS ON THE THIS DRAWING.
3. EXOTHERMIC WELD. TYPICAL FOR ALL CONNECTIONS ON THIS DRAWING.
4. DOWN CONDUCTOR. SEE DRAWING EP391 FOR CONNECTION TO GROUNDING ELECTRODE SYSTEM.
5. PROVIDE A THRU-ROOF CONNECTOR. CONNECT TO STRUCTURAL STEEL COLUMN BELOW ROOF.
6. ROUTE CABLE UNDER ROOF WALKPADS. PROVIDE CABLE PROTECTION UNDER WALK PADS.



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadyview Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE


LIGHTNING PROTECTION PLAN

SHEET NUMBER

EP394

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:15 PM AESI Proj. No.: 21-154



1 **ENLARGED POWER PLAN - MDF 225**
Scale: 1/2" = 1'-0"

NOTES:

1. PROVIDE MDF BUSWAY 2UPSBUS1. 100A, 208V, 3 PHASE, 4 WRE. STARLINE 100T OR OWNER APPROVED EQUIVALENT. MOUNT AT +10'-0" AFF. PROVIDE END FEED UNIT WITH METERING AND ANGLED DISPLAY COVER. PROVIDE (6) CBDC-X-L630C-4 (30A, 2P, 208V, L630C, 15FT SO CORD & STRAIN RELIEF).
2. PROVIDE MDF BUSWAY 2NBUS1. 100A, 208V, 3 PHASE, 4 WRE. STARLINE 100T OR OWNER APPROVED EQUIVALENT. MOUNT AT +10'-0" AFF. PROVIDE END FEED UNIT WITH METERING AND ANGLED DISPLAY COVER. PROVIDE (6) CBDC-X-L630C-4 (30A, 2P, 208V, L630C, 15FT SO CORD & STRAIN RELIEF).
3. PROVIDE ELECTRIC STRIKE POWER SUPPLY IN NEMA 1 BOX. MOUNT 12" ABOVE DOOR. PROVIDE POWER SUPPLY OF SAME MANUFACTURER AS ELECTRIC STRIKE. SEE DOOR HARDWARE SCHEDULE IN ARCHITECTURAL DRAWINGS FOR DETAILS.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoreline Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ENLARGED POWER PLANS

SHEET NUMBER

EP401

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:16 PM AESI Proj. No: 21-154
0 1/2" 1" 2"




1 **FIRST FLOOR MEZZANINE 480V POWER PLAN**
Scale: 1/4" = 1'-0"

GENERAL NOTES:


1. SEE DRAWING E001 FOR SYMBOLS, ABREVIATIONS, AND GENERAL NOTES.
2. SEE DRAWING SERIES EP5## FOR DETAILS.
3. SEE DRAWING SERIES EP6## FOR SCHEDULES.
4. SEE DRAWING SERIES EP7## FOR DIAGRAMS.

(#) PLAN NOTES:

1. PROVIDE VFD-MAU-1-1-A. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
2. PROVIDE VFD-MAU-1-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
3. PROVIDE VFD-AHU-1-1-A. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
4. PROVIDE SW-AHU-2-1. 60A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK AT +54" AFF ON AHU MEZZANINE.
5. PROVIDE SW-AHU-2-2. 60A, 480V, 3 PHASES, HEAVY DUTY. MOUNT ON STRUT RACK AT +54" AFF ON AHU MEZZANINE.
6. PROVIDE VFD-AHU-2-3. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
7. PROVIDE VFD-AHU-2-4. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
8. PROVIDE VFD-MAU-1-1-B. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
9. PROVIDE VFD-MAU-1-1-C. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
10. PROVIDE VFD-MAU-1-1-D. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
11. PROVIDE VFD-AHU-1-1-B. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
12. PROVIDE VFD-AHU-1-1-C. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
13. PROVIDE VFD-AHU-1-1-D. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
14. PROVIDE VFD-P-1-1. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.
15. PROVIDE VFD-P-1-2. SEE SCHEDULE ON EP601 FOR DETAILS. MOUNT ON STRUT RACK AT +54"AFF.



2 **SECOND FLOOR MEZZANINE 1 480V POWER PLAN**
Scale: 1/4" = 1'-0"



3 **SECOND FLOOR MEZZANINE 2 480V POWER PLAN**
Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

MEZZANINE 480V POWER PLANS

SHEET NUMBER

EP403


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:22 PM AESI Proj. No: 21-154



NOTES:

A. MINIMUM 2" INSULATED STAND-OFF FROM WALL TOM BACK SIDE OF PLATE, 2'-0" ON CENTER.


10 GROUNDING BUS BAR
Scale: NONE




NOTES:

A. SEE GROUND BUS BAR SCHEDULE ON SHEET EP608.

9 SUBSTATION AND MAIN BUILDING BUS BAR GROUNDING
Scale: NONE




5 AIR TERMINAL PIPE MOUNTED
Scale: NONE




NOTE:
REFER TO DRAWING CJ6.H302 FOR SENSING POINT LOCATIONS.

1 REFRIGERANT MONITOR SENSE POINT
Scale: NONE




6 GROUNDING TEST WELL DETAIL
Scale: NONE



NOTES:

A. PROVIDE ROOF BOOT AND SEAL.
B. PROVIDE ROOF PENETRATION.


7 LIGHTNING PROTECTION THRU-ROOF DETAIL
Scale: NONE




LIGHTNING DOWN CONDUCTOR DETAIL NOTES:

1. ALL CONNECTIONS BETWEEN LIGHTNING CONDUCTOR AND STRUCTURAL MEMBERS ARE TO BE MADE WITH EXOTHERMIC WELD.
2. LEAVE FIVE (5) FEET MINIMUM OF CABLE EXPOSED OUTSIDE OF PIER WALL FOR CONNECTION TO GROUND ELECTRODE SYSTEM.
3. ELECTRICAL CONTRACTOR SHALL COORDINATE INSTALLATION OF CONDUCTOR SLEEVE WITH FOUNDATION AND STRUCTURAL WORK.
4. PROTECT EXPOSED CABLE ENDS DURING CONSTRUCTION WITH TWO (2) FEET MINIMUM OF DURABLE HEAT SHRINK TUBING. CUT OFF TUBING AFTER CONSTRUCTION IS COMPLETE.
5. LEAVE THREE (3) FEET MINIMUM EXPOSED CABLE ABOVE PIER FOR LATER CONNECTION TO STEEL COLUMNS. PROTECT EXPOSED CABLE AS INDICATED IN NOTE #4. AFTER PLACEMENT OF STEEL NEATLY TRAIN CABLE INTO STEEL COLUMN FLANGE INTERIOR, CUT OFF EXCESS CABLE AND EXOTHERMIC WELD TO STEEL COLUMN.
6. TOUCH-UP STEEL COLUMN SURFACE AFTER EXOTHERMIC WELD TO MATCH PRIOR FINISH.
7. CONNECT LIGHTNING PROTECTION DOWN CONDUCTOR TO GROUNDING ROD/RING WITH EXOTHERMIC WELD.


2 LIGHTNING DOWN CONDUCTOR DETAIL
Scale: NONE



12 HEAT TRACE RTD AND JUNCTION BOX DETAIL
Scale: NONE




11 HEAT TRACE CONTROLLER BOTTOM SIDE TERMINAL BLOCKS
Scale: NONE



STEEL COLUMN GROUNDING DETAIL NOTES:


1. ALL CONNECTIONS BETWEEN GROUNDING CONDUCTOR AND STRUCTURAL MEMBERS ARE TO BE MADE WITH EXOTHERMIC WELD.
2. LEAVE FIVE (5) FEET MINIMUM OF CABLE EXPOSED OUTSIDE OF PIER WALL FOR CONNECTION TO GROUND ELECTRODE SYSTEM.
3. ELECTRICAL CONTRACTOR SHALL COORDINATE INSTALLATION OF CONDUCTOR SLEEVE WITH FOUNDATION AND STRUCTURAL WORK.
4. PROTECT EXPOSED CABLE ENDS DURING CONSTRUCTION WITH TWO (2) FEET MINIMUM OF DURABLE HEAT SHRINK TUBING. CUT OFF TUBING AFTER CONSTRUCTION IS COMPLETE.
5. LEAVE THREE (3) FEET MINIMUM EXPOSED CABLE ABOVE PIER FOR LATER CONNECTION TO STEEL COLUMNS. PROTECT EXPOSED CABLE AS INDICATED IN NOTE #4. AFTER PLACEMENT OF STEEL NEATLY TRAIN CABLE INTO STEEL COLUMN FLANGE INTERIOR, CUT OFF EXCESS CABLE AND EXOTHERMIC WELD TO STEEL COLUMN.
6. TOUCH-UP STEEL COLUMN SURFACE AFTER EXOTHERMIC WELD TO MATCH PRIOR FINISH.

8 STEEL COLUMN GROUNDING DETAIL
Scale: NONE



PRIMARY - 480V, 3 3W & GROUND ϕ SECONDARY - 208Y/120V, 3 4W & GROUND ϕ

3 TRANSFORMER CONNECTION DIAGRAM
Scale: NONE



CONCRETE ENCASED ELECTRODE DETAIL NOTES:

1. ALL CONNECTIONS BETWEEN GROUNDING ELECTRODE CONDUCTOR AND STRUCTURAL MEMBERS ARE TO BE MADE WITH EXOTHERMIC WELD.
2. LEAVE FIVE (5) FEET MINIMUM OF CABLE EXPOSED OUTSIDE OF PIER WALL FOR CONNECTION TO GROUND ELECTRODE SYSTEM.
3. ELECTRICAL CONTRACTOR SHALL COORDINATE INSTALLATION OF CONDUCTOR WITH FOUNDATION AND STRUCTURAL WORK.
4. PROTECT EXPOSED CABLE ENDS DURING CONSTRUCTION WITH TWO (2) FEET MINIMUM OF DURABLE HEAT SHRINK TUBING. CUT OFF TUBING AFTER CONSTRUCTION IS COMPLETE.

4 CONCRETE ENCASED ELECTRODE GROUNDING DETAIL
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

POWER DETAILS


SHEET NUMBER

EP501


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:23 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



1 **15KV MAIN SERVICE SWITCHGEAR BUS DIAGRAM**
Scale: NONE



2 **15KV MAIN SERVICE SWITCHGEAR ELEVATION**
Scale: NONE



3 **MAIN SERVICE SWITCHGEAR REMOTE HMI/OIT CONTROL CABINET**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:23 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadetree Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SUBSTATION DETAILS - MSS DIAGRAM AND ELEVATION

SHEET NUMBER

EP502



1 SUBSTATION DETAILS - CUP - USS-CH-1 / CH-2

Scale: NONE

DETAIL NOTES:

1. ETHERNET ROUTER WITH (2) FIBER AND (4) COPPER PORTS FOR NETWORK CONNECTIONS TO SCADA SYSTEM.
2. TRANSFORMER SHALL BE CAST COIL DESIGN.
3. MICROPROCESSOR BASED POWER METERING WITH ETHERNET COMMUNICATION INTERFACE TO SUBSTATION GATEWAY.
4. PROVIDE KIRK-KEY INTERLOCK SCHEME FOR PRIMARY SELECTIVE, TO PREVENT PARALLELING SERVICES. FOR SECONDARY MAIN BREAKER OPEN BEFORE SWITCH OPERATION.
5. PROVIDE R/C SNUBBER TO PROTECT AGAINST SWITCHING INDUCED TRANSIENTS.
6. SUBSTATION COMMUNICATIONS GATEWAY.
7. BREAKER PROTECTIVE RELAY UNIT WITH DIGITAL COMMUNICATIONS TO SUBSTATION GATEWAY.
8. COMMUNICATIONS LINK. THE MANUFACTURER SHALL WIRE NETWORK TO ALL COMMUNICATION CAPABLE DEVICES WITHIN THE SUBSTATION TO A CENTRAL GATEWAY IN SWITCHGEAR SECTION.
9. 1200A, 3-PHASE SEGMENTED BUS WITH GROUND.
10. CONTROL POWER TRANSFORMER FOR SUBSTATION, WITH CABLED CONNECTION AND ALTERNATOR CONTROL BETWEEN SUBSTATIONS.
11. TRANSITION SECTION.

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:24 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SUBSTATION DETAILS - USS-CH-1 / CH-2

SHEET NUMBER

EP503




1 CUP SUBSTATION DETAIL USS-MECH-1/USS-MECH-2

Scale: NONE

DETAIL NOTES:

1. ETHERNET ROUTER WITH (2) FIBER AND (4) COPPER PORTS FOR NETWORK CONNECTIONS TO SCADA SYSTEM.
2. TRANSFORMER SHALL BE CAST COIL DESIGN.
3. MICROPROCESSOR BASED POWER METERING WITH ETHERNET COMMUNICATION INTERFACE TO SUBSTATION GATEWAY.
4. PROVIDE KIRK-KEY INTERLOCK SCHEME FOR PRIMARY SELECTIVE, TO PREVENT PARALLELING SERVICES. FOR SECONDARY MAIN BREAKER OPEN BEFORE SWITCH OPERATION.
5. PROVIDE FACTORY INSTALLED (SPD) SURGE PROTECTION DEVICE.
6. SUBSTATION COMMUNICATIONS GATEWAY.
7. BREAKER TRIP UNIT WITH DIGITAL COMMUNICATIONS TO SUBSTATION GATEWAY.
8. COMMUNICATIONS LINK. THE MANUFACTURER SHALL WIRE NETWORK TO ALL COMMUNICATION CAPABLE DEVICES WITHIN THE SUBSTATIOM TO A CENTRAL GATEWAY IN SWITCHGEAR SECTION.
9. PROVIDE R/C SNUBBER TO PROTECT AGAINST SWITCHING INDUCED TRANSIENTS.
10. 5000A 3-PHASE, 4-WIRE, LOW IMPEDANCE BUS DUCT WITH GROUND.
11. CONTROL POWER TRANSFORMER FOR SUBSTATION, WITH CABLED CONNECTION AND ALTERNATOR CONTROL BETWEEN SUBSTATIONS.
12. AUTOMATIC TRANSFER CONTROL WITH AUTO / MANUAL SELECTOR SWITCH AND SYNC CONTROL. INCLUDES CONTACTS FOR INHIBIT CONTROL FROM PS MASTER CONTROLLER.



2 EMERGENCY SUBSTATION DETAIL CUP-ESS

Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:24 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 305 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION
CHECKED BY: AESI	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


SUBSTATION DETAILS - USS-MECH1/MECH2 AND ESS

SHEET NUMBER

EP504




1 PARALLELING SWITCHGEAR BUS DIAGRAM
Scale: NONE




PARALLELING SWITCHGEAR IS TOP ENTRY


2 PARALLELING SWITCHGEAR ELEVATION
Scale: NONE



MV AUTOMATIC TRANSFER SWITCH BUS DIAGRAM




MV AUTOMATIC TRANSFER SWITCH ELEVATION MV-ATS ARE TOP ENTRY




MV AUTOMATIC TRANSFER SWITCH ONE-LINE

3 TYPICAL MV-ATS DETAILS
Scale: NONE



ELEVATION VIEW



PLAN VIEW

4 PS GENERATOR MASTER CONTROLS
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SUBSTATION DETAILS - PS DIAGRAM AND ELEVATION


SHEET NUMBER

EP505


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:25 PM AESI Proj. No: 21-154
0 1/2" 1" 2"




NOTES:
1. THESE DETAILS SHOW THE GENERAL INSTALLATION METHOD.
2. SEE HEAT TRACE SCHEDULE SHEET EP608 AND SPECIFICATION. FOR INSULATION TYPE AND THICKNESS SEE MECHANICAL DRAWINGS.




5 ELECTRICAL POWER HEAT TRACE DETAILS
Scale: 1/4" = 1'-0"



NOTES:
1. THESE DETAILS SHOW THE GENERAL INSTALLATION METHOD.
2. SEE MANUFACTURERS DETAILS FOR MINIMUM BEND RADIUS AND SPACING.
3. SEE MANUFACTURER'S FLANGE ADDER CHART.
4. FOR PIPES WITH MORE THAN ONE PASS OF EHT CABLE, APPLY THE FULL FLANGE ADDER FOR EACH PASS OF EHT CABLE ON EACH FLANGE PAIR.
5. FOR SOME APPLICATION IT MAY BE PHYSICALLY IMPOSSIBLE TO INSTALL ALL PHYSICALLY IMPOSSIBLE TO INSTALL ALL OF THE RECOMMENDED EHT CABLE ON THE FLANGE PAIR. IN THIS CASE, USE UP THE REMAINING EHT CABLE ON THE PIPE TO EITHER SIDE OF THE FLANGED PAIR.




ISOMETRIC




BLIND FLANGE DEAD END


6 ELECTRICAL POWER HEAT TRACE FLANGE DETAILS
Scale: 1/4" = 1'-0"




NOTES:
1. THESE DETAILS SHOW THE GENERAL INSTALLATION METHOD.
2. SEE MANUFACTURERS DETAILS FOR MINIMUM BEND RADIUS AND SPACING.
3. THIS DETAIL DOES NOT APPLY TO DUMMY LEG SUPPORTS. SEE MANUFACTURER'S DETAILS FOR DUMMY LEG SUPPORT INSTALLATIONS.



1 ELECTRICAL POWER HEAT TRACE DEAD LEG DETAILS
Scale: NONE




INSTALLATION OF SINGLE PASS OF EHT CABLE ON VERTICAL ELBOW




INSTALLATION OF MULTI-PASS OF EHT CABLE ON VERTICAL ELBOW

NOTES:
1. THESE DETAILS SHOW THE GENERAL INSTALLATION METHOD




INSTALLATION OF SINGLE PASS OF EHT CABLE ON HORIZONTAL ELBOW



INSTALLATION OF MULTI-PASS OF EHT CABLE ON HORIZONTAL ELBOW

2 ELECTRICAL POWER MULTIPLE TRACE DETAILS
Scale: NONE



SIDE VIEW

SIDE VIEW

NOTES:
1. THESE DETAILS SHOW THE GENERAL INSTALLATION METHOD. THE EHT CABLE INSTALLATION WILL LOOK DIFFERENT FOR DIFFERENT VALVE SHAPES AND EHT LENGTHS.
2. SEE MANUFACTURERS DETAILS FOR MINIMUM BEND RADIUS AND SPACING.
3. FOR PIPES WITH MORE THAN ONE PASS OF EHT CABLE, APPLY THE FULL VALVE ADDER FOR EACH PASS OF EHT CABLE ON EACH VALVE
4. FOR SOME APPLICATIONS IT MAY BE PHYSICALLY IMPOSSIBLE TO INSTALL ALL OF THE RECOMMENDED EHT CABLE ON THE VALVE. IN THIS CASE, USE UP THE REMAINING EHT ON EITHER SIDE OF THE VALVE.
5. SEE MANUFACTURER'S INSTALLATION SHEETS FOR THE ADDER CHART FOR VALVES.

4 ELECTRICAL POWER HEAT TRACE VALVE DETAILS
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL DETAILS

SHEET NUMBER


EP506

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:26 PM AESI Proj No: 21-154


0 1/2" 1" 2"




2 **MV-ATS-CUP-CH-A CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




1 **MSS CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



3 **MV-ATS-CUP-CH-B CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



5 **PS GENERATOR CABLE AND CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



4 **MV-ATS-CUP-MECH-A CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:34 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoreline Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL DETAILS

SHEET NUMBER

EP507



4 **MV-ATS-IUH-OS-A CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



1 **MV-ATS-CUP-MECH-B CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

5 **MV-ATS-IUH-OS-B CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

2 **MV-ATS-IUH-EQ-A CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

3 **MV-ATS-IUH-EQ-B CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:40 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL DETAILS

SHEET NUMBER


EP508




5 **CH-5 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




3 **CH-3 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




1 **CH-1 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



6 **CH-6 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



4 **CH-4 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



2 **CH-2 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:46 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL DETAILS

SHEET NUMBER


EP509




5 UTILITY CHASE ENTRY ELEVATION 1
Scale: 1/4" = 1'-0"



3 USS-CH-2A CONDUIT ELEVATION
Scale: 1/4" = 1'-0"



1 USS-CH-1A CONDUIT ELEVATION
Scale: 1/4" = 1'-0"



6 UTILITY CHASE ENTRY ELEVATION 2
Scale: 1/4" = 1'-0"

4 USS-CH-2B CONDUIT ELEVATION
Scale: 1/4" = 1'-0"

2 USS-CH-1B CONDUIT ELEVATION
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:01:52 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadybrook Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL DETAILS

SHEET NUMBER


EP510




7 **G7 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




4 **G4 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




1 **G1 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




8 **G8 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




5 **G5 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




2 **G2 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



9 **G9 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



6 **G6 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



3 **G3 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:00 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL DETAILS

SHEET NUMBER


EP511




5 **HRC-5 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"




3 **HRC-3 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



1 **HRC-1 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



4 **HRC-4 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



2 **HRC-2 CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY **AESI**	
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE


ELECTRICAL DETAILS

SHEET NUMBER


EP512

0 1/2" 1" 2"


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:07 PM AESI Proj. No: 21-154



1 **IUH LOOP PUMP VFD ELEVATION**
Scale: 1/4" = 1'-0"



3 **FUEL OIL CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



2 **HHW PUMP CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:12 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL DETAILS

SHEET NUMBER


EP513



2 **ESS CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



1 **COOLONG WATER PUMPS CONDUIT ELEVATION**
Scale: 1/4" = 1'-0"



3 **COOLING TOWER SECTION - LIGHTNING PROTECTION**
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:15 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ELECTRICAL DETAILS

SHEET NUMBER

EP514



1 **DUCTBANK ELEVATION LEAVING THE CUP**
Scale: 1/2" = 1'-0"

9



2 **UTILITY DUCTBANK ELEVATION ENTERING CUP**
Scale: 1/2" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: **AESI**	
APPROVED BY: **Approver**	
PROJECT NO.: **21-154**	

SHEET TITLE

ELECTRICAL DETAILS

SHEET NUMBER

EP515

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:18 PM AESI Proj. No: 21-154

AUTOMATIC TRANSFER SWITCH SCHEDULE

NOTES:
1. NOT USED

UNIT TAG	LOCATION	VOLTS	AMPS	PHASES	POLES	WIRES	AIC RATING	EQUIPMENT SERVED	NOTES
ATS-LS1	CUP EMERGENCY ELECTRICAL ROOM 215	480 V	800 A	3	4	4	65	2HLS1	
ATS-EL1	CUP EMERGENCY ELECTRICAL ROOM 215	480 V	800 A	3	4	4	65	2HEL1	
ATS-EQ1	CUP EMERGENCY ELECTRICAL ROOM 215	480 V	800 A	3	4	4	65	2HEQ1	
ATS-GEN1	CUP EMERGENCY ELECTRICAL ROOM 215	480 V	800 A	3	4	4	65	2GEN1	

480V UPS SCHEDULE

Panel Name	Location	KW	PHASES	PRIMARY VOLTAGE	SECONDARY VOLTAGE	BATTERY RUN TIME	UNIT MOUNTING	NOTES
2EQUPS1	CUP EMERGENCY ELECTRICAL ROOM 215	160 kW	3	480 V	480 V	30MIN	FLOOR	
2GENUPS1	CUP EMERGENCY ELECTRICAL ROOM 215	160 kW	3	480 V	480 V	30MIN	FLOOR	

CUP SWITCHGEAR AND SUBSTATION SCHEDULE

SWITCHGEAR	SUBSTATION	PRIMARY VOLTAGE	XFMR SIZE AA (KVA)	XFMR SIZE FA (KVA)	SECONDARY VOLTAGE	BUS AMPS	CONTROL POWER	TRANSFER CONTROL AUTO / MANUAL	SINGLE / DOUBLE ENDED	COMMUNICATION TCP/IP ETHERNET
MSS		13,200			13,200	2,000	125VDC	AUTO	DOUBLE	X
PS		13,200			13,200	2,000	125VDC	AUTO	DOUBLE	X
	ESS-CUP	13,200	2000	2660	480/277	3,200	CPT	-	SINGLE	X
	USS-CH1	13,200	7500	9975	4,160	1,200	CPT	MANUAL	DOUBLE	X
	USS-CH2	13,200	7500	9975	4,160	1,200	CPT	MANUAL	DOUBLE	X
	USS-Mech1	13,200	3000	3990	480/277	5,000	CPT	AUTO	DOUBLE	X
	USS-Mech2	13,200	3000	3990	480/277	5,000	CPT	AUTO	DOUBLE	X

CUP MV-ATS SCHEDULE

SWITCHGEAR	PRIMARY VOLTAGE	NORMAL SOURCE	EMERGENCY SOURCE	BUS AMPS	CONTROL POWER	BYPASS	TRANSFER CONTROL AUTOMATIC	COMMUNICATION TCP/IP ETHERNET
MV-ATS-IUH-OS-A	13,200	MSS	PS	1,200	125VDC	X	X	X
MV-ATS-IUH-OS-B	13,200	MSS	PS	1,200	125VDC	X	X	X
MV-ATS-IUH-EQ-A	13,200	MSS	PS	1,200	125VDC	X	X	X
MV-ATS-IUH-EQ-B	13,200	MSS	PS	1,200	125VDC	X	X	X
MV-ATS-CUP-MECH-A	13,200	MSS	PS	1,200	125VDC	X	X	X
MV-ATS-CUP-MECH-B	13,200	MSS	PS	1,200	125VDC	X	X	X
MV-ATS-CUP-CH-A	13,200	MSS	PS	1,200	125VDC	X	X	X
MV-ATS-CUP-CH-B	13,200	MSS	PS	1,200	125VDC	X	X	X

VARIABLE FREQUENCY DRIVE SCHEDULE

NOTES:
1. SCHEDULE NOTES
2. SCHEDULE NOTES

UNIT TAG	LOCATION	EQUIPMENT SERVED	MOTOR DATA HP	FLA	VOLTS	PH	CONTROLLER DATA CIRCUIT BREAKER FRAME	TRIP	NEMA SIZE	NEMA ENCLOSURE	NOTES
VFD-AHU-1-1-A	Space 224	AHU-1-1-A	10	14 A	480 V	3	30 A	30 A	1	1	
VFD-AHU-1-1-B	Space 224	AHU-1-1-B	10	14 A	480 V	3	30 A	30 A	1	1	
VFD-AHU-1-1-C	Space 224	AHU-1-1-C	10	14 A	480 V	3	30 A	30 A	1	1	
VFD-AHU-1-1-D	Space 224	AHU-1-1-D	10	14 A	480 V	3	30 A	30 A	1	1	
VFD-AHU-2-1		AHU-2-1	7.5	11 A	480 V	3	25 A	25 A	1	1	
VFD-AHU-2-2		AHU-2-2	7.5	11 A	480 V	3	25 A	25 A	1	1	
VFD-AHU-2-3		AHU-2-3	10	14 A	480 V	3	30 A	30 A	X	X	
VFD-AHU-2-4		AHU-2-4	2	3 A	480 V	3	20 A	20 A	1	1	
VFD-CHW-FLTR-1	CHILLER PLANT 114	CHW-FLTR-1	25	34 A	480 V	3	45 A	45 A	2	1	
VFD-CHWP-1	RECEIVING 105	CHWP-1	250	303 A	480 V	3	400 A	400 A	5	1	
VFD-CHWP-2	RECEIVING 105	CHWP-2	250	303 A	480 V	3	400 A	400 A	5	1	
VFD-CHWP-3	RECEIVING 105	CHWP-3	250	303 A	480 V	3	400 A	400 A	5	1	
VFD-CHWP-4	RECEIVING 105	CHWP-4	250	303 A	480 V	3	400 A	400 A	5	1	
VFD-CHWP-5	RECEIVING 105	CHWP-5	250	303 A	480 V	3	400 A	400 A	5	1	
VFD-CHWP-6	RECEIVING 105	CHWP-6	250	303 A	480 V	3	400 A	400 A	5	1	
VFD-CHWP-7	RECEIVING 105	CHWP-7	250	303 A	480 V	3	400 A	400 A	5	1	
VFD-CP-9	RECEIVING 105	CP-9	10	14 A	480 V	3	30 A	30 A	2	1	
VFD-CT-1	15KV SWITCHGEAR 212	CT-1	125	156 A	480 V	3	225 A	225 A	5	4X	
VFD-CT-2	15KV SWITCHGEAR 212	CT-2	125	156 A	480 V	3	225 A	225 A	5	4X	
VFD-CT-3	15KV SWITCHGEAR 212	CT-3	125	156 A	480 V	3	225 A	225 A	5	4X	
VFD-CT-4	15KV SWITCHGEAR 212	CT-4	125	156 A	480 V	3	225 A	225 A	5	4X	
VFD-CT-5	15KV SWITCHGEAR 212	CT-5	125	156 A	480 V	3	225 A	225 A	5	4X	
VFD-CT-6	15KV SWITCHGEAR 212	CT-6	125	156 A	480 V	3	225 A	225 A	5	4X	
VFD-CT-BS-FLTR-1	MECHANICAL 206	CT-BS-FLTR-1	20	27 A	480 V	3	35 A	35 A	2	1	
VFD-CT-BS-FLTR-2	MECHANICAL 206	CT-BS-FLTR-2	20	27 A	480 V	3	35 A	35 A	2	1	
VFD-CT-FLTR-1	CHILLER PLANT 114	CT-FLTR-1	25	34 A	480 V	3	45 A	45 A	2	1	
VFD-CTP-1	CHILLER PLANT 114	CTP-1	250	302 A	480 V	3	600 A	600 A	6	1	
VFD-CTP-2	CHILLER PLANT 114	CTP-2	250	302 A	480 V	3	400 A	400 A	6	1	
VFD-CTP-3	CHILLER PLANT 114	CTP-3	250	302 A	480 V	3	400 A	400 A	6	1	
VFD-CTP-4	CHILLER PLANT 114	CTP-4	250	302 A	480 V	3	400 A	400 A	6	1	
VFD-CTP-5	CHILLER PLANT 114	CTP-5	250	302 A	480 V	3	400 A	400 A	6	1	
VFD-CTP-6	CHILLER PLANT 114	CTP-6	250	302 A	480 V	3	400 A	400 A	6	1	
VFD-DWRP-1	RECEIVING 105	DWRP-1	0.5	1 A	120 V	1	20 A	20 A	0	1	
VFD-EF-1-1	MECHANICAL 206	EF-1-1	0.25	1 A	480 V	3	20 A	20 A	1	1	
VFD-EF-2-1	MECHANICAL 206	EF-2-1	0.25	1 A	480 V	3	20 A	20 A	1	1	
VFD-EF-2-2	CORRIDOR 201	EF-2-2	0.25	1 A	480 V	3	20 A	20 A	X	1	
VFD-EF-2-3	15KV SWITCHGEAR 212	EF-2-3	0.25	1 A	480 V	3	20 A	20 A	1	1	
VFD-EF-2-4	15KV SWITCHGEAR 212	EF-2-4	0.25	1 A	480 V	3	20 A	20 A	1	1	
VFD-EF-2-5	15KV SWITCHGEAR 212	EF-2-4	0.25	1 A	480 V	3	20 A	20 A	1	1	
VFD-EF-2-6	GENERATOR ROOM A 220	EF-2-6	1	2 A	480 V	3	20 A	20 A	X	1	
VFD-EF-2-7	MSS SERVICE SWITCHGEAR 216	EF-2-7	1.5	3 A	480 V	3	20 A	20 A	X	1	
VFD-FO-FLTR-1	CHILLER PLANT 114	FO-FLTR-1	0.5	1 A	480 V	3	15 A	15 A	0	1	
VFD-FO-FLTR-2	CHILLER PLANT 114	FO-FLTR-2	0.5	1 A	480 V	3	15 A	15 A	0	1	
VFD-HHW-FLTR-1	BOILER PLANT 109	HHW-FLTR-1	25	34 A	480 V	3	45 A	45 A	2	1	
VFD-HHWP-1	BOILER PLANT 109	HHWP-1	125	156 A	480 V	3	200 A	200 A	5	1	
VFD-HHWP-2	BOILER PLANT 109	HHWP-2	125	156 A	480 V	3	200 A	200 A	5	1	
VFD-HHWP-3	BOILER PLANT 109	HHWP-3	125	156 A	480 V	3	200 A	200 A	5	1	
VFD-HHWP-4	BOILER PLANT 109	HHWP-4	125	156 A	480 V	3	200 A	200 A	5	1	
VFD-HHWP-5	BOILER PLANT 109	HHWP-5	125	156 A	480 V	3	200 A	200 A	5	1	
VFD-HHWP-6	BOILER PLANT 109	HHWP-6	125	156 A	480 V	3	200 A	200 A	5	1	
VFD-HRCWP-1	RECEIVING 105	HRCWP-1	15	21 A	480 V	3	30 A	30 A	3	1	
VFD-HRCWP-2	RECEIVING 105	HRCWP-2	15	21 A	480 V	3	30 A	30 A	3	1	
VFD-HRCWP-3	RECEIVING 105	HRCWP-3	15	21 A	480 V	3	30 A	30 A	3	1	
VFD-HRHHWP-1	RECEIVING 105	HRHHWP-1	60	77 A	480 V	3	125 A	125 A	4	1	
VFD-HRHHWP-2	RECEIVING 105	HRHHWP-2	60	77 A	480 V	3	125 A	125 A	4	1	
VFD-HRHHWP-3	RECEIVING 105	HRHHWP-3	60	77 A	480 V	3	125 A	125 A	4	1	
VFD-HRW-2-1	MECHANICAL 206	HRW-2-1	0.5	1 A	480 V	3	20 A	20 A	0	1	
VFD-MAU-1-1-A	Space 224	MAU-1-1-A	5	8 A	480 V	3	20 A	20 A	1	1	
VFD-MAU-1-1-B	Space 224	MAU-1-1-B	5	8 A	480 V	3	20 A	20 A	1	1	
VFD-MAU-1-1-C	Space 224	MAU-1-1-C	5	8 A	480 V	3	20 A	20 A	1	1	
VFD-MAU-1-1-D	Space 224	MAU-1-1-D	5	8 A	480 V	3	20 A	20 A	1	1	
VFD-MAU-1-2	Space 224	MAU-1-2	10	14 A	480 V	3	30 A	30 A	1	1	
VFD-MAU-2-1	MECHANICAL 206	MAU-2-1	7.5	11 A	480 V	3	20 A	20 A	X	1	
VFD-MAU-2-2	MECHANICAL 224	MAU-2-2	2	3 A	480 V	3	20 A	20 A	X	1	
VFD-P-1-1	Space 224	P-1-1	0.75	2 A	480 V	3	20 A	20 A	0	1	
VFD-P-1-2	Space 224	P-1-2	0.75	2 A	480 V	3	20 A	20 A	0	1	
VFD-P-2-1	MECHANICAL 206	P-2-1	0.333	1 A	480 V	3	20 A	20 A	0	1	
VFD-P-2-2	MECHANICAL 224	P-2-2	0.33	7 A	120 V	1	20 A	20 A	0	1	
VFD-REF-1	MECHANICAL 206	REF-1	7.5	11 A	480 V	3	20 A	20 A	1	1	
VFD-REF-2	MECHANICAL 206	REF-2	7.5	11 A	480 V	3	20 A	20 A	1	1	
VFD-RF-1	15KV SWITCHGEAR 212	RF-1	5	8 A	480 V	3	20 A	20 A	1	1	
VFD-RF-2	15KV SWITCHGEAR 212	RF-2	5	8 A	480 V	3	20 A	20 A	1	1	

Updated 1/10/2023 - IUH Loads from 9/27/2022 WSP email - CUP Schedules - SSB Updated - Assumption Plaza Garage and CIH are removed from scope.

Normal Power Analysis IUHMC / SSB / Plaza Garage / CUP Normal Power MVA (Demand)	0.5	1	1.5	2	2.5	3	3.5	4	4.5	5	>>>>	10	12	14	2026 Sub Total MVA	2040
Normal Power System																
IUHMC Normal	10748VA														10.748	2.73
IUHMC Equipment	4815 KVA														4.815	1.2
CUP	18826 KVA (Based on Schedules, will update with profile load)														9.413	4.18
SSB	3000 KVA														3	
Plaza Garage	0 KVA														0	
CIH	0 KVA														0	
Normal Power Total															27.98	36.09
															1,223.8 Amps @ 13.2KV	(1,578.6 Amps) @ 13.2KV

Updated 1/10/2023 - IUH Loads from 9/27/2022 WSP email - CUP Schedules - SSB from BOD.

Emergency and Stanby Power Analysis IUHMC / SSB / Plaza Garage / CUP Emergency and Standby Power MVA	0.5	1	1.5	2	2.5	3	3.5	4	4.5	5	5.5	6	6.5	>>>	21	2026 Sub Total MVA	2040
Standby Power System																	
CUP Chiller Plant and Mechanical	18826 KVA (Based on 2026 max profile load, see note 1)															9.413	4.18
CUP Fire Pump	414 KVA															0.414	
IUHMC Equipment	4815KVA									1204 KVA						4.815	1.2
IUHMC Optional Standby	3075 KVA							920 KVA								3.075	0.92
CUP Emergency	1036 KVA	125 KVA														1.036	0.12
SSB Emergency	500 KVA															0.5	
Parking Garage Emergency	0 KVA															0	
Standby Power Sub Total																19.25	6.42

IUHMC Building Essential System MVA	0.5	1	1.5	2	2.5	3	3.5	4	4.5	5	5.5	6	6.5	7	2026 Sub Total MVA	2040
Essential Generator System																
Life Safety	1069.4 KVA														1.069	
Critical	2731.5 KVA														2.732	
IT Equipment	1424.8KVA														1.425	
Imaging Equipment	617.8...														0.618	
Elevator Service	855.1 KVA														0.855	
Essential Equipment	974.3 KVA														0.974	
Future IUHMC Expansion	1840 KVA															1.84
IUHMC Essential Power															7.673	1.84

Notes 1 CUP... Total... 26.93 35.19
2 Assump... Total... 21.5408 28.1488

Generator Loading (DD Documents) Updated 1/10/2023

Emergency...			Bus 1 (5 Generators)				Bus 2 (4 Generators + Space for 10th Gen)												
Load Priority	Load Description	Building / Load Served	P1	P2	P3	P4a	P4b	P6	P8	P1	P2	P3	P4	P5	P7	P8	P9	P10	ATS / MV-ATS	Associated Substations
Essential			Load (KVA) / Priority Assignment														N+1	Future		
P1	Life Safety 1	IUHMC - Essential Fdr A	534.7																ATS	ESS01 & ESS02
P1	Critical 1		682.8																ATS	
P1	Critical 6		682.8																ATS	
P2	Critical 3 (IT Equip)		712.4																ATS	
P2	Critical 8 (Imaging)		308.9																ATS	
P2	Equipment 1			243.6															ATS	Inhibit control
P3	Equipment 4			243.6															ATS	Inhibit control
P3A	Elevator 1				213.8														ATS	Inhibit control
P3B	Elevator 4				213.8														ATS	Inhibit control
P1	Life Safety 2	IUHMC - Essential Fdr B								534.7									ATS	ESS01 & ESS02
P1	Critical 2									682.8									ATS	
P1	Critical 5									682.8									ATS	
P2	Critical 4 (IT Equip)									712.4									ATS	
P2	Critical 7 (Imaging)									308.9									ATS	
P2	Equipment 2										243.6								ATS	Inhibit control
P3	Equipment 3										243.6								ATS	Inhibit control
P3A	Elevator 2											213.8							ATS	Inhibit control
P3B	Elevator 3											213.8							ATS	Inhibit control
P1	Emergency LS	CUP								40									ATS	ESS-CUP
P2	Equipment									279.8	279.8								ATS	Inhibit control
P3	Elevator											33.2							ATS	Inhibit control
P1	Fire Pump									414									FPC	
P1	Emergency LS	SSB	42																ATS	ESS-SSB
P2	Equipment		142	142															ATS	Inhibit control
P3	Elevator				180														ATS	Inhit control
P1	Emergency LS	Plaza Parking Garage	0																ATS	ESS- PG
P2	Equipment			0															ATS	Inhibit control
P3	Elevator				0														ATS	Inhibit control
Optional...																				
P4	Sub EQ Fdr A	IUHMC - Mech / Ventilation				2407.5													MV-ATS	USS-EQ1 & USS-EQ2
P4	Sub EQ Fdr B	IUHMC - Mech / Ventilation											2407.5						MV-ATS	USS-EQ1 & USS-EQ2
P8	Sub 1A / 2A	CUP Chillers							3000										MV-ATS	USS-CH1 & USS-CH2
P8	Sub 1B / 2B	CUP Chillers														3000			MV-ATS	USS-CH1 & USS-CH2
P6	Sub OS Fdr A	IUHMC - Normal / Optional						1537.5											MV-ATS	USS-OS1 & USS-OS2 & USS-OS3
P7	Sub OS Fdr B	IUHMC - Normal / Optional													1537.5				MV-ATS	USS-OS1 & USS-OS2 & USS-OS3
P4	Sub 3A / 4A	CUP Mech Systems					3022.9												MV-ATS	USS-Mech1 & USS-Mech2
P5	Sub 3B / 4B	CUP Mech Systems												886.2					MV-ATS	USS-Mech1 & USS-Mech2
Priority by...																				
		Incoming Priortity Loading (KVA)	3105.6							3655.4										
		Incremental Loading (KVA)	3105.6							3655.4									Side A - 1 Gen ...	
1st G On Bus	3MW Units	Power Generation Available (KVA	3750							3750									Side B - 1 Gen -...	
		Incoming Priortity Loading (KVA)		629.2							767									
		Incremental Loading (KVA)		3734.8							4422.4								Side A - 2 Gen ...	
2nd G On...	3MW Units	Power Generation Available (KVA		7500							7500								Side B - 2 Gen -...	
		Incoming Priortity Loading (KVA)			607.6							460.8								
		Incremental Loading (KVA)			4342.4							4883.2							Side A - 3 Gen ...	
3rd G On Bus	3MW Units	Power Generation Available (KVA			11250							11250							Side B - 3 Gen -...	
		Incoming Priortity Loading (KVA)				2407.5	3022.9						2407.5	886.2	1537.5					
		Incremental Loading (KVA)				6749.9	9772.8						7290.7	8176.9	9714.4				Side A - 4 Gen ...	
4th G On Bus	3MW Units	Power Generation Available (KVA				15000	15000						15000	15000	15000				Side B - 4 Gen -...	
		Incoming Priortity Loading (KVA)						1537.5												
		Incremental Loading (KVA)						11310.3											Side A - 5 Gen ...	
5th G On Bus	3MW Units	Power Generation Available (KVA						18750												
		Incoming Priortity Loading (KVA)							3800							3800	-			
		Incremental Loading (KVA)							15110.3							13514.4	**28624.7**		8 Gen = each...	
Tie 1/2 Close	(9 Gens On E Bus)	Power Generation Available (KVA							-							-	**33750**		9 Gen = each...	

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway North, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**

CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
POWER SCHEDULES

SHEET NUMBER
EP601

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:21 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

PANELBOARD SCHEDULE

Branch Panel...	1NH4		**New/Exist:**	NEW		**Location:**	RECEIVING 105		**Project Name:**	Central Utility Plant							
SPD:	YES		**Main:**	MCB		**Mounting:**	Surface		**Project No.**	Project Number							
Voltage	480Y/277V		**Amp:**	225 A		**Kaic Rating:**	65		**Date**	February 10, 2023							
Feed From:	SWBD7		**Enclosure:**	Type 1		**Feeder:**	SEE CABLE SCHEDULE			Applied Engineering Services (317) 810-4141							

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1					Motor; Heating; Receptacle;...	3.65 1.14								2
3	T-1NL3	3	125 A				2.56 1.14		Motor		20 A	3	BCU-1	4
5								3.88 1.14						6
7						1.14 1.14								8
9	BCU-2	3	20 A		Motor		1.14 1.14		Motor		20 A	3	BCU-4	10
11								1.14 1.14						12
13						1.88 3.88								14
15	BRP-1,2	3	20 A		Motor		1.88 3.88		Motor		30 A	3	VFD-CP-9	16
17								1.88 3.88						18
19						1.88 0.00								20
21	SP-1 IN TUNNEL	3	20 A		Motor		1.88 0.00		Heating		30 A	3	DWH-1	22
23								1.88 0.00						24
25						0.00 0.00								26
27	Spare	3	20 A		--		0.00 0.00		--		30 A	3	Spare	28
29								0.00 0.00						30
31						0.00 0.00								32
33	Spare	3	20 A		--		0.00 0.00		--		30 A	3	Spare	34
35								0.00 0.00						36
37	Spare	1	20 A		--	0.00 0.00			--		20 A	1	Spare	38
39	Spare	1	20 A		--		0.00 0.00		--		20 A	1	Spare	40
41	Spare	1	20 A		--			0.00 0.00	--		20 A	1	Spare	42
						14.73 kVA	**13.6 kVA**	**15.0 kVA**						

	Connected KVA	Demand Factor	Demand KVA
Lighting Load (KVA)			
Receptacle Load (KVA)	6.44	NEC	6.44
Heating Load (KVA)	0.08	1.00	0.08
Motor Load (KVA)	36.80	1.08	39.70
Other Load (KVA)			
Total Load (KVA)	43.31		46.22

Trip Unit Description
Molded Case with Fixed Trip Unit
Molded Case with Electronic Trip Unit (LI)
Molded Case with Electronic Trip iUnit (LSI)

Notes:

PANELBOARD SCHEDULE

Branch Panel...	1NH1		**New/Exist:**	NEW		**Location:**	BOILER PLANT 109		**Project Name:**	Central Utility Plant							
SPD:	YES		**Main:**	MCB		**Mounting:**	Surface		**Project No.**	Project Number							
Voltage	480Y/277V		**Amp:**	225 A		**Kaic Rating:**	65		**Date**	February 10, 2023							
Feed From:	SWBD5		**Enclosure:**	Type 1		**Feeder:**	SEE CABLE SCHEDULE			Applied Engineering Services (317) 810-4141							

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1					Motor; Receptacle; Spare	3.75 1.14								2
3	T-1NL1	3	125 A				3.56 1.14		Motor		20 A	3	BCU-9	4
5								1.98 1.14						6
7						1.14 1.14								8
9	BCU-6	3	20 A		Motor		1.14 1.14		Motor		20 A	3	BCU-8	10
11								1.14 1.14						12
13						1.14 1.14								14
15	BCU-7	3	20 A		Motor		1.14 1.14		Motor		20 A	3	BCU-13	16
17								1.14 1.14						18
19						1.14 0.00								20
21	BCU-10	3	20 A		Motor		1.14 0.00		Motor		20 A	3	P-1-1	22
23								1.14 0.00						24
25						16.63 0.00								26
27	Welding Outlet CHILLER PLANT 114	3	20 A		Other		16.63 0.00		Motor		20 A	3	P-1-2	28
29								16.63 0.00						30
31						0.00 0.00								32
33	Spare	3	20 A		--		0.00 0.00		--		20 A	3	Spare	34
35								0.00 0.00						36
37						0.00 0.00								38
39	Spare	3	20 A		--		0.00 0.00		--		20 A	3	Spare	40
41								0.00 0.00						42
						27.24 kVA	**27.1 kVA**	**25.5 kVA**						

	Connected KVA	Demand Factor	Demand KVA
Lighting Load (KVA)			
Receptacle Load (KVA)	7.56	NEC	7.56
Heating Load (KVA)			
Motor Load (KVA)	22.33	1.04	23.19
Other Load (KVA)	49.88	0.80	39.91
Total Load (KVA)	79.78		70.66

Trip Unit Description
Molded Case with Fixed Trip Unit
Molded Case with Electronic Trip Unit (LI)
Molded Case with Electronic Trip iUnit (LSI)

Notes:

PANELBOARD SCHEDULE

Branch Panel...	2NH1		**New/Exist:**	NEW		**Location:**	15KV SWITCHGEAR 212		**Project Name:**	Central Utility Plant							
SPD:	YES		**Main:**	MCB		**Mounting:**	Surface		**Project No.**	Project Number							
Voltage	480Y/277V		**Amp:**	225 A		**Kaic Rating:**	65		**Date**	February 10, 2023							
Feed From:	SWBD7		**Enclosure:**	Type 1		**Feeder:**	SEE CABLE SCHEDULE			Applied Engineering Services (317) 810-4141							

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1					Other; Motor; Receptacle; Spare	7.91 0.00								2
3	T-2NL1	3	125 A				7.14 0.00		Motor		20 A	3	AHU-2-4	4
5								3.49 0.00						6
7						0.00 0.00								8
9	VFD-AHU-2-1	3	25 A		Motor		0.00 0.00		Motor		20 A	3	VFD-AHU-2-3	10
11								0.00 0.00						12
13						0.00 0.17								14
15	AHU-2-2	3	15 A		Motor		0.00 0.17		Motor		20 A	3	VEF-EF-2-5	16
17								0.00 0.17						18
19						0.00 2.10								20
21	VFD-EF-2-7	3	20 A		Motor		0.00 2.10		Motor		20 A	3	VFD-RF-2	22
23								0.00 2.10						24
25						2.10 0.17								26
27	VFD-RF-1	3	20 A		Motor		2.10 0.17		Motor		20 A	3	EF-2-3	28
29								2.10 0.17						30
31						0.00 0.00								32
33	Spare	3	20 A		--		0.00 0.00		--		15 A	3	Spare	34
35								0.00 0.00						36
37						0.00 0.00								38
39	Spare	3	25 A		--		0.00 0.00		--		20 A	3	Spare	40
41								0.00 0.00						42
						12.45 kVA	**11.7 kVA**	**8.0 kVA**						

	Connected KVA	Demand Factor	Demand KVA
Lighting Load (KVA)			
Receptacle Load (KVA)	14.50	NEC	12.25
Heating Load (KVA)			
Motor Load (KVA)	17.67	1.09	19.24
Other Load (KVA)	0.00	Not Computed	0.00
Total Load (KVA)	32.17		31.49

Trip Unit Description
Molded Case with Fixed Trip Unit
Molded Case with Electronic Trip Unit (LI)
Molded Case with Electronic Trip iUnit (LSI)

Notes:

PANELBOARD SCHEDULE

Branch Panel...	1NH2		**New/Exist:**	NEW		**Location:**	BOILER PLANT 109		**Project Name:**	Central Utility Plant							
SPD:	YES		**Main:**	MCB		**Mounting:**	Surface		**Project No.**	Project Number							
Voltage	480Y/277V		**Amp:**	225 A		**Kaic Rating:**	65		**Date**	February 10, 2023							
Feed From:	SWBD6		**Enclosure:**	Type 1		**Feeder:**	SEE CABLE SCHEDULE			Applied Engineering Services (317) 810-4141							

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1						0.94 2.11								2
3	ROP SKID	3	15 A		Motor		0.94 2.11		Motor		15 A	3	RO CIP SKID PUMP	4
5								0.94 2.11						6
7						0.67 0.00								8
9	LOAD BANK FANS	3	20 A		Motor		0.67 0.00		--		20 A	3	Spare	10
11								0.67 0.00						12
13						0.00 0.00			--		20 A	1	Spare	14
15	Spare	3	15 A		--		0.00 0.00		--		20 A	1	Spare	16
17								0.00 0.00	--		20 A	1	Spare	18
19	Spare	1	20 A		--	0.00 0.00			--		20 A	1	Spare	20
21	Spare	1	20 A		--		0.00 0.00		--		20 A	1	Spare	22
23	Spare	1	20 A		--			0.00 0.00	--		20 A	1	Spare	24
25	Spare	1	20 A		--	0.00 0.00			--		20 A	1	Spare	26
27	Spare	1	20 A		--		0.00 0.00		--		20 A	1	Spare	28
29	Spare	1	20 A		--			0.00 0.00	--		20 A	1	Spare	30
31	Spare	1	20 A		--	0.00 0.00			--		20 A	1	Spare	32
33	Spare	1	20 A		--		0.00 0.00		--		20 A	1	Spare	34
35	Spare	1	20 A		--			0.00 0.00	--		20 A	1	Spare	36
37	Spare	1	20 A		--	0.00 0.00			--		20 A	1	Spare	38
39	Spare	1	20 A		--		0.00 0.00		--		20 A	1	Spare	40
41	Spare	1	20 A		--			0.00 0.00	--		20 A	1	Spare	42
						3.72 kVA	**3.7 kVA**	**3.7 kVA**						

	Connected KVA	Demand Factor	Demand KVA
Lighting Load (KVA)			
Receptacle Load (KVA)		NEC	
Heating Load (KVA)			
Motor Load (KVA)	11.15	1.14	12.72
Other Load (KVA)			
Total Load (KVA)	11.15		12.72

Trip Unit Description
Molded Case with Fixed Trip Unit
Molded Case with Electronic Trip Unit (LI)
Molded Case with Electronic Trip iUnit (LSI)

Notes:

PANELBOARD SCHEDULE

Branch Panel...	2NH2		**New/Exist:**	NEW		**Location:**	CORRIDOR 201		**Project Name:**	Central Utility Plant							
SPD:	YES		**Main:**	MCB		**Mounting:**	Surface		**Project No.**	Project Number							
Voltage	480Y/277V		**Amp:**	225 A		**Kaic Rating:**	65		**Date**	February 10, 2023							
Feed From:	SWBD7		**Enclosure:**	Type 1		**Feeder:**	SEE CABLE SCHEDULE			Applied Engineering Services (317) 810-4141							

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1					Other; Motor; Receptacle; Spare	7.33 3.05								2
3	T-2NL2	3	125 A				6.38 3.05		Motor		20 A	3	VFD-REF-1	4
5								5.03 3.05						6
7						0.17 3.05								8
9	EF-1-1	3	20 A		Motor		0.17 3.05		Motor		20 A	3	VFD-REF-2	10
11								0.17 3.05						12
13						0.17 0.00								14
15	EF-2-1	3	20 A		Motor		0.17 0.00		Motor		20 A	3	EF-2-6	16
17								0.17 0.00						18
19						0.17 0.69								20
21	FVD-EF-2-2	3	20 A		Motor		0.17 0.69		Motor		20 A	3	FCU-R-1	22
23								0.17 0.69						24
25						3.05 0.00								26
27	VFD-P-2-1	3	20 A		Motor		3.05 0.00		--		20 A	3	Spare	28
29								3.05 0.00						30
31						13.58 0.00								32
33	HRW-2-1	3	20 A		Motor		13.58 0.00		--		20 A	3	Spare	34
35								13.58 0.00						36
37						0.00 0.00								38
39	Spare	3	125 A		--		0.00 0.00		--		20 A	3	Spare	40
41								0.00 0.00						42
						31.23 kVA	**30.3 kVA**	**28.9 kVA**						

	Connected KVA	Demand Factor	Demand KVA
Lighting Load (KVA)			
Receptacle Load (KVA)	13.24	NEC	11.62
Heating Load (KVA)			
Motor Load (KVA)	77.22	1.13	87.40
Other Load (KVA)			
Total Load (KVA)	90.46		99.02

Trip Unit Description
Molded Case with Fixed Trip Unit
Molded Case with Electronic Trip Unit (LI)
Molded Case with Electronic Trip iUnit (LSI)

Notes:

PANELBOARD SCHEDULE

Branch Panel...	1NH3		**New/Exist:**	NEW		**Location:**	CHILLER PLANT 114		**Project Name:**	Central Utility Plant							
SPD:	YES		**Main:**	MCB		**Mounting:**	Surface		**Project No.**	Project Number							
Voltage	480Y/277V		**Amp:**	225 A		**Kaic Rating:**	65		**Date**	February 10, 2023							
Feed From:	SWBD7		**Enclosure:**	Type 1		**Feeder:**	SEE CABLE SCHEDULE			Applied Engineering Services (317) 810-4141							

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1					Motor; Receptacle; Spare	3.39 1.14								2
3	T-1NL2	3	125 A				1.80 1.14		Motor		20 A	3	BCU-3	4
5								0.86 1.14						6
7						1.14 1.14								8
9	BCU-15	3	20 A		Motor		1.14 1.14		Motor		20 A	3	BCU-14	10
11								1.14 1.14						12
13						1.14 1.14								14
15	BCU-5	3	20 A		Motor		1.14 1.14		Motor		20 A	3	BCU-11	16
17								1.14 1.14						18
19						0.00 0.00								20
21	Spare	3	20 A		--		0.00 0.00		--		20 A	3	Spare	22
23								0.00 0.00						24
25						0.00 0.00								26
27	Spare	3	20 A		--		0.00 0.00		--		20 A	3	Spare	28
29								0.00 0.00						30
31	Spare	1	20 A		--	0.00 0.00			--		20 A	1	Spare	32
33	Spare	1	20 A		--		0.00 0.00		--		20 A	1	Spare	34
35	Spare	1	20 A		--			0.00 0.00	--		20 A	1	Spare	36
37	Spare	1	20 A		--	0.00 0.00			--		20 A	1	Spare	38
39	Spare	1	20 A		--		0.00 0.00		--		20 A	1	Spare	40
41	Spare	1	20 A		--			0.00 0.00	--		20 A	1	Spare	42
						9.11 kVA	**7.5 kVA**	**6.6 kVA**						

	Connected KVA	Demand Factor	Demand KVA
Lighting Load (KVA)			
Receptacle Load (KVA)	4.32	NEC	4.32
Heating Load (KVA)			
Motor Load (KVA)	18.90	1.05	19.76
Other Load (KVA)			
Total Load (KVA)	23.22		24.08

Trip Unit Description
Molded Case with Fixed Trip Unit
Molded Case with Electronic Trip Unit (LI)
Molded Case with Electronic Trip iUnit (LSI)

Notes:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadybend Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	**AESI**
CHECKED BY	**AESI**
APPROVED BY	**Approver**
PROJECT NO.	**21-154**

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

POWER SCHEDULES

SHEET NUMBER

EP602

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:23 PM AESI Proj. No: 21-154

PANELBOARD SCHEDULE

Branch Panel...	2NL1			**New/Exist:**	NEW			**Location:**	15KV SWITCHGEAR 212				**Project Name:**	Central Utility Plant				
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface				**Project No.**	Project Number				
Voltage	208Y/120V			**Amp:**	200 A			**Kaic Rating:**	22				**Date**	February 10, 2023				
Feed From:	T-2NL1			**Enclosure:**	Type 1			**Feeder:**	SEE T-2NL1 PLAN NOTE					Applied Engineering Services (317) 810-4141				

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1	Receptacle CUP EMERGENCY...	1	20 A		Receptacle	1.44	1.44		Receptacle		20 A	1	Receptacle AES SERVICE SWITCHGEAR...	2
3	Receptacle 15KW SWITCHGEAR 212	1	20 A		Receptacle			1.44	1.44	Receptacle		20 A	1	Receptacle CORRIDOR 227	4
5	Receptacle Room 213, 224	1	20 A		Receptacle				0.36	1.08	Receptacle		20 A	1	Receptacle CONTROL ROOM 209	6
7	Receptacle TOILET / SHOWER 205A	1	20 A		Receptacle	1.44	1.26				Receptacle		20 A	1	Receptacle OFFICE 204	8
9	Receptacle GENERATOR CONTROL 208	1	20 A		Receptacle			1.26	1.44		Receptacle		20 A	1	Receptacle MAINTENANCE WORKROOM...	10
11	UH-3 Space 224	1	20 A		Motor					0.67	0.00	--	20 A	1	Spare	12
13	UH-4	1	20 A		Motor	0.67	0.00					--	20 A	1	Spare	14
15	Receptacle LOCKER / BREAK RM 205	1	20 A		Receptacle			0.36	0.00			--	20 A	1	Spare	16
17	Other LOCKER / BREAK RM 205	1	20 A		Other;..					0.18	0.00	--	20 A	1	Spare	18
19	MONITOR LOCKER / BREAK RM 205	1	20 A		Receptacle	1.00	0.00					--	20 A	1	Spare	20
21	DAMPER ACT. COL. 6-7	1	20 A		Motor			0.30	0.00			--	20 A	1	Spare	22
23	DAMPER ACT. COL. 7-8	1	20 A		Motor					0.30	0.00	--	20 A	1	Spare	24
25	DAMPER ACT. COL. 8-9	1	20 A		Motor	0.30	0.00					--	20 A	1	Spare	26
27	DAMPER ACT. MONITOR SOUTH WEST	1	20 A		Motor			0.90	0.00			--	20 A	1	Spare	28
29	DAMPER ACT. MONITOR SOUTH EAST	1	20 A		Motor					0.90	0.00	--	20 A	1	Spare	30
31	REceptacle Mezzanine 1st floor	1	20 A		Receptacle	0.36	0.00					--	20 A	1	Spare	32
33	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	34
35	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	36
37	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	38
39	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	40
41	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	42
						7.91 kVA		**7.1 kVA**			**3.5 kVA**					

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	14.50	NEC	12.25	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)	4.04	1.04	4.21		
Other Load (KVA)	0.00	Not Computed	0.00		
Total Load (KVA)	18.54		16.46		

PANELBOARD SCHEDULE

Branch Panel...	2NL2			**New/Exist:**	NEW			**Location:**	CORRIDOR 201				**Project Name:**	Central Utility Plant				
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface				**Project No.**	Project Number				
Voltage	208Y/120V			**Amp:**	200 A			**Kaic Rating:**	22				**Date**	February 10, 2023				
Feed From:	T-2NL2			**Enclosure:**	Type 1			**Feeder:**	SEE T-2NL2 PLAN NOTE					Applied Engineering Services (317) 810-4141				

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1						0.00	1.26		Receptacle		20 A	1	Receptacle JANITOR / STORAGE 223	2
3	2NBUSL1	3	100 A		Other		0.00	1.44	Receptacle		20 A	1	Receptacle GENERATOR SWICHGEAR 210	4
5								0.00	1.44	Receptacle		20 A	1	Receptacle GENERATOR EXHAUST...	6
7	Receptacle ROOF	1	20 A		Receptacle	0.90	1.08			Receptacle		20 A	1	Receptacle ROOF	8
9	RECEPT MDF DATA 225	1	20 A		Receptacle		0.72	0.90		Receptacle		20 A	1	RECEPT MDF DATA 225	10
11	Receptacle OFFICE 203	1	20 A		Receptacle				0.72	0.00					12
13	Receptacle OFFICE 226	1	20 A		Receptacle	1.08	0.00				100 A	3	Spare	14
15	Receptacle GENERATOR ROOM A 220	1	20 A		Receptacle			1.44	0.00						16
17	UH-1 GENERATOR ROOM A 220	1	20 A		Motor					0.67	0.00	--	20 A	1	Spare	18
19	Receptacle MECHANICAL 224	1	20 A		Receptacle	1.08	0.00					--	20 A	1	Spare	20
21	UH-2	1	20 A		Motor			0.67	0.00			--	20 A	1	Spare	22
23	VFD-P-2-2	1	20 A		Motor					0.00	0.00	--	20 A	1	Spare	24
25	FCU-N-2	1	20 A		Motor	0.73	0.00					--	20 A	1	Spare	26
27	BCU-16	1	20 A		Motor			0.73	0.00			--	20 A	1	Spare	28
29	DAMPER ACT. COL. 3-4	1	20 A		Motor					0.30	0.00	--	20 A	1	Spare	30
31	DAMPER ACT. COL. 4-5	1	20 A		Motor	0.30	0.00					--	20 A	1	Spare	32
33	DAMPER ACT. COL. 5-6	1	20 A		Motor			0.30	0.00			--	20 A	1	Spare	34
35	DAMPER ACT. MONITOR NORTH EAST	1	20 A		Motor					0.90	0.00	--	20 A	1	Spare	36
37	DAMPER ACT. MONITOR NORTH WEST	1	20 A		Motor	0.90	0.00					--	20 A	1	Spare	38
39	Receptacle Mezzanine	1	20 A		Receptacle			0.18	0.00			--	20 A	1	Spare	40
41	Receptacle LOCKER / BREAK RM 205	1	20 A		Receptacle					1.00	0.00	--	20 A	1	Spare	42
						7.33 kVA		**6.4 kVA**			**5.0 kVA**					

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	13.24	NEC	11.62	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)	5.50	1.03	5.68		
Other Load (KVA)					
Total Load (KVA)	18.74		17.30		

PANELBOARD SCHEDULE

Branch Panel...	1NL1			**New/Exist:**	NEW			**Location:**	BOILER PLANT 109				**Project Name:**	Central Utility Plant				
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface				**Project No.**	Project Number				
Voltage	208Y/120V			**Amp:**	200 A			**Kaic Rating:**	22				**Date**	February 10, 2023				
Feed From:	T-1NL1			**Enclosure:**	Type 1			**Feeder:**	SEE T-1NL1 PLAN NOTE					Applied Engineering Services (317) 810-4141				

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1	Receptacle CHILLER PLANT ELECTRICAL...	1	20 A		Receptacle	1.08	1.44		Receptacle		20 A	1	Receptacle CHILLER PLANT ELECTRICAL...	2
3	Receptacle CHILLER PLANT ELECTRICAL...	1	20 A		Receptacle			1.44	1.08	Receptacle		20 A	1	Receptacle BOILER PLANT 109	4
5	Receptacle BOILER PLANT 109	1	20 A		Receptacle					1.08	0.90	Receptacle	20 A	1	Receptacle BOILER PLANT 109	6
7	FCU-S-2	1	20 A		Motor	0.73	0.50					Motor	20 A	2	OVERHEAD DOOR	8
9	Receptacle MEZZ	1	20 A		Receptacle			0.54	0.50							10
11	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	12
13	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	14
15	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	16
17	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	18
19	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	20
21	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	22
23	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	24
25	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	26
27	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	28
29	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	30
31	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	32
33	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	34
35	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	36
37	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	38
39	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	40
41	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	42
						3.75 kVA		**3.6 kVA**			**2.0 kVA**					

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	7.56	NEC	7.56	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)	1.73	1.14	1.98		
Other Load (KVA)					
Total Load (KVA)	9.29		9.54		

PANELBOARD SCHEDULE

Branch Panel...	1NL2			**New/Exist:**	NEW			**Location:**	CHILLER PLANT 114				**Project Name:**	Central Utility Plant				
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface				**Project No.**	Project Number				
Voltage	208Y/120V			**Amp:**	200 A			**Kaic Rating:**	22				**Date**	February 10, 2023				
Feed From:	T-1NL2			**Enclosure:**	Type 1			**Feeder:**	SEE T-1NL2 PLAN NOTE					Applied Engineering Services (317) 810-4141				

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1	Receptacle CHILLER PLANT 114	1	20 A		Receptacle	1.08	1.08		Receptacle		20 A	1	Receptacle FIRE PUMP ROOM 108	2
3	Receptacle CHILLER PLANT 114	1	20 A		Receptacle			1.08	0.72	Receptacle		20 A	1	Receptacle CHILLER PLANT 114	4
5	Receptacle	1	20 A		Receptacle					0.36	0.50	Motor	20 A	2	Motor CHILLER PLANT 114	6
7	FCU-S-1	1	20 A		Motor	0.73	0.50									8
9	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	10
11	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	12
13	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	14
15	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	16
17	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	18
19	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	20
21	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	22
23	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	24
25	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	26
27	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	28
29	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	30
31	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	32
33	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	34
35	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	36
37	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	38
39	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	40
41	Spare	1	20 A		--					0.00						42
						3.39 kVA		**1.8 kVA**			**0.9 kVA**					

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	4.32	NEC	4.32	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)	1.73	1.14	1.98		
Other Load (KVA)					
Total Load (KVA)	6.05		6.30		

PANELBOARD SCHEDULE

Branch Panel...	1NL3			**New/Exist:**	NEW			**Location:**	RECEIVING 105				**Project Name:**	Central Utility Plant				
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface				**Project No.**	Project Number				
Voltage	208Y/120V			**Amp:**	200 A			**Kaic Rating:**	22				**Date**	February 10, 2023				
Feed From:	T-1NL3			**Enclosure:**	Type 1			**Feeder:**	SEE T-1NL3 PLAN NOTE					Applied Engineering Services (317) 810-4141				

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)	B (KVA)	C (KVA)	Load...	Type	Rating	Pole	Load Name	Ckt
1	DWS-2	1	20 A		Motor	0.36	0.36							
3	DWS-1	1	20 A		Motor			0.36	0.54					
5	Receptacle Space 229	1	20 A		Receptacle					0.54	1.26	Receptacle	20 A	1	Receptacle RECEIVING 105	6
7	Receptacle WATER PUMP ROOM 107	1	20 A		Receptacle	0.90	0.18					Receptacle	20 A	1	Receptacle ENTRY 102	8
9	Receptacle CHILLER PLANT 114	1	20 A		Receptacle			0.72	0.50			Receptacle	20 A	1	DOOR 109U ELECTRIC STRIKE PS	10
11	CHEM. TREAT INST. RECEIVING 105	1	20 A		Receptacle					0.72	0.36	Receptacle	20 A	1	DESK RECEIVING 105	12
13	FCU-N-1	1	20 A		Motor	0.73	0.13					Motor	20 A	1	DWRP-1	14
15	ESEW-2 HEAT TRACE	1	20 A		Heating			0.08	0.36			Receptacle	20 A	1	Receptacle STAIR #1 001	16
17	OVERHEAD DOOR	2	20 A		Motor					0.50	0.50	Motor	20 A	2	OVERHEAD DOOR	18
19						0.50	0.50									20
21	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	22
23	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	24
25	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	26
27	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	28
29	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	30
31	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	32
33	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	34
35	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	36
37	Spare	1	20 A		--	0.00	0.00					--	20 A	1	Spare	38
39	Spare	1	20 A		--			0.00	0.00			--	20 A	1	Spare	40
41	Spare	1	20 A		--					0.00	0.00	--	20 A	1	Spare	42
						3.65 kVA		**2.6 kVA**			**3.9 kVA**					

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	6.44	NEC	6.44	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)	0.08	1.00	0.08	Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)	3.57	1.07	3.82		
Other Load (KVA)					
Total Load (KVA)	10.09		10.34		

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:25 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**

CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
POWER SCHEDULES

SHEET NUMBER
EP603

SWITCHBOARD SCHEDULE

Panel Name:	2EQH1	**New/Exi...**	NEW	**Location:**	CUP EMERGENCY ELECTRIC...	**Project Name:**	Central Utility Plant
SPD:	YES	**Main:**	800A LSI	**Mounting:**	FLOOR	**Project Number:**	Project Number
Voltage:	480Y/277V	**Amp:**	800 A	**Kaic...**	65	**Date:**	February 10, 2023
Feed From:	ATS-EQ1	**Enclosu...**	NEMA 1	**Feeder:**	SEE CABLE SCHEDULE		Applied Engineering Services (317) 810-4141

Ckt	Load Name	Pole	Frame	Trip	Trip...	Basis of Design	Lights	Receptacles	Heating	Power	Motor
1	2EQUPS1	3	200 A	200 A				17 kVA			42 kVA
2	SB-1	3	90 A	90 A							54 kVA
3	Spare	3	200 A	200 A							
4	Spare	3	90 A	90 A							
5	T-2EQL1	3	125 A	125 A					0 VA		
6	T-1EQL1	3	400 A	20 A					0 VA		
7											
8											
9											
10											
11											
12											
13											
14											
15											
16											
17											
18											
19											
20											
Sub-Total in KVA:								**17 kVA**	**0 VA**		**96 kVA**

	Connected KVA	Demand Factor	Demand Kva	Trip Type	Trip Unit Description	Note:
Lighting Load (KVA)					Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	17	79	14	LI	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)	0	Not Computed	0	LSI	Molded Case with Electronic Trip Unit (LSI)	
Motor Load (KVA)	96	114	109	LSIG	Molded Case with Electronic Trip Unit (LSIG)	
Other Load (KVA)	0	Not Computed	0			
Total Load (KVA)	113	109	123			

SWITCHBOARD SCHEDULE

Panel Name:	2ELH1	**New/Exi...**	NEW	**Location:**	CUP EMERGENCY ELECTRIC...	**Project Name:**	Central Utility Plant
SPD:	YES	**Main:**	800A LSI	**Mounting:**	FLOOR	**Project Number:**	Project Number
Voltage:	480Y/277V	**Amp:**	800 A	**Kaic...**	65	**Date:**	February 10, 2023
Feed From:	ATS-EL1	**Enclosu...**	NEMA 1	**Feeder:**	SEE CABLE SCHEDULE		Applied Engineering Services (317) 810-4141

Ckt	Load Name	Pole	Frame	Trip	Trip...	Basis of Design	Lights	Receptacles	Heating	Power	Motor
1	ELEVATOR	3	150 A	150 A							
2	T-2ELL1	3	40 A	40 A							
3	Spare	3	150 A	150 A							
4	Spare	3	40 A	40 A							
5											
6											
7											
8											
9											
10											
11											
12											
13											
14											
15											
16											
17											
18											
19											
20											
Sub-Total in KVA:											

	Connected KVA	Demand Factor	Demand Kva	Trip Type	Trip Unit Description	Note:
Lighting Load (KVA)					Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)				LI	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				LSI	Molded Case with Electronic Trip Unit (LSI)	
Motor Load (KVA)				LSIG	Molded Case with Electronic Trip Unit (LSIG)	
Other Load (KVA)	0	Not Computed	0			
Total Load (KVA)	0	100	0			

PANELBOARD SCHEDULE

Branch Panel...	2EQUPSH1	**New/Exist:**	NEW	**Location:**	CUP EMERGENCY ELECTRICAL...	**Project Name:**	Central Utility Plant
SPD:	YES	**Main:**	MCB	**Mounting:**	Surface	**Project No.**	Project Number
Voltage	480Y/277V	**Amp:**	225 A	**Kaic Rating:**	65	**Date**	February 10, 2023
Feed From:	2EQUPS1	**Enclosure:**	Type 1	**Feeder:**	SEE CABLE SCHEDULE		Applied Engineering Services (317) 810-4141

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)		B (KVA)		C (KVA)		Load...	Type	Rating	Pole	Load Name	Ckt
1						6.49	6.49										2
3	CRAC-1	3	30 A		Motor			6.49	6.49			Motor		30 A	3	CRAC-2	4
5										6.49	6.49						6
7					Other; Receptacle; Spare	6.38	0.50										8
9	T-2EQUPSL1	3	125 A					5.94	0.50			Motor		20 A	3	ACCU-1	10
11										4.86	0.50						12
13						0.50	0.00										14
15	ACCU-2	3	20 A		Motor			0.50	0.00			--		20 A	3	Spare	16
17										0.50	0.00						18
19						0.00	0.00										20
21	Spare	3	20 A		--			0.00	0.00			--		30 A	3	Spare	22
23										0.00	0.00						24
25						0.00	0.00					--		20 A	1	Spare	26
27	Spare	3	20 A		--			0.00	0.00			--		20 A	1	Spare	28
29										0.00	0.00	--		20 A	1	Spare	30
31	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare	32
33	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	34
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	36
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare	38
39	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	40
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	42
						20.35 kVA		**19.9 kVA**		**18.8 kVA**							

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	17.18	NEC	13.59	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)	41.90	1.12	46.76		
Other Load (KVA)	0.00	Not Computed	0.00		
Total Load (KVA)	59.08		60.35		

PANELBOARD SCHEDULE

Branch Panel...	2EQL1	**New/Exist:**	NEW	**Location:**	CUP EMERGENCY ELECTRICAL...	**Project Name:**	Central Utility Plant
SPD:	YES	**Main:**	MCB	**Mounting:**	Surface	**Project No.**	Project Number
Voltage	208Y/120V	**Amp:**	200 A	**Kaic Rating:**	22	**Date**	February 10, 2023
Feed From:	T-2EQL1	**Enclosure:**	Type 1	**Feeder:**	SEE T-2EQL1 PLAN NOTE		Applied Engineering Services (317) 810-4141

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)		B (KVA)		C (KVA)		Load...	Type	Rating	Pole	Load Name	Ckt
1	HC-1	2	30 A		Heating	0.00	0.00					Heating		30 A	1	HC-18	2
3								0.00	0.00			Heating		30 A	1	HC-19	4
5	HC-2	2	30 A		Heating					0.00	0.00	Heating		30 A	1	HC-20	6
7						0.00	0.00					Heating		30 A	1	HC-21	8
9	HC-3	2	30 A		Heating			0.00	0.00			Heating		30 A	1	HC-22	10
11										0.00	0.00	Heating		30 A	1	HC-23	12
13	HC-4	2	30 A		Heating	0.00	0.00					Heating		30 A	1	HC-24	14
15								0.00	0.00			Heating		30 A	2	HC-25	16
17	HC-5	1	30 A		Heating					0.00	0.00						18
19	HC-6	1	30 A		Heating	0.00	0.00					Heating		30 A	2	HC-26	20
21	HC-7	1	30 A		Heating			0.00	0.00			--		20 A	1	Spare	22
23	HC-8	1	30 A		Heating					0.00	0.00	Heating		30 A	2	HC-27	24
25	HC-9	1	30 A		Heating	0.00	0.00										26
27	HC-10	1	30 A		Heating			0.00	0.00			Heating		30 A	2	HC-28	28
29	HC-11	1	30 A		Heating					0.00	0.00						30
31	HC-12	1	30 A		Heating	0.00	0.00					Heating		30 A	1	HC-29	32
33	HC-13	1	30 A		Heating			0.00	0.00			Heating		30 A	1	HC-30	34
35	HC-14	1	30 A		Heating					0.00	0.00	--		20 A	1	Spare	36
37	HC-15	1	30 A		Heating	0.00	0.00					--		20 A	1	Spare	38
39	HC-16	1	30 A		Heating			0.00	0.00			--		20 A	1	Spare	40
41	HC-17	1	30 A		Heating					0.00	0.00	--		20 A	1	Spare	42
						0.00 kVA		**0.0 kVA**		**0.0 kVA**							

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)	0.00	Not Computed	0.00	Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	0.00		0.00		

PANELBOARD SCHEDULE

Branch Panel...	2EQUPSL1	**New/Exist:**	NEW	**Location:**	CUP EMERGENCY ELECTRICAL...	**Project Name:**	Central Utility Plant
SPD:	YES	**Main:**	MCB	**Mounting:**	Surface	**Project No.**	Project Number
Voltage	208Y/120V	**Amp:**	225 A	**Kaic Rating:**	22	**Date**	February 10, 2023
Feed From:	T-2EQUPSL1	**Enclosure:**	Type 1	**Feeder:**	SEE T-2EQUPSL1 PLAN NOTE		Applied Engineering Services (317) 810-4141

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)		B (KVA)		C (KVA)		Load...	Type	Rating	Pole	Load Name	Ckt
1	NAC PANEL CONTROL 112	1	20 A		Other	0.00	0.50					Receptacle		20 A	1	DOOR 215A ELECTRIC STRIKE PS	2
3	ACCESS CONTROL PANEL CONTROL 112	1	20 A		Other			0.00	0.50			Receptacle		20 A	1	DOOR 214A ELECTRIC STRIKE PS	4
5	NITROGEN GENERATOR Space 224	1	20 A		Receptacle					0.50	0.50	Receptacle		20 A	1	DOOR 216A ELECTRIC STRIKE PS	6
7						0.00	0.50					Receptacle		20 A	1	DOOR 301 ELECTRIC STRIKE PS	8
9	2EQUPSBUSL1	3	100 A		Other			0.00	0.18			Receptacle		20 A	1	DATA RACK 1	10
11										0.00	0.18	Receptacle		20 A	1	DATA RACK 2	12
13	NITROGEN GENERATOR MECHANICAL...	1	20 A		Receptacle	0.50	0.18					Receptacle		20 A	1	DATA RACK 3	14
15	DOOR 224 ELECTRIC STRIKE PS	1	20 A		Receptacle			0.50	0.18			Receptacle		20 A	1	DATA RACK 4	16
17	DOOR 222A ELECTRIC STRIKE PS	1	20 A		Receptacle					0.50	0.18	Receptacle		20 A	1	DATA RACK 5	18
19	DOOR 220A ELECTRIC STRIKE PS	1	20 A		Receptacle	0.50	0.18					Receptacle		20 A	1	DATA RACK 6	20
21	DOOR 208C ELECTRIC STRIKE PS	1	20 A		Receptacle			1.50	0.00			--		20 A	1	Spare	22
23	DOOR 209 ELECTRIC STRIKE PS	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare	24
25	NITROGEN GENERATOR MECHANICAL...	1	20 A		Receptacle	0.50	0.00					--		20 A	1	Spare	26
27	FACP 209 CONTROL ROOM	1	20 A		Receptacle			0.50	0.00			--		20 A	1	Spare	28
29	SECURITY PANEL 209 CONTROL ROOM	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare	30
31	Receptacle CONTROL ROOM 209	1	20 A		Receptacle	1.08	0.00					--		20 A	1	Spare	32
33	Receptacle CONTROL ROOM 209	1	20 A		Receptacle			1.08	0.00			--		20 A	1	Spare	34
35	MONITOR CONTROL ROOM 209	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare	36
37	DOOR 225 ELECTRIC STRIKE PS	1	20 A		Receptacle	0.50	0.00					--		20 A	1	Spare	38
39	DOOR 227 ELECTRIC STRIKE PS	1	20 A		Receptacle			0.50	0.00			--		20 A	1	Spare	40
41	DOOR 213A ELECTRIC STRIKE PS	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare	42
						6.38 kVA		**5.9 kVA**		**4.9 kVA**							

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	17.18	NEC	13.59	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)	0.00	Not Computed	0.00		
Total Load (KVA)	17.18		13.59		

PANELBOARD SCHEDULE

Branch Panel...	2ELL1	**New/Exist:**	NEW	**Location:**	CUP EMERGENCY ELECTRICAL...	**Project Name:**	Central Utility Plant
SPD:	YES	**Main:**	MCB	**Mounting:**	Surface	**Project No.**	Project Number
Voltage	208Y/120V	**Amp:**	100 A	**Kaic Rating:**	42	**Date**	February 10, 2023
Feed From:	T-2ELL1	**Enclosure:**	Type 1	**Feeder:**	SEE T-2ELL1 PLAN NOTE		Applied Engineering Services (317) 810-4141

Ckt	Load Name	Pole	Rating	Type	Load...	A (KVA)		B (KVA)		C (KVA)		Load...	Type	Rating	Pole	Load Name	Ckt
1	ELEVATOR LIGHTS AND CONTROLS	1	20 A		Other	0.00	0.00					--		20 A	1	Spare	2
3	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	4
5	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	6
7	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare	8
9	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	10
11	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	12
13	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare	14
15	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	16
17	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	18
19	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare	20
21	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	22
23	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	24
25	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare	26
27	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	28
29	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	30
31	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare	32
33	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	34
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	36
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare	38
39	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare	40
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare	42
						0.00 kVA		**0.0 kVA**		**0.0 kVA**							

	Connected KVA	Demand Factor	Demand KVA	Trip Unit Description	Notes:
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)	0.00	Not Computed	0.00		
Total Load (KVA)	0.00		0.00		

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

POWER SCHEDULES

SHEET NUMBER

EP604

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:27 PM AESI Proj. No: 21-154

PANELBOARD SCHEDULE

Branch Panel...	2GENUPSH1			**New/Exist:**	NEW			**Location:**	CUP EMERGENCY ELECTRICAL...			**Project Name:**	Central Utility Plant						
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface			**Project No.**	Project Number						
Voltage	480Y/277V			**Amp:**	200 A			**Kaic Rating:**	65			**Date**	February 10, 2023						
Feed From:	2GENUPS1			**Enclosure:**	Type 1			**Feeder:**	SEE CABLE SCHEDULE				Applied Engineering Services (317) 810-4141						
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**		**B (KVA)**		**C (KVA)**		**Load...**	**Type**	**Rating**	**Pole**	**Load Name**		**Ckt**	
1						2.00	0.00											2	
3	T-2GENUPSL1	3	125 A		Receptacle; Spare			2.00	0.00			--		125 A	3	Spare		4	
5										2.00	0.00							6	
7						0.00	0.00											8	
9	Spare	3	20 A		--			0.00	0.00			--		20 A	3	Spare		10	
11										0.00	0.00							12	
13	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		14	
15	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		16	
17	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		18	
19	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		20	
21	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		22	
23	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		24	
25	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		26	
27	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		28	
29	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		30	
31	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		32	
33	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		34	
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		36	
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		38	
39	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		40	
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		42	
						2.00 kVA		**2.0 kVA**		**2.0 kVA**									

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	6.00	NEC	6.00	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	6.00		6.00		

PANELBOARD SCHEDULE

Branch Panel...	2GENUPSL1			**New/Exist:**	NEW			**Location:**	CUP EMERGENCY ELECTRICAL...			**Project Name:**	Central Utility Plant						
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface			**Project No.**	Project Number						
Voltage	208Y/120V			**Amp:**	225 A			**Kaic Rating:**	22			**Date**	February 10, 2023						
Feed From:	T-2GENUPSL1			**Enclosure:**	Type 1			**Feeder:**	SEE T-2GENUPSL1 PLAN NOTE				Applied Engineering Services (317) 810-4141						
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**		**B (KVA)**		**C (KVA)**		**Load...**	**Type**	**Rating**	**Pole**	**Load Name**		**Ckt**	
1	MASTER GENERATOR CONTROL 208	1	20 A		Receptacle	0.50	0.00					--		20 A	1	Spare		2	
3	GENERATOR CONTROL-G1 208	1	20 A		Receptacle			0.50	0.00			--		20 A	1	Spare		4	
5	GENERATOR CONTROL-G2 208	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare		6	
7	GENERATOR CONTROL-G3 208	1	20 A		Receptacle	0.50	0.00					--		20 A	1	Spare		8	
9	GENERATOR CONTROL-G4 208	1	20 A		Receptacle			0.50	0.00			--		20 A	1	Spare		10	
11	GENERATOR CONTROL-G5 208	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare		12	
13	GENERATOR CONTROL-G6 208	1	20 A		Receptacle	0.50	0.00					--		20 A	1	Spare		14	
15	GENERATOR CONTROL-G7 208	1	20 A		Receptacle			0.50	0.00			--		20 A	1	Spare		16	
17	GENERATOR CONTROL-G8 208	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare		18	
19	GENERATOR CONTROL-G9 208	1	20 A		Receptacle	0.50	0.00					--		20 A	1	Spare		20	
21	GENERATOR CONTROL-G10 208	1	20 A		Receptacle			0.50	0.00			--		20 A	1	Spare		22	
23	D00R 218A ELECTRIC STRIKE PS	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare		24	
25	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		26	
27	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		28	
29	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		30	
31	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		32	
33	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		34	
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		36	
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		38	
39	Spare	1	20 A		--			0.00	0.00			--		20 A	1	Spare		40	
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		42	
						2.00 kVA		**2.0 kVA**		**2.0 kVA**									

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	6.00	NEC	6.00	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	6.00		6.00		

PANELBOARD SCHEDULE

Branch Panel...	2EQUPSL2			**New/Exist:**	NEW			**Location:**	CUP EMERGENCY ELECTRICAL...			**Project Name:**	Central Utility Plant						
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface			**Project No.**	Project Number						
Voltage	208Y/120V			**Amp:**	400 A			**Kaic Rating:**	22			**Date**	February 10, 2023						
Feed From:	2EQUPSL1			**Enclosure:**	Type 1			**Feeder:**	SEE T-2EQUPSL1 PLAN NOTE				Applied Engineering Services (317) 810-4141						
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**		**B (KVA)**		**C (KVA)**		**Load...**	**Type**	**Rating**	**Pole**	**Load Name**		**Ckt**	
1							0.00					--		20 A	1	Spare		2	
3	DOOR 113D ELECTRIC STRIKE PS	1	20 A		Receptacle			0.50	0.00			--		20 A	1	Spare		4	
5	DOOR 109S ELECTRIKE PS	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare		6	
7	DOOR 109S POWER SUPPLY	1	20 A		Receptacle	0.50	0.00					--		20 A	1	Spare		8	
9	DOOR 109M ELECTRIC STRIKE PS	1	20 A		Receptacle			0.50	0.00			--		20 A	1	Spare		10	
11	MONITOR CONTROL 112	1	20 A		Receptacle					0.50	0.00	--		20 A	1	Spare		12	
13	Receptacle CONTROL 112	1	20 A		Receptacle	1.44	0.00					--		20 A	1	Spare		14	
15	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		16	
17	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		18	
19	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		20	
21	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		22	
23	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		24	
25	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		26	
27	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		28	
29	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		30	
31	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		32	
33	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		34	
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		36	
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		38	
39	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		40	
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		42	
						1.94 kVA		**1.0 kVA**		**1.0 kVA**									

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	3.94	NEC	3.94	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	3.94		3.94		

SWITCHBOARD SCHEDULE

Panel Name:	2GENH1			**New/Exi...**	NEW			**Location:**	CUP EMERGENCY ELECTRIC...			**Project Name:**	Central Utility Plant						
SPD:	YES			**Main:**	800A LSI			**Mounting:**	FLOOR			**Project Number:**	Project Number						
Voltage:	480Y/277V			**Amp:**	800 A			**Kaic...**	65			**Date:**	February 10, 2023						
Feed From:	ATS-GEN1			**Enclosu...**	NEMA1			**Feeder:**	SEE CABLE SCHEDULE				Applied Engineering Services (317) 810-4141						
Ckt	**Load Name**	**Pole**	**Frame**	**Trip**	**Trip...**	**Basis of Design**			**Lights**	**Receptacles**	**Heating**	**Power**	**Motor**						
1	2GENUPSH1	3	200 A	200 A						6 kVA									
2	T-2GENL1	3	125 A	125 A															
3	FO-P-1 CONTROL PANEL	3	15 A	15 A								3 kVA							
4	FO-P-2 CONTROL PANEL	3	15 A	15 A								3 kVA							
5	FO-P-3 CONTROL PANEL	3	15 A	15 A								2 kVA							
6	FO-P-4 CONTROL PANEL	3	15 A	15 A								2 kVA							
7	VFD-FO-FLTR-1	3	15 A	15 A									1 kVA						
8	VFD-FO-FLTR-2	3	15 A	15 A									1 kVA						
9	MSS BATTERY CHARGER	3	60 A	60 A															
10	MSS BATERY CHARGER	3	60 A	60 A															
11	PS/MV-ATS BATTERY CHARGER	3	60 A	60 A															
12	PS/MV-ATS BATTERY CHARGER	3	60 A	60 A															
13	Spare	3	200 A	200 A															
14	Spare	3	125 A	125 A															
15	Spare	3	15 A	15 A															
16	Spare	3	15 A	15 A															
17	Spare	3	60 A	60 A															
18	Spare	3	60 A	60 A															
19																			
20																			
Sub-Total in KVA:										**6 kVA**		**11 kVA**	**3 kVA**						

	Connected KVA	**Demand Factor**	**Demand Kva**	**Trip Type**	**Trip Unit Description**	**Note:**
Lighting Load (KVA)					Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)	6	100	6	LI	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				LSI	Molded Case with Electronic Trip Unit (LSI)	
Motor Load (KVA)	3	113	3	LSIG	Molded Case with Electronic Trip Unit (LSIG)	
Other Load (KVA)	6	80	5			
Total Load (KVA)	26	96	25			

SWITCHBOARD SCHEDULE

Panel Name:	2LSH1			**New/Exi...**	NEW			**Location:**	CUP EMERGENCY ELECTRIC...			**Project Name:**	Central Utility Plant						
SPD:	YES			**Main:**	800A LSI			**Mounting:**	FLOOR			**Project Number:**	Project Number						
Voltage:	480Y/277V			**Amp:**	800 A			**Kaic...**	62			**Date:**	February 10, 2023						
Feed From:	ATS-LS1			**Enclosu...**	NEMA 1			**Feeder:**	SEE CABLE SCHEDULE				Applied Engineering Services (317) 810-4141						
Ckt	**Load Name**	**Pole**	**Frame**	**Trip**	**Trip...**	**Basis of Design**			**Lights**	**Receptacles**	**Heating**	**Power**	**Motor**						
1	1LSH1	3	225 A	225 A					10 kVA										
2	2LSH2	3	225 A	225 A					0 kVA										
3	2LSUPSH1	3	30 A	30 A															
4	JP-1 CONTROLLER	3	20 A	20 A									4 kVA						
5	JP-2 CONTROLLER	3	20 A	20 A									4 kVA						
6	Spare	3	225 A	20 A															
7	Spare	3	400 A	30 A															
8	Spare	3	400 A	20 A															
9																			
10																			
11																			
12																			
13																			
14																			
15																			
16																			
17																			
18																			
19																			
20																			
Sub-Total in KVA:									**10 kVA**				**8 kVA**						

	Connected KVA	**Demand Factor**	**Demand Kva**	**Trip Type**	**Trip Unit Description**	**Note:**
Lighting Load (KVA)	10	100	10		Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)				LI	Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				LSI	Molded Case with Electronic Trip Unit (LSI)	
Motor Load (KVA)	8	113	9	LSIG	Molded Case with Electronic Trip Unit (LSIG)	
Other Load (KVA)						
Total Load (KVA)	18	106	19			

PANELBOARD SCHEDULE

Branch Panel...	2GENL1			**New/Exist:**	NEW			**Location:**	CUP EMERGENCY ELECTRICAL...			**Project Name:**	Central Utility Plant						
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface			**Project No.**	Project Number						
Voltage	208Y/120V			**Amp:**	225 A			**Kaic Rating:**	65			**Date**	February 10, 2023						
Feed From:	T-2GENL1			**Enclosure:**	Type 1			**Feeder:**	SEE T-2GENL1 PLAN NOTE				Applied Engineering Services (317) 810-4141						
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**		**B (KVA)**		**C (KVA)**		**Load...**	**Type**	**Rating**	**Pole**	**Load Name**		**Ckt**	
1	FO-DT-1 CORRIDOR 201	1	20 A		Other	0.70	0.00					--		20 A	1	Spare		2	
3	FO-DT-2 CORRIDOR 201	1	20 A		Other			0.70	0.00			--		20 A	1	Spare		4	
5	FO-DT-3 CORRIDOR 201	1	20 A		Other					0.70	0.00	--		20 A	1	Spare		6	
7	FO-DT-4 CORRIDOR 201	1	20 A		Other	0.70	0.00					--		20 A	1	Spare		8	
9	FO-DT-5 CORRIDOR 201	1	20 A		Other			0.70	0.00			--		20 A	1	Spare		10	
11	FO-DT-6 GENERATOR ROOM B 218	1	20 A		Other					0.70	0.00	--		20 A	1	Spare		12	
13	FO-DT-7 GENERATOR ROOM B 218	1	20 A		Other	0.70	0.00					--		20 A	1	Spare		14	
15	FO-DT-8 GENERATOR ROOM B 218	1	20 A		Other			0.70	0.00			--		20 A	1	Spare		16	
17	FO-DT-9 GENERATOR ROOM B 218	1	20 A		Other					0.70	0.00	--		20 A	1	Spare		18	
19	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		20	
21	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		22	
23	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		24	
25	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		26	
27	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		28	
29	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		30	
31	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		32	
33	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		34	
35	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		36	
37	Spare	1	20 A		--	0.00	0.00					--		20 A	1	Spare		38	
39	Spare	1	20 A		--		0.00	0.00				--		20 A	1	Spare		40	
41	Spare	1	20 A		--					0.00	0.00	--		20 A	1	Spare		42	
						2.09 kVA		**2.1 kVA**		**2.1 kVA**									

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)				Molded Case with Electronic Trip iUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)	6.26	0.80	5.01		
Total Load (KVA)	6.26		5.01		

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY	**AESI**
CHECKED BY	**AESI**
APPROVED BY	**Approver**
PROJECT NO.	**21-154**

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

POWER SCHEDULES

SHEET NUMBER

EP605

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:29 PM AESI Proj. No: 21-154

PANELBOARD SCHEDULE

Branch Panel...	1EQL1			**New/Exist:**	NEW			**Location:**	RECEIVING 105					**Project Name:**	Central Utility Plant				
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface					**Project No.**	Project Number				
Voltage	208Y/120V			**Amp:**	200 A			**Kaic Rating:**	22					**Date**	February 10, 2023				
Feed From:	T-1EQL1			**Enclosure:**	Type 1			**Feeder:**	SEE CABLE SCHEDULE						Applied Engineering Services (317) 810-4141				
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**	**B (KVA)**	**C (KVA)**	**Load...**	**Type**	**Rating**	**Pole**	**Load Name**	**Ckt**					
1	HC-31	2	20 A		Heating	0.00								2					
3							0.00							4					
5	HC-32	2	20 A		Heating			0.00						6					
7						0.00								8					
9	Heating RECEIVING 105	1	20 A		Heating		0.00							10					
11														12					
13														14					
15														16					
17														18					
19														20					
21														22					
23														24					
25														26					
27														28					
29														30					
31														32					
33														34					
35														36					
37														38					
39														40					
41														42					
						0.00 kVA	**0.0 kVA**	**0.0 kVA**											

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)	0.00	Not Computed	0.00	Molded Case with Electronic Trip IUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	0.00		0.00		

PANELBOARD SCHEDULE

Branch Panel...	2EQL1			**New/Exist:**	NEW			**Location:**	CUP EMERGENCY ELECTRICAL...					**Project Name:**	Central Utility Plant				
SPD:	YES			**Main:**	MCB			**Mounting:**	Surface					**Project No.**	Project Number				
Voltage	208Y/120V			**Amp:**	200 A			**Kaic Rating:**	22					**Date**	February 10, 2023				
Feed From:	T-2EQL1			**Enclosure:**	Type 1			**Feeder:**	SEE T-2EQL1 PLAN NOTE						Applied Engineering Services (317) 810-4141				
Ckt	**Load Name**	**Pole**	**Rating**	**Type**	**Load...**	**A (KVA)**	**B (KVA)**	**C (KVA)**	**Load...**	**Type**	**Rating**	**Pole**	**Load Name**	**Ckt**					
1	HC-1	2	30 A		Heating	0.00	0.00		Heating		30 A	1	HC-18	2					
3								0.00	Heating		30 A	1	HC-19	4					
5	HC-2	2	30 A		Heating			0.00	Heating		30 A	1	HC-20	6					
7						0.00	0.00		Heating		30 A	1	HC-21	8					
9	HC-3	2	30 A		Heating		0.00	0.00	Heating		30 A	1	HC-22	10					
11								0.00	Heating		30 A	1	HC-23	12					
13	HC-4	2	30 A		Heating	0.00	0.00		Heating		30 A	1	HC-24	14					
15							0.00	0.00	Heating		30 A	2	HC-25	16					
17	HC-5	1	30 A		Heating			0.00						18					
19	HC-6	1	30 A		Heating	0.00	0.00		Heating		30 A	2	HC-26	20					
21	HC-7	1	30 A		Heating		0.00	0.00						22					
23	HC-8	1	30 A		Heating			0.00	Heating		30 A	2	HC-27	24					
25	HC-9	1	30 A		Heating	0.00	0.00							26					
27	HC-10	1	30 A		Heating		0.00	0.00	Heating		30 A	2	HC-28	28					
29	HC-11	1	30 A		Heating			0.00						30					
31	HC-12	1	30 A		Heating	0.00	0.00		Heating		30 A	1	HC-29	32					
33	HC-13	1	30 A		Heating		0.00	0.00	Heating		30 A	1	HC-30	34					
35	HC-14	1	30 A		Heating			0.00	--		20 A	1	Spare	36					
37	HC-15	1	30 A		Heating	0.00	0.00		--		20 A	1	Spare	38					
39	HC-16	1	30 A		Heating		0.00	0.00	--		20 A	1	Spare	40					
41	HC-17	1	30 A		Heating			0.00	--		20 A	1	Spare	42					
						0.00 kVA	**0.0 kVA**	**0.0 kVA**											

	Connected KVA	**Demand Factor**	**Demand KVA**	**Trip Unit Description**	**Notes:**
Lighting Load (KVA)				Molded Case with Fixed Trip Unit	
Receptacle Load (KVA)		NEC		Molded Case with Electronic Trip Unit (LI)	
Heating Load (KVA)	0.00	Not Computed	0.00	Molded Case with Electronic Trip IUnit (LSI)	
Motor Load (KVA)					
Other Load (KVA)					
Total Load (KVA)	0.00		0.00		

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadybrook Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY **AESI**	
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

ELECTRICAL DETAILS

SHEET NUMBER

EP606

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:30 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

Equipment ID	Load Description	Copper Cable and Conduit	Projectd CT Size Load (Amps)	Tag	Location in Building
MAIN SERVICE SWITCHGEAR (MSS)					
MSS-FDR-1 - Spare (Future Cap Bank)	(Future Cap Bank)		1200		
MSS-FDR-2 - Spare			1200		
MSS-FDR-3 - MV-ATS-IUH-OS-A	Normal Power to MV-ATS-IUH-OS-A	(2)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0009*	IUH
MSS-FDR-4 - MV-ATS-IUH-EQ-A	Normal Power to MV-ATS-IUH-EQ-A	(2)4"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0008*	IUH
MSS-FDR-5 - MV-ATS-CUP-MECH-A	Normal Power to MV-ATS-CUP-MECH-A	(1)5"C, (3)250KCMIL, MV105 W (1) #1/0 GND EACH	1200	*C-15K-0007*	CUP 2ND FLOOR
MSS-FDR-6 - MV-ATS-CUP-CH-A	Normal Power to MV-ATS-CUP-CH-A	(2)5"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0006*	CUP 2ND FLOOR
MSS-FDR-7 - EV1	Normal Power to EV1	(1)5"C, (3)250KCMIL, MV105 W (1) #3/0 GND	1200	*C-15K-0005*	EV
MSS-FDR-8 - SPARE	Spare		1200		PG
MSS-FDR-9 - PG-A	Normal Power to PG-A	(1)5"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0004*	
MSS-FDR-10 - MSSB-A	Normal Power to SSB-A	(3)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0003*	SSB
MSS-MAIN A - Bus A	UTILITY FEED Handoff in Manhole to SS MAIN A - BUS A	(4)6"C, (3)750KCMIL, MV105 W (1) #4/0 GND EACH	2000	*C-15K-0001*	CUP 2ND FLOOR
MSS-TIE BUS A - B	Tie		2000		
MSS-Main B - Bus B	UTILITY FEED Handoff in Manhole to SS MAIN B - BUS B	(4)6"C, (3)750KCMIL, MV105 W (1) #4/0 GND EACH	2000	*C-15K-0002*	CUP 2ND FLOOR
MSS-FDR-11 - MSSB-B	Normal Power to SSB-B	(1)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0010*	SSB
MSS-FDR-12 - PG-B	Normal Power to PG-B	(1)5"C, (3)350KCMIL, MV105 W (1) #3/0 GND	1200	*C-15K-0011*	PG
MSS-FDR-13 - SPARE (Future EV1)	Spare		1200		
MSS-FDR-14 - MV-ATS-CUP-CH-B	Normal Power to MV-ATS-CUP-CH-B	(2)5"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0012*	CUP 2ND FLOOR
MSS-FDR-15 - MV-ATS-CUP-MECH-B	Normal Power to MV-ATS-CUP-MECH-B	(1)5"C, (3)250KCMIL, MV105 W (1) #1/0 GND EACH	1200	*C-15K-0013*	CUP 2ND FLOOR
MSS-FDR-16 - MV-ATS-IUH-EQ-B	Normal Power to MV-ATS-IUH-EQ-B	(2)4"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0014*	IUH
MSS-FDR-17 - MV-ATS-IUH-OS-B	Normal Power to MV-ATS-IUH-OS-B	(2)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0015*	IUH
MSS-FDR-18 - Spare (Future Cap Bank)	(Future Cap Bank)	(3)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	1200		
PARALLELING SWITCHGEAR (PS)					
PS-GEN-1	Generator 1	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN1*	CUP 2ND FLOOR
PS-GEN-2	Generator 2	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN2*	CUP 2ND FLOOR
PS-GEN-3	Generator 3	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN3*	CUP 2ND FLOOR
PS-GEN-4	Generator 4	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN4*	CUP 2ND FLOOR
PS-GEN-5	Generator 5	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN5*	CUP 2ND FLOOR
PS-FDR-1 - MV-ATS-IUH-OS-A	Emergency Power to MV-ATS-IUH-OS-A	(2)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0016*	IUH
PS-FDR-2 - MV-ATS-IUH-EQ-A	Emergency Power to MV-ATS-IUH-EQ-A	(2)4"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0017*	IUH
PS-FDR-3 - MV-ATS-CUP-MECH-A	Emergency Power to MV-ATS-CUP-MECH-A	(1)5"C, (3)250KCMIL, MV105 W (1) #1/0 GND EACH	1200	*C-15K-0018*	CUP 2ND FLOOR
PS-FDR-4 - MV-ATS-CUP-CH-A	Emergency Power to MV-ATS-CUP-CH-A	(2)5"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0019*	CUP 2ND FLOOR
PS-FDR-5 - SSB-A	Emergency Power to SSB-A	(1)5"C, (3)250KCMIL, MV105 W/ (1) #1 GND	400	*C-15K-0020*	SSB
PS-FDR-6 - PG-A	Emergency Power to PG-A	(1)5"C, (3)250KCMIL, MV105 W/ (1) #1 GND	400	*C-15K-0021*	PG
PS-FDR-7 - SPARE	Spare		1200		
PS-FDR-8 - IUH LIFE SAFETY SUB A	Emergency Power to IUH-ESS-A	(2)5"C, (3)350KCMIL, MV105 W/ (1) #1 GND EACH	1200	*C-15K-0022*	IUH
PS-FDR-9 - SPARE	Spare		400		
PS-FDR-10 - SPARE	Spare		1200		
PS-TIE BUS A - B			2000		
PS-FDR-11 - MV-ATS-CUP-CH-B	Emergency Power to MV-ATS-CUP-CH-B	(2)5"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0023*	CUP 2ND FLOOR
PS-FDR-12 - MV-ATS-CUP-MECH-B	Emergency Power to MV-ATS-CUP-MECH-B	(1)5"C, (3)250KCMIL, MV105 W (1) #1/0 GND EACH	1200	*C-15K-0024*	CUP 2ND FLOOR
PS-FDR-13 - MV-ATS-IUH-EQ-B	Emergency Power to MV-ATS-IUH-EQ-B	(2)4"C, (3)350KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0025*	IUH
PS-FDR-14 - MV-ATS-IUH-OS-B	Emergency Power to MV-ATS-IUH-OS-B	(2)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	1200	*C-15K-0026*	IUH
PS-FDR-15 - IUH LIFE SAFETY SUB B	Emergency Power to IUH-ESS-B	(2)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND EACH	1200	*C-15K-0027*	IUH
PS-FDR-16 - CUP LIFE SAFETY SUB	Emergency Power to CUP-ESS	(2)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND EACH	1200	*C-15K-0028*	CUP 2ND FLOOR
PS-FDR-17 - SPARE	Spare		1200		
PS-FDR-18 - SPARE	Spare		400		
PS-FDR-19 - CUP LOAD BANK	Load Bank	(1)4"C, (3)500KCMIL, MV105 W/ (1) #1 GND	400	*C-15K-0029*	CUP ROOF
PS-FDR-20 - SPARE	Spare		400		
PS-GEN-6	Generator 6	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN6*	CUP 2ND FLOOR
PS-GEN-7	Generator 7	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN7*	CUP 2ND FLOOR
PS-GEN-8	Generator 8	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN8*	CUP 2ND FLOOR
PS-GEN-9	Generator 9	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400	*C-15K-GEN9*	CUP 2ND FLOOR
PS-GEN-10 (Future)	Generator 10 (Future)	(1)4"C, (3)#2/0, MV105 W (1) #4 GND	400		
MV-ATS-IUH-OS-A					
MV-ATS-IUH-OS-A - FDR-1	ATS Power to MV-NORM-PRIMARY-A	(2)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	800	*C-15K-0030*	IUH
MV-ATS-IUH-OS-A - FDR-2	Spare		800		
MV-ATS-IUH-EQ-1					
MV-ATS-IUH-EQ-A - FDR-1	ATS Power to MV-EQUIP-PRIMARY-A	(2)5"C, (3)350KCMIL, MV105 W/ (1) #1 GND EACH	800	*C-15K-0031*	IUH
MV-ATS-IUH-EQ-A - FDR-2	Spare		800		
MV-ATS-IUH-OS-B					
MV-ATS-IUH-OS-B - FDR-1	ATS Power to MV-NORM-PRIMARY-B	(2)5"C, (3)500KCMIL, MV105 W (1) #3/0 GND EACH	800	*C-15K-0032*	IUH
MV-ATS-IUH-OS-B - FDR-2	Spare		800		
MV-ATS-IUH-EQ-B					
MV-ATS-IUH-EQ-B - FDR-1	ATS Power to MV-EQUIP-PRIMARY-B	(2)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND EACH	800	*C-15K-0033*	IUH
MV-ATS-IUH-EQ-B - FDR-2	Spare		800		
MV-ATS-CUP-MECH-A					
MV-ATS-CUP-MECH-A - FDR-1	ATS Power to USS-MECH1 Main A	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	600	*C-15K-0034*	CUP 1ST FLOOR
MV-ATS-CUP-MECH-A - FDR-2	Spare		600		CUP 1ST FLOOR
MV-ATS-CUP-MECH-A - FDR-3	ATS Power to USS-MECH2 Main A	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	600	*C-15K-0035*	
MV-ATS-CUP-MECH-A - FDR-4	Spare		600		
MV-ATS-CUP-MECH-B					
MV-ATS-CUP-MECH-B - FDR-1	ATS Power to USS-MECH1 Main B	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	600	*C-15K-0036*	CUP 1ST FLOOR
MV-ATS-CUP-MECH-B - FDR-2	Spare		600		CUP 1ST FLOOR
MV-ATS-CUP-MECH-B - FDR-3	ATS Power to USS-MECH2 Main B	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	600	*C-15K-0037*	
MV-ATS-CUP-MECH-B - FDR-4	Spare		600		
MV-ATS-CUP-CH-A					
MV-ATS-CUP-CH-A - FDR-1	ATS Power to USS-CH1 Main A	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	600	*C-15K-0038*	CUP 1ST FLOOR
MV-ATS-CUP-CH-A - FDR-2	Spare		600		CUP 1ST FLOOR
MV-ATS-CUP-CH-A - FDR-3	ATS Power to USS-CH2 Main A	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	600	*C-15K-0039*	
MV-ATS-CUP-CH-A - FDR-4	Spare		600		
MV-ATS-CUP-CH-B					
MV-ATS-CUP-CH-B - FDR-1	ATS Power to USS-CH1 Main B	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	600	*C-15K-0040*	CUP 1ST FLOOR
MV-ATS-CUP-CH-B - FDR-2	Spare		600		CUP 1ST FLOOR
MV-ATS-CUP-CH-B - FDR-3	ATS Power to USS-CH2 Main B	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	600	*C-15K-0041*	
MV-ATS-CUP-CH-B - FDR-4	Spare		600		
USS-CH-1					
USS-CH1 - FDR-1	CH#1	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	400	*C-5K-0001*	CUP 1ST FLOOR
USS-CH1 - FDR-2	CH#3	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	400	*C-5K-0002*	CUP 1ST FLOOR
USS-CH1 - FDR-3	CH#5	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	400	*C-5K-0003*	CUP 1ST FLOOR
USS-CH1 - FDR-4	Spare		400		
USS-CH-2					
USS-CH1 - FDR-1	CH#2	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	400	*C-5K-0004*	CUP 1ST FLOOR
USS-CH1 - FDR-2	CH#4	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	400	*C-5K-0005*	CUP 1ST FLOOR
USS-CH1 - FDR-3	CH#6	(1)4"C, (3)350KCMIL, MV105 W/ (1) #1 GND	400	*C-5K-0006*	CUP 1ST FLOOR
USS-CH1 - FDR-4	Spare		400		

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadybrook Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

POWER SCHEDULES

SHEET NUMBER

EP607

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:31 PM AESI Proj. No.: 21-154

Equipment ID	Load Description	Cable	Projectd CT Size Load (Amps)	Tag	Location in Building
1NH1					
1NH1#1,3,5 - Transformer for 1NL1	T-1NL1	(1) 1-1/2"C, (3) #1, W (1) #6 GND	125	*C-480-0094*	BOILER PLANT 109
1NH1#2,4,6 - Blower Coil Unit 9	BCU-9	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0095*	BOILER PLANT 109
1NH1#7,9,11 - Blower Coil Unit 6	BCU-6	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0096*	FIRE PUMP ROOM 108
1NH1#8,10,12 - Blower Coil Unit 8	BCU-8	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0097*	BOILER PLANT 109
1NH1#13,15,17 - Blower Coil Unit 7	BCU-7	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0098*	BOILER PLANT 109
1NH1#14,16,18 - Blower Coil Unit 13	BCU-13	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0099*	CHILLER PLANT 114
1NH1#19,21,23 - Blower Coil Unit 10	BCU-10	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0100*	CHILLER PLANT 114
1NH1#20,22,24 - Spare	Spare	(1) 3/4"C, (3) #12, W (1) #12 GND	15	*C-480-0101*	BOILER PLANT 109
1NH1#25,27,29 - Welding Outlet	Welding Outlet	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0102*	CHILLER PLANT 114
1NH1#26,28,30, - Blower Coil Pump 1-1	P-1-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0164*	MEZZANINE
1NH1#31,33,35, - Blower Coil Pump 1-2	P-1-2	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0165*	MEZZANINE
1NH2					
1NH2#1,3,5 - Reverse Osmosis Pump Skid	RO-1	(1) 3/4"C, (3) #12, W (1) #12 GND	15	*C-480-0103*	BOILER PLANT 109
1NH2#2,4,6 - Reverse Osmosis Clean In Place	RO CIP SKID	(1) 3/4"C, (3) #12, W (1) #12 GND	15	*C-480-0104*	BOILER PLANT 109
1NH3					
1NH3#1,3,5 - Transformer for 1NL2	T-1NL2	(1) 1-1/2"C, (3) #1, W (1) #6 GND	125	*C-480-0105*	CHILLER PLANT 114
1NH3#2,4,6 - Blower Coil Unit 3	BCU-3	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0106*	RECEIVING 105
1NH3#7,9,11 - Blower Coil Unit 15	BCU-15	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0107*	CHILLER PLANT 114
1NH3#8,10,12 - Blower Coil Unit 14	BCU-14	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0108*	CHILLER PLANT 114
1NH3#13,15,17 - Blower Coil Unit 5	BCU-5	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0109*	RECEIVING 105
1NH3#14,16,18 - Blower Coil Unit 11	BCU-11	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0156*	BOILER PLANT 109
1NH4					
1NH4#1,3,5 - Transformer for 1NL3	T-1NL3	(1) 1-1/2"C, (3) #1, W (1) #6 GND	125	*C-480-0110*	RECEIVING 105
1NH4#2,4,6 - Blower Coil Unit 1	BCU-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0111*	RECEIVING 105
1NH4#7,9,11 - Blower Coil Unit 2	BCU-2	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0112*	RECEIVING 105
1NH4#8,10,12 - Blower Coil Unit 4	BCU-4	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0113*	RECEIVING 105
1NH4#13,15,17 - Brine Pumps	BRP-1,2	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0124*	RECEIVING 105
1NH4#14,16,18 - Tower Water Return Pump	CP-9	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0155*	RECEIVING 105
1NH4#19,21,23 - Sump Pump 1	SP-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-168*	RECEIVING 105
1NH4#20,22,24 - Domestic Water Heater 1	DWH-1	(1) 3/4"C, (3) #10, W (1) #10 GND	30	*C-480-169*	RECEIVING 105
2NH1					
2NH1#1,3,5 - Transformer for 2NL1	T-2NL1	(1) 1-1/2"C, (3) #1, W (1) #6 GND	125	*C-480-0114*	15KW SWITCHGEAR 212
2NH1#2,4,6 - Air Handling Unit 2-4	AHU-2-4	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0115*	MEZZANINE 2XX
2NH1#7,9,11 - Air Handling Unit 2-1	AHU-2-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0116*	MEZZANINE 2XX
2NH1#8,10,12 - Air Handling Unit 2-5	AHU-2-5	(1) 3/4"C, (3) #12, W (1) #12 GND	15	*C-480-0117*	MEZZANINE 2XX
2NH1#13,15,17 - Air Handling Unit 2-2	AHU-2-2	(1) 3/4"C, (3) #12, W (1) #12 GND	15	*C-480-0118*	MEZZANINE 2XX
2NH1#14,16,18 - Exhaust Fan 2-5	EF-2-5	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0147*	15KV SWITCHGEAR 212
2NH1#19,21,23 - Exhaust Fan 2-7	EF-2-7	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0148*	MSS SWITCHGEAR 216
2NH1#20,22,24 - Return Fan 2	RF-2	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0149*	15KW SWITCHGEAR 212
2NH1#25,27,29 - Return Fan 1	RF-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0150*	15KW SWITCHGEAR 212
2NH1#26,28,30 - Exhaust Fan 2-3	EF-2-3	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0151*	15KW SWITCHGEAR 212
2NH1#31,33,35 - Exhaust Fan 2-4	EF-2-4	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0152*	15KW SWITCHGEAR 212
2NH2					
2NH2#1,3,5 - Transformer for 2NL2	T-2NL2	(1) 1-1/2"C, (3) #1, W (1) #6 GND	125	*C-480-0119*	15KW SWITCHGEAR 212
2NH2#2,4,6 - Rooftop Exhaust Fan 1	REF-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0120*	MECHANICAL 224
2NH2#7,9,11 - Exhaust Fan 1-1	EF-1-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0121*	MECHANICAL 206
2NH2#8,10,12 - Rooftop Exhaust Fan 2	REF-2	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0122*	MECHANICAL 206
2NH2#13,15,17 - Exhaust Fan 2-1	EF-2-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0123*	MECHANICAL 206
2NH2#14,16,18 - Exhaust Fan 2-6	EF-2-6	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0153*	MECHANICAL 206
2NH2#19,21,23 - Exhaust Fan 2-2	EF-2-2	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0154*	MECHANICAL 206
2NH2#20,22,24 - Fan Coil Unit 1-1	FCU-1-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0157*	VEST. 101
2NH2#25,27,29 - Exhaust Coil Pump	P-2-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0166*	MECHANICAL 206
2NH2#26,28,30 - Heat Recovery Wheel 2-1	HRW-2-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0167*	MECHANICAL 206
2EQUPSH1					
2EQUPSH1#1,3,5 - Computer Room A/C 1	CRAC-1	(1) 3/4"C, (3) #10, W (1) #10 GND	30	*C-480-0131*	MECHANICAL 224
2EQUPSH1#2,4,6 - Computer Room A/C 2	CRAC-2	(1) 3/4"C, (3) #10, W (1) #10 GND	30	*C-480-0132*	MECHANICAL 224
2EQUPSH1#7,9,11 - T-2EQUPSL1	T-2EQUPSL1	(1) 1-1/2"C, (3) #1, W (1) #6 GND	125	*C-480-0133*	15KW SWITCHGEAR 212
2EQUPSH1#8,10,12 - Air Conditioning Condenser Unit 1	ACCU-1	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0172*	ROOF
2EQUPSH1#13,15,17 - Air Conditioning Condenser Unit 2	ACCU-2	(1) 3/4"C, (3) #12, W (1) #12 GND	20	*C-480-0173*	ROOF
2GENUPSH1					
2EQUPSH1#7,9,11 - T-2GENUPSL1	T-2GENUPSL1	(1) 1-1/2"C, (3) #1, W (1) #6 GND	125	*C-480-0190*	CUP EMERGENCY ELECTRICAL ROOM 215

Equipment ID	Load Description	Copper Cable and Conduit	Aluminum Cable and Conduit	Projectd CT Size Load (Amps)	Tag	Location in Building
CUP-ESS						
CUP-ESS-FDR-1 - ATS LIFE SAFETY	E Power to Life Safety ATS	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0001*	CUP EMERGENCY ELECTRICAL ROOM 215
CUP-ESS-FDR-2 - ATS ELEVATOR	E Power to Elevator ATS	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0002*	CUP EMERGENCY ELECTRICAL ROOM 215
CUP-ESS-FDR-3 - Spare	Spare			1600		
CUP-ESS-FDR-4 - Spare	Spare			1600		
CUP-ESS-FDR-5 - GEN EQUIPMENT	E Power to Generator Equipment...	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0003*	CUP EMERGENCY ELECTRICAL ROOM 215
CUP-ESS-FDR-6 - Spare	Spare			1600		
CUP-ESS-FDR-7 - Spare	Spare			1600		
CUP-ESS-FDR-8 - Fire Pump 1 Emergency	Emergency Feeder to FP-1	(7) 3/C 500KCMIL, W/ (1) 350KCMIL GND	(7) 3/C 500KCMIL, W/ (1) 350KCMIL GND	2500	*C-480-0004*	FIRE PUMP ROOM 108
CUP-ESS-FDR-9 - Spare	Spare			800		
CUP-ESS-FDR-10 - Spare	Spare			400		
CUP-ESS-FDR-11 - ATS EQUIPMENT	E Power to Equipment ATS	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0006*	CUP EMERGENCY ELECTRICAL ROOM 215
CUP-ESS-FDR-12 - Fire Pump 2 Emergency	Emergency Feeder to FP-2	(7) 3/C 500KCMIL, W/ (1) 350KCMIL GND	(7) 3/C 500KCMIL, W/ (1) 350KCMIL GND	2500	*C-480-0007*	FIRE PUMP ROOM 108
USS-MECH1						
USS-MECH1-FDR-1 - Heat Recovery Chiller 1	HRC-1	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0008*	CHILLER PLANT 114
USS-MECH1-FDR-2 - Heat Recovery Chiller 3	HRC-3	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0009*	CHILLER PLANT 114
USS-MECH1-FDR-3 - Switchboard 5	SWBD-5	(5) 4"C, (4)500KCMIL, W/ (1) #4/0 GND EACH	(5) 4"C, (4)600KCMIL, W/ (1) #350KCMIL GND EACH	1600	*C-480-0010*	CHILLER PLANT ELECTRICAL ROOM 113
USS-MECH1-FDR-4 - Switchboard 1	SWBD-1	(5) 4"C, (4)500KCMIL, W/ (1) #4/0 GND EACH	(5) 4"C, (4)600KCMIL, W/ (1) #350KCMIL GND EACH	1600	*C-480-0011*	CHILLER PLANT ELECTRICAL ROOM 113
USS-MECH1-FDR-5 - Automatic Transfer Switch - Elevator	ATS-EL	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0176*	CUP EMERGENCY ELECTRICAL ROOM 215
USS-MECH1-FDR-6 - Spare	Spare			1600		
USS-MECH1-FDR-7 - Spare	Spare			1600		
USS-MECH1-FDR-8 - Spare	Spare			1600		
USS-MECH1-FDR-9 - Spare	Spare			1600		
USS-MECH1-FDR-10 - Switchboard 7	SWBD-7	(5) 4"C, (4)500KCMIL, W/ (1) #4/0 GND EACH	(5) 4"C, (4)600KCMIL, W/ (1) #350KCMIL GND EACH	800	*C-480-0012*	CHILLER PLANT ELECTRICAL ROOM 113
USS-MECH1-FDR-11 - Automatic Transfer Switch - Generator	ATS-GEN	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0177*	CUP EMERGENCY ELECTRICAL ROOM 215
USS-MECH1-FDR-12 - Spare	Spare			800		
USS-MECH1-FDR-13 - Switchboard 3	SWBD-3	(5) 4"C, (4)500KCMIL, W/ (1) #4/0 GND EACH	(5) 4"C, (4)600KCMIL, W/ (1) #350KCMIL GND EACH	1600	*C-480-0013*	CHILLER PLANT ELECTRICAL ROOM 113
USS-MECH1-FDR-14 - Heat Recovery Chiller 5	HRC-5	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0014*	CHILLER PLANT 114
USS-MECH1-FDR-15 - Spare	Spare			800		
USS-MECH1-FDR-16 - Fire Pump 1 Normal	FP-1 Controller	(7) 3/C 500KCMIL, W/ (1) 350KCMIL GND	(7) 3/C 500KCMIL, W/ (1) 350KCMIL GND	2500	*C-480-0015*	FIRE PUMP ROOM 108
USS-MECH2						
USS-MECH2-FDR-1 - Heat Recovery Chiller 2	HRC-2	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0016*	CHILLER PLANT 114
USS-MECH2-FDR-2 - Spare	Spare			800		
USS-MECH2-FDR-3 - Switchboard 6	SWBD-6	(5) 4"C, (4)500KCMIL, W/ (1) #4/0 GND EACH	(5) 4"C, (4)600KCMIL, W/ (1) #350KCMIL GND EACH	1600	*C-480-0017*	CHILLER PLANT ELECTRICAL ROOM 113
USS-MECH2-FDR-4 - Switchboard 2	SWBD-2	(5) 4"C, (4)500KCMIL, W/ (1) #4/0 GND EACH	(5) 4"C, (4)600KCMIL, W/ (1) #350KCMIL GND EACH	1600	*C-480-0018*	CHILLER PLANT ELECTRICAL ROOM 113
USS-MECH2-FDR-5 - Automatic Transfer Switch - Life Safety	ATS-LS	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0174*	CUP EMERGENCY ELECTRICAL ROOM 215
USS-MECH2-FDR-6 - Spare	Spare			1600		
USS-MECH2-FDR-7 - Spare	Spare			1600		
USS-MECH2-FDR-8 - Spare	Spare			1600		
USS-MECH2-FDR-9 - Spare	Spare			1600		
USS-MECH2-FDR-10 - Automatic Transfer Switch - Equipment	ATS-EQ	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0175*	CUP EMERGENCY ELECTRICAL ROOM 215
USS-MECH2-FDR-11 - Spare	Spare			800		
USS-MECH2-FDR-12 - Spare	Spare			1600		
USS-MECH2-FDR-13 - Switchboard 4	SWBD-4	(5) 4"C, (4)500KCMIL, W/ (1) #4/0 GND EACH	(5) 4"C, (4)600KCMIL, W/ (1) #350KCMIL GND EACH	1600	*C-480-0020*	CHILLER PLANT ELECTRICAL ROOM 113
USS-MECH2-FDR-14 - Heat Recovery Chiller 4	HRC-4	(2) 4"C, (4)600KCMIL, W (1) #1/0 GND EACH	(2) 4"C, (4)750KCMIL, W (1) #1/0 GND EACH	800	*C-480-0021*	CHILLER PLANT 114
USS-MECH2-FDR-15 - Spare	Spare			800		
USS-MECH2-FDR-16 - Fire Pump 2 normal	FP-2 Controller	(7) 3/C 500KCMIL, W/ (1) 350KCMIL GND	(7) 3/C 500KCMIL, W/ (1) 350KCMIL GND	2500	*C-480-0022*	FIRE PUMP ROOM 108
SWBD-1						
SWBD-1-FDR-1 - VFD for Cooling Tower Fan 1	VFD-CT-1	(1) 2"C, (3) #4/0, W (1) #4 GND	(1) 2-1/2"C, 300KCMIL, W (1) #4 GND	225	*C-480-0023*	CHILLER PLANT 114
SWBD-1-FDR-2 - VFD for Cooling Tower Fan 3	VFD-CT-3	(1) 2"C, (3) #4/0, W (1) #4 GND	(1) 2-1/2"C, 300KCMIL, W (1) #4 GND	225	*C-480-0024*	CHILLER PLANT 114
SWBD-1-FDR-3 - VFD for Cooling Tower Fan 5	VFD-CT-5	(1) 2"C, (3) #4/0, W (1) #4 GND	(1) 2-1/2"C, 300KCMIL, W (1) #4 GND	225	*C-480-0025*	CHILLER PLANT 114
SWBD-1-FDR-4 - VFD for Cooling Tower Pump 1	VFD-CTP-1	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0026*	CHILLER PLANT 114
SWBD-1-FDR-5 - VFD for Cooling Tower Pump 3	VFD-CTP-3	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0027*	CHILLER PLANT 114
SWBD-1-FDR-6 - VFD for Cooling Tower Pump 5	VFD-CTP-5	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0028*	CHILLER PLANT 114
SWBD-1-FDR-7 - VFD for Tower Basin Sweeper	VFD-CT-BASIN-SWP-FLTR-1			35	*C-480-0030*	MECHANICAL 206
SWBD-1-FDR-8 - CT-1 Basin Heaters	CT-HTR-1	(1) 1-1/2"C, (3) #1, W (1) #8 GND		100	*C-480-0178*	COOLING TOWER 1 MEZZ
SWBD-1-FDR-9 - CT-3 Basin Heaters	CT-HTR-2	(1) 1-1/2"C, (3) #1, W (1) #8 GND		100	*C-480-0179*	COOLING TOWER 1 MEZZ
SWBD-1-FDR-10 - CT-5 Basin Heaters	CT-HTR-3	(1) 1-1/2"C, (3) #1, W (1) #8 GND		100	*C-480-0180*	COOLING TOWER 1 MEZZ
SWBD-2						
SWBD-2-FDR-1 - VFD for Cooling Tower Fan 2	VFD-CT-2	(1) 2"C, (3) #4/0, W (1) #4 GND	(1) 2-1/2"C, 300KCMIL, W (1) #4 GND	225	*C-480-0031*	CHILLER PLANT 114
SWBD-2-FDR-2 - VFD for Cooling Tower Fan 4	VFD-CT-4	(1) 2"C, (3) #4/0, W (1) #4 GND	(1) 2-1/2"C, 300KCMIL, W (1) #4 GND	225	*C-480-0032*	CHILLER PLANT 114
SWBD-2-FDR-3 - VFD for Cooling Tower Fan 6	VFD-CT-6	(1) 2"C, (3) #4/0, W (1) #4 GND	(1) 2-1/2"C, 300KCMIL, W (1) #4 GND	225	*C-480-0033*	CHILLER PLANT 114
SWBD-2-FDR-4 - VFD for Cooling Tower Pump 2	VFD-CTP-2	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0034*	CHILLER PLANT 114
SWBD-2-FDR-5 - VFD for Cooling Tower Pump 4	VFD-CTP-4	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0035*	CHILLER PLANT 114
SWBD-2-FDR-6 - VFD for Cooling Tower Pump 6	VFD-CTP-6	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0036*	CHILLER PLANT 114
SWBD-2-FDR-7 - VFD for Tower Basin Sweeper	VFD-CT-BASIN-SWP-FLTR-2	(1) 3/4"C, (3) #8, W (1) #10 GND		35	*C-480-0038*	MECHANICAL 206
SWBD-2-FDR-8 - VFD for Cooling Tower Filter	VFD-CC-SS-FLTR-1	(1) 3/4"C, (3) #6, W (1) #10 GND		45	*C-480-0039*	CHILLER PLANT 114
SWBD-2-FDR-9 - CT-2 Basin Heaters	CT-HTR-2	(1) 1-1/2"C, (3) #1, W (1) #8 GND		100	*C-480-0181*	COOLING TOWER 1 MEZZ
SWBD-2-FDR-10 - CT-4 Basin Heaters	CT-HTR-4	(1) 1-1/2"C, (3) #1, W (1) #8 GND		100	*C-480-0182*	COOLING TOWER 1 MEZZ
SWBD-2-FDR-11 - CT-6 Basin Heaters	CT-HTR-6	(1) 1-1/2"C, (3) #1, W (1) #8 GND		100	*C-480-0183*	COOLING TOWER 1 MEZZ
SWBD-3						
SWBD-3-FDR-1 - VFD for Chilled Water Pump 1	VFD-CHWP-1	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0040*	RECEIVING 105
SWBD-3-FDR-2 - VFD for Chilled Water Pump 3	VFD-CHWP-3	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0041*	RECEIVING 105
SWBD-3-FDR-3 - VFD for Chilled Water Pump 5	VFD-CHWP-5	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0042*	RECEIVING 105
SWBD-3-FDR-4 - VFD for Chilled Water Pump 7	VFD-CHWP-7	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0043*	RECEIVING 105
SWBD-3-FDR-5 - VFD for Hosp. Recirc. Heating Hot Water Pump 1	VFD-HRHHWP-1	(1) 1-1/2"C, (3) #1, W (1) #6 GND		125	*C-480-0044*	RECEIVING 105
SWBD-3-FDR-6 - VFD for Hosp. Recirc. Heating Hot Water Pump 1	VFD-HRHHWP-3	(1) 1-1/2"C, (3) #1, W (1) #6 GND		125	*C-480-0045*	RECEIVING 105
SWBD-3-FDR-7 - VFD for Hosp. Recirc. Chilled Water Pump 1	VFD-HRCWP-1	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0046*	RECEIVING 105
SWBD-3-FDR-8 - VFD for Hosp. Recirc. Chilled Water Pump 3	VFD-HRCWP-3	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0047*	RECEIVING 105
SWBD-4						
SWBD-4-FDR-1 - VFD for Chilled Water Pump 2	VFD-CHWP-2	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0048*	RECEIVING 105
SWBD-4-FDR-2 - VFD for Chilled Water Pump 4	VFD-CHWP-4	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0049*	RECEIVING 105
SWBD-4-FDR-3 - VFD for Chilled Water Pump 6	VFD-CHWP-6	(1) 4"C, (3) 600KCMIL, W (1) #3 GND	(1) 4"C, (3)750KCMIL, W/ (1) #3 GND	400	*C-480-0050*	RECEIVING 105
SWBD-4-FDR-4 - VFD for Hosp. Recirc. Heating Hot Water Pump 2	VFD-HRHHWP-2	(1) 1-1/2"C, (3) #1, W (1) #6 GND		125	*C-480-0051*	RECEIVING 105
SWBD-4-FDR-5 - VFD for Hosp. Recirc. Chilled Water Pump 2	VFD-HRCWP-2	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0052*	RECEIVING 105
SWBD-4-FDR-6 - VFD for Chiulled Water Filter	FVD-CHW-SS-FLTR-1	(1) 3/4"C, (3) #6, W (1) #10 GND		45	*C-480-0053*	MECHANICAL 206
SWBD-5						
SWBD-5-FDR-1 - VFD for Heating Hot Water Filter 1	VFD-HHW-FLTR-1	(1) 3/4"C, (3) #6, W (1) #10 GND		45	*C-480-0054*	BOILER PLANT 109
SWBD-5-FDR-2 - VFD for Heating Hot Water Pump 1	VFD-HHWP-1	(1) 2"C, (3) #3/0, W (1) #6 GND	(1) 2-1/2"C, (3) #250KCMIL, W (1) #6 GND	200	*C-480-0055*	BOILER PLANT 109
SWBD-5-FDR-3 - VFD for Heating Hot Water Pump 3	VFD-HHWP-3	(1) 2"C, (3) #3/0, W (1) #6 GND	(1) 2-1/2"C, (3) #250KCMIL, W (1) #6 GND	200	*C-480-0056*	BOILER PLANT 109
SWBD-5-FDR-4 - VFD for Heating Hot Water Pump 5	VFD-HHWP-5	(1) 2"C, (3) #3/0, W (1) #6 GND	(1) 2-1/2"C, (3) #250KCMIL, W (1) #6 GND	200	*C-480-0057*	BOILER PLANT 109
SWBD-5-FDR-5 - Spare	Spare					
SWBD-5-FDR-6 - Steam Boiler 3	SB-3	(1) 1-1/4C, (3) #2, W (1) #8 GND		90	*C-480-0059*	BOILER PLANT 109
SWBD-5-FDR-7 - Heating Hot Water Boiler 1	HHWB-1	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0060*	BOILER PLANT 109
SWBD-5-FDR-8 - Heating Hot Water Boiler 3	HHWB-3	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0061*	BOILER PLANT 109
SWBD-5-FDR-9 - Heating Hot Water Boiler 5	HHWB-5	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0062*	BOILER PLANT 109
SWBD-5-FDR-10 - Heating Hot Water Boiler 7	HHWB-7	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0063*	BOILER PLANT 109
SWBD-5-FDR-11 - Fuel Oil Filter	VFD-FO-FLTR-1	(1) 3/4"C, (3) #12, W (1) #12 GND		15	*C-480-0064*	FUEL OIL ROOM 103
SWBD-5-FDR-12 - Fuel Oil Pump Skid 1	FO-P-1	(1) 3/4"C, (3) #12, W (1) #12 GND		15	*C-480-0065*	FUEL OIL ROOM 103
SWBD-5-FDR-13 - Fuel Oil Pump Skid 3	FO-P-3	(1) 3/4"C, (3) #12, W (1) #12 GND		15	*C-480-0066*	FUEL OIL ROOM 103
SWBD-5-FDR-14 - DA Pump	DA-1	(1) 1-1/2"C, (3) #1, W (1) #6 GND		125	*C-480-0067*	BOILER PLANT 109
SWBD-5-FDR-15 - Condensate Return Pump	CST-1	(1) 3/4"C, (3) #8, W (1) #10 GND		40	*C-480-0068*	BOILER PLANT 109
SWBD-5-FDR-16 - Panel 1NH1	1NH1	(1) 2"C, (3) #4/0, W (1) #4 GND	(1) 2-1/2"C, 300KCMIL, W (1) #4 GND	225	*C-480-0069*	BOILER PLANT 109
SWBD-6						
SWBD-6-FDR-1 - VFD for Heating Hot Water Pump 2	VFD-HHWP-2	(1) 2"C, (3) #3/0, W (1) #6 GND	(1) 2-1/2"C, (3) #250KCMIL, W (1) #6 GND	200	*C-480-0070*	BOILER PLANT 109
SWBD-6-FDR-2 - VFD for Heating Hot Water Pump 4	VFD-HHWP-4	(1) 2"C, (3) #3/0, W (1) #6 GND	(1) 2-1/2"C, (3) #250KCMIL, W (1) #6 GND	200	*C-480-0071*	BOILER PLANT 109
SWBD-6-FDR-3 - VFD for Heating Hot Water Pump 6	VFD-HHWP-6	(1) 2"C, (3) #3/0, W (1) #6 GND	(1) 2-1/2"C, (3) #250KCMIL, W (1) #6 GND	200	*C-480-0072*	BOILER PLANT 109
SWBD-6-FDR-4 - Steam Boiler 2	SB-2	(1) 1-1/4C, (3) #2, W (1) #8 GND		90	*C-480-0073*	BOILER PLANT 109
SWBD-6-FDR-5 - Heating Hot Water Boiler 2	HHWB-2	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0074*	BOILER PLANT 109
SWBD-6-FDR-6 - Heating Hot Water Boiler 4	HHWB-4	(1) 3/4"C, (3) #10, W (1) #10 GND		30	*C-480-0075*	BOILER PLANT 109
SWBD-6-FDR-7 - Heating Hot Water Boiler 6	HHWB

HEAT TRACE CIRCUIT	LINE DESCRIPTION	LINE SIZE	INSULATION THICKNESS	DUTY	DRAWING REFERENCE	ESTIMATED PIPE LENGTH	TEMP F	ESTIMATED VALVES TO WRAP	ESTIMATED FLANGES TO WRAP	HEAT TAPE MODEL #	VOLTS	AMPS	HEAT TAPE POWER CONNECTOR	HEAT TAPE END CONNECTOR	HEAT TAPE TEE CONNECTOR	HEAT TRACE CONTROLLER
1	MAIN CTWR - (TOWERS CT-1, CT-2, CT-3)	48"	2"	FREEZE PROTECTION	M701	113	AMB	5	2	15QTVR2-CT	208	30	1	1	0	HC1
2	MAIN CTWR - (TOWERS CT-4, CT-5, CT-6)	36"	2"	FREEZE PROTECTION	M701	83	AMB	5	2	15QTVR2-CT	208	30	1	1	0	HC2
3	MAIN CTWS - (TOWERS CT-1, CT-2, CT-3)	48"	2"	FREEZE PROTECTION	M701	113	AMB	5	2	15QTVR2-CT	208	30	1	1	0	HC3
4	MAIN CTWS - (TOWERS CT-4, CT-5, CT-6)	36"	2"	FREEZE PROTECTION	M701	96	AMB	5	2	15QTVR2-CT	208	30	1	1	0	HC4
5	CTWR - CT1	18"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC5
6	CTWS - CT1	24"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC5
7	CTWR - CT2	18"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC6
8	CTWS - CT2	24"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC6
9	CTWR - CT3	18"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC7
10	CTWS - CT3	24"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC7
11	CTWR - CT4	18"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC8
12	CTWS - CT4	24"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC8
13	CTWR - CT5	18"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC9
14	CTWS - CT5	24"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC9
15	CTWR - CT6	18"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC10
16	CTWS - CT6	24"	2"	FREEZE PROTECTION	M701	6	AMB	1	1	10QTVR1-CT	120	30	1	1	0	HC10
17	CTSS (TOWERS CT-1, CT-2, CT-3)	6"	2"	FREEZE PROTECTION	M701	74	AMB	3	0	5QTVR1-CT	120	30	1	1	0	HC11
18	CTSR (TOWERS CT-1, CT-2, CT-3)	6"	2"	FREEZE PROTECTION	M701	65	AMB	3	0	5QTVR1-CT	120	30	1	1	0	HC11
19	CTSS (TOWERS CT-4, CT-5, CT-6)	6"	2"	FREEZE PROTECTION	M701	153	AMB	3	0	5QTVR1-CT	120	30	1	1	0	HC12
20	CTSR (TOWERS CT-4, CT-5, CT-6)	6"	2"	FREEZE PROTECTION	M701	144	AMB	3	0	5QTVR1-CT	120	30	1	1	0	HC12
21	CTSS - CT1	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC13
22	CTSR - CT1	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC13
23	CTSS - CT2	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC14
24	CTSR - CT2	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC14
25	CTSS - CT3	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC15
26	CTSR - CT3	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC15
27	CTSS - CT4	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC16
28	CTSR - CT4	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC16
29	CTSS - CT5	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC17
30	CTSR - CT5	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC17
31	CTSS - CT6	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC18
32	CTSR - CT6	6"	2"	FREEZE PROTECTION	M701	38	AMB	1	4	5QTVR1-CT	120	30	1	2	1	HC18
33	CT-1 SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	61	AMB	6	1	3BTV1-CR	120	30	1	6	6	HC19
34	CT-2 SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	61	AMB	6	1	3BTV1-CR	120	30	1	6	6	HC20
35	CT-3 SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	61	AMB	6	1	3BTV1-CR	120	30	1	6	6	HC21
36	CT-4 SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	61	AMB	6	1	3BTV1-CR	120	30	1	6	6	HC22
37	CT-5 SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	61	AMB	6	1	3BTV1-CR	120	30	1	6	6	HC23
38	CT-6 SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	61	AMB	6	1	3BTV1-CR	120	30	1	6	6	HC24
39	CTE-1 (TOWERS CT-1, CT-2, CT-3)	18"	2"	FREEZE PROTECTION	M701	94	AMB	4	1	15QTVR2-CT	208	30	1	1	0	HC25
40	CTE-2 (TOWERS CT-1, CT-2, CT-3)	18"	2"	FREEZE PROTECTION	M701	94	AMB	4	1	15QTVR2-CT	208	30	1	1	0	HC26
41	CTE-1 (TOWERS CT-4, CT-5, CT-6)	18"	2"	FREEZE PROTECTION	M701	94	AMB	4	1	15QTVR2-CT	208	30	1	1	0	HC27
42	CTE-2 (TOWERS CT-4, CT-5, CT-6)	18"	2"	FREEZE PROTECTION	M701	94	AMB	4	1	15QTVR2-CT	208	30	1	1	0	HC28
43	CTE-1 SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	3	AMB	1	0	3BTV1-CR	120	30	1	6	6	HC29
44	CTE-2 SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	3	AMB	1	0	3BTV1-CR	120	30	1	6	6	HC29
45	MAIN CTWR SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	20	AMB	2	0	3BTV1-CR	120	30	1	6	6	HC30
45	MAIN CTWS SANITARY DRAIN	4"	2"	FREEZE PROTECTION	M701	20	AMB	2	0	3BTV1-CR	120	30	1	6	6	HC30
46	2500 GAL SULFURIC ACID TANK TK-1	2500 GAL...	BLANKET	FREEZE PROTECTION	M708	TANK	AMB	0	0	BLANKET	208	30	**1**	**1**	0	HC31
47	SULFURIC ACID LINE	2"	2"	FREEZE PROTECTION	M708	18	AMB	2	1	3BTV1-CR	120	20	1	1	0	HC31
48	1500 GAL BLEACH TANK TK-2	1500 GAL...	BLANKET	FREEZE PROTECTION	M708	TANK	AMB	0	0	BLANKET	208	30	**1**	**1**	0	HC32
49	BLEACH LINE	2"	2"	FREEZE PROTECTION	M708	8	AMB	2	1	3BTV1-CR	120	20	1	1	0	HC32
50	EYE WASH STATION, COURTYARD	1.25"	2"	FREEZE PROTECTION		68	AMB	0	1	3BTV1-CR	120	20	1	1	0	HC33

NOTES:

JBS-100A	HEAT TRACE POWER CONNECTOR
E-100-L-A	HEAT TRACE "LIGHTED" END CONNECTOR (USED WITH FREEZE PROTECTION, LIGHT ON WHEN HEAT TAPE ON).
T-100	HEAT TRACE TEE CONNECTOR
GT	GLASS TAPE USED TO SECURE TRACE TO PIPE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: **AESI**	
APPROVED BY: **Approver**	
PROJECT NO.: **21-154**	


SHEET TITLE

POWER SCHEDULES

SHEET NUMBER

EP609

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:33 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



1 **PRIMARY ONE LINE DIAGRAM**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:33 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


PRIMARY ONE LINE DIAGRAM

SHEET NUMBER


EP701



1 MSS SINGLE LINE DIAGRAM
Scale: NONE



2 REDUNDANT 125V DC BATTERY SYSTEM FOR MSS
Scale: NONE



3 REMOTE CONTROL PANEL WITH HMI/OIT MSS
Scale: NONE

LEGEND

M	MICROPROCESSOR METERING DEVICE
ATC	AUTOMATIC TRANSFER CONTROLLER
43S/S (A M)	AUTO / MANUAL TRANSFER SELECTOR
25	SYNC CHECK RELAY
27	UNDER VOLTAGE RELAY
47	PHASE SEQUENCE RELAY
50/51	PHASE OVERCURRENT RELAY
50G/51G	GROUND OVERCURRENT RELAY
62	TIME DELAY OR OPENING RELAY
86	LOCK-OUT RELAY
87B	MAIN BUS DIFFERENTIAL RELAY
H.I.D	HIGH IMPEDANCE DIFFERENTIAL PROTECTION
	POTENTIAL TRANSFORMER
	CURRENT TRANSFORMER
	FUSE FOR PT'S - PRIMARY AND SECONDARY
	MEDIUM VOLTAGE BREAKER

4 MV SINGLE LINE DIAGRAM LEGEND
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

MSS SINGLE LINE DIAGRAM


SHEET NUMBER

EP702


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:34 PM AESI Proj. No: 21-154



REDUNDANT 125V DC BATTERY SYSTEM FOR PS AND MV-ATS



MASTER CONTROLLER AND SCADA SYSTEM



PARALLELING SWITCHGEAR (PS)

1 **CENTRAL STANDBY/EMERGENCY ONE LINE DIAGRAM**
Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:24 PM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Greystone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

PS ONE LINE DIAGRAM

SHEET NUMBER

EP703



1 USS-MECH1 SINGLE LINE DIAGRAM
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY **AESI**	
APPROVED BY **Approver**	
PROJECT NO. **21-154**	


SHEET TITLE

USS-MECH1 SINGLE LINE DIAGRAM

SHEET NUMBER

EP704

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:34 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



1 **USS-MECH2 SINGLE LINE DIAGRAM**
Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:35 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadrow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY **AESI**	
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

USS-MECH2 SINGLE LINE DIAGRAM

SHEET NUMBER

EP705



1 **USS-CH1 SINGLE LINE DIAGRAM**
Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:35 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz


100% Desgin Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**
CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
USS-CH1 SINGLE LINE DIAGRAM

SHEET NUMBER
EP706



1 **USS-CH2 SINGLE LINE DIAGRAM**
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


USS-CH2 SINGLE LINE DIAGRAM

SHEET NUMBER

EP707

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:35 PM AESI Proj. No: 21-154
0 1/2" 1" 2"

REFER TO PRIMARY ONE LINE DIAGRAM EP701



1 **USS-CUP-ESS SINGLE LINE DIAGRAM**
Scale: 1/4" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:35 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shelborne Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: **AESI**	
APPROVED BY: **Approver**	
PROJECT NO.: **21-154**	

SHEET TITLE


USS-CUP-ESS SINGLE LINE DIAGRAM

SHEET NUMBER

EP708



1 **SWBD1 ELEVATION**
Scale: NONE



2 **SWBD1 SINGLE LINE DIAGRAM**
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY	CERTIFICATION
AESI	PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY	
AESI	
APPROVED BY	
Approver	
PROJECT NO.	
21-154	


SHEET TITLE

SWBD1 SINGLE LINE DIAGRAM


SHEET NUMBER

EP709

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:36 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



1 **SWBD2 ELEVATION**
Scale: NONE



2 **SWBD2 SINGLE LINE DIAGRAM**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:36 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE


SWBD2 SINGLE LINE DIAGRAM

SHEET NUMBER

EP710



1 **SWBD3 ELEVATION**
Scale: NONE



2 **SWBD3 SINGLE LINE DIAGRAM**
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SWBD3 SINGLE LINE DIAGRAM


SHEET NUMBER

EP711

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1) AESI Proj. No: 21-154
2/10/2023 3:02:36 PM
0 1/2" 1" 2"



1 **SWBD4 ELEVATION**
Scale: NONE



2 **SWBD4 SINGLE LINE DIAGRAM**
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadybrook Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

SWBD4 SINGLE LINE DIAGRAM


SHEET NUMBER

EP712

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:37 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



1 **SWBD5 ELEVATION**
Scale: NONE



2 **SWBD5 SINGLE LINE DIAGRAM**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:37 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: **AESI**	
APPROVED BY: **Approver**	
PROJECT NO.: **21-154**	

SHEET TITLE


SWBD5 SINGLE LINE DIAGRAM

SHEET NUMBER

EP713



1 **SWBD6 ELEVATION**
Scale: NONE



2 **SWBD6 SINGLE LINE DIAGRAM**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:37 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadrone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE


SWBD6 SINGLE LINE DIAGRAM

SHEET NUMBER

EP714



1 **SWBD7 ELEVATION**
Scale: NONE



2 **SWBD7 SINGLE LINE DIAGRAM**
Scale: NONE

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:38 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: **AESI**	
APPROVED BY: **Approver**	
PROJECT NO.: **21-154**	

SHEET TITLE

SWBD7 SINGLE LINE DIAGRAM

SHEET NUMBER

EP715



1 ELECTRICAL SCADA SYSTEM SCHEMATIC DIAGRAM

Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:38 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadylane Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

ELECTRICAL SCADA SYSTEM SCHEMATIC DIAGRAM

SHEET NUMBER

EP716



1 **ARC FLASH ONELINE - OVERALL**
Scale: NONE

NOTES:

1. PROTECTIVE DEVICE SETTINGS PROVIDED WITH SPECIFICATIONS.

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1) 2/10/2023 3:02:40 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: **AESI**	
APPROVED BY: **Approver**	
PROJECT NO.: **21-154**	


SHEET TITLE

ONELINE DIAGRAM FOR ARC FLASH - OVERALL

SHEET NUMBER


EP717





2 **EYEWASH HEAT TRACE DETAIL**
Scale: NONE

1 **HEAT TRACE SCHEMATIC**
Scale: NONE



CHEMICAL TREATMENT

OWNER
Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT
Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 330 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS


NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE
HEAT TRACE SCHEMATIC

SHEET NUMBER
EP718

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:40 PM AESI Proj. No: 21-154






12' X 6' X 7' MANHOLE

DIMENSIONS

		LENGTH IN.	WIDTH IN.	HEIGHT IN.
	INSIDE	144	72	84
	OUTSIDE	154	82	95
RECOMMENDED	HOLE SIZE	178	94	-

	THICKNESS IN.		WEIGHT LBS.
WALL	5	TOP	16,111
ROOF	6	BOTTOM	14,178
FLOOR	5	TOTAL	30,289




O.D. 154" X 82"X 95"
I.D. 12' X 6' X 7'


NOTES:

ALL MATERIALS USED IN THE MANHOLE SHALL BE RESISTANT TO CORROSION AND ALL STEEL SHALL BE GALVANIZED OR ZINC COATED. MANHOLES SHALL BE PROVIDED WITH A GROUND ROD SLEEVE TO ACCOMMODATE A 3/4" COPPER GROUND ROD. THE CONTRACTOR SHALL BOND ALL METALLIC APPARATUS IN THE MANHOLE WITH A #4 COPPER SOLID GROUND CONDUCTOR. CONTRACTOR SHALL WATERPROOF ALL PENETRATIONS AND JOINTS ON THE MANHOLE TO PREVENT WATER PENETRATION. EXTENSION RINGS FOR MANHOLE OPENING SHALL BE FURNISHED AND INSTALLED WITH THE MANHOLE TO BRING THE COVER UP TO GRADE. COVER SHALL READ "ELECTRICAL" OR "TELECOM" AS NEEDED AND BE H-20 RATED.


3 TYPICAL ELECTRICAL MANHOLE
Scale: NONE




1 TYPICAL ELECTRICAL MANHOLE DETAIL
Scale: NONE



6 SCADA SERVER CABINET DETAIL
Scale: NONE




5 SCADA MANHOLE DETAIL
Scale: NONE



NOTES:

1. PROVIDE #4/0 AWG BARE COPPER GROUND LOOP.
2. PROVIDE 3/4" x 10'-0" COPPER CLAD GROUND ROD. CONNECT TO GROUND LOOP VIA EXOTHERMIC WELD. COORDINATE GROUND AND SLEEVE LOCATION WITH MANHOILE MANUFACTURER.
3. PROVIDE #4 AWG SOLID BARE COPPER FROM MANHOLE COVER RING TO GROUND LOOP. CONNECT TO RING BY DRILLING AND TAPPING TO ACCEPT A 1/4"-20 THREAD SCREW. PROVIDE A SINGLE-HOLE COMPRESSION LUG ON THE WIRE. PROVIDE EXOTHERMIC WELD AT GROUND LOOP.
4. PROVIDE #4 AWG SOLID BARE COPPER FROM MANHOLE REBAR GROUNDING TAB TO GROUNDING LOOP. FIELD VERIFY QUANTITY. COORDINATE LOCATIONS WITH MANHOLE MANUFACTURER.
5. PROVIDE CONNECTION OF #4/0AWG BARE COPPER GROUNDING CONDUCTOR RUN WITH DUCTBANK TO MANHOLE GROUND LOOP WITH EXOTHERMIC WELD.

4 TYPICAL ELECTRICAL MANHOLE GROUNDING DETAIL
Scale: NONE



2 MH-1 CABLE ROUTING DETAIL
Scale: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:41 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


ELECTRICAL SITE DETAILS

SHEET NUMBER


UE501




5 **EMERGENCY A DUCT BANK**
Scale: NONE




1 **AES UTILITY CIR A SERVICE**
Scale: NONE




6 **EMERGENCY B DUCT BANK**
Scale: NONE




2 **AES UTILITY CIR B SERVICE**
Scale: NONE



7 **EMERGENCY DUCT BANKS A AND B COMBINED**
Scale: NONE



3 **NORMAL A DUCT BANK**
Scale: NONE



4 **NORMAL B DUCT BANK**
Scale: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

ELECTRICAL SITE DETAILS

SHEET NUMBER

UE502

0 1/2" 1" 2"
ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 3:02:41 PM AESI Proj. No: 21-154



DIRECTORY.....C:\ProjectWise\VS Engineering\2104729 - IU Health AAHC\CAD\02 VS Engineering\02 Sheet Files\
FILE.....2104729-MH-AAHC-Site Early Packages.dwg
DIMSCALE..1 LTSCALE....20
PLOTTED BY...JMowery
DATE.....Jan 13,2023 - 1:05pm

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 11:51:12 AM AESI Proj. No.: 21-154

0 1/2" 1" 2"

HEALTH

VS ENGINEERING

50% DETAILED DESIGN SET

CERTIFIED BY:

JOHN C. ZANT, JR. , P.E.

01/13/2023
DATE

IU HEALTH

NEW DOWNTOWN HOSPITAL

OVERALL CAMPUS PACKAGE

INDIANAPOLIS, INDIANA

KEY MAP



DESIGNED: JFM	DRAWN: JFM
CHECKED: JZ	CHECKED: JZ

HORIZONTAL SCALE
1" = 100'

VERTICAL SCALE
N/A

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

OVERALL SITE LAYOUT

PROJECT NUMBER
2104729

SHEET
C100

SITE DRAWINGS PROVIDED FOR REFERENCE TO SCALE DISTANCE FOR MV CABLING BETWEEN CUP AND AAHC DEMARK POINT

FOR REFERENCE ONLY

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46033
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY	CERTIFICATION
AESI	PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY **AESI**	
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

OVERALL SITE LAYOUT

SHEET NUMBER

C100



LEGEND

- PROPOSED MANHOLE
- PROPOSED INLET
- PROPOSED PIPE
- PIPE TO BE REMOVED

STORM SEWER LOCATIONS

ECO	ECO PARK
HC	HOSPITAL SURROUNDS
NPK	NORTH PARKING LOT
NQ	NORTH QUAD
PC	PRIVATE CONNECTION
RRD	RING ROAD (EXISTING)
SEN	SENATE SYSTEM
SPK	SOUTH PARKING LOT
SQ	SOUTH QUAD
SSB	SOUTH SERVICE BUILDING

NOTES

1. ALL RRD STRUCTURES INSTALLED BY PREVIOUS IU HEALTH CONTRACTOR.
2. ALL NCOE STRUCTURES TO BE INSTALLED BY IU HEALTH CONTRACTOR.
3. NON-STORM UTILITIES IDENTIFIED FOR REFERENCE PURPOSES ONLY. SEE UTILITY SHEETS FOR ADDITIONAL INFORMATION.
4. PROPERTY LINES NOT CALLED OUT FOR PLAN CLARITY PURPOSES. SEE SHEETS C101-C106 FOR PROPERTY LINE INFORMATION.

SITE DRAWINGS PROVIDED FOR REFERENCE TO SCALE DISTANCE FOR MV CABLING BETWEEN CUP AND AAHC DEMARK POINT

FOR REFERENCE ONLY

DIRECTORY....C:\ProjectWise\VS Engineering\2104729 - IU Health AAHC\CAD\02 VS Engineering\02 Sheet Files\
FILE.....2104729-Campus Storm Layout.dwg
DIMSCALE...1 LTSCALE....20
PLOTTED BY...JRowery
DATE.....Jan 13,2023 - 1:09pm

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 11:51:13 AM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

50% DETAILED DESIGN SET

CERTIFIED BY:

JOHN C. ZANT, JR. , P.E.

01/13/2023
DATE


IU HEALTH

NEW DOWNTOWN HOSPITAL

OVERALL CAMPUS PACKAGE

INDIANAPOLIS, INDIANA

KEY MAP



DESIGNED: JFM	DRAWN: JFM
CHECKED: JZ	CHECKED: JZ
HORIZONTAL SCALE	1" = 30'
VERTICAL SCALE	N/A

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

STORM SEWER LAYOUT

PROJECT NUMBER
2104729
SHEET
C703

100% Desgin Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION


DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

SSB TO AAHC DEMARK MANHOLES

SHEET NUMBER

C703



DIRECTORY....C:\ProjectWise\VS Engineering\2104729 - IU Health AAHC\CAD\02 VS Engineering\02 Sheet Files\
FILE.....2104729-Campus Storm Layout.dwg
DIMSCALE...1 LTSCALE....20
PLOTTED BY...JMowery
DATE.....Jan 13,2023 - 1:09pm

LEGEND

- PROPOSED MANHOLE
- PROPOSED INLET
- PROPOSED PIPE
- PIPE TO BE REMOVED

STORM SEWER LOCATIONS

ECO	ECO PARK
HC	HOSPITAL SURROUNDS
NPK	NORTH PARKING LOT
NQ	NORTH QUAD
PC	PRIVATE CONNECTION
RRD	RING ROAD (EXISTING)
SEN	SENATE SYSTEM
SPK	SOUTH PARKING LOT
SQ	SOUTH QUAD
SSB	SOUTH SERVICE BUILDING

NOTES

1. ALL RRD STRUCTURES INSTALLED BY PREVIOUS IU HEALTH CONTRACTOR.
2. ALL NCOE STRUCTURES TO BE INSTALLED BY IU HEALTH CONTRACTOR.
3. NON-STORM UTILITIES IDENTIFIED FOR REFERENCE PURPOSES ONLY. SEE UTILITY SHEETS FOR ADDITIONAL INFORMATION.
4. PROPERTY LINES NOT CALLED OUT FOR PLAN CLARITY PURPOSES. SEE SHEETS C101-C106 FOR PROPERTY LINE INFORMATION.

SITE DRAWINGS PROVIDED FOR REFERENCE TO SCALE DISTANCE FOR MV CABLING BETWEEN CUP AND AAHC DEMARK POINT

FOR REFERENCE ONLY

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 11:51:13 AM AESI Proj No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

VS ENGINEERING

50% DETAILED DESIGN SET

CERTIFIED BY:

JOHN C. ZANT, JR. , P.E.

01/13/2023
DATE

IU HEALTH

NEW DOWNTOWN HOSPITAL

OVERALL CAMPUS PACKAGE

INDIANAPOLIS, INDIANA

KEY MAP

DESIGNED:	JFM	DRAWN:	JFM
CHECKED:	JZ	CHECKED:	JZ

HORIZONTAL SCALE
1" = 30'
VERTICAL SCALE
N/A

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

STORM SEWER LAYOUT

PROJECT NUMBER
2104729

SHEET
C705

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY	CERTIFICATION
AESI	PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE

CUP TO SSB

SHEET NUMBER

C705



PHASING LEGEND:

- PHASE 1
- PHASE 2
- PHASE 3
- PHASE 4
- PHASE 5A AND 5B

NOTES:

1. THE CONSTRUCTION SEQUENCING SHOWN IS AFTER THE COMPLETION OF ENABLING UTILITIES, RING ROAD, AND NCOE STORM CONSTRUCTION.
2. CONSTRUCTION SEQUENCING OUTLINES THE VARIOUS PUBLIC UTILITIES AND NOT INDIVIDUAL BUILDING SERVICE CONNECTIONS.
3. CONSTRUCTION SEQUENCING IS NOT ALL INCLUSIVE.
4. PHASE 1 INCLUDES ALL PUBLIC UTILITIES ALONG 14TH STREET FROM CAPITOL TO MISSIOURI. PHASE 1 MUST BE COMPLETED PRIOR TO WATER SERVICE CONNECTION FROM THE AAHC.
5. PHASE 2 INCLUDES CHILLED WATER AND STEAM LINES REQUIRED FOR THE IU SCHOOL OF MEDICINE. PHASE 2 MUST BE COMPLETED PRIOR TO WATER SERVICE CONNECTION FROM THE CUP.
6. PHASE 1 AND PHASE 2 WORK CAN OCCUR CONCURRENTLY. HOWEVER, THE RELOCATION OF THE WATER MAIN IN 14TH STREET (PHASE 1) MUST BE COMPLETED PRIOR TO THE INSTALLATION OF THE STEAM LINE IN 14TH STREET (PHASE 2).
7. PHASE 3 INCLUDES ALL PUBLIC UTILITIES ALONG 13TH STREET FROM CAPITOL TO SENATE. PHASE 3 MUST BE COMPLETED PRIOR TO WATER SERVICE CONNECTION FROM THE CUP.
8. PHASE 4 INCLUDES ALL PUBLIC UTILITIES ALONG SENATE FROM 14TH TO 12TH STREET.
9. DEMOLITION OF THE PEOPLE MOVER IS REQUIRED IN ORDER TO COMPLETE PHASE 4 WORK.
10. PHASE 4 MUST BE CONSTRUCTED IN ORDER TO PROVIDE POWER TO THE CUP.
11. PHASE 5A INCLUDES THE DEMOLITION OF THE PUBLIC UTILITIES IN SENATE TO FACILIATE THE PLAZA GARAGE CONSTRUCTION. PHASES 1 – 4 MUST BE COMPLETED PRIOR TO THE START OF PHASE 5A. FRESENIUS MUST BE DEMOLISHED PRIOR TO STARTING PHASE 5A.
12. PHASE 5B INCLUDES THE INSTALLATION OF THE PRIMARY ELECTRICAL FEED FROM THE SUBSTATION TO THE CUP. PHASE 5B REQUIRES THE COMPLETION OF THE PLAZA GARAGE PRIOR TO START OF CONSTRUCTION.

UTILITIES

INDIANAPOLIS POWER AND LIGHT COMPANY / AES INDIANA
1230 W. MORRIS ST.
INDIANAPOLIS, IN 46221
PHONE: 317–261–8617
CONTACT: JANET SNODGRASS

IUPUI
1050 WISHARD BLVD. SUITE 4000
INDIANAPOLIS, IN 46202
PHONE: 317–274–7106
CONTACT: RYAN SCHAFER

CITIZENS ENERGY GROUP /CWA AUTHORITY, INC. – WATER
2150 DR. MARTIN LUTHER KING JR. ST.
INDIANAPOLIS, IN 46202
PHONE: 317–927–4351
ATTN: BRAD HOSTETLER

CITIZENS ENERGY GROUP /CWA AUTHORITY, INC. – SANITARY
2150 DR. MARTIN LUTHER KING JR. ST.
INDIANAPOLIS, IN 46202
PHONE: 317–927–4351
ATTN: BRAD HOSTETLER

CITIZENS ENERGY GROUP – GAS
2150 DR. MARTIN LUTHER KING JR. ST.
INDIANAPOLIS, IN 46202
PHONE: 317–927–4684
ATTN: RICH MILLER

CITIZENS ENERGY GROUP – THERMAL
266 KENTUCKY AVE.
INDIANAPOLIS, IN 46255
PHONE: 317–308–9910
ATTN: PHILIP SEARCY

SITE DRAWINGS PROVIDED FOR REFERENCE TO SCALE DISTANCE FOR MV CABLING BETWEEN CUP AND AAHC DEMARK POINT

FOR REFERENCE ONLY

50% DETAILED DESIGN SET

CERTIFIED BY:

KAITLYN M. CURRIE, P.E.

12/14/2022

DATE


IU HEALTH

NEW DOWNTOWN HOSPITAL

OVERALL CAMPUS PACKAGE

INDIANAPOLIS, INDIANA

KEY MAP



DESIGNED: JPJ	DRAWN: MDY
CHECKED: KMC	CHECKED: JPJ
HORIZONTAL SCALE	
1" = 80'	
VERTICAL SCALE	

REVISION SCHEDULE

NO.	DESCRIPTION	DATE

PROPOSED UTILITIES SEQUENCING

PROJECT NUMBER 2104729

SHEET C500

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shoshone Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Desgin Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY	AESI
CHECKED BY	AESI
APPROVED BY	Approver
PROJECT NO.	21-154

CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE


CUP SITE DEMARK POINTS

SHEET NUMBER

C706

DIRECTORY....C:\ProjectWise\VS Engineering\2104729 - IU Health AAHC\CAD\06 AS\
FILE.....2104729-MH-AAHC-C-Campus Utility Sheets-zz.dwg
DIMSCALE..20 LTSCALE....1
PLOTTED BY..mgriffith
DATE.....Jan 11,2023 - 12:58pm

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/10/2023 11:51:14 AM AESI Proj. No: 21-154



1 **Tunnel ISO**
Scale:



2 **UTILITY TUNNEL OVERALL PLAN**
Scale: 1/16" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:37 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038
317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE


UTILITY TUNNEL

SHEET NUMBER

UT100



1 **UTILITY TUNNEL CUP OVERALL**
Scale: 3/16" = 1'-0"



2 **UTILITY TUNNEL CUP UTILITY LAYOUT**
Scale: 3/8" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:38 PM AESI Proj. No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

UTILITY TUNNEL - CUP

SHEET NUMBER


UT101

GENERAL NOTES:


1. REFER TO STRUCTURAL DRAWINGS FOR STRUCTURE DESIGN.
2. DOOR SHOWN FOR REFRENCE - SCOPE HAS NOT BEEN DETERMINED YET.

MECHANICAL PLAN NOTES:


1. TBD



1 **UTILITY TUNNEL CUP MECHANICAL - HVAC PLAN**
Scale: 3/16" = 1'-0"



3 **STEAM AND PCR ASSEMBLY**
Scale: 1/4" = 1'-0"



2 **STEAM IN TUNNEL**
Scale:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

MECHANICAL


SHEET NUMBER

UT101.1


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:39 PM AESI Proj. No: 21-154
0 1/2" 1" 2"



1 **UTILITY TUNNEL CUP FIRE PLUMBING PLAN**
Scale: 3/16" = 1'-0"



3 **UTILITY TUNNEL SUMP PUMPS**
Scale:



2 **UTILITY TUNNEL CUP FIRE PROTECTION PLAN**
Scale: 3/16" = 1'-0"

GENERAL NOTES:

1. REFER TO STRUCTURAL DRAWINGS FOR STRUCTURE DESIGN.
2. DOOR SHOWN FOR REFRENCE - SCOPE HAS NOT BEEN DETERMINED YET.

PLUMBING PLAN NOTES:

1. TBD

FIRE PROTECTION PLAN NOTES:

1. TBD

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**
CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE
PLUMBING - FIRE PROTECTION

SHEET NUMBER
UT101.2

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:40 PM AESI Proj. No: 21-154




1 **POWER PLAN**
Scale: 3/16" = 1'-0"

GENERAL NOTES:

1. REFER TO STRUCTURAL DRAWINGS FOR STRUCTURE DESIGN.
2. DOOR SHOWN FOR REFRENCE - SCOPE HAS NOT BEEN DETERMINED YET.

POWER PLAN NOTES:

1. PROVIDE RECEPTACLE. MOUNT ON PIPE SUPPORT AT 1'-6" ABOVE GRADE.
2. PROVIDE SP-1 SWITCH. 30A, 3 PHASE, HEAVY DUTY, NEMA 4X. MOUNT AT 4'-0" AFF ON WALL. CONNECT TO PUMP CONTROL PANEL. SEE MECHANICAL DRAWING FOR PUMP DETAILS.



2 **SYSTEMS PLAN**
Scale: 3/16" = 1'-0"

SYSTEMS PLAN NOTES:

1. TBD

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY **AESI**	
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

POWER - SYSTEMS

SHEET NUMBER

UT101.3

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:40 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

GENERAL NOTES:


1. REFER TO STRUCTURAL DRAWINGS FOR STRUCTURE DESIGN.
2. DOOR SHOWN FOR REFRENCE - SCOPE HAS NOT BEEN DETERMINED YET.

LIGHTING PLAN NOTES:

1. TBD



1 **LIGHTING PLAN**
Scale: 3/16" = 1'-0"



2 **PHOTOMETRIC PLAN**
Scale: 3/16" = 1'-0"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	

SHEET TITLE


LIGHTING

SHEET NUMBER


UT101.4


0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:41 PM AESI Proj. No: 21-154



1 **UTILITY TUNNEL CUP PIPING SUPPORT**
Scale: 3/8" = 1'-0"





2 **UTILITY TUNNEL CUP PIPING SUPPORT PLAN**
Scale: 3/16" = 1'-0"

TYPICAL FOR ALL SUPPORTS

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:41 PM AESI Proj No: 21-154
0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE


UTILITY SUPPORT DETAILS

SHEET NUMBER


UT101.5




1 UTILTIY TUNNEL SSB OVERALL
Scale: 3/32" = 1'-0"



2 UTILITY TUNNEL SSB LAYOUT 1
Scale: 3/16" = 1'-0"



3 UTILITY TUNNEL SSB LAYOUT 2
Scale: 3/16" = 1'-0"



4 UTILITY TUNNEL SSB LAYOUT 3
Scale: 3/16" = 1'-0"

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:43 PM AESI Proj No: 21-154

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: **AESI**
CHECKED BY: **AESI**
APPROVED BY: **Approver**
PROJECT NO.: **21-154**
CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION

SHEET TITLE

UTILITY TUNNEL - SSB

SHEET NUMBER

UT102



1 **UTILITY TUNNEL SSB MECHANICAL PLAN**
Scale: 3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:43 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

SSB - MECHANICAL

SHEET NUMBER

UT102.1



1 **UTILITY TUNNEL SSB FIRE PROTECTION PLAN**
Scale: 3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:43 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS
NO. DATE DESCRIPTION


DESIGNED BY **AESI**	CERTIFICATION
CHECKED BY **AESI**	PRELIMINARY NOT FOR CONSTRUCTION
APPROVED BY **Approver**	
PROJECT NO. **21-154**	

SHEET TITLE

SSB - FIRE PROTECTION

SHEET NUMBER

UT102.2



1 **UTILITY TUNNELSSB SYSTEMS PLAN**
Scale: 3/32" = 1'-0"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:44 PM AESI Proj. No: 21-154

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023


REVISIONS
NO. DATE DESCRIPTION

DESIGNED BY **AESI**
CHECKED BY **AESI**
APPROVED BY **Approver**
PROJECT NO. **21-154**

CERTIFICATION
PRELIMINARY NOT FOR CONSTRUCTION


SHEET TITLE
SSB - SYSTEMS

SHEET NUMBER
UT102.3




1 FIRST FLOOR PNEUMATIC TUBE PLAN -

Scale: 3/32" = 1'-0"



2 UTILITY TUNNEL CUP PNEUMATIC TUBE PLAN

Scale: 3/16" = 1'-0"



3 UTILITY TUNNEL SSB PNEUMATIC TUBE PLAN

Scale: 3/16" = 1'-0"

GENERAL NOTES:

1. COORDINATE WITH STRUCTURAL PLANS FOR UTILITY TUNNEL CONSTRUCTION.
2. SSB STRUCTURAL SHOWN FOR REFERENCE. COORDINATE WITH SSB STRUCTURAL PLANS FOR UTILTIY TUNNEL CONSTRUCTION
3. SSB ARCHITECTURAL SHOWN FOR REFERENCE.
4. PNEUMATIC TUBES SHOWN FOR REFERENCE. COORDINATE WITH PNEUMATIC TUBE PLANS BY ST. ONGE.

PLAN NOTES:

1. PNEUMATIC TUBES DOWN TO UTILITY TUNNEL.
2. PNEUMATIC TUBES DOWN AND OUT WEST WALL OF BUILDING.
3. PNEUMATIC TUBES UP TO CUP FIRST FLOOR.
4. HAND OFF TO SSB STRUCTURAL.
5. HAND OFF TO CUP STRUCTURAL.
6. PNEUMATIC TUBES UP INTO SSB.

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions
structural engineers
8770 North St., Ste. 100
Fishers, IN 46038
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: AESI	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: AESI	
APPROVED BY: Approver	
PROJECT NO.: 21-154	


SHEET TITLE

PNEUMATIC TUBES

SHEET NUMBER

UT103

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
2/9/2023 3:42:44 PM AESI Proj. No: 21-154



PNEUMATIC TUBE SHEET LIST	
Sheet Number	Sheet Name
PT000	PNEUMATIC TUBE COVER SHEET
PT100	PNEUMATIC TUBE RISER DIAGRAM
PT200	PNEUMATIC TUBE PLANS - LOWER LEVEL
PT201	PNEUMATIC TUBE PLANS - FIRST FLOOR
PT300	PNEUMATIC TUBE EQUIPMENT
PT301	PNEUMATIC TUBE MISC. PARTS
PT302	PNEUMATIC TUBE WALL & FLOOR PENETRATIONS

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadowlawn Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: WT	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: WT	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


PNEUMATIC TUBE COVER SHEET

SHEET NUMBER

PT000

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
1/19/2023 3:43:11 PM AESI Proj. No:



WORK INSIDE HOSPITAL
IS NOT IN CONTRACT FOR
CUP PROJECT

- STANDARD STATION
- XPRESS STATION
- TWO PORT DIVERTER
- FOUR PORT DIVERTER
- SIX PORT DIVERTER
- 6" O.D. TRANSPORT TUBE
- 6" O.D. XPRESS TRANSPORT TUBE
- REMOTE PERSONNEL INDICATOR
- REMOTE ARRIVAL INDICATOR
- BLOWER
- CONTROL STATION
- TRAFFIC CONTROL UNIT

THIS WORK NOT IN CONTRACT FOR
CUP PROJECT

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1) AES Proj. No:
1/19/2023 3:43:11 PM

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

IUH MCC Central Utility Plant

Applied Engineering Services
9575 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
905 North Capitol Avenue, Suite 100,
Indianapolis, IN 46204
(317)353-3281

CE Solutions structural engineers
8770 North St., Ste. 100 Fishers, IN 46038 | 317.818.1912 cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

Design Development
2022-05-04

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: WT	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: WT	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


PNEUMATIC TUBE RISER DIAGRAM

SHEET NUMBER

PT100



1 LOWER LEVEL
1/16" = 1'-0"



KEY PLAN
SCALE: NONE

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: WT	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: WT	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


PNEUMATIC TUBE PLANS - LOWER LEVEL

SHEET NUMBER


PT200

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
1/19/2023 3:43:12 PM AESI Proj No:



1 FIRST FLOOR
1/16" = 1'-0"



KEY PLAN
SCALE: NONE

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
1/19/2023 3:43:13 PM AESI Proj. No:

0 1/2" 1" 2"

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied
Engineering Services
9975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS
ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions
structural engineers
10 Shadow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: WT	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: WT	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

PNEUMATIC TUBE PLANS - FIRST FLOOR

SHEET NUMBER


PT201



Standard Station

A. Motor
   1. 105 to 125 VAC, 60 Hz, 1 phase, 5 amps
B. Heat output - 130 BTU/Hour
   1. Operating temperature maintained between 0˚ to 120˚ F
   2. Humidity levels maintained at 0 to 90%
C. Control Requirements
   1. Provide Ethernet drop for system controls

PNEUMATIC TUBE SEND/RECEIVE STATION




Transfer Units (Diverters)

A. Motor
   1. 105 to 125 VAC, 60 Hz, 1 phase, 5 amps
B. Heat output - 130 BTU/Hour
   1. Operating temperature maintained between 0˚ to 120˚ F
   2. Humidity levels maintained at 0 to 90%
C. Control Requirements
   1. Provide Ethernet drop for system controls

NIC

6x1 TRANSFER UNIT




Transfer Units (Diverters)


A. Motor
   1. 105 to 125 VAC, 60 Hz, 1 phase, 5 amps
B. Heat output - 130 BTU/Hour
   1. Operating temperature maintained between 0˚ to 120˚ F
   2. Humidity levels maintained at 0 to 90%
C. Control Requirements
   1. Provide Ethernet drop for system controls

NIC


4x1 TRANSFER UNIT




FLOOR PENETRATION DETAIL



OPTIONAL TUBE SUPPORT DETAIL




PNEUMATIC TUBE EXPANSION JOINT DETAIL



Blowers (6 inch system)


A. Shifter Valve Motor
   1. 105-125 VAC, 60 Hz, 1 phase, 5.4 amps (Swisslog only)
B. Blower Motor
   1. 480 Volt, 50/60 Hz, 3 Phase, 40 amp connection is preferred
C. Air flow - 330 SCFM
   1. System in Pressure - Air is pulled from the blower room and exhausted to the pressure relief valve above the station.
   2. System in Vacuum - Air is pulled from the station and exhausted after the first transfer unit in the zone.
D. Heat output - 8,000 BTU/Hour
   1. Operating temperature maintained between 0˚ to 120˚ F
   2. Humidity levels maintained at 0 to 90%
E. Control Requirements
   1. Provide Ethernet drop for system controls

NIC




POWER SUPPLY	FREQUENCY	PHASED POWER	CURRENT	FULL LOAD CURRENT
200-230	50/60	3 PHASE	10	28
460	50/60	3 PHASE	10	12.5

PNEUMATIC TUBE BLOWER



PNEUMATIC TUBE SUPPORT DETAIL



NIC

COMMUNICATION CONTROL PANEL

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
1/19/2023 3:43:13 PM AESI Proj. No:

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
5975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadybrook Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION


DESIGNED BY: WT	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: WT	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE


PNEUMATIC TUBE EQUIPMENT

SHEET NUMBER


PT300



1 TYPICAL TUBING (STRAIGHT END)




2 TYPICAL TUBE HANGER




3 TYPICAL SOLID SLEEVE




4 TYPICAL CLAMP SLEEVE



5 TYPICAL TUBING (ONE END EXPANDED)




6 COMPRESSION COUPLING




7 COMPRESSION COUPLING




CHANNEL NUT




SADDLE NUT ASSEMBLY



8 90° LONG RADIUS BEND (STRAIGHT END)



9 90° LONG RADIUS BEND (ONE END EXPANDED)



SLOTTED STRUT



90° STRUT BRACKET



45° STRUT BRACKET



SQUARE WASHER PLATE

10 TYPICAL UNISTRUT HANGING COMPONENTS

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
9975 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadow Hollow Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: WT	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: WT	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

PNEUMATIC TUBE MISC. PARTS

SHEET NUMBER

PT301


ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
1/19/2023 3:43:13 PM AESI Proj. No:

0 1/2" 1" 2"

System No. C-AJ-8081

F Rating - 2 Hr

T Rating - 1 Hr



TOP VIEW SECTION A-A

1. Floor or Wall Asse1. Floor or Wall Assembly — Min 2-1/2 in. (64 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m³) concrete floor or
min 3-1/2 in. (89 mm) reinforced lightweight or normal weight concrete wall. Wall may also be constructed of any UL Classified Concrete Blocks*.
Max diameter of opening is 8 in. (203 mm).
See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.

2. Metallic Sleeve — (Optional) Nom 8 in. (203 mm) diam (or smaller) Schedule 40 (or heavier) steel sleeve cast or grouted into floor or wall
assembly, flush with floor or wall surfaces or extending a max of 3 in. (76 mm) above floor or beyond both surfaces of wall.

2A. Sheet Metal Sleeve — (Optional, Not Shown) - Max 6 in. (152 mm) diam, min No. 26 ga galv steel provided with a No. 26 ga galv steel square
flange spot welded to the sleeve at approx mid-height, or flush with bottom of sleeve in floors, and sized to be a min of 2 in. (51 mm) larger than
the sleeve diam. The sleeve is to be cast in place and may extend a max of 4 in. (102 mm) below the bottom of the floor and a max of 1 in. (25
mm) above the top surface of the concrete floor.

2B. Sheet Metal Sleeve — (Optional, Not Shown) - Max 8 in. (203 mm) diam, min No. 24 ga galv steel provided with a No. 24 ga galv steel square
flange spot welded to the sleeve at approx mid-height, or flush with bottom of sleeve in floors, and sized to be a min of 2 in. (51 mm) larger than
the sleeve diam. The sleeve is to be cast in place and may extend a max of 4 in. (102 mm) below the bottom of the floor and a max of 1 in. (25
mm) above the top surface of the concrete floor.

3. Steel Tube — Nom 6 in. (152 mm) diam (or smaller) No. 16 ga steel tube installed eccentrically within the opening. The annular space between
the tube and the periphery of the opening shall be min 1/4 in. (6 mm) to max 1-3/4 in. (45 mm). Tube to be rigidly supported on both sides of floor
or wall assembly.

4. Cables — Max four 3/8 in. (10 mm) diam two pair No. 22 AWG foil shielded plenum rated communication cables with polyvinyl chloride (PVC)
insulation and jacket. Min separation between cables and periphery of opening shall be 1/4 in. (6 mm). Separation between cables and tube shall
be min 0 in. (point contact) to max 1 in. (25 mm). Cables to be rigidly supported on both sides of floor or wall assembly.

5. Firestop System — The firestop system shall consist of the following:

A. Packing Material — Min 1-1/2 in. (38 mm) thickness of min 4 pcf (64 kg/m³) mineral wool batt insulation firmly packed into opening as a
permanent form. Packing material to be recessed from top surface of floor or both surfaces of wall to accommodate the required thickness of
fill material.

B. Fill, Void or Cavity Material* - Sealant — Min 1 in. (25 mm) thickness of fill material applied within the annulus, flush with top surface of floor
or with both surfaces of wall.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant


*Bearing the UL Classification Mark
mbly

1 TYPICAL FLOOR PENETRATION DETAIL

System No. W-L-8023

F Ratings -1&2 Hr (See Item 1)

T Rating - 0 Hr



FRONT VIEW SECTION A-A

1. Wall Assembly — The 1 or 2 hr fire rated board/stud wall assembly shall be constructed of the materials and in the manner specified in the
individual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following
construction features.

A. Studs — Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm)
lumber spaced 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC.

B. Gypsum Board* — One or two layers of nom 5/8 in. (16 mm) thick gypsum board as specified in the individual Wall and Partition Design. Max
diam of opening is 7 in. (178 mm).
The hourly F Rating of the firestop system is equal to the hourly rating of the wall assembly.

2. Steel Tube — Nom 6 in. (152 mm) diam (or smaller) No. 16 ga steel tube installed eccentrically within the opening. The tube may be installed at
an angle not greater than 45 degrees from perpendicular. The annular space between the tube and the periphery of the opening shall be min 1/4
in. (6 mm) to max 3/4 in. (19 mm). Tube to be rigidly supported on both sides of wall assembly.

3. Cables — Max three 3/8 in (10 mm) diam two pair No. 22 AWG foil shielded communication cables with polyvinyl chloride (PVC) insulation and
jacket. The cables may be installed at an angle not greater than 45 degrees from perpendicular in line with steel tube (Item 2). Min separation
between cables and periphery of opening shall be 1/4 in. (6 mm). Separation between cables and tube shall be min 0 in. (point contact) to max 1
in. (25 mm). Cables to be rigidly supported on both sides of wall assembly.

4. Fill, Void or Cavity Material* - Sealant — Min 5/8 in. (16 mm) thickness of fill material applied within annulus for 1 hr rated walls. Min 1-1/4 in. (32
mm) thickness of fill material applied within annulus for 2 hr rated walls. Fill material applied flush with both surfaces of wall.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant

*Bearing the UL Classification Mark

2 TYPICAL WALL PENETRATION DETAIL

OWNER

Indiana University Health
Medical Center Campus
340 W. 10th Street
Indianapolis, IN, 46202

PROJECT

Central Utility Plant

Applied Engineering Services
9375 Castle Creek Parkway N Drive, Suite 300 • Indianapolis, Indiana 46250
Tel: 317.810.4141 • Fax: 317.810.4140 • www.applied-e-s.com

VPS ARCHITECTURE
528 Main Street, Suite 400
Evansville, IN 47708
(812) 423-7729 | www.vpsarch.com

CE Solutions structural engineers
10 Shadetree Drive
Carmel, IN 46032
317.818.1912
cesolutionsinc.com

Cripe
Solutions by Design Since 1937
9339 Priority Way West Drive, Suite 100
Indianapolis, IN 46240
(317) 844-6777 | www.cripe.biz

100% Design Development Documents
February 10, 2023

REVISIONS

NO.	DATE	DESCRIPTION

DESIGNED BY: WT	CERTIFICATION: PRELIMINARY NOT FOR CONSTRUCTION
CHECKED BY: WT	
APPROVED BY: Approver	
PROJECT NO.	

SHEET TITLE

PNEUMATIC TUBE WALL & FLOOR PENETRATIONS

SHEET NUMBER

PT302

0 1/2" 1" 2"

ORIGINAL SHEET SIZE IS 30" X 42" (ARCH E1)
11/9/2023 3:43:13 PM AESI Proj. No: