



Freestanding Medical Office Building Buildout for:
Sullivan County Community Hospital
Sullivan, Indiana



Sheet Re-Issue Log
(Individual revisions clouded and labeled within each sheet)

ADD #02	03/22/2024

PROJECT NUMBER
23987.02
DATE
February 28, 2024

A1.1n
FLOOR PLAN
NOTED

GENERAL NEW WORK NOTES:

- A. DOOR FRAMES TO BE CAULKED TO FLOOR AT NON-CARPET LOCATIONS.
- B. PROVIDE CONTINUOUS WOOD BLOCKING & ANCHORAGE OR OTHER ADEQUATE SUPPORT AS REQUIRED FOR EQUIPMENT, LOCKERS, WALL SUPPORTED COUNTERS AND CABINETS.
- C. PROVIDE MANUAL SHADES AT ALL EXTERIOR WINDOWS. **ADD #02**
- D. EQUIPMENT SHOWN FOR REFERENCE ONLY AND WILL BE PROVIDED BY OWNER.
- E. PROVIDE MOCK UPS FOR EXAM ROOM AS NOTED IN SPECIFICATIONS PRIOR TO OUTLET INSTALLATION. **ADD #02**
- F. BASE BID TO INCLUDE NOTE 5 IN ALTERNATE A1 SPACE.

PLAN KEY NOTES:

1. PROVIDE DOOR AS A PART OF ALTERNATE A1.
2. PROVIDE BLOCKING FOR OWNER PROVIDED SIGNAGE ON WALL.
3. PROVIDE SHUT OFF VALVES FOR TESTING TOILETS, SEE PLUMBING.
4. PROVIDE 18x12 ACCESS PANEL TO FIRE SPRINKLER PIPE. COORDINATE LOCATION WITH FIRE PROTECTION. **ADD #02**
5. NO INTERIOR GYPSUM BOARD IS NEEDED ON SHELL SIDE OF SPACE, HOWEVER INSULATION IS TO BE PROVIDED IN WALLS AND SECURED AS NECESSARY.



NOTED FLOOR PLAN
PLAN NORTH 8' 0" 8'