



811
Know what's below.
Call before you dig.

CAUTION

LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED UPON ABOVE GROUND EVIDENCE (INCLUDING, BUT NOT LIMITED TO, MANHOLES, INLETS, VALVES, AND MARKS MADE UPON THE GROUND BY OTHERS) AND ARE SPECULATIVE IN NATURE. THERE MAY ALSO BE OTHER EXISTING UNDERGROUND UTILITIES FOR WHICH THERE IS NO ABOVE GROUND EVIDENCE OR FOR WHICH NO ABOVE GROUND EVIDENCE WAS OBSERVED. THE EXACT LOCATIONS OF SAID EXISTING UNDERGROUND UTILITIES SHOULD BE VERIFIED BY THE CONTRACTOR PRIOR TO ANY AND ALL CONSTRUCTION.

CALL 811 OR 1-800-382-5544
48 HOURS BEFORE DIGGING



THE CONTENTS OF THIS DOCUMENT ARE THE SOLE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. AND MAY NOT BE REPRODUCED OR TRANSFERRED IN ANY WAY WITHOUT THE WRITTEN CONSENT OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC.

ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES, AND OTHER DOCUMENTS AND INSTRUMENTS PREPARED BY MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. (DESIGN PROFESSIONAL) AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. SHALL RETAIN ALL COMMON LAW, STATUTORY, AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THERETO. THIS STATEMENT SHALL NOT BE REMOVED FROM THIS DRAWING FOR ANY REASON.

DATE	REVISIONS	BY




WABASH VALLEY HEALTH CENTER, INC.
1436 LOCUST STREET
TERRE HAUTE, INDIANA 47807
BUILDING ADDITIONS & RENOVATION

MICHAEL R. WALDBIESER
ENGINEERING & CONSULTING, INC.
REGISTERED PROFESSIONAL ENGINEER
STATE OF INDIANA, LICENSE NO. 1950108
SYCAMORE BUILDING
19 SOUTH 66th STREET, SUITE 804
TERRE HAUTE, INDIANA 47807
PHONE: (812) 232-6510

SCALE: 1" = 20'-0"
DATE: 09-11-19
DRAWN BY: MRW
APPROVED BY: MRW

PROJECT: 18-20
FILE: ExSite #F
C1



NUMBERED NOTES:

- 1 REMOVE ALL EXISTING SOILS AND CONSTRUCTION AS REQUIRED FOR NEW PARKING LOT INSTALLATION.
- 2 EXISTING CONCRETE CURB REMAINS ALONG THIS PROPERTY LINE.
- 3 REMOVE EXISTING WOOD FENCE ALONG THIS PROPERTY LINE COMPLETE.
- 4 REMOVE EXISTING CHAIN LINK FENCE COMPLETE ALONG THIS PROPERTY LINE.
- 5 REMOVE EXISTING CONCRETE AROUND EXISTING DRYWELL INLET COMPLETE. REFER TO MYERS ENGINEERING DRAWINGS FOR MORE WORK.
- 6 REMOVE EXISTING CONCRETE CURBS AND SEPTIC TANK GRAVEL COMPLETE.
- 7 REMOVE ALL EXISTING CONSTRUCTION AS REQUIRED TO INSTALL NEW CURB CUTS AND APPROACHES PER CITY OF TERRE HAUTE STANDARDS.
- 8 REMOVE EXISTING CURB CUT COMPLETE.
- 9 REMOVE ALL EXISTING ASPHALT PAVING AND ADDITIONAL UNDERCUTS AS REQUIRED TO INSTALL NEW ASPHALT PAVEMENT.
- 10 REMOVE ALL EXISTING ASPHALT PAVING AND ADDITIONAL UNDERCUTS AS REQUIRED TO INSTALL NEW ASPHALT PAVEMENT FROM ABANDONED ALLEY.
- 11 REMOVE ALL EXISTING ASPHALT PAVING AND ADDITIONAL UNDERCUTS AS REQUIRED TO INSTALL NEW CONCRETE PAVEMENT. REMOVE EXISTING CONCRETE PADS AND CHAIN LINK FENCES AROUND EXISTING A/C UNITS. REMOVE EXISTING CONCRETE ENTRY.
- 12 REMOVE ALL EXISTING ASPHALT PAVING/CONCRETE PAVEMENT AND ADDITIONAL UNDERCUTS AS REQUIRED TO INSTALL NEW ASPHALT PAVEMENT. REMOVE EXISTING POURED CONCRETE STAIRS COMPLETE.
- 13 EXISTING CHAIN LINK FENCE AROUND EXISTING GENERATOR TO REMAIN.
- 14 REMOVE ALL EXISTING ASPHALT PAVING AND ADDITIONAL UNDERCUTS AS REQUIRED TO INSTALL NEW ASPHALT PAVEMENT AND BUILDING ADDITION. REMOVE EXISTING POURED CONCRETE RAMP COMPLETE. REMOVE EXISTING CONCRETE PAD AND CHAIN LINK FENCE AROUND EXISTING A/C UNIT.
- 15 REMOVE EXISTING CONCRETE PAVEMENT AS REQUIRED TO INSTALL NEW WATER SERVICE.
- 16 REMOVE PORTION OF EXISTING GUARDRAIL AS SHOWN. REMOVE VERTICAL POSTS AS REQUIRED. PATCH CONCRETE PAVEMENT AFTER REMOVAL.
- 17 REPAIR AND/OR REPLACE EXISTING STONE CAPS AS REQUIRED. FIELD VERIFY EXTENT OF WORK. STONE CAPS TO BE SET WITH EPOXY ANCHORS.
- 18 REMOVE EXISTING CHAIN LINK FENCE AND GATE COMPLETE.
- 19 REMOVE EXISTING GUARDRAIL COMPLETE.
- 20 REMOVE AND REPLACE EXISTING SIDEWALK, CONCRETE CURB, RETAINING WALL, AND ASPHALT PAVEMENT AS REQUIRED TO INSTALL NEW DOMESTIC WATER SERVICE AND NEW FIRE SERVICE.
- 21 REMOVE EXISTING ASPHALT PAVEMENT IN PROPERTY EASEMENT AREA (15'-0" FROM NORTH PROPERTY LINE). REQUIRED TO INSTALL NEW UNDERGROUND/RELOCATED ELECTRICAL LINES. SEE SITE UTILITY PLAN.
- 22 REMOVE PORTION OF EXISTING ALLEY (WIDTH AS REQUIRED) TO INSTALL NEW UNDERGROUND ELECTRICAL CONDUIT. SEE SITE UTILITY PLAN.
- 23 REMOVE EXISTING DRYWELL COMPLETE.
- 24 REMOVE EXISTING DRYWELL COMPLETE. NEW DRYWELL WILL BE INSTALLED AT THIS LOCATION. SEE CIVIL DRAWINGS BY MYERS ENGINEERING.

CONSTRUCTION PHASING NOTE:

REFER TO CONSTRUCTION PHASING DRAWINGS #PH1, #PH2, AND #PH3 FOR THE CONSTRUCTION SEQUENCE OF THE PROJECT.

DATE	REVISIONS	BY



WABASH VALLEY HEALTH CENTER, INC.
1436 LOCUST STREET
TERRE HAUTE, INDIANA 47807
BUILDING ADDITIONS & RENOVATION

MICHAEL R. WALDBIESER
ENGINEER & CONSULTING, INC.
STRUCTURAL ENGINEERING AND CONSULTING
SYCAMORE BUILDING
19 SOUTH 66th STREET, SUITE 804
TERRE HAUTE, INDIANA 47807
PHONE: (812) 232-6510

SCALE: 1" = 20'-0"	PROJECT: 18-20
DATE: 09-11-19	FILE: ExSite #F
DRAWN BY: MRW	
APPROVED BY: MRW	


C2

CAUTION
LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED UPON ABOVE GROUND EVIDENCE (INCLUDING, BUT NOT LIMITED TO, MANHOLES, INLETS, VALVES, AND MARKS MADE UPON THE GROUND BY OTHERS) AND ARE SPECULATIVE IN NATURE. THERE MAY ALSO BE OTHER EXISTING UNDERGROUND UTILITIES FOR WHICH THERE IS NO ABOVE GROUND EVIDENCE OR FOR WHICH NO ABOVE GROUND EVIDENCE WAS OBSERVED. THE EXACT LOCATIONS OF SAID EXISTING UNDERGROUND UTILITIES SHOULD BE VERIFIED BY THE CONTRACTOR PRIOR TO ANY AND ALL CONSTRUCTION.

**CALL 811 OR 1-800-382-5544
48 HOURS BEFORE DIGGING**

DEMOLITION SITE PLAN
SCALE: 1" = 20'-0"

THE CONTENTS OF THIS DOCUMENT ARE THE SOLE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. AND MAY NOT BE REPRODUCED OR TRANSFERRED IN ANY WAY WITHOUT THE WRITTEN CONSENT OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES, AND OTHER DOCUMENTS AND INSTRUMENTS PREPARED BY MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. (DESIGN PROFESSIONAL) AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. SHALL RETAIN ALL COMMON LAW, STATUTORY, AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THERETO. THIS STATEMENT SHALL NOT BE REMOVED FROM THIS DRAWING FOR ANY REASON.



NUMBERED NOTES:

- 1 NEW PRE-CAST CONCRETE BUMPER
SEE DETAIL 4/C4
TYPICAL AT LOCATIONS SHOWN
- 2 NEW CONCRETE PAVEMENT SECTION
SEE DETAIL 6/C4
- 3 NEW ASPHALT PAVEMENT SECTION
TO BE USED IN ALLEY PORTION
OF PROJECT
SEE DETAIL 7/C4
- 4 NEW ASPHALT PAVEMENT SECTION
TO BE USED IN NEW PARKING LOTS
AND PATCH OF EXISTING ASPHALT
PAVING OF PROJECT
SEE DETAIL 8/C4
- 5 NEW HANDICAPPED ACCESS POINT
DEPRESSED CONCRETE CURB DETAIL
SEE DETAIL 9/C4
- 6 NEW CONCRETE CURB
SEE DETAIL 10/C4
- 7 PARKING LOT STRIPPING
SEE DETAIL 11/C4
- 8 8" POURED CONCRETE SECTION
PER CITY OF TERRE HAUTE STANDARDS.
- 9 FLUSH TRANSITION AT SIDEWALK CROSSING
SEE DETAIL ON DRAWING C4.
- 10 NEW 6'-0" HIGH CHAIN LINK FENCE WITH
VINYL SLATS.
SEE DETAIL 12/C4.
REQUIRED BY CITY OF TERRE HAUTE AREA PLANNING
DEPARTMENT.
- 11 NEW SIGN TO INDICATE DELIVERY AND EMERGENCY
VEHICLE PARKING ONLY
- 12 ALUMINUM ENTRY CANOPY WITH BUILT IN GUTTER.
BUILDING SUPPORTED.
NO EXTERNAL COLUMNS.
- 13 ALUMINUM ENTRY CANOPY WITH BUILT IN GUTTER.
MOUNTED TO BUILDING WITH EXTERNAL COLUMNS.
- 14 NEW SITE LIGHTING POLE
COMPLETE BY ELECTRICAL CONTRACTOR.
REFER TO DRAWING #E3.3.
- 15 NEW GENERATOR PAD LOCATION
SEE DETAIL 13/C4.
ALSO PROVIDE AND INSTALL NEW CHAIN
LINK FENCE AROUND NEW GENERATOR.
PROVIDE DOUBLE GATE LIKE EXISTING.
PROVIDE HEIGHT TO MATCH EXISTING.
- 16 NEW DUMPSTER PAD LOCATION
SEE DETAIL 13/C4.
- 17 NEW ASPHALT PAVEMENT SECTION
TO BE USED IN NEW PARKING LOTS
AND PATCH OF EXISTING ASPHALT
PAVING OF PROJECT
SEE DETAIL 8/C4
- 18 NEW ASPHALT PAVEMENT SECTION
FOR REPAIR OF ALLEY.
SEE DETAIL 7/C4
- 19 NEW 6'-0" HIGH CHAIN LINK FENCE WITH
VINYL SLATS.
SEE DETAIL 12/C4.
INSTALLED ON TREE SIDE OF DUMPSTER.
FINAL SIZE AS DIRECTED BY THE OWNER.
- 20 NEW PIPE BOLLARDS FOR PROTECTION OF
NEW FENCING.
SEE DETAIL 20/C4.
TYPICAL OF 2

INTERIOR CURB CUT NOTE:

THERE IS A MINIMUM OF 12'-0" FROM THE INTERIOR LOT LINE
TO ANY CURB CUT ON THE PROPERTY.

SITE PLAN NOTE:

GENERAL CONTRACTOR SHALL INCLUDE IN THE BID ALL PERMIT FEES REQUIRED
BY THE CITY OF TERRE HAUTE FOR WORK PERFORMED IN THE RIGHT OF WAY.
I.e. CURB REMOVAL AND REPLACEMENT AND SIDEWALK REPLACEMENT.
CONTACT CITY OF TERRE HAUTE ENGINEERING DEPARTMENT FOR COST OF PERMITS.

DATE	REVISIONS	BY



WABASH VALLEY HEALTH CENTER, INC.
1436 LOCUST STREET
TERRE HAUTE, INDIANA 47807
BUILDING ADDITIONS & RENOVATION


MICHAEL R. WALDBIESER
ENGINEERING & CONSULTING, INC.
STRUCTURAL ENGINEER, LICENSED IN INDIANA
SYCAMORE BUILDING
19 SOUTH 66th STREET, SUITE 804
TERRE HAUTE, INDIANA 47807
PHONE: (812) 232-6510

SCALE: 1" = 20'-0"	PROJECT: 18-20
DATE: 09-11-19	FILE: NSite #F
DRAWN BY: MRW	
APPROVED BY: MRW	

C3

CAUTION
LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES
SHOWN ON THIS PLAN ARE BASED UPON ABOVE GROUND
EVIDENCE (INCLUDING, BUT NOT LIMITED TO,
MANHOLES, INLETS, VALVES, AND MARKS MADE UPON
THE GROUND BY OTHERS) AND ARE SPECULATIVE IN
NATURE. THERE MAY ALSO BE OTHER EXISTING
UNDERGROUND UTILITIES FOR WHICH THERE IS NO
ABOVE GROUND EVIDENCE OR FOR WHICH NO ABOVE
GROUND EVIDENCE WAS OBSERVED. THE EXACT
LOCATIONS OF SAID EXISTING UNDERGROUND UTILITIES
SHOULD BE VERIFIED BY THE CONTRACTOR PRIOR TO
ANY AND ALL CONSTRUCTION.

CALL 811 OR 1-800-382-5544
48 HOURS BEFORE DIGGING



THE CONTENTS OF THIS DOCUMENT ARE THE SOLE PROPERTY OF
MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC.
AND MAY NOT BE REPRODUCED OR TRANSFERRED IN ANY WAY
WITHOUT THE WRITTEN CONSENT OF MICHAEL R. WALDBIESER
ENGINEERING & CONSULTING, INC.
ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD
DATA, NOTES, AND OTHER DOCUMENTS AND INSTRUMENTS
PREPARED BY MICHAEL R. WALDBIESER ENGINEERING &
CONSULTING, INC. (DESIGN PROFESSIONAL) AS INSTRUMENTS OF
SERVICE SHALL REMAIN THE PROPERTY OF MICHAEL R.
WALDBIESER ENGINEERING & CONSULTING, INC. MICHAEL R.
WALDBIESER ENGINEERING & CONSULTING, INC. SHALL RETAIN
ALL COMMON LAW, STATUTORY, AND OTHER RESERVED RIGHTS,
INCLUDING THE COPYRIGHT THERE TO. THIS STATEMENT SHALL
NOT BE REMOVED FROM THIS DRAWING FOR ANY REASON.





Diagram illustrating the cross-section of a concrete slab with reinforcement details:


- WELDED WIRE FABRIC PLACED AT MID-DEPTH
- SAW CUT 1/4 SLAB DEPTH
- CORNERS ROUNDED WITH EDGING TOOL
- LOCATE AT 5'-0" O.C.

SIDEWALK NOTES:

1. INSTALL EXPANSION MATERIAL BETWEEN ALL SIDEWALKS AND BUILDING WALLS.



811
 what's below.
 Call before you dig.



- ① **CONCRETE:** 4,000 PSI WITH 4-6% AIR ENTRAINMENT. LIGHT BROOM FINISH
- ② **GRANULAR BASE COURSE:** INDOT #53 STONE BASE - COMPACT 100% DRY DENSITY, STANDARD PROCTOR. GRANULAR BASE IS NOT ACCEPTABLE.
- ③ **SUBGRADE:** REMOVE ALL HIGHLY ORGANIC MATERIAL AND PROOF ROLL SURFACE. REMOVE ALL AREAS SHOWING PUMPING AND REPLACE WITH GRANULAR MATERIAL. FILL MATERIAL SHALL BE PLACED IN LIFTS NOT EXCEEDING 8" AND COMPACTED TO 100% DRY DENSITY - MODIFIED PROCTOR.

- 1 SURFACE COAT: BITUMINOUS SURFACE NO. 11
- 2 TACK COAT: 10 GALLON PER SQUARE YARD, RAPID CURE LIQUID ASPHALT.
- 3 ASPHALTIC BASE COURSE: BITUMINOUS NO. 8.
- 4 PRIME COAT: 30 GALLON PER SQUARE YARD, MEDIUM CURE LIQUID ASPHALT.
ONLY IF REQUIRED BY INDOT DESIGN STANDARDS
- 5 BASE COURSE: INDOT #53 CRUSHED STONE AGGREGATE - COMPACT 100% DRY DENSITY, STANDARD PROCTOR. GRANULAR BASE IS NOT ACCEPTABLE.
- 6 SUBGRADE: REMOVE ADDITIONAL 16" OF MATERIAL UNDER THE BASE COURSE AS DIRECTED IN THE SOILS REPORT BY PATRIOT ENGINEERING & ENVIRONMENTAL, INC.




Diagram illustrating the layout of a concrete curb and pavement edge. The diagram shows a cross-section of the curb and pavement edge, with dimensions and labels indicating the structure and measurements.

Labels and Dimensions:

- CONCRETE CURB
- PAVEMENT EDGE
- CENTER OF CURB CUT
- Dimensions: 1'-6", 5'-0", 1'-6"



[illegible]

Diagram illustrating a preferred sidewalk cross-section. The sidewalk is 6'-0" wide. The transition from the sidewalk to the street is 2'-0" wide and flush. The curb height is 2'-0". The diagram is labeled "PREFERRED SIDEWALK" and includes a note: "Residential Driveway or Commercial Driveway without Yield or Stop Control".



RESIDENTIAL DRIVEWAY or COMMERCIAL DRIVEWAY without Yield or Stop Control

FLUSH TRANSITION

6'-0" Min.

6'-0" Min.

6'-0" Min.

PREFERRED SIDEWALK CROSSING

RESIDENTIAL DRIVEWAY or COMMERCIAL DRIVEWAY without Yield or Stop Control

FLUSH TRANSITION*

6'-0" Min.

6'-0" Min.

6'-0" Min.

SIDEWALK TRANSITION

Sidewalk Transition (Typ.)

RESIDENTIAL DRIVEWAY or COMMERCIAL DRIVEWAY without Yield or Stop Control

FLUSH TRANSITION

6'-0" Min.

6'-0" Min.

6'-0" Min.

WIDE SIDEWALK

RESIDENTIAL DRIVEWAY or COMMERCIAL DRIVEWAY without Yield or Stop Control

FLUSH TRANSITION

6'-0" Min.

6'-0" Min.

6'-0" Min.

SIDEWALK APRON OFFSET

FLUSH TRANSITION

6'-0" Min.

6'-0" Min.

6'-0" Min.

Flared Side (Typ.)

NOTES:

1. All slopes are absolute rather than relative to the sidewalk or roadway grade. Slopes at least 0.50% less than the maximum are preferred.
2. A sidewalk driveway crossing shall only be used on a sidewalk at a residential driveway or a commercial driveway without yield or stop control. A curb ramp shall be used at all other crossings. See Standard Drawing Series E 604-SDWK for curb ramp details.
3. Where a sidewalk transition is used to lower or raise the sidewalk to connect with a residential driveway or commercial driveway without yield or stop control, the running slope of the transition shall be 8.33% maximum.
4. The grade of the sidewalk across the driveway shall not exceed the grade of the adjacent roadway.
5. The area between the driveway and a flared side or sidewalk transition shall match the driveway profile and transverse slope.
6. A turning space is not required at the top of a sidewalk transition.
7. Objects such as a utility cover, vault frame, and grating shall be placed outside a sidewalk transition.
8. A detectable warning surface shall not be placed at the crossings of a residential driveway. A detectable warning surface may be placed at the crossing of a commercial driveway without yield or stop control.
9. See Standard Drawing E 604-SDWK-01 and -02 for Sidewalk Details.
10. See Standard Drawing Series E 610-DR for drives.

INDIANA DEPARTMENT OF TRANSPORTATION	
SIDEWALK DRIVEWAY CROSSING	
SEPTEMBER 2016	
STANDARD DRAWING NO.	E 604-SDWK-03
	<i>/s/ Elizabeth W. Phillips</i> 03/16/16 DESIGN STANDARDS ENGINEER DATE <i>/s/ Mark J. Miller</i> 03/16/16 CHIEF ENGINEER DATE


NOTES:

1. All slopes are absolute rather than relative to the sidewalk or roadway grade. Slopes at least 0.50% lose to the maximum are preferred.
2. A sidewalk driveway crossing shall only be shown on a sidewalk at a residential driveway or a commercial driveway without stop or stop control. A curb ramp shall be placed at all other crossings. See Standard Drawing Series E 610-DRIV for curb ramp details.
3. Where a sidewalk transition is used to lower or raise the sidewalk to connect with a residential driveway or commercial driveway without stop or stop control, the running slope of the transition shall be 8.33% maximum.
4. The grade of the sidewalk across the driveway shall not exceed the grade of the adjacent roadway.
5. The area between the driveway and a flared side or sidewalk transition shall match the driveway profile and transverse slope.
6. A turning space is not required at the top of a sidewalk transition.
7. Objects such as a utility cover, vault frame, and grating shall be placed outside a sidewalk transition.
8. A detectable warning surface shall not be placed at the crossings of a residential driveway. A detectable warning surface may be placed at the crossing of a commercial driveway without stop or stop control.

See Standard Drawing E 601-SDWV-01 and -02 for Sidewalk Details.

See Standard Drawing Series E 610-DRIV for Driveway Details.

INDIANA DEPARTMENT OF TRANSPORTATION	
SIDEWALK DRIVEWAY CROSSING	
SEPTEMBER 2016	
STANDARD DRAWING NO.	E 604-SDWK-03



REGISTERED
No.
10200124
STATE OF
INDIANA
PROFESSIONAL ENGINEER

<i>/s/ Elizabeth W. Phillips</i>	03/16/16
DESIGN STANDARDS ENGINEER	DATE
<i>/s/ Mark A. Miller</i>	03/18/16
CHIEF ENGINEER	DATE

THE CONTENTS OF THIS DOCUMENT ARE THE SOLE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. AND MAY NOT BE REPRODUCED OR TRANSFERRED IN ANY WAY WITHOUT THE WRITTEN CONSENT OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. THIS DOCUMENT, INCLUDING ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES, AND OTHER DOCUMENTS AND INSTRUMENTS PREPARED BY MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. AND THE RESULTS OF ANY INVESTIGATIONS OR SERVICE SHALL REMAIN THE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. SHALL RETAIN ALL COMMERCIAL, PATENT, COPYRIGHT, AND OTHER INTELLECTUAL RIGHTS IN THE CONTENTS OF THIS DOCUMENT. NO STATEMENT SHALL NOT BE REMOVED FROM THIS DRAWING FOR ANY REASON.

[illegible]

WABASH VALLEY HEALTH CENTER, INC.
1436 LOCUST STREET
TERRE HAUTE, INDIANA 47807
BUILDING ADDITIONS & RENOVATION

MICHAEL R. WALDBIESER
ENGINEERING & CONSULTING, INC.
STRUCTURAL PLUMBING, MECHANICAL & ELECTRICAL DESIGN


PHONE: (812) 232-6510

SYCAMORE BUILDING
19 SOUTH 6th STREET, SUITE 804
TERRE HAUTE, INDIANA 47807


SCALE: AS NOTED
DATE: 09-11-19
DRAWN BY: MRW
APPROVED BY: MRW

PROJECT: 18-20
FILE: Site Det #F

C4



NEW PRE-CAST CONCRETE VAULT COMPLETE BY PLUMBING CONTRACTOR PER INDIANA AMERICAN WATER COMPANY REQUIREMENTS IN BASE BID FOR NEW DOMESTIC WATER SERVICE & SPRINKLER SYSTEM. IAWC WILL NEED TO PROVIDE 45 GPM THRU ONE 2" WATER METER SEE DRAWING #P4.0 FOR PRE-CAST VAULT SIZE.



NEW SITE UTILITY PLAN
SCALE: 1" = 20'-0"

CAUTION

LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED UPON ABOVE GROUND EVIDENCE (INCLUDING, BUT NOT LIMITED TO, MANHOLES, INLETS, VALVES, AND MARKS MADE UPON THE GROUND BY OTHERS) AND ARE SPECULATIVE IN NATURE. THERE MAY ALSO BE OTHER EXISTING UNDERGROUND UTILITIES FOR WHICH THERE IS NO ABOVE GROUND EVIDENCE OR FOR WHICH NO ABOVE GROUND EVIDENCE WAS OBSERVED. THE EXACT LOCATIONS OF SAID EXISTING UNDERGROUND UTILITIES SHOULD BE VERIFIED BY THE CONTRACTOR PRIOR TO ANY AND ALL CONSTRUCTION.

CALL 811 OR 1-800-382-5544
48 HOURS BEFORE DIGGING

THE CONTENTS OF THIS DOCUMENT ARE THE SOLE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. AND MAY NOT BE REPRODUCED OR TRANSFERRED IN ANY WAY WITHOUT THE WRITTEN CONSENT OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC.

ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES, AND OTHER DOCUMENTS AND INSTRUMENTS PREPARED BY MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. (DESIGN PROFESSIONAL) AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. SHALL RETAIN ALL COMMON LAW, STATUTORY, AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THERETO. THIS STATEMENT SHALL NOT BE REMOVED FROM THIS DRAWING FOR ANY REASON.

DATE	REVISIONS	BY



WABASH VALLEY HEALTH CENTER, INC.
1436 LOCUST STREET
TERRE HAUTE, INDIANA 47807
BUILDING ADDITIONS & RENOVATION

MICHAEL R. WALDBIESER
ENGINEERING & CONSULTING, INC.
STRUCTURAL ENGINEERING, ARCHITECTURAL & ELECTRICAL DESIGN


SYCAMORE BUILDING
19 SOUTH 66th STREET, SUITE 804
TERRE HAUTE, INDIANA 47807

PHONE: (812) 232-6510

SCALE: 1" = 20'-0"
DATE: 09-11-19
DRAWN BY: MRW
APPROVED BY: MRW

PROJECT: 18-20
FILE: NSite #F

C5



- SITE SCOPE OF WORK:**
1. ALL SITE DEMOLITION AS INDICATED ON DRAWING #C2.
 2. ALL SITE WORK LOCATED WITHIN INDICATED LINE.
 3. ALL EXCAVATION, GRADING AND BACKFILL.
 4. SITE DRAINAGE COMPLETE INCLUDING BUT NOT LIMITED TO:
 - DRYWELLS/CATCH BASINS
 - CONNECTION PIPING BETWEEN DRYWELLS/CATCH BASINS
 - DOWNSPOUT BOOT
 - EXCAVATION AND BACKFILL
 5. UNDERGROUND ELECTRICAL WORK AS FOLLOWS:
 - PROVIDE AND INSTALL UNDERGROUND CONDUIT FOR RELOCATION OF DUKE ENERGY SERVICE LINES
 - PROVIDE AND INSTALL CONDUITS AND WIRING FOR NEW SITE LIGHTING POLES
 6. NEW CONCRETE PAD FOR NEW POWER TRANSFORMER
 7. ALSO INCLUDES NEW CHAIN LINK FENCE AROUND NEW GENERATOR
 8. NEW CONCRETE PAD FOR DUMPSTERS
 9. CONCRETE AND ASPHALT PAVING INCLUDING ALL REINFORCING AND ACCESSORIES
 10. PARKING LOT STRIPPING AND SITE SIGNAGE
 11. PARKING LOT PRE-CAST CONCRETE BUMPERS
 12. PARKING LOT PRE-CAST CONCRETE TRAFFIC CONTROL BARRIERS
 13. CONCRETE CURB CUTS, CONCRETE CURBS, SIDEWALKS, SIDEWALK TRANSITIONS AT NEW CURB CUTS, AND 8" THICK CONCRETE PAVEMENT AT NEW CURB CUTS.
 14. EXCAVATION AND BACKFILL ASSOCIATED WITH TWO NEW CONCRETE RAMPS.
 15. CONCRETE FOUNDATIONS, WALLS, AND WALKING SURFACE FOR TWO NEW RAMPS.
 16. ALSO INCLUDES ALL HANDRAILS
 17. EROSION CONTROL COMPLETE
 18. ALL SITE FENCING
 19. ALL MOBILIZATION AND DEMOBILIZATION COSTS FOR PHASING OF WORK.
 20. ALL COST CHARGED BY DUKE ENERGY FOR NEW UNDERGROUND ELECTRICAL SERVICE TO THE BUILDING.
 21. PATCHING OF EXISTING ASPHALT AS REQUIRED.
 22. NEW BIKE RACK
 23. SITE STONE/MASONRY WALL WORK ON SOUTH SIDE OF PROJECT.
 24. CONCRETE BASES FOR NEW SITE LIGHTING.




811
Know what's below.
Call before you dig.

CAUTION

LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED UPON ABOVE GROUND EVIDENCE (INCLUDING, BUT NOT LIMITED TO, MANHOLES, INLETS, VALVES, AND MARKS MADE UPON THE GROUND BY OTHERS) AND ARE SPECULATIVE IN NATURE. THERE MAY ALSO BE OTHER EXISTING UNDERGROUND UTILITIES FOR WHICH THERE IS NO ABOVE GROUND EVIDENCE OR FOR WHICH NO ABOVE GROUND EVIDENCE WAS OBSERVED. THE EXACT LOCATIONS OF SAID EXISTING UNDERGROUND UTILITIES SHOULD BE VERIFIED BY THE CONTRACTOR PRIOR TO ANY AND ALL CONSTRUCTION.

**CALL 811 OR 1-800-382-5544
48 HOURS BEFORE DIGGING**



N
S
E
W

**GRANT FUNDING SCOPE OF WORK
NEW SITE PLAN**

SCALE: 1" = 20'-0"

THE CONTENTS OF THIS DOCUMENT ARE THE SOLE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. AND MAY NOT BE REPRODUCED OR TRANSFERRED IN ANY WAY WITHOUT THE WRITTEN CONSENT OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC.


ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES, AND OTHER DOCUMENTS AND INSTRUMENTS PREPARED BY MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. (DESIGN PROFESSIONAL) AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. MICHAEL R. WALDBIESER ENGINEERING & CONSULTING, INC. SHALL RETAIN ALL COMMON LAW, STATUTORY, AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREON. THIS STATEMENT SHALL NOT BE REMOVED FROM THIS DRAWING FOR ANY REASON.

DATE	REVISIONS	BY



WABASH VALLEY HEALTH CENTER, INC.
1436 LOCUST STREET
TERRE HAUTE, INDIANA 47807

BUILDING ADDITIONS & RENOVATION



**MICHAEL R. WALDBIESER
ENGINEERING & CONSULTING, INC.**

STRUCTURAL ENGINEERING, ARCHITECTURAL & ELECTRICAL DESIGN

SYCAMORE BUILDING
19 SOUTH 66th STREET, SUITE 804
TERRE HAUTE, INDIANA 47807

PHONE: (812) 232-6510



SCALE: 1" = 20'-0"	PROJECT: 18-20
DATE: 09-11-19	FILE: NSite #F
DRAWN BY: MRW	APPROVED BY: MRW

C6

Drainage Plan


1436 Locust Street, Terre Haute
Sec. 15, Township 12 North, Range 9 West
Vigo County, Indiana

NOTE:
Roof Drains Shall Be 6" HDPE Pipe Sloped At A
Minimum Of 1.0% Unless Otherwise Noted.





COMBINATION CATCH BASIN DRYWELL DETAIL

NOT TO SCALE



STORM SEWER TRENCH DETAIL UNDER PAVEMENT


NOT TO SCALE



SCALE: 1"=20'




The locations of underground utilities as shown hereon are based on above ground structures and/or field locates, and record drawings provided by others, the actual locations of which may vary upon a more detailed sub-surface inspection. No excavations were made for purpose of this survey. Before proceeding with any excavation, the proper offices should be contacted for the verification of utility types and/or locations.



Emm Miller
9/9/2019

1436 Locust Street



MYERS ENGINEERING, INC.
325 WEST HONEY CREEK DRIVE
TERRE HAUTE, INDIANA 47802
PHONE: (812) 238-9731
FAX: (812) 238-1353
http://MyersEngineering.com

DATE	NO.	REVISIONS	BY	CHECKED

CLIENT: Michael R. Waldbieser Engineering & Consultants, Inc.
RECORD OWNER: Wabash Valley Health Center Inc.

Drainage Plan

DRAWN BY: EMM	DATE: 09/09/2019
CHECKED BY: MJV	PROJECT NUMBER: TM18-318-03
APPROVED BY: EMM	FILE NAME: TM18-318 Civil.DWG
SCALE: 1"=20'	DRAWING NAME: Drainage Plan

DO NOT SCALE PRINT

SHEET C1.0

SIGNED AND SEALED HARD COPY IS THE INSTRUMENT OF SERVICE. THIS DRAWING MAY NOT BE REPRODUCED WITHOUT THE WRITTEN PERMISSION OF MYERS ENGINEERING, INC.

Storm Water Pollution Prevention Plan

1436 Locust Street, Terre Haute
Sec. 15, Township 12 North, Range 9 West
Vigo County, Indiana

Construction Plan Element (Section A)

A1. Plan Index

See general information Sheet C1.0

A2. 11x17 Inch Plat of Area

Sheet C1.0

A3. Narrative Describing the Nature and Purpose of Project

The proposed project is the building addition, Demolition of an existing parking lot and the construction of new parking lot to include drainage in the City of Terre Haute in the Harrison Township, Vigo County, Indiana.

A4. Vicinity Map

See Sheet C3.0

A5. Legal Description of the Project

Section 15 Township 12 North Range 9 West, Vigo County, Harrison Township
Latitude: 39°28'40" N, Longitude: 87°23'41" W

A6. Location of all Proposed Improvements

See Sheet C3.0

A7. Hydrologic Unit Code

HUC14: 05120111050060

A8. Notation of any State or Federal Water Quality Permits

There are no known wetlands within the construction limits.

9. Specific Points where Stormwater Discharge Leaves Site

Stormwater will leave the site via sheet flow into a network of new drywells. Water will leave the site through infiltration into the soil.

A10. Location of all Wetlands, Lakes and Watercourses

There are no known wetlands within the construction limits. The Wabash River is approximately 1 mile West from the project site.

A11. Identification of all Receiving Waters

Final receiving water will be the Wabash River.

A12. Identification of Potential Discharge to Ground Water

Runoff may enter the groundwater via natural filtration through the soil. No known abandoned wells on site.

A13. 100 year Floodplains, Floodways and Fringes

This property is not located in a floodplain per FEMA Map 18167C0132C, February 18th, 2011.

A14. Pre Construction and Post Construction Estimate of Peak Discharge

The 10-year pre-construction peak discharge was calculated to be X.X-cfs and the 25-year post construction peak discharge from the site was calculated to be X.X-cfs.

A15. Adjacent Land Use

Adjacent land use:

North: 1st Avenue, Residential (Single Family Dwelling)
South: Locust Street, Residential (Single Family Dwelling)
East: Residential (Single Family Dwelling)
West: Residential (Single Family Dwelling)

A16. Construction Limits

See Plan Sheet C1.0.

A17. Identification of Existing Vegetative Cover

The existing project site consists primarily of a parking lot and buildings, a small portion of the site is a grass lot.

A18. Soils Map Including Soil Descriptions

Soil types present on-site is Elston Sandy Loam, 0 to 2 percent slopes.

A19. Location and Size of Proposed Stormwater Systems

See Plan Sheet C1.0.

A20. Plans for any Off-Site Activities Associated with Project

All construction activity should be contained to the site.

A21. Location of Proposed Soil Stockpiles and/or Borrow Areas

Soil stockpiles will be located on site as shown on the erosion control plan sheet C3.0. Any amount of topsoil stockpiled shall be surrounded with silt fence prior to placing any material there. If the soil stockpile is left idle for 7 days or longer, temporary seeding in accordance with Indiana Department of Environmental Management must be applied within the stockpile location.

A22. Existing Site Topography

See Plan Sheet C1.0.

A23. Proposed Final Topography

See Plan Sheet C1.0.

Stormwater Pollution Prevention Plan - Construction Component (Section B)

B1. Description of Potential Pollutant Sources

Potential pollutant sources associated with the construction are anticipated to be silt runoff, petroleum and petroleum based chemicals from equipment and vehicles, fertilizer used for temporary and permanent seeding and, concrete from truck washout. These are all addressed in this plan.

B2. Sequence of Implementation

Pre-Construction Practices

1. Notify IDEM Rule 5 coordinator (317-233-1864) and City of Terre Haute Public Works Office within 48 hours of starting construction. Schedule a pre-construction meeting after the perimeter practices have been installed.
2. Perimeter silt fence shall be installed prior to any land disturbing activities as shown on the Erosion Control Plan. See sheet C3.0.
3. A 3' buffer area of existing vegetation shall be maintained between disturbed areas and silt fence.
4. Topsoil stockpiles will be located on the site, as shown on the erosion control plans. Any amount of topsoil stockpiled shall be surrounded with silt fence prior to placing any material there.
5. There will be a construction entrance from 1st Avenue on the North side of the project. The construction entrance will be constructed of No. 2 stone placed to a depth of 8-in placed on top of geotextile fabric. This entrance shall be a minimum of 50-ft. long x 24-ft wide, to allow for two-way traffic.
6. Install Construction Entrance, fueling area, port-a-potty, solid waste bin, concrete washout facility and equipment staging area.
7. Post the contact information at the construction entrance. Include a copy of the NOI and contact information for the on-site person who is responsible for implementing the storm water pollution prevention plan. The SWPPP should be on-site and weekly site reports need to be available within 48 hours of a request.

During Construction Practices

1. Inspection and maintenance of the Erosion Control practices initiated will continue throughout the construction time period. Inspections will be at least once a week. Inspections will be made following every ½ inch rain event. Inspection is to be made by construction personnel trained individually and erosion control practices.
2. All areas on the property that have been cleared or graded shall have temporary seeding planted as early as possible. All areas left undisturbed for 7 days SHALL be temporary seeded.
3. All disturbed areas shall have permanent seed within 7 days after finished grading operations as specified in C4.0.
4. All disturbed areas not at final grade left idle for more than 7 days shall be temporary seeded as per C4.0.
5. Install Temporary Inlet Protection as shown on the Erosion Control Plan. See sheet C3.0.
6. Land disturbing activities shall be kept to a minimum until these practices are installed.
7. Install catch basin and pipe structures. Install inlet and outlet protection immediately after structure is installed. See sheet C3.0.
8. Complete paving. If paving is delayed for 7 days or more the disturbed areas should be seeded. Backfill as needed.

Post Construction Practices

1. Inspection and maintenance of the Erosion Control practices initiated will continue after construction is complete. Sediment control practices shall be removed after the site is stabilized.
2. The contractor shall remove the temporary erosion or sediment control devices as each area is permanently stabilized.

B3. Stable Construction Entrance

The construction entrance for this project will be located as shown on sheet C3.0. Property shall be kept cleared of sediment, trash and any construction materials (including fluids). Access to the construction entrance will be from 1st Avenue on the North side of the project, which shall be kept clean of mud and silt.

B4. Sediment Control for Sheet Flow

Sheet flow will be the primary runoff type on this project. Silt fence will be placed as directed in the Erosion Control Plan. See sheet C3.0.

B5. Sediment Control for Concentrated Flow

N/A

B6. Storm Inlet Protection

Temporary erosion control inlet protection will be placed around each of the storm inlets.

B7. Runoff Control Measures

N/A

B8. Storm Water Outlet Protection

N/A

B9. Grade Stabilization Locations

N/A

B10. Location, Dimensions, Specifications and Details of Each Stormwater Quality Measure

See sheet C3.0 and C4.0

B11. Temporary Surface Stabilization Methods

All areas left disturbed for 7 days or more shall have temporary seeding applied according to the attached specifications (Indiana Department of Environmental Management Manuel, Chapter 7). If construction is completed in an area, permanent seeding may be applied instead of temporary. Temporary seeding shall be applied as follows:

Seed Species	Rate/Acre	Planting Depth	Optimum Dates
Wheat or Rye	150 lbs	1 to 1.5 in.	9/15 to 10/30
Spring Oats	100 lbs	1 in.	3/1 to 4/15
Annual Ryegrass	40 lbs	0.25 in.	3/1 to 5/1 & 8/1 to 9/1
German Millet	40 lbs	1 to 2 in.	5/1 to 6/1
Sudangrass	35 lbs	1 to 2 in.	5/1 to 7/30
Buckwheat	60 lbs	1 to 2 in.	4/15 to 6/1
Corn (Broadcast)	300 lbs	1 to 2 in.	5/11-8/10
Sorghum	35 lbs	1 to 2 in.	5/1-7/15

B12. Permanent Surface Stabilization Specifications

Once construction is completed in areas outside of the building, sidewalk, or paving limits, permanent seeding is to take place. This is to be done according to the attached specifications for Permanent Seeding. The specifications state what type of seed mixes are to be used and how to apply them. Optimum seeding dates are March 1 to May 10 and August 10 to September 30. Seeding done between May 10 and August 10 may require irrigation. As an alternative, temporary seeding may be used until the optimum dates for permanent seeding.

B13. Material Handling and Spill Prevention Plan

Materials that may be present on site during construction will be petroleum-based products. These materials should be handled in a common area used to fuel and service equipment. Any spill of petroleum that exceeds 55 gallons must be reported to the Indiana Department of Environmental Management, Office of Environmental Response at (888)233-7745 or (317)233-7745 within 2 hours as well as the Terre Haute Fire Depatment. Any smaller spills will be contained and all affected materials shall be removed and hauled to an approved location for disposal. All materials used on site shall have an available MSDS sheet to specify what is to be done in case of a spill.

B14. Monitoring and Maintenance Guidelines for each Proposed S/W Quality Measure

Monitoring and maintenance of the practices will be in accordance with the attached specification for each practice. The contractor shall have a person knowledgeable in erosion and sediment control that shall inspect the site for storm water pollution deficiencies at least weekly and again within 24 hours of every ½ inch rain event.

B15. Erosion and Sediment Control Specifications for each Building Lot

N/A

Stormwater Pollution Prevention Plan - Post Construction Component (Section C)

C1. Description of Pollutants and their Sources Associated with Proposed Land Use

The site will be used as a Parking Lot, Sidewalk and Landscaping. Possible post construction pollutants would be gas/oil from vehicles in and out of the site as well as salt/sand and trash/litter.

C2. Sequence Describing Stormwater Quality Measure Implementation

Areas to be seeded will be fine graded in order to establish a good stand of grass in order to prevent erosion. Permanent seeding must be done within 7 days of the end of construction.

C3. Description of Proposed Post Construction Stormwater Quality Measures


Permanent seeding will be in accordance with the attached specifications. See sheet C4.0.

C4. Location, Dimensions, Specifications and Details of each Stormwater Quality Measure

All seeding locations are shown on the plans, and will encompass a very small area. The remaining area will be covered with building, or asphalt pavement.

C5. Description of Maintenance Guidelines for Post Construction S/W Quality Measures

Contractor will be responsible for establishing and maintaining the seeded areas until grass is fully established and pavement has been placed. After that time, the property owner will then assume responsibility for maintaining the seeded areas and drywells as needed.




Evan M. Miller
9/9/2019

SIGNED AND SEALED HARD COPY IS THE INSTRUMENT OF SERVICE. THIS DRAWING MAY NOT BE REPRODUCED WITHOUT THE WRITTEN PERMISSION OF MYERS ENGINEERING, INC.

1436 Locust Street			
		MYERS ENGINEERING, INC. ENGINEERING, INC. Copyright © 2019 http://MyersEngineering.com	
DATE	NO.	REVISIONS	BY CHECKED
CLIENT:		RECORD OWNER:	
Michael R. Waldbieser Engineering & Consultants, Inc.		Wabash Valley Health Center Inc.	
Stormwater Pollution Prevention Plan			
DRAWN BY:	EMM	DATE:	09/09/2019
CHECKED BY:	MJV	PROJECT NUMBER:	TM18-318-03
APPROVED BY:	EMM	FILE NAME:	TM18-318 Civil.DWG
SCALE:	N/A	DRAWING NAME:	SWPPP
DO NOT SCALE PRINT			SHEET C2.0

1436 Locust Street, Terre Haute
Sec. 15, Township 12 North, Range 9 West
Vigo County, Indiana



SIGNED AND SEALED HARD COPY IS THE INSTRUMENT OF SERVICE. THIS DRAWING MAY NOT BE REPRODUCED WITHOUT THE WRITTEN PERMISSION OF MYERS ENGINEERING, INC.

Erosion Control Plan Details

1436 Locust Street, Terre Haute
Sec. 15, Township 12 North, Range 9 West
Vigo County, Indiana

CONSTRUCTION SEQUENCE FOR SITE EROSION CONTROL PRACTICES

STEP 1. Evaluate the Site

Before construction, evaluate the entire site, marking for protection any important trees and associated rooting zones, unique areas to be preserved, on-site septic system absorption fields, and vegetation suitable for filter strips, especially in perimeter areas.

Identify Vegetation To Be Saved

- Select and identify the trees, shrubs, and other vegetation that you want to save (see "Vegetation Filter Strips" under Step 2 below).

Protect Trees and Sensitive Areas

- To prevent root damage, do not grade, burn, place soil piles, or park vehicles near trees or in areas marked for preservation.
- Place plastic mesh or snow fence barriers around tree's drip line to protect the area below their branches.
- Place a physical barrier, such as plastic fencing, around the area designated for a septic system absorption field (if applicable).

STEP 2. Install Perimeter Erosion and Sediment Controls

Identify the areas where sediment-laden runoff could leave the construction site, and install perimeter controls to minimize the potential for off-site sedimentation. It's important that perimeter controls are in place before any other earth-moving activities begin.

Protect Down-Slope Areas

With Silt Fence

- Use silt fencing along the perimeter of the lot's downslope side(s) to trap sediment (see Specifications).

Install Gravel Drive

- Restrict all lot access to this drive to prevent vehicles from tracking mud on to roadways.

STEP 3. Prepare the Site for Construction


Prepare the site for construction and for installation of utilities. Make sure all contractors (especially the excavating contractor) are aware of areas to be protected.

Salvage and Stockpile the Topsoil/Subsoil

- Remove topsoil (typically the upper 4 to 6 inches of soil material) and stockpile.
- Remove subsoil and stockpile separately from the topsoil.

NOTE:

- 1 THE FRAME SHALL BE WRAPPED WITH ONE CONTINUOUS PIECE OF GEOTEXTILE FABRIC, AND WITH A MIN. 2'-0" OVERLAP.
- 2 GEOTEXTILE FABRIC SHALL BE BURIED A MIN. OF 1'-0".



- Locate the stockpiles away from any downslope street, driveway, stream, lake, wetland, ditch, or drainageway.

- Immediately after stockpiling, temporary-seed the stockpiles with annual rye or winter wheat and/or place sediment barriers around the perimeter of the piles.

STEP 4. Build the Structure(s) and Install the Utilities

Construct the site and install the utilities then consider the following.

Install Temporary Erosion Control Measures

- Inlet Protectors
- Silt Fence
- Erosion control blanket
- Riprap check dams once ditches are cut
- Temporary sediment trap at pond outlet pipe once pond is constructed

Seed or Sod Bare Areas

- Any area left disturbed for 7 days must be temporary seeded.
- Follow recommendations of a professional landscaping contractor for installation of sod.
- Water newly seeded/sodded areas every day or two to keep the soil moist. Less watering is needed once grass is 2 inches tall

STEP 5. Maintain the Control Practices

Maintain all erosion and sediment control practices until construction is complete and the site is stabilized.

- Inspect the control practices a minimum of twice a week and after each storm event, making any needed repairs immediately.
- Toward the end of each work day, sweep or scrape up any soil tracked onto roadways. Do not flush areas with water.
- By the end of the next work day after a storm event, clean up any soil washed off site.

STEP 6. Revegetate the Site


Immediately after all outside construction activities are complete, stabilize the lot with sod, seed, and/or mulch.

Redistribute the Stockpiled Topsoil and Subsoil

- Spread the stockpiled subsoil to rough grade.
- Spread the stockpiled topsoil to a depth of 4 to 6 inches over rough-graded areas.
- Fertilize and lime according to soil test results or recommendations of a seed supplier or a professional landscaping contractor.

STEP 7. Remove Remaining Temporary Control Measures

Once the sod and/or vegetation is well established, remove any remaining temporary erosion and sediment control practices.



Erosion Control Practices shall be as per the IDEM Indiana Storm Water Quality Manual, unless stated otherwise.

Erosion Control Blankets

To be used in areas where slope is 3:1 or greater

Permanent Seeding Recommendations

Per Plans, INDOT Type "U"

Temporary Seeding: (If areas remain open for 15 days)

Species	Rate/acre	Depth	Optimal Dates
Wheat or Rye	150 lbs.	1 to 1 1/2 in.	9/15 to 10/30

Mulch Anchoring

Tack, Crimp, or Apply biodegradable netting over mulch and staple with 6-8 in. wire staples. Follow manufacturer's recommendations for installation.

Stabilizing measures

Temporary or permanent seeding, silt fence, or other erosion control measures shall be used within seven days after the land has been disturbed. Erosion control measures will be maintained throughout construction.

Staged Clearing





Will be utilized to reduce the amount of disturbed area during construction.

Soil Stockpiles

Will be surrounded with silt fence.



Evan M. Miller
9/1/2019



SIGNED AND SEALED HARD COPY IS THE INSTRUMENT OF SERVICE. THIS DRAWING MAY NOT BE REPRODUCED WITHOUT THE WRITTEN PERMISSION OF MYERS ENGINEERING, INC.

1436 Locust Street			
		MYERS ENGINEERING, INC. 322 WEST HONEY CREEK DRIVE TERRE HAUTE, INDIANA 47802 PHONE: (812) 238-9731 FAX: (812) 238-1353 http://MyersEngineering.com	
DATE	NO.	REVISIONS	BY
CLIENT:		RECORD OWNER:	
Michael R. Waldbieser Engineering & Consultants, Inc.		Wabash Valley Health Center Inc.	
Erosion Control Details			
DRAWN BY:	EMM	DATE:	09/09/2019
CHECKED BY:	MJV	PROJECT NUMBER:	TM18-318-03
APPROVED BY:	EMM	FILE NAME:	TM18-318 Civil.DWG
SCALE:	N/A	DRAWING NAME:	Erosion Control Details
DO NOT SCALE PRINT			SHEET C4.0