LOUVER SCHEDULE

TAG	MANUFACTURER	MODEL	DESIGNATION	NOMINAL DIMENSIONS (IN) WIDTH	HEIGHT	DEPTH	FREE AREA (SF)	AIRFLOW (CFM)	VELOCITY (FPM)	MOUNTING HEIGHT (A.F.F.)	WEIGHT (LBS)	NOTES
L-1	GREENHECK	EAD-635-216x56	INTAKE	216	56	6	48.4	40,000	827	13'-4"	348	2,3
L-2	GREENHECK	EAD-635-216x56	INTAKE	216	56	6	48.4	40,000	827	13'-4"	348	2,3
L-3	GREENHECK	ESD-635-102X36	EXHAUST	102	36	6	14.4	9400	653	17'-2'	100	2,3
L-4	GREENHECK	ESD-635-102X36	INTAKE	102	36	6	14.4	6000	417	17'-2'	100	2,3
L-5	GREENHECK	ESD-635-140x36	EXHAUST	140	36	6	19.7	10,200	517	14'-2"	111	2,3
L-6	GREENHECK	ESD-403-24X14	INTAKE	24	14	4	0.8	140	176	10'-0"	8	2,3
L-7	GREENHECK	FDS-402-24X14	EXHAUST	24	14	4	0.6	140	251	10'-0"	11	2,3

NOTES:
1. PROVIDE MOTORIZED DAMPER INTERLOCKED WITH EXHAUST FAN.
2. REFER TO DETAIL 3/M5.1.
3. COLORS AS SELECTED BY ARCHITECT FROM MANUFACTURER'S STANDARD COLOR RANGE

FAN POWERED VAV SCHEDULE

TAG		MANF	MODEL	SIZE	INLET DIA (IN)	AIR FLOW (CFM) FAN FLOW	MAX PRIMARY	MIN PRIMARY	MAX AIR PRESSURE DROP (IN WG)	COIL CAPACITY (MBH)	AIR TEMPERATURE (°F) ENTERING	LEAVING	AIR DISCHARGE NC	WATER PRESSURE DROP (FT WG)	WATER FLOW (GPM)	WATER TEMPERATURE (°F) ENTERING	LEAVING	FAN MOTOR TYPE	HP	VOLTAGE	PHASE	MCA	DIMENSIONS (IN) LENGTH	HEIGHT	WIDTH	WEIGHT (LBS)	NOTES
FPV	1-12	PRICE	FDC	20	8	510	510	160	0.04	9.60	69.00	86.20	-	0.18	1.05	140.00	121.60	ECM	1/3	277	1	3.00	51.5	18.5	26	135	1,2,3,4
FPV	1-15	PRICE	FDC	30	10	830	830	430	0.19	27.20	64.60	94.80	23	1.39	2.35	140.00	116.50	ECM	1/2	277	1	4.80	51.5	18.5	26	141	1,2,3,4,7
FPV	1-16	PRICE	FDC	30	8	810	810	430	0.19	27.2	64.80	94.8	23	1.39	2.35	140.00	116.5	ECM	1/2	277	1	4.80	51.5	18.5	26	141	1,2,3,4,7
FPV	1-17	PRICE	FDC	60	14	2110	2110	1050	0.24	72.10	65.00	96.60	28	2.36	4.31	140.00	106.10	ECM	2@3/4	277	1	12.80	65	21	52	272	1,2,3,5,7
FPV	1-22	PRICE	FDC	30	8	830	830	750	0.19	17.60	68.50	88.10	24	0.27	0.94	140.00	101.90	ECM	1/2	277	1	4.80	51.5	18.5	26	141	1,2,3,4
FPV	1-23	PRICE	FDC	10	6	380	380	180	0.16	9.1	67.60	89.50	20	0.06	0.51	140.00	104.30	ECM	1/4	277	1	2.90	41	16	20	104	1,2,3,4
FPV	1-24	PRICE	FDC	30	8	720	720	170	0.17	10.50	70.60	83.20	21	0.08	0.46	140.00	93.00	ECM	1/2	277	1	4.80	46	18.5	26	141	1,2,3,4
FPV	2-1	PRICE	FDC	30	8	880	880	340	0.21	17.00	67.30	85.00	24	0.22	0.83	140.00	98.50	ECM	1/2	277	1	4.80	46	18.5	26	141	1,2,3,4
FPV	2-2	PRICE	FDC	30	10	1160	1160	580	0.24	40.00	65.00	96.80	26	2.33	2.78	140.00	110.80	ECM	1/2	277	1	4.80	46	18.5	26	147	1,2,3,4,7
FPV	2-3	PRICE	FDC	30	10	1060	1060	550	0.21	37.50	64.60	97.20	25	1.98	2.53	140.00	110.00	ECM	1/2	277	1	4.80	46	18.5	26	147	1,2,3,4,7
FPV	2-4	PRICE	FDC	30	10	1060	1060	550	0.21	37.70	64.60	97.40	25	2.03	2.57	140.00	110.30	ECM	1/2	277	1	4.80	46	18.5	26	147	1,2,3,4,7
FPV	2-5	PRICE	FDC	30	10	1060	1060	550	0.21	37.70	64.60	97.40	25	2.03	2.57	140.00	110.30	ECM	1/2	277	1	4.80	46	18.5	26	147	1,2,3,4,7
FPV	2-6	PRICE	FDC	30	10	1180	1180	960	0.25	48.20	58.70	96.40	26	4.04	3.78	140.00	114.10	ECM	1/2	277	1	4.80	46	18.5	26	147	1,2,3,4,7
FPV	2-7	PRICE	FDC	30	10	1150	1150	450	0.3	22.40	66.70	85.70	26	0.43	1.22	140.00	102.80	ECM	1/2	277	1	4.80	46	18.5	26	141	1,2,3,4
FPV	2-8	PRICE	FDC	60	16	2230	2230	1280	0.26	64.40	63.50	90.20	29	1.37	3.18	140.00	98.90	ECM	2@3/4	277	1	12.80	49	21	52	272	1,2,3,6
FPV	2-9	PRICE	FDC	40	10	1550	1550	900	0.39	45.50	63.40	90.40	30	2.35	2.79	140.00	107.00	ECM	3/4	277	1	7.50	46	18.5	26	155	1,2,3,4,7
FPV	2-10	PRICE	FDC	60	16	2350	2350	1370	0.28	69.00	63.30	90.50	30	1.63	3.50	140.00	100.00	ECM	2@3/4	277	1	12.80	49	21	52	272	1,2,3,6
FPV	2-11	PRICE	FDC	40	12	1700	1700	1020	0.45	51.20	63.00	90.80	33	3.39	3.42	140.00	109.70	ECM	3/4	277	1	7.50	46	18.5	26	155	1,2,3,4
FPV	2-12	PRICE	FDC	30	10	1100	1100	560	0.22	38.30	64.80	96.90	26	2.05	2.59	140.00	110.10	ECM	1/2	277	1	4.80	46	18.5	26	147	1,2,3,4

NOTES:
1. PROVIDE STARTER / DISCONNECT PER DIVISION 26 SPECIFICATIONS.
2. REFER TO DETAIL 1/M5.1.
3. REFER TO 7/M7.4 FOR CONTROLS.
4. ALTERNATE BID: INSTALL ONE (1) BIPOLAR IONIZATION UNIT (iAIRE MODEL ION-0AA00, RATED 2000 CFM/EA). INSTALL UNIT ON DISCHARGE DUCTWORK OF VAV BOX. UNIT TO BE POWERED FROM VAV CONTROL BOX.
5. ALTERNATE BID: INSTALL THREE (3) BIPOLAR IONIZATION UNIT (iAIRE MODEL ION-0AA00, RATED 1000 CFM/EA) FOR BLOCK SERVING KITCHEN. INSTALL UNITS ON DISCHARGE DUCTWORK OF VAV BOX. UNIT TO BE POWERED FROM VAV CONTROL BOX.
6. ALTERNATE BID: INSTALL TWO (2) BIPOLAR IONIZATION UNIT (iAIRE MODEL ION-0AA00, RATED 2000 CFM/EA). INSTALL UNIT ON DISCHARGE DUCTWORK OF VAV BOX. UNIT TO BE POWERED FROM VAV CONTROL BOX.
7. PROVIDE 3-WAY VALVES FOR COILS.

AIR TERMINAL SCHEDULE

TAG	MANUFACTURER	MODEL	CFM RANGE	PANEL SIZE (IN)	NECK SIZE (IN)	STYLE	INSTALLATION	FINISH	PRESSURE (IN.)	NC	THROW	NOTES
EA-1	PRICE	80 SERIES	0-180	8X8	-	EGG CRATE	CEILING	WHITE POWDER COAT	0.1	21	-	4,5
EA-2	PRICE	80 SERIES	180-720	16X16	-	EGG CRATE	CEILING	WHITE POWDER COAT	0.1	25	-	4,5
EB-1	PRICE	95 SERIES	0-7500	32X32	-	HEAVY DUTY GYM GRILLE	WALL	WHITE POWDER COAT	0.2	47	-	1,4
ES-1	PRICE	MSRRP	0-110	6X6	-	MAXIMUM SECURITY	CEILING / WALL	WHITE POWDER COAT	0.13	19	-	-
ES-2	PRICE	MSRRP	0-225	10x10	-	MAXIMUM SECURITY	CEILING / WALL	BRUSHED ALUMINUM	0.13	21	-	1
ES-3	PRICE	MSRRP	110-600	16x16	-	MAXIMUM SECURITY	CEILING / WALL	WHITE POWDER COAT	0.13	25	-	1
ES-4	PRICE	MSL	0-3400	24X24	-	MINIMUM SECURITY	CEILING	WHITE POWDER COAT	0.27	34	-	-
ES-P	-	-	-	-	-	-	-	-	-	-	-	3
RA-1	PRICE	80 SERIES	0-650	12X12	-	EGG CRATE	CEILING / DUCT	WHITE POWDER COAT	0.085	20	-	4,5
RA-2	PRICE	80 SERIES	650-2200	22x22	-	EGG CRATE	CEILING	WHITE POWDER COAT	0.132	25	-	4,5
RS-1	PRICE	MSRRP	0-200	9X9	-	MAXIMUM SECURITY	CEILING	WHITE POWDER COAT	0.13	23	-	
RS-2	PRICE	MSL	0-200	8X8	-	MEDIUM SECURITY	CEILING	WHITE POWDER COAT	0.07	18	-	-
RS-3	PRICE	MSRRP	450-800	20X20	-	MAXIMUM SECURITY	CEILING / DUCT / WALL	WHITE POWDER COAT	0.07	19	-	1
RS-4	PRICE	MSRRP	800-1200	24X24	-	MAXIMUM SECURITY	CEILING / WALL	WHITE POWDER COAT	0.07	20	-	1
RS-5	PRICE	MSL	0-2400	24X24	-	MINIMUM SECURITY	CEILING	WHITE POWDER COAT	0.12	22	-	-
SA-1	PRICE	SCD	0-180	24X24	6	SQUARE CONE	CEILING	WHITE POWDER COAT	0.06	15	4	-
SA-2	PRICE	SCD	180-315	24X24	8	SQUARE CONE	CEILING	WHITE POWDER COAT	0.08	22	6	-
SB-1	PRICE	520 SERIES	0-360	16x8	-	LOUVERED FACE	WALL / DUCT	WHITE POWDER COAT	0.062	15	14	1,6
SB-2	PRICE	520 SERIES	360-750	14X12	-	LOUVERED FACE	WALL / DUCT	WHITE POWDER COAT	0.03	24	17	1,6
SB-3	PRICE	520 SERIES	1000-1900	24X24	-	LOUVERED FACE	CEILING	WHITE POWDER COAT	0.016	19	23	-
SL-1	PRICE	SDS WITH SDA PLENUM	0-250	48" LENGTH	7	LINEAR SLOT	CEILING	WHITE POWDER COAT	0.15	27	9 H / 4 V	2
SS-1	PRICE	MSRRCD	50-180	9X9	-	MAXIMUM SECURITY	CEILING	WHITE POWDER COAT	0.18	25	9	7
SS-2	PRICE	MSRRCD	400-800	18X18	-	MAXIMUM SECURITY	CEILING	WHITE POWDER COAT	0.006	27	17	7
SS-3	PRICE	MSD	0-800	18X18	-	MAXIMUM SECURITY	CEILING	WHITE POWDER COAT	0.074	28	10	7
SS-4	PRICE	MSRRCD	0-400	12X12	-	MAXIMUM SECURITY	CEILING / WALL	WHITE POWDER COAT	0.136	27	23	7
SS-P	-	-	-	-	-	-	-	-	-	-	-	3
TA-1	PRICE	80 SERIES	0-650	12X12	-	EGG CRATE	CEILING	WHITE POWDER COAT	0.085	20	-	4,5
TS-1	PRICE	MSRRP	0-400	12x12	-	MAXIMUM SECURITY	CEILING / WALL	WHITE POWDER COAT	0.124	26	-	1
TS-2	PRICE	MSRRP	400-1200	24X24	-	MAXIMUM SECURITY	CEILING	WHITE POWDER COAT	0.031	20	-	1
TS-3	PRICE	MSL	400-1200	18X18	-	MINIMUM SECURITY	CEILING	WHITE POWDER COAT	0.083	20	-	-

NOTES:
1. COLORS AS SELECTED BY ARCHITECT FROM MANUFACTURER'S STANDARD COLOR RANGE FOR WALL MOUNTED AIR TERMINALS.
2. 2 SLOT DIFFUSER WITH 1" SLOT WIDTH. PROVIDE OPTIONAL BUTTERFLY DAMPER WHERE INDICATED ON THE PLANS AND ABOVE INACCESSIBLE CEILINGS TO ALLOW FOR BALANCING AT THE AIR TERMINALS
3. PROVIDED BY PREFABRICATED CELL MANUFACTURER.
4. PROVIDE FRONT OPERATED DAMPER TO ALLOW FOR BALANCING AT THE AIR TERMINALS WHERE INDICATED ON THE PLANS.
5. PROVIDE 45 DEGREE DEFLECTION.
6. PROVIDE 45° DEFLECTION, 3/4" BLADE SPACING
7. REFER TO PLANS FOR THROW DIRECTIONS ON THE AIR TERMINALS.

SHUT-OFF VAV SCHEDULE

TAG		MANUFACTURER	MODEL	SIZE	AIRFLOW (CFM) MAX PRIMARY	MIN PRIMARY	REHEAT	MAX AIR PRESSURE DROP (IN. WG)	COIL CAPACITY (MBH)	AIR TEMPERATURE (°F) ENTERING	LEAVING	WATER PRESSURE DROP (FT WG)	WATER FLOW (GPM)	WATER TEMPERATURE (°F) ENTERING	LEAVING	COIL ROWS	NC	DIMENSIONS (IN) LENGTH	WIDTH	HEIGHT	WEIGHT (LBS)	NOTES
VAV	1-1	PRICE	SDV5	8	570	370	370	0.32	15.40	55	93.30	0.43	1.57	140.00	120.20	2	22	26	12	10	24	1,2
VAV	1-2	PRICE	SDV5	10	980	480	480	0.43	20.5	55	94.30	0.79	1.92	140.00	118.40	2	-	26	14	12.5	30	1,2
VAV	1-3	PRICE	SDV5	8	500	260	260	0.26	10.80	55	93.10	0.12	0.77	140.00	111.80	2	21	26	12	10	24	1,2
VAV	1-4	PRICE	SDV5	8	440	150	150	0.21	6.00	55	91.20	0.02	0.31	140.00	101.20	2	20	26	12	10	24	1,2
VAV	1-5	PRICE	SDV5	8	480	260	260	0.24	8.70	55	92.60	0.06	0.53	140.00	107.20	2	21	26	12	10	24	1,2
VAV	1-6	PRICE	SDV5	6	180	110	110	0.09	4.50	55	91.70	0.01	0.23	140.00	101.90	2	23	26	12	8	20	1,2
VAV	1-7	PRICE	SDV5	6	420	220	220	0.41	9.10	55	92.70	0.08	0.72	140.00	114.50	2	28	21	12	8	12	1,2
VAV	1-8	PRICE	SDV5	6	390	280	280	0.36	7.90	55	93.00	0.06	0.57	140.00	112.00	2	27	26	12	8	20.	1,2
VAV	1-9	PRICE	SDV5	10	1020	500	500	0.45	21.30	55	94.20	0.91	2.08	140.00	119.30	2	-	26	14	12.5	30	1,2
VAV	1-10	PRICE	SDV5	10	800	420	420	0.31	17.70	55	93.70	0.44	1.39	140.00	114.30	2	-	26	14	12.5	30	1,2
VAV	1-11	PRICE	SDV5	8	470	200	200	0.23	5.50	55	93.40	0.02	0.29	140.00	102.10	2	20	26	12	10	24	1,2
VAV	1-13	PRICE	SDV5	4	130	80	80	0.03	3.30	55	91.90	0.41	0.84	140.00	132.20	1	30	28	12	8	19	1,2
VAV	1-14	PRICE	SDV5	4	170	80	80	0.03	3.00	55	88.40	0.14	0.46	140.00	127.40	1	25	28	12	8	19	1,2
VAV	1-18	PRICE	SDV5	6	250	210	210	0.12	7.70	55	91.80	0.05	0.51	140.00	110.00	2	25	26	12	8	20	1,2
VAV	1-19	PRICE	SDV5	6	310	310	310	0.24	6.50	55	92.10	0.03	0.40	140.00	107.40	2	25	26	12	8	20	1,2
VAV	1-20	PRICE	SDV5	6	360	330	330	0.27	7.50	55	92.90	0.05	0.51	140.00	110.70	2	26	26	12	8	20	1,2
VAV	1-21	PRICE	SDV5	6	320	120	120	0.25	6.90	55	107.30	0.13	0.94	140.00	125.30	2	25	26	12	8	20	1,2
VAV	1-25	PRICE	SDV5	12	1300	650	650	0.41	27.40	55.00	93.80	1.41	2.37	140.00	116.60	2	-	26	16	15	37	1,2
VAV	2-13	PRICE	SDV5	6	430	240	240	0.29	10.00	55.00	93.10	0.12	0.88	140.00	117.20	2	26	26	12	8	20	1,2,3
VAV	2-14	PRICE	SDV5	10	780	590	590	0.3	24.90	55.00	93.80	1.79	3.04	140.00	123.40	2	-	26	14	12.5	30	1,2,3

NOTES:
1. REFER TO DETAIL 1/M5.1.
2. REFER TO 1/M7.4 FOR CONTROLS.
3. ALTERNATE BID: INSTALL ONE (1) BIPOLAR IONIZATION UNIT (iAIRE MODEL ION-0AA00, RATED 2000 CFM/EA). INSTALL UNIT ON DISCHARGE DUCTWORK OF VAV BOX. UNIT TO BE POWERED FROM VAV CONTROL BOX.

FAN COIL UNIT SCHEDULE

TAG		MANUFACTURER	MODEL	AREA SERVED	TYPE	CFM	TSP (IN H20)	FILTER	COOLING COIL CAPACITY (MBH) TOTAL	SENSIBLE	ENTERING AIR TEMP (°F) DRY BULB	WET BULB	LEAVING AIR TEMP (°F) DRY BULB	WET BULB	ROW QUANTITY	WATER TEMPERATURE (°F) ENTERING	LEAVING	WATER FLOW (GPM)	MAX WATER PRESSURE DROP (FT WG)	HEATING COIL CAPACITY (MBH)	AIR TEMPERATURE (°F) ENTERING	LEAVING	ROW QUANTITY	WATER TEMPERATURE (°F) ENTERING	LEAVING	WATER FLOW (GPM)	MAX WATER PRESSURE DROP (FT WG)	ELECTRICAL DATA VOLTAGE	PHASE	FREQUENCY (HZ)	FLA	MCA	FUSE (AMP)	EXTERNAL DIMENSIONS (IN) LENGTH (IN)	WIDTH (IN)	HEIGHT (IN)	WEIGHT (LBS)	NOTES
FCU	1	TRANE	FCHB120	VESTIBULE	VERTICAL (RECESSED)	1200	0.5	1" THROW AWAY	26.62	24.38	76	64	57.34	56.63	3	44	58	3.79	4.20	22.12	70	87	1	140	100	1.11	7.12	115	1	60	4.9	6.07	15	78	10	30	253	1,2,3,4,5
FCU	2	TRANE	FCD*080	MECHANICAL ROOM	HORIZONTAL	659	0.4	1" THROW AWAY	16.09	12.81	80	67	59.68	58.41	3	44	58	2.35	2.57	13.02	60	80.57	1	140	120	1.3	0.68	115	1	60	3.1	3.88	15	56	26	10	164	1,2,3,4
FCU	3	TRANE	FCD*080	MECHANICAL ROOM	HORIZONTAL	659	0.4	1" THROW AWAY	16.09	12.81	80	67	59.68	58.41	3	44	58	2.35	2.57	13.02	60	80.57	1	140	120	1.3	0.68	115	1	60	3.1	3.88	15	56	26	10	164	1,2,3,4
FCU	4	TRANE	FCB*080	INTERIOR CHASE	FLOOR	438	0.4	1" THROW AWAY	7.02	7.02	80	67	63.94	62.07	2	44	58	1.01	0.43	11.36	60	84.29	1	140	100	0.57	0.54	115	1	60	3.1	3.88	15	56.25	9.875	25.188	164	1,2,3
FCU	5	TRANE	FCB*080	EXTERIOR CHASE	FLOOR	438	0.4	1" THROW AWAY	7.02	7.02	80	67	63.94	62.07	2	44	58	1.01	0.43	11.36	60	84.29	1	140	100	0.57	0.54	115	1	60	3.1	3.88	15	56.25	9.875	25.188	164	1,2,3
FCU	6	TRANE	FCB*080	EXTERIOR CHASE	FLOOR	438	0.4	1" THROW AWAY	7.02	7.02	80	67	63.94	62.07	2	44	58	1.01	0.43	11.36	60	84.29	1	140	100	0.57	0.54	115	1	60	3.1	3.88	15	56.25	9.875	25.188	164	1,2,3
FCU	7	TRANE	FCB*080	EXTERIOR CHASE	FLOOR	438	0.4	1" THROW AWAY	7.02	7.02	80	67	63.94	62.07	2	44	58	1.01	0.43	11.36	60	84.29	1	140	100	0.57	0.54	115	1	60	3.1	3.88	15	56.25	9.875	25.188	164	1,2,3
FCU	8	TRANE	FCB*080	EXTERIOR CHASE	FLOOR	438	0.4	1" THROW AWAY	7.02	7.02	80	67	63.94	62.07	2	44	58	1.01	0.43	11.36	60	84.29	1	140	100	0.57	0.54	115	1	60	3.1	3.88	15	56.25	9.875	25.188	164	1,2,3
FCU	9	TRANE	FCB*080	INTERIOR CHASE	FLOOR	438	0.4	1" THROW AWAY	7.02	7.02	80	67	63.94	62.07	2	44	58	1.01	0.43	11.36	60	84.29	1	140	100	0.57	0.54	115	1	60	3.1	3.88	15	56.25	9.875	25.188	164	1,2,3

NOTES:
1. PROVIDE STARTER / DISCONNECT PER DIVISION 26 SPECIFICATIONS.
2. REFER TO DETAIL 5/M5.1.
3. REFER TO 2/M7.3 FOR CONTROLS.
4. PROVIDE CONDENSATE PUMP.
5. PROVIDE FRONT STAMPED LOUVER INLET AND OUTLET.

ELECTRIC DUCT HEATER SCHEDULE

TAG		MANUFACTURER	TYPE	EQUIPMENT SERVED	CFM	DESIGN AMBIENT TEMP (F)	TEMP RISE (F)	ELECTRICAL DATA VOLT / PH.	MCA	MOCP	NOTES
EDH	1	THERMOLEC	SC	ERV-1	140	-3	40	208 / 1	14.43	20	1,2,3

NOTES:
1. PROVIDE STARTER / DISCONNECT PER DIVISION 26 SPECIFICATIONS.
2. REFER TO DETAIL 7/ M5.2.
3. REFER TO CONTROL SCHEMATIC 2/M7.1.

DEDICATED OUTDOOR AIR SYSTEM SCHEDULE

TAG		MANF	MODEL	SIZE	SERVING	OUTSIDE AIR CFM	ESP (IN H2O)	WEIGHT (LBS.)	COOLING GROSS TOTAL CAPACITY (MBH)	GROSS SENSIBLE CAPACITY (MBH)	NET TOTAL CAPACITY	NET SENSIBLE CAPACITY	ENTERING AIR TEMPERATURE DB	WB	LEAVING AIR TEMPERATURE DB	WB	HEATING FUEL TYPE	INPUT (MBH)	OUTPUT (MBH)	LEAVING AIR TEMPERATURE DB	WB	ELECTRICAL DATA FAN HP	VOLT	PHASE	HZ	MCA	FLA	MFS	DIMENSIONS LENGTH	WIDTH	HEIGHT	WEIGHT (LBS)	NOTES
DOAS	1	TRANE	HORIZON	OABD - B036	ELECTRICAL	150	1	2901	40.2	21.8	39.7	21.3	93 °F	76 °F	52.9 °F	51.9 °F	NATURAL GAS	50	40	82.8 °F	63.3 °F	6	460	3	60	18	16.3	25	119	52	55	1305	1,2,3,4,5,6

NOTES:
1. PROVIDE STARTER / DISCONNECT PER DIVISION 26 SPECIFICATIONS.
2. MANUFACTURER PROVIDED COMBINATION OUTDOOR AIR SENSOR.
3. MANUFACTURER PROVIDED SMOKE DETECTOR.
4. MANUFACTURER PROVIDED NON-FUSED DISCONNECT SWITCH WITH 115 VOLT OUTLET.
5. MANUFACTURER PROVIDED CONDENSER HAIL GUARD.
6. PROVIDE REMOTE LOCATED DIGITAL DISPLAY PROGRAMMABLE CONTROLLER INTERFACED WITH DDC SYSTEM.

HEAT PUMP INDOOR UNIT SCHEDULE

TAG		MANUFACTURER	MODEL	CFM	MINIMUM OA (CFM)	COOLING CAPACITY (MBH) TOTAL	LAT (F)	HEATING CAPACITY (MBH)	LAT (F)	ELECTRICAL VOLT / PH.	MCA	FUSE AMPS	WEIGHT (LBS.)	NOTES
HPI	1	TRANE / MITSUBISHI	TPLFYP012FM140A	335	60	12	54.4	13.5	90	208 / 1	0.29	15	36.3	1,2,3,4,5
HPI	2	TRANE / MITSUBISHI	TPLFYP012FM140A	335	60	12	54.4	13.5	90	208 / 1	0.29	15	36.3	1,2,3,4,5
HPI	3	TRANE / MITSUBISHI	TPLFYP012FM140A	335	20	12	54.4	13.5	90	208 / 1	0.29	15	36.3	1,2,3,4,5
HPI	4	TRANE / MITSUBISHI	TPKFYP024KM142A	920	-	24	59.2	15.3	84.1	208 / 1	0.63	15	46	1,2,3,4,5

NOTES:
1. PROVIDE THERMOSTAT WITH EACH INDOOR UNIT.
2. PROVIDE CONDENSATE PUMP.
3. PROVIDE SINGLE CENTRAL CONTROLLER.
4. PROVIDE OUTSIDE AIR CONSTANT FLOW REGULATOR SIMILAR TO ALDES CAR3-L-4-R4.
5. REFER TO DETAIL 10/M5.2.

LAUNDRY MAKE UP AIR UNIT

TAG		MANF.	MODEL	SERVING	AIR FLOW DATA CFM	E.S.P.	AIR TEMPERATURE (°F) ENTERING	LEAVING	GAS DATA FUEL TYPE	GAS INPUT (MBH)	GAS OUTPUT (MBH)	MAX GAS PRESSURE (IN WC)	GAS INLET CONNECTION (IN)	ELECTRICAL DATA VOLTAGE	PHASE	HP	DIMENSIONS (IN) LENGTH	WIDTH	HEIGHT	WEIGHT (LBS)	NOTES
LMAU	1	TRANE	GGAA15PFHF0N6BN301A	LAUNDRY	1800	1	-3	55	NATURAL GAS	150	120	0.75	3/4"	460	3	2	78	33	51	566	1,2
LMAU	2	TRANE	GGAA15PFHF0N6BN301A	LAUNDRY	1800	1	-3	55	NATURAL GAS	150	120	0.75	3/4"	460	3	2	78	33	51	566	1,2

NOTES:
1. PROVIDE STARTER (VFD) / DISCONNECT PER DIVISION 26 SPECIFICATIONS.
2. INTERLOCK WITH DRYERS. REFER TO CONTROLS SCHEMATIC 4/M7.1.

EXPANSION TANK SCHEDULE

TAG		MANUFACTURER	MODEL	SYSTEM SERVED	TANK FILL TEMPERATURE	TANK MAX. TEMPERATURE	TANK FILL PRESSURE (PSI)	TANK MAX PRESSURE (PSI)	REQUIRED TANK VOLUME (GAL)	REQUIRED ACCEPTANCE VOLUME (GAL)	TANK ORIENTATION	TANK TYPE	WEIGHT (LBS)	NOTES
ET	1	BELL & GOSSETT	D-60	CHILLED WATER	40 °F	160 °F	12	125	22.77	10.6	HORIZONTAL	DIAPHRAGM	103	1,2
ET	2	BELL & GOSSETT	D-80	HEATED HOT WATER	40 °F	160 °F	12	125	42.92	19.97	HORIZONTAL	DIAPHRAGM	145	1,2

NOTES:
1. TANK TO BE ASME RATED.
2. REFER TO DETAIL 1/M5.3 AND 2/M5.3.

ENERGY RECOVERY VENTILATOR UNIT SCHEDULE

| TAG | | MANUFACTUR