CONSTRUCTION PLANS FOR: KNOX COUNTY JAIL

VINCENNES, KNOX COUNTY, INDIANA

SHEET INDEX: SHEET# SHEET NAME C000 **COVER SHEET** C001 GENERAL NOTES SHEET C100 **EXISTING CONDITIONS/SITE DEMOLITION PLAN** C201 C300 SITE UTILITY PLAN SITE UTILITY PLAN ALTERNATES C301 C400 SITE GRADING PLAN C401 SITE GRADING PLAN ALTERNATES C500 **EROSION CONTROL PLAN** C501 **EROSION CONTROL DETAILS** STORMWATER POLLUTION PREVENTION PLAN C502 **CONSTRUCTION DETAILS**

REVISIONS :		
REVISION #	REVISION DESCRIPTION	DATE
REVISION #1	ADDENDUM #2	02.21.2022

FLOOD NOTE:

THE ACCURACY OF ANY FLOOD HAZARD DATA SHOWN ON THESE PLANS IS SUBJECT TO MAP SCALE UNCERTAINTY AND TO ANY OTHER UNCERTAINTY IN LOCATION OR ELEVATION ON THE REFERENCED FLOOD INSURANCE RATE MAP. THE WITHIN DESCRIBED TRACT OF LAND LIES WITHIN FLOOD HAZARD ZONE B AS SAID TRACT PLOTS BY SCALE ON COMMUNITY PANEL NUMBER 1804220150C DATED 02/15/1985 FOR THE FLOOD INSURANCE RATE MAPS FOR KNOX COUNTY, INDIANA (UNINCORPORATED AREAS).

DISCLAIMER:

EXISTING CONDITIONS/SURVEY INFORMATION PROVIDED BY PROVIDENCE LAND GROUP, LLC. RQAW IS NOT RESPONSIBLE FOR THE ACCURACY OF THE EXISTING CONDITION/SURVEY INFORMATION PROVIDED. CONTRACTOR TO FIELD VERIFY LOCATION AND SIZES OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION AND CONTACT ENGINEER AND OWNER IF DISCREPANCIES OCCUR.

BENCH MARK:

5/8" IRON PIN WITH PLASTIC CAP INSCRIBED "PROVIDENCE LG CONTROL POINT" SET FLUSH + - 68' SOUTHWEST OF STRUCTURE 105 AND + - 189' SOUTHEAST OF STRUCTURE 104.

NORTHING 1,235,642.51 EASTING 2,826,160.69

ELEV. = 416'.69 CP2

5/8" IRON PIN WITH PLASTIC CAP INSCRIBED "PROVIDENCE LG CONTROL POINT" SET FLUSH LOCATED IN AN ISLAND FOR AN ASPHALT PARKING LOT BEING + - 108' WEST OF STRUCTURE 111 AND + - 105' SOUTHEAST OF STRUCTURE 112.

NORTHING 1,235,947.07 EASTING 2,826,527.39 ELEV. = 416'.58



CALL 2 WORKING DAYS BEFORE YOU DIG 1-800-382-5544

CALL TOLL FREE PER INDIANA STATE LAW IC8-1-26. IT IS AGAINST THE LAW TO EXCAVATE WITHOUT NOTIFYING THE UNDERGROUND LOCATION SERVICE TWO (2) WORKING DAYS BEFORE COMMENCING

PLANS PREPARED FOR:

KNOX COUNTY COMMISSIONERS 111 NORTH 7TH STREET VINCENNES, INDIANA 47591 TELEPHONE: (812) 890-2623 CONTACT PERSON: TRENT HINKLE, COMMISSIONER TAHINKLE@KNOXCOUNTY.IN.GOV

PLANS PREPARED BY:

RQAW CORPORATION 8770 NORTH STREET, SUITE 110 FISHERS, INDIANA 46038 TELEPHONE: (317) 588-1798 CONTACT PERSON: CALEB ROTHENBERGER EMAIL: CROTHENBERGER@RQAW.COM



OPERATING AUTHORITIES

CITY JURISDICTION CITY OF VINCENNES 201 VIGO STREET VINCENNES, IN 47591 TELEPHONE: (812) 882-4357 JOHN SPRAGUE, CITY ENGINEER

SANITARY SEWER AUTHORITY VINCENNES WATER UTILITIES 403 BUSSERON ST. VINCENNES, IN 47591 TELEPHONE: (812) 882-7877 STAN ECK, COLLECTIONS SYSTEM MANAGER

GAS SERVICE AUTHORITY CENTERPOINT ENERGY 1 VECTREN SQUARE **EVANSVILLE, IN 47708** TELEPHONE: (800) 227-1376

COMMUNICATIONS NEW WAVE COMMUNICATIONS 102 N 5TH STREET VINCENNES, IN 47591 TELEPHONE: (812) 895-7676

COMMUNICATIONS METRO FIBERNET, LLC 287 N 15TH STREET VINCENNES, IN 47591 TELEPHONE: (812) 255-1155

STORM SEWER AUTHORITY **VINCENNES WATER UTILITIES** 403 BUSSERON ST. VINCENNES, IN 47591 TELEPHONE: (812) 882-7877 HUNTER PINNELL, STORMWATER **MANAGER**


WATER AUTHORITY **VINCENNES WATER UTILITIES** 403 BUSSERON ST. VINCENNES, IN 47591 TELEPHONE: (812) 882-7877 DAVE ABEL

ELECTRICAL/POWER AUTHORITY DUKE ENERGY 1000 E. MAIN ST. PLAINFIELD, IN 46168 TELEPHONE: (800) 521-2232

COMMUNICATIONS SMITHVILLE TELEPHONE 1600 W TEMPERANCE STREET ELLETTSVILLE, IN 47429 TELEPHONE: (812) 876-2211

SITE VICINITY MAP

NOT TO SCALE



SITE LOCATION MAP NOT TO SCALE

C000

Revision ADDENDUM #2 02.21.2022

Project #: 20-700-151-2 Designed By: MSO Drawn By: JLB Checked By: CJR

Date: 12/29/2021

NOT FOR CONSTRUCTION

COVER SHEET

DEMOLITION NOTES

- 1. CLEAR AND GRUB ALL TREES AND VEGETATION NECESSARY FOR CONSTRUCTION.
- 2. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO REMOVE ALL MUD, DIRT, GRAVEL, AND ANY OTHER MATERIALS TRACKED ONTO ANY PUBLIC OR PRIVATE STREETS OR SIDEWALKS. THE CONTRACTOR SHALL USE MEASURES TO CONTROL DUST AT ALL TIMES.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING, OR VERIFYING, THAT ALL PERMITS AND APPROVALS ARE OBTAINED FROM THE RESPECTIVE CITY, COUNTY, AND STATE AGENCIES PRIOR TO STARTING CONSTRUCTION.
- 3. ALL EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO COMMENCING DEMOLITION.
- 4. ENSURE SAFE PASSAGE OF PERSONS AROUND AREAS OF DEMOLITION AND CONSTRUCTION. CONDUCT OPERATIONS TO PREVENT DAMAGE TO ADJACENT STRUCTURES AND OTHER FACILITIES AND INJURY TO PERSONS.
- 5. CONDUCT DEMOLITION AND CONSTRUCTION OPERATIONS TO ENSURE MINIMAL INTERFERENCE WITH STREETS, WALKS, AND OTHER ADJACENT OCCUPIED STRUCTURES.
- 6. ALL UTILITIES TO BE REMOVED SHALL BE DISCONNECTED AND CAPPED AT THE NEAREST CONNECTION POINT UNLESS SPECIFIED OTHERWISE.
- 7. UTILITIES ARE SHOWN TO BE APPROXIMATE. THE CONTRACTOR SHALL COORDINATE WITH RESPECTIVE UTILITY COMPANY(S) FOR THE REMOVAL, RELOCATION, AND/OR DEMOLITION OF ALL EXISTING UTILITIES.
- 8. ALL DEMOLISHED MATERIALS SHALL BE REMOVED AND LEGALLY DISPOSED OF OFF-SITE UNLESS NOTED OTHERWISE.
- 9. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING PROPER DRAINAGE IN DEMOLITION AREAS.
- 10. PROMPTLY REPAIR DAMAGE TO ADJACENT FACILITIES CAUSED BY DEMOLITION AND CONSTRUCTION OPERATIONS AT NO EXTRA TO THE OWNER.
- 11. DEMOLITION ITEMS INCLUDE BUT ARE NOT LIMITED TO DEMOLITION ITEMS INDICATED ON THIS PLAN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO REMOVE OR RELOCATE ITEMS WHICH INTERFERE WITH NEW CONSTRUCTION.
- 12. THE OWNER/DEVELOPER AND/OR CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING QUALITY CONTROL AT ALL TIMES DURING THE CONSTRUCTION PROCESS.
- 13. CONTACT OWNER IMMEDIATELY IF CONTAMINATED SOILS ARE ENCOUNTERED DURING CONSTRUCTION. CONTAMINATED SOILS MUST BE HAULED OFF-SITE AND PROPERLY DISPOSED.

EROSION CONTROL NOTES

- 1. SEE SHEET C501 FOR SOILS MAP AND SOIL CHARACTERISTICS.
- 2. SEE SHEET C502 FOR EROSION CONTROL DETAILS.
- 3. ALL EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO CONSTRUCTION.
- 4. ACCESS TO THE SITE SHALL BE RESTRICTED TO THE TO THE LOCATION AS SHOWN. NO OTHER SITE ACCESS IS AVAILABLE UNLESS THE CONTRACTOR OBTAINS APPROVAL FROM ADJACENT PROPERTY OWNER AND APPROVAL FROM THE CITY OF VINCENNES MS4 OPERATOR.
- 5. SEE EROSION CONTROL SEQUENCE AND IMPLEMENTATION NOTES ON SHEET C501.
- 6. EROSION CONTROL MAINTENANCE SITE TO BE INSPECTED ONCE A WEEK AND AFTER EVERY RAINFALL EVENT. MAKE REPAIRS IMMEDIATELY.
- 7. THE SITE IS NOT LOCATED ON OR ADJACENT TO ANY FLOODWAY/FLOOD PLAIN AREAS.
- 8. EROSION CONTROL MEASURES SHALL BE MAINTAINED THROUGHOUT THE ENTIRE CONSTRUCTION PROCESS AND UNTIL ALL DISTURBED AREAS ARE STABILIZED.
- 9. AREAS THAT WILL BE DISTURBED FOR MORE THAN 15 DAYS SHALL BE STABILIZED IMMEDIATELY WITH TEMPORARY SEEDING. ALL DISTURBED YARD/GRASS AREAS MUST BE STABILIZED WITH PERMANENT SEEDING MEASURES.
- 10. SEE THIS SHEET FOR GENERAL SEEDING AND SURFACE STABILIZATION PROCEDURES.
- 11. CONTRACTOR SHALL IMPLEMENT AND MAINTAIN ADDITIONAL EROSION CONTROL MEASURES AT REQUEST OF LOCAL AND/OR STATE STORMWATER AND EROSION CONTROL INSPECTORS.
- 12. ALL EXCESS CUT FROM SITE TO BE INCORPORATED INTO EXISTING BERMS ON SITE. COORDINATE EXACT LOCATION WITH OWNER. NO CUT TO BE REMOVED FROM SITE.
- 13. THIS PLAN SHALL NOT BE CONSIDERED ALL INCLUSIVE AS THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT SOIL SEDIMENT FROM LEAVING THE SITE.
- 14. SEDIMENT LADEN WATER SHALL BE DETAINED BY EROSION CONTROL PRACTICES AS NEEDED TO MINIMIZE SEDIMENTATION IN RECEIVING WATER. NO STORMWATER SHALL BE DISCHARGED FROM THE SITE IN A MANNER THAT CAUSES EROSION AT THE POINT OF DISCHARGE.
- 15. WASTE AND UNUSED BUILDING MATERIALS SHALL NOT BE ALLOWED TO BE CARRIED FROM THE SITE BY STORMWATER RUNOFF. PROPER DISPOSAL OF ALL WASTE AND UNUSED BUILDING MATERIALS IS REQUIRED.
- 16. PRIOR TO COMPLETION OF THE PROJECT, CONTRACTOR SHALL CLEAN OUT ALL STORM DRAINAGE STRUCTURES AND RESTORE ALL DITCHES AND BASINS TO DESIGNED GRADES.

SITE PLAN NOTES

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING, OR VERIFYING, THAT ALL PERMITS AND APPROVALS ARE OBTAINED FROM THE RESPECTIVE CITY, COUNTY, AND STATE AGENCIES PRIOR TO STARTING CONSTRUCTION.
- 2. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES IN THE VICINITY OF THE CONSTRUCTION AREA PRIOR TO STARTING CONSTRUCTION.
- 3. IT SHALL BE THE CONTRACTORS RESPONSIBILITY FOR NOTIFICATION AND COORDINATION OF ALL CONSTRUCTION WITH RESPECTIVE UTILITY COMPANIES.
- 4. ALL CONSTRUCTION ACTIVITY ON THIS SITE IS TO BE PERFORMED IN COMPLIANCE WITH MOST CURRENT APPLICABLE OSHA STANDARDS FOR WORKER SAFETY.
- 5. ALL RADII AND STREET DIMENSIONS SHALL BE MEASURED TO FACE OF CURB OR FACE OF INTEGRAL CURB AND WALK. ALL DIMENSIONS TO THE BUILDING ARE TO THE OUTSIDE OF BUILDING FOUNDATION WALL.
- 6. EXISTING PAVEMENT TO BE SAW CUT IN ALL AREAS WHERE INDICATED NEW PAVEMENT TO JOIN EXISTING PAVEMENT.
- 7. THE EDGE OF THE EXISTING ASPHALT PAVEMENT SHALL BE PROPERLY SEALED WITH A TACK COAT MATERIAL IN ALL AREAS WHERE NEW ASPHALT PAVEMENT IS INDICATED TO JOIN EXISTING ASPHALT.
- 8. ALL CONSTRUCTION JOINTS SHALL BE SAWN, CLEANED OF DEBRIS, BLOWN DRY AND IMMEDIATELY SEALED WITH THE APPROPRIATE SEALANT ACCORDING TO MANUFACTURER'S DIRECTIONS.
- 9. ALL PARKING STRIPES ARE TO BE 4" WHITE PAINT. ADA PARKING AREAS AND ACCESS AISLES TO BE 4" BLUE PAINT.
- 10. BEARINGS, DIMENSIONS AND EASEMENTS ARE SHOWN FOR REFERENCE ONLY. SEE RECORD SURVEYS AND PLATS FOR EXACT INFORMATION.
- 11. SEE ARCHITECTURAL PLANS FOR DETAILS OF BUILDINGS AND BUILDING DIMENSIONS.
- 12. TEMPORARY TRAFFIC CONTROL DURING CONSTRUCTION TO CONFORM TO APPLICABLE LOCAL STANDARDS. MUTCD AND INDOT SPECIFICATIONS.
- 13. ANY DISCREPANCIES OR CONFLICTS WHICH BECOME APPARENT BEFORE OR DURING CONSTRUCTION SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION OR REDESIGN MAY OCCUR.
- 14. CONTACT ENGINEER IF ADDITIONAL DIMENSIONS ARE NEEDED FOR CONSTRUCTION.
- 15. SEE STRUCTURAL PLANS FOR DETAILS OF CONCRETE STOOPS TO BE CONSTRUCTED OUTSIDE BUILDING AT ENTRY POINTS. ALL STOOPS TO BE 5'X5' UNLESS NOTED OTHERWISE.

UTILITY NOTES

- 1. RIM OR TOP OF CASTING ELEVATION EQUALS THE LOWEST POINT ON THE CASTING WHERE WATER ENTERS THE STRUCTURE OR THE TOP OF A SOLID CASTING.
- 2. PIPE LENGTHS ARE MEASURED FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE OR END OF PIPE END SECTION.
- WATER MAINS THROUGHOUT THE PROJECT SHALL BE INSTALLED WITH AT LEAST 60 INCHES OF COVER FROM
 FINISH GRADE TO TOP OF WATER LINE. CONTRACTOR TO PROVIDE ALL FITTINGS REQUIRED TO ASSURE PROPER
 INSTALLATION OF WATER MAINS AND LATERALS.
- 4. ELECTRICAL CONDUIT SHALL BE INSTALLED AT A MINIMUM OF 36 INCHES BELOW THE FINISH GRADE. ENDS OF THE CONDUIT SHALL BE MARKED BY INSTALLING A 4X4 WOOD POST PAINTED RED.
- 5. LOCATIONS OF EXISTING UNDERGROUND UTILITY LOCATIONS ARE APPROXIMATE. THE CONTRACTOR IS TO FIELD VERIFY ALL HORIZONTAL AND VERTICAL LOCATIONS PRIOR TO CONSTRUCTION.
- 6. ALL 6" SANITARY SEWER LATERALS ARE TO BE CONSTRUCTED WITH SDR-35 PVC @ 1.04% MINIMUM SLOPE UNLESS NOTED OTHERWISE. ALL 8" SANITARY SEWER MAINS SHALL BE CONSTRUCTED OF SDR-35 PVC @ 0.40% MINIMUM SLOPE
- 7. TRACER WIRE IS REQUIRED ON ALL SANITARY SEWER LATERALS.
- 8. SEE CITY OF VINCENNES STANDARDS FOR WATER AND SEWER SPECIFICATIONS.
- 9. CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY COORDINATION WITH LOCAL JURISDICTION AND ALL RESPECTIVE UTILITY COMPANIES FOR GAS, ELECTRIC, TELEPHONE, AND CABLE SERVICES.
- 10. CONTRACTOR IS RESPONSIBLE FOR COORDINATING AND PROVIDING TRAFFIC CONTROL PER LOCAL STANDARDS AND REQUIREMENTS. ALL STREET CUTS SHALL BE REPAIRED PER LOCAL REQUIREMENTS.
- 11. SEE ARCHITECTURAL PLANS FOR DETAILED INFORMATION AND EXACT LOCATIONS FOR UTILITIES COMING INTO THE BUILDING.
- 12. SEE ARCHITECTURAL PLANS FOR EXACT LOCATIONS OF DOWNSPOUTS AND ROOF DRAINS.
- 13. FOR VIEWING CLARITY OF THESE CONSTRUCTION PLANS, PIPES OR STRUCTURES MAY NOT BE SHOWN TO SCALE.
- 14. ALL UTILITY MATERIALS AND INSTALLATION SHALL CONFORM TO LOCAL STANDARDS FOR EACH UTILITY AGENCY HAVING JURISDICTION.
- 15. IN THE EVENT OF A CONFLICT BETWEEN WATER LINES AND STORM DRAINS, THE CONTRACTOR SHALL EITHER ADJUST THE WATER LINE DOWNWARD IN SUCH A MANNER SO THAT THE PIPE MANUFACTURER'S RECOMMENDATIONS ON PIPE DEFLECTION AND JOINT STRESS ARE NOT EXCEEDED OR THE CONTRACTOR SHALL PROVIDE APPROPRIATE BENDS AND CROSSINGS.
- 16. WATER AND SEWER MAIN CROSSINGS SHALL BE IN ACCORDANCE WITH 10 STATE STANDARDS. WATER AND SEWER MAINS SHALL HAVE A MINIMUM HORIZONTAL SEPARATION OF 10 FEET FROM EDGE OF PIPE TO EDGE OF PIPE. WATER PIPES CROSSING ABOVE SEWER PIPES MUST HAVE A MINIMUM VERTICAL SEPARATION OF 18 INCHES CLEARANCE BETWEEN PIPES.
- 17. THE CONTRACTOR SHALL CONTACT ENGINEER FOR ALL QUESTIONS REGARDING UTILITY PLAN DISCREPANCIES AND/OR CONFLICTS IN THE FIELD.

ES GRADING NOTES

- 1. ALL ELEVATIONS AT CONSTRUCTION LIMITS SHALL MATCH EXISTING GRADE.
- 2. TOPSOIL SHALL BE PLACED IN ALL LANDSCAPE AND YARD AREAS WITH A MINIMUM DEPTH OF 6".
- 3. MAINTAIN SITE DRAINAGE AT ALL TIMES DURING EARTHWORK OPERATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY DRAINAGE FACILITIES IF NECESSARY THROUGHOUT CONSTRUCTION.

FILL AREAS FOR PAVEMENTS ARE TO BE STRIPPED OF ALL TOPSOIL PRIOR TO PLACEMENT OF FILL.

- 4. CONTOURS SHOW GRADING INTENT. THE CONTRACTOR MUST USE PROPOSED SPOT GRADE ELEVATIONS AND
- PROFILES TO BUILD SITE. CONTACT ENGINEER IF ADDITIONAL SPOT GRADES ARE NEEDED FOR CONSTRUCTION.

 5. PAVEMENT AREAS SHALL BE CONSTRUCTED OF SUITABLE FILL MATERIAL AND COMPACTED PER SPECIFICATIONS.
- 6. ANY DISCREPANCIES OR CONFLICTS WHICH BECOME APPARENT BEFORE OR DURING CONSTRUCTION SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION
- 7. SEE STORM SEWER PROFILES FOR STORM SEWER INVERT AND RIM ELEVATIONS.
- 8. CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING THAT STAKED GRADES MATCH DESIGN ELEVATIONS AND POSITIVE DRAINAGE TO STORMWATER MANAGEMENT SYSTEM IS ACHIEVED. CONTACT ENGINEER IF DESIGN ELEVATIONS DO NOT PROVIDE POSITIVE DRAINAGE.
- 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING EARTHWORK QUANTITIES AND INCLUDE ANY NECESSARY EXPORT OR IMPORT OF MATERIAL. IMPORT MATERIAL SHALL BE PRE-APPROVED BY THE ENGINEER/ARCHITECT. IT IS THE CONTRACTOR'S RESPONSIBILITY TO REVIEW THE EXISTING CONDITIONS AND INCLUDE IN THEIR BID ALL EARTHWORK COSTS INCLUDING IMPORTS AND/OR EXORTS NECESSARY TO MAKE THE
- 10. CONTRACTOR TO ADJUST ALL EXISTING SURFACE INFRASTRUCTURE (HYDRANTS, VALVES, HANDHOLES, CASTINGS, IRRIGATION SYSTEM, UTILITY PEDESTALS, ETC.) AS REQUIRED TO MEET PROPOSED GRADE AT NO
- 11. PROVIDE POSITIVE DRAINAGE WITHOUT PONDING IN ALL AREAS. AFTER INSTALLATION, CONTRACTOR TO TEST FOR AND CORRECT, IF ANY, STANDING WATER CONDITIONS AT NO COST TO OWNER.
- 12. CONTRACTOR TO PERPETUATE ANY SUBSURFACE DRAIN TILES OR PIPES ENCOUNTERED DURING CONSTRUCTION AND PROVIDE POSITIVE OUTLET TO DOWNSTREAM RECEIVING SYSTEM. CONTRACTOR TO NOTIFY THE ENGINEER WITH ANY CIRCUMSTANCES WHERE THIS CANNOT BE ACCOMPLISHED.



/ CIVII

BID SET ARD OF COMMISSIONER

0

KNOX

KNOX COUNTY JUSTICE

0

<u> </u>	Revision	Date
	ADDENDUM #2	02.21.2022

Project #: 20-700-151-2

Designed By: MSO


Drawn By: JLB

Date: 12/29/2021

Checked By: CJR

NOT FOR CONSTRUCTION

GENERAL NOTES





COUNTY BOARD OF COMMISSIONERS

OX COUNTY JUSTICE CAMPUS

BID

Revision Date
ADDENDUM #2 02.21.2022

Project #: 20-700-151-2

KNOX


Designed By: MSO

Drawn By: JLB

Checked By: CJR


Date: 12/29/2021

NOT FOR CONSTRUCTION





SITE DEMOLITION PLAN





COMMISSIONERS BOARD KNOX COUNTY KNOX

SET

BID

Revision

ADDENDUM #2 02.21.2022

Date


Project #: 20-700-151-2

Designed By: MSO


Drawn By: JLB

Date: 12/29/2021

NOT FOR CONSTRUCTION



SITE LAYOUT PLAN





KNOX COUNTY BOARD OF COMMISSIONERS KNOX COUNTY JUSTICE CAMPUS

Revision Date

1 ADDENDUM #2 02.21.2022

Project #: 20-700-151-2


Designed By: MSO

Drawn By: JLB

Checked By: CJR

Date: 12/29/2021

NOT FOR CONSTRUCTION



SITE UTILITY PLAN





PLAN ALTERNATE NOTES

ALL WORK SHOWN AND NOTED SHALL BE BID AS PART OF THE RESPECTIVE ALTERNATE IT IS ASSOCIATED WITH. ALTERNATE BID SHOULD INCLUDE ANY REDUCTION OF COST DUE TO BASE BID
WORK BEING MADE OBSOLETE BY THE ALTERNATE SCOPE OF

REFER TO OTHER DISCIPLINES FOR COORDINATION OF ASSOCIATED ALTERNATES. (ARCHITECTURE, STRUCTURAL, MEP)
REFER TO GRADING AND DRAINAGE PLANS FOR COORDINATION







ARD

#	Revision	Date
1	ADDENDUM #2	02.21.2022


Project #: 20-700-151-2 Designed By: MSO

Drawn By: JLB


Date: 12/29/2021

Checked By: CJR

NOT FOR CONSTRUCTION



UTILITY PLAN ALTERNATES





	INVER		RT CASTIN		ING STRU		JCTURE	
	MARK	INLET	OUTLET	ELEVATION	TYPE	TYPE	DETAIL	
	STR-1	409.00 W 409.75 NW	409.00	413.75	R2554	INLET	C602	
	STR-2	409.50± NW 411.50 SW	409.50	413.75	R2554	INLET	C602	
<u> </u>	STR-3		409.90	413.90	R2554	INLET	C602	
	STR-4	411.15	410.65	414.25	R2554	INLET	C602	
	EXISTING 107	-	-	413.63	R3405	INLET	C602	

GENERAL NOTES

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING, AND VERIFYING, THAT ALL PERMITS AND APPROVALS ARE OBTAINED FROM THE RESPECTIVE CITY, COUNTY, STATE AND FEDERAL AGENCIES PRIOR TO STARTING CONSTRUCTION.
- CONTRACTOR SHALL VERIFY LOCATION AND INVERT ELEVATIONS OF EXISTING SEWERS PRIOR TO START OF CONSTRUCTION.
- CONTRACTOR SHALL MAINTAIN A COMPLETE AND OPERABLE UTILITY SYSTEM AT ALL
- CONTRACTOR SHALL INCLUDE COSTS FOR CUTTING AND PATCHING AS REQUIRED IN THEIR BID PROPOSAL TO COMPLETELY INSTALL THE WORK INDICATED.
- EXISTING CONDITIONS AND IS UNCONFIRMED. CONTRACTOR IS REQUIRED TO FIELD VERIFY THIS INFORMATION AND NOTIFY ARCHITECT OF ANY DISCREPANCIES SO
- CONTRACTOR SHALL COORDINATE EXACT UTILITY LOCATIONS WITH THE OWNER AND LOCAL UTILITY COMPANIES PRIOR TO COMMENCING ANY WORK. UTILIZE THE INDIANA UNDERGROUND UTILITY LOCATION SERVICE AT 811 OR 800-382-5544 PRIOR TO ANY
- G. ALL EXCESS EARTHWORK CUT FROM SITE TO BE DEPOSITED AND INCORPORATED INTO EXISTING BERMS ON SITE. NO EXCESS EARTHWORK TO BE HAULED OFF SITE. COORDINATE EXACT LOCATION WITH OWNER. REFER TO PLAN FOR LOCATION OF BERMS.

GENERAL NOTES

- REFER TO UTILITY DETAILS FOR NOTE REFERENCES.
- ALL CASTINGS SHALL HAVE THE WORDS 'NO DUMPING DRAINS TO STREAM" CAST IN RAISED OR RECESSED LETTERS AT A MINIMUM OF 1" HEIGHT. A SYMBOL OF A FISH SHALL ALSO BE
- CAST WITH THE LETTERS.
 CASTINGS TO BE NEENAH TYPE OR APPROVED EQUAL.
 CONTRACTOR TO VERIFY LOCATIONS AND ELEVATIONS OF EXISTING UTILITIES PRIOR TO THE
- START OF CONSTRUCTION.

O PLAN NOTES

- 1. DOWNSPOUT ADAPTER. REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATION.
- COORDINATE SIZE, LOCATION AND ELEVATION OF PIPING AND CONTINUATION INSIDE BUILDING WITH PLUMBING PLANS.

Know what's below.

Call before you dig.

Project #: 20-700-151-2

Drawn By: JLB

Checked By: NBV

Designed By: NBV

Date: 01/28/2022



SITE GRADING & DRAINAGE PLAN

Designed By: NBV Drawn By: JLB

Checked By: NBV Date: 01/28/2022




ALTERNATES GRADING & DRAINAGE PLAN

Know what's below.


Call before you dig.

O PLAN NOTES

- 1. DOWNSPOUT ADAPTER. REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATION.
- 2. COORDINATE SIZE, LOCATION AND ELEVATION OF PIPING AND CONTINUATION INSIDE BUILDING WITH PLUMBING PLANS.
- 3. 8" HDPE ROOF DRAIN PIPING SYSTEM AT MINIMUM 0.50% SLOPE OR AS NOTED. CONNECT DOWNSPOUTS TO PIPING WHERE INDICATED.




2 ALTERNATE D- GRADING PLAN
SCALE: 1"=20"



414.04 × 414

1 ALTERNATE A- GRADING PLAN
SCALE: 1"=20"






COMMISSIONERS ARD

#	Revision	Date
1	ADDENDUM #2	02.21.2022

Designed By: MSO Drawn By: JLB Checked By: CJR

NOT FOR CONSTRUCTION



EROSION CONTROL PLAN

INSTALLATION:

MAINTENANCE:

PREFABRICATED WASHOUT SYSTEMS/CONTAINERS:

DESIGNED AND INSTALLED SYSTEMS:

OVERFLOW OF THE SYSTEM (OPTIONAL).

11. INSPECT DAILY AND AFTER EACH STORM EVENT.

FOR RECYCLING SHOULD BE CHECKED LOCALLY.

SYSTEM OR BASIN FOR FURTHER DEWATERING.

USED TO CONSTRUCT THE SYSTEM.

8. INSTALL SIGNAGE THAT IDENTIFIES CONCRETE WASHOUT AREAS.

9. POST SIGNS DIRECTING CONTRACTORS AND SUPPLIERS TO DESIGNATED LOCATIONS.

13. INSPECT THE SYSTEM FOR LEAKS, SPILLS, AND TRACKING OF SOIL BY EQUIPMENT.

15. ONCE CONCRETE WASTES HARDEN, REMOVE AND DISPOSE OF THE MATERIAL.

14. INSPECT THE POLYETHYLENE LINING FOR FAILURE, INCLUDING TEARS AND PUNCTURES.

1. INSTALL AND LOCATE ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

2. UTILIZE AND FOLLOW THE DESIGN IN THE STORM WATER POLLUTION PREVENTION PLAN TO INSTALL THE SYSTEM. 3. DEPENDENT UPON THE TYPE OF SYSTEM. FITHER EXCAVATE THE PIT OR INSTALL THE CONTAINMENT SYSTEM.

12. INSPECT THE INTEGRITY OF THE OVERALL STRUCTURE INCLUDING, WHERE APPLICABLE, THE CONTAINMENT SYSTEM.

22.PREFABRICATED UNITS ARE OFTEN PUMPED AND THE COMPANY SUPPLYING THE UNIT PROVIDES THIS SERVICE.

BEING DISPOSED OF IMPROPERLY, IDENTIFY THE VIOLATORS AND TAKE APPROPRIATE ACTION.

NOT TO SCALE

6. PLACE FLAGS, SAFETY FENCING, OR EQUIVALENT TO PROVIDE A BARRIER TO CONSTRUCTION EQUIPMENT AND OTHER TRAFFIC.

10. WHERE NECESSARY, PROVIDE STABLE INGRESS AND EGRESS OR ALTERNATIVE APPROACH PAD FOR CONCRETE WASHOUT SYSTEMS.

17. UPON REMOVAL OF THE SOLIDS, INSPECT THE STRUCTURE. REPAIR THE STRUCTURE AS NEEDED OR CONSTRUCT A NEW SYSTEM.

19. THE PLASTIC LINER SHOULD BE REPLACED AFTER EVERY CLEANING; THE REMOVAL OF MATERIAL WILL USUALLY DAMAGE THE LINING. 20. THE CONCRETE WASHOUT SYSTEM SHOULD BE REPAIRED OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE WASTE.

25. HOLES, DEPRESSIONS AND OTHER LAND DISTURBANCES ASSOCIATED WITH THE SYSTEM SHOULD BE BACKFILLED, GRADED, AND STABILIZED.

GENERAL STAPLE RECOMMENDATIONS

CONCRETE WASHOUT DETAIL

CONCRETE WASHOUT (ABOVE GRADE)

4. A BASE SHALL BE CONSTRUCTED AND PREPARED THAT IS FREE OF ROCKS AND OTHER DEBRIS THAT MAY CAUSE TEARS OR PUNCTURES IN THE POLYETHYLENE LINING.

5. INSTALL THE POLYETHYLENE LINING. FOR EXCAVATED SYSTEMS, THE LINING SHOULD EXTEND OVER THE ENTIRE EXCAVATION. THE LINING FOR BERMED SYSTEMS SHOULD BE INSTALLED OVER THE POOLING AREA WITH ENOUGH MATERIAL TO EXTEND THE LINING OVER THE BERM OR CONTAINMENT SYSTEM. THE LINING SHOULD BE SECURED WITH PINS, STAPLES, OR OTHER

7. PLACE A NON-COLLAPSING, NON-WATER HOLDING COVER OVER THE WASHOUT FACILITY PRIOR TO A PREDICTED RAINFALL EVENT TO PREVENT ACCUMULATION OF WATER AND POSSIBLE

16. EXCESS CONCRETE SHOULD BE REMOVED WHEN THE WASHOUT SYSTEM REACHES 50 PERCENT OF THE DESIGN CAPACITY. USE OF THE SYSTEM SHOULD BE DISCONTINUED UNTIL

18. DISPOSE OF ALL CONCRETE IN A LEGAL MANNER. REUSE THE MATERIAL ON SITE, RECYCLE, OR HAUL THE MATERIAL TO AN APPROVED CONSTRUCTION/DEMOLITION LANDFILL SITE.

APPROPRIATE MEASURES CAN BE INITIATED TO CLEAN THE STRUCTURE. PREFABRICATED SYSTEMS SHOULD ALSO UTILIZE THIS CRITERION, UNLESS THE MANUFACTURER HAS ALTERNATE

RECYCLING OF MATERIAL IS ENCOURAGED. THE WASTE MATERIAL CAN BE USED FOR MULTIPLE APPLICATIONS INCLUDING BUT NOT LIMITED TO ROADBEDS AND BUILDING. THE AVAILABILITY

21. CONCRETE WASHOUT SYSTEMS ARE DESIGNED TO PROMOTE EVAPORATION. HOWEVER, IF THE LIQUIDS DO NOT EVAPORATE AND THE SYSTEM IS NEAR CAPACITY IT MAY BE NECESSARY TO VACUUM OR REMOVE THE LIQUIDS AND DISPOSE OF THEM IN AN ACCEPTABLE METHOD. DISPOSAL MAY BE ALLOWED AT THE LOCAL SANITARY SEWER AUTHORITY PROVIDED THEIR NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMITS ALLOW FOR ACCEPTANCE OF THIS MATERIAL. ANOTHER OPTION WOULD BE TO UTILIZE A SECONDARY CONTAINMENT

23.INSPECT CONSTRUCTION ACTIVITIES ON A REGULAR BASIS TO ENSURE SUPPLIERS, CONTRACTORS, AND OTHERS ARE UTILIZING DESIGNATED WASHOUT AREAS. IF CONCRETE WASTE IS

24.WHEN CONCRETE WASHOUT SYSTEMS ARE NO LONGER REQUIRED, THE CONCRETE WASHOUT SYSTEMS SHALL BE CLOSED. DISPOSE OF ALL HARDENED CONCRETE AND OTHER MATERIALS

SILT FENCE

INSTALLATION

INSTALLED PARALLEL TO THE SLOPE CONTOUR

<u>LOCATION</u>

INSPECT WITHIN 24 HOURS OF A RAIN EVENT AND AT LEAST ONCE EVERY SEVEN CALENDAR

MINIMUM 10 FEET BEYOND THE TOE OF SLOPE TO PROVIDE A BROAD, SHALLOW SEDIMENT

1. LAYOUT THE LOCATION OF THE FENCE SO THAT IT IS PARALLEL TO THE CONTOUR OF THE SLOPE AND AT LEAST 10 FEET BEYOND THE TOE OF THE SLOPE TO PROVIDE A SEDIMENT STORAGE AREA. TURN THE ENDS OF THE FENCE UP SLOPE SUCH THAT THE POINT OF CONTACT BETWEEN THE GROUND AND THE BOTTOM OF THE FENCE END TERMINATES AT A

2. EXCAVATE AN EIGHT-INCH DEEP BY FOUR-INCH WIDE TRENCH ALONG THE ENTIRE LENGTH OF

3. INSTALL THE SILT FENCE WITH THE FILTER FABRIC LOCATED ON THE UP-SLOPE SIDE OF THE

5. LAY THE LOWER FOUR INCHES OF FILTER FABRIC ON THE BOTTOM OF THE TRENCH AND

EXCAVATED TRENCH AND THE SUPPORT POSTS ON THE DOWN-SLOPE SIDE OF THE TRENCH. 4. DRIVE THE SUPPORT POSTS AT LEAST 18 INCHES INTO THE GROUND, TIGHTLY STRETCHING THE

FABRIC BETWEEN THE POSTS AS EACH IS DRIVEN INTO THE SOIL. A MINIMUM OF 12 INCHES

OF THE FILTER FABRIC SHOULD EXTEND INTO THE TRENCH. (IF IT IS NECESSARY TO JOIN THE

ACCESSIBLE FOR MAINTENANCE (REMOVAL OF SEDIMENT AND SILT FENCE REPAIR)

HIGHER ELEVATION THAN THE TOP OF THE FENCE AT ITS LOWEST POINT.


THE FENCE LINE. INSTALLATION BY PLOWING IS ALSO ACCEPTABLE.

ENDS OF THE TWO FENCE, USE THE WRAP JOINT METHOD SHOWN.)

6. BACKFILL THE TRENCH WITH SOIL MATERIAL AND COMPACT IT IN PLACE.

EXTEND IT TOWARD THE UP-SLOPE SIDE OF THE TRENCH.

- IF FABRIC TEARS, STARTS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED PORTION IMMEDIATELY. NOTE: ALL REPAIRS SHOULD MEET SPECIFICATIONS AS
- REMOVE DEPOSITED SEDIMENT WHEN IT IS CAUSING THE FILTER FABRIC TO BULGE OR WHEN IT REACHES ONE-HALF THE HEIGHT OF THE FENCE AT ITS LOWEST POINT. WHEN CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE THE FENCE AND SEDIMENT DEPOSITS, GRADE THE SITE TO BLEND WITH THE SURROUNDING AREA, AND STABILIZE.



SILT FENCE DETAIL

NOT TO SCALE

(COMP. BACKFILL)

GRADE AND APPLY SOIL AMENDMENTS.

ULTRAVIOLET AND HEAT EXPOSURE

SEEDING FREQUENCY SEED ROUGH GRADED AREAS DAILY WHILE SOIL IS STILL LOOSE AND MOIST.

DENSITY OF VEGETATIVE COVER EIGHTY PERCENT OR GREATER OVER THE SOIL SURFACE.

 SOIL AMENDMENTS — SELECT MATERIALS AND RATES AS DETERMINED BY A SOIL TEST (CONTACT YOUR COUNTY SOIL AND WATER CONSERVATION DISTRICT OR COOPERATIVE EXTENSION OFFICE FOR ASSISTANCE AND SOIL INFORMATION, INCLUDING AVAILABLE SOIL TESTING SERVICES) OR 400 TO 600 POUNDS OF 12-12-12 ANALYSIS FERTILIZER, OR EQUIVALENT. CONSIDER THE USE OF REDUCED PHOSPHOROUS APPLICATION WHERE SOIL TESTS INDICATE ADEQUATE PHOSPHOROUS LEVELS IN THE SOIL PROFILE.

 SEED - SELECT APPROPRIATE PLANT SPECIES SEED OR SEED MIXTURES ON THE BASIS OF QUICK GERMINATION, GROWTH, AND TIME OF YEAR TO BE SEEDED (SEE TABLE 1). ANCHORING MULCH — STRAW, HAY, WOOD FIBER, ETC. (TO PROTECT SEEDBED, RETAIN MOISTURE, AND ENCOURAGE PLANT GROWTH). ANCHORED TO PREVENT REMOVAL BY WIND OR WATER OR COVERED WITH MANUFACTURED EROSION CONTROL BLANKETS.

TABLE 1. SLOPE STEEPNESS RESTRICTIONS							
SEED SPECIES*	RATE PER ACRE	PLANTING DEPTH	OPTIMUM DATES**				
WHEAT OR RYE	150 LBS.	1 TO 1-1/2 INCHES	SEPT. 15-0CT. 30				
SPRING OATS	100 LBS.	1 INCH	MARCH 1-APRIL 15				
ANNUAL RYEGRASS	40 LBS.	1/4 INCH	MARCH 1-MAY 1 AUG. 1-SEPT. 1				
GERMAN MILLET	40 LBS.	1 TO 2 INCHES	MAY 1-JUNE 1				
SUDANGRASS	35 LBS.	1 TO 2 INCHES	MAY 1-JULY 30				
BUCKWHEAT	60 LBS.	1 TO 2 INCHES	APRIL 15-JUNE 1				
CORN (BROADCAST)	300 LBS.	1 TO 2 INCHES	MAY 11-AUG. 10				

SORGHUM 35 LBS. 1 TO 2 INCHES MAY 1-JULY 15 *PERENNIAL SPECIES MAY BE USED AS A TEMPORARY COVER. ESPECIALLY IF THE AREA T BE SEEDED WILL REMAIN IDLE FOR MORE THAN ONE YEAR. **SEEDING DONE OUTSIDE THE OPTIMUM SEEDING DATES INCREASES THE CHANCES OF SEEDING FAILURE. DATES MAY BE EXTENDED OR SHORTENED BASED ON THE LOCATION OF THE PROJECT WITHIN THE STATE.

MULCH ALONE IS AN ACCEPTABLE TEMPORARY COVER AND MAY BE USED IN LIEU OF TEMPORARY SEEDING, PROVIDED THAT IT IS APPROPRIATELY ANCHORED.

A HIGH POTENTIAL FOR FERTILIZER, SEED, AND MULCH TO WASH EXISTS ON STEEP BANKS, CUTS, AND IN CHANNELS AND AREAS OF CONCENTRATED FLOW.

SEEDING APPLICATION SEEDBED PREPARATION

- STAINLESS STEEL

GEOTEXTILE FILTER

FABRIC (INNER LAYER)

BAND (HEMMED INTO

. TEST SOIL TO DETERMINE PH AND NUTRIENT LEVELS. 2. APPLY SOIL AMENDMENTS AS RECOMMENDED BY THE SOIL TEST. IF TESTING IS NOT DONE, APPLY 400 TO 600 POUNDS PER ACRE OF 12-12-12 ANALYSIS FERTILIZER, OR 3. WORK THE SOIL AMENDMENTS INTO THE UPPER TWO TO FOUR INCHES OF THE SOIL WITH A DISK OR RAKE OPERATED ACROSS THE SLOPE.

1. SELECT A SEED SPECIES OR AN APPROPRIATE SEED MIXTURE AND APPLICATION RATE 2. APPLY SEED UNIFORMLY WITH A DRILL OR CULTIPACKER SEEDER OR BY BROADCASTING. • CHECK FOR EROSION OR MOVEMENT OF MULCH; REPAIR DAMAGED AREAS, RESEED, PLANT OR COVER SEED TO THE DEPTH SHOWN IN TABLE 1.

IF DRILLING OR BROADCASTING THE SEED, ENSURE GOOD SEED-TO-SOIL CONTACT BY FIRMING THE SEEDBED WITH A ROLLER OR CULTIPACKER AFTER COMPLETING SEED OPERATIONS. DAILY SEEDING WHEN THE SOIL IS MOIST IS USUALLY MOST EFFECTIVE. IF SEEDING IS DONE WITH A HYDROSEEDER, FERTILIZER AND MULCH CAN BE

3. APPLY MULCH AND ANCHOR IT IN PLACE. SEEDING MAINTENANCE

• INSPECT WITHIN 24 HOURS OF EACH RAIN EVENT AND AT LEAST ONCE EVERY SEVEN

APPLIED WITH THE SEED IN A SLURRY MIXTURE.

CALENDAR DAYS. CHECK FOR EROSION OR MOVEMENT OF MULCH AND REPAIR IMMEDIATELY.

 MONITOR FOR EROSION DAMAGE AND ADEQUATE COVER (80 PERCENT DENSITY); RESEED, FERTILIZE, AND APPLY MULCH WHERE NECESSARY. IF NITROGEN DEFICIENCY IS APPARENT, TOP-DRESS FALL SEEDED WHEAT OR RYE SEEDING WITH 50 POUNDS PER ACRE OF NITROGEN IN FEBRUARY OR MARCH.

TABLE 1. SLOPE STEEPNESS RESTRICTIONS

MATERIAL*	RATE PER ACRE	COMMENTS
STRAW OR HAY	2 TONS	SHOULD BE DRY, FREE OF UNDESIRABLE SEEDS. SPREAD BY HAND OR MACHINE. MUST BE CRIMPED OR ANCHORED (SEE TABLE 2).
WOOD FIBER OR CELLULOSE	1 TON	APPLY WITH A HYDRAULIC MULCH MACHINE AND USE WITH TACKING AGENT.

*MULCHING IS NOT RECOMMENDED IN CONCENTRATED FLOWS. CONSIDER EROSION CONTROL BLANKETS OR OTHER STABILIZATION METHODS.

• THE MULCH SHOULD HAVE A UNIFORM DENSITY OF AT LEAST 75 PERCENT OVER

TABLE 2. MULCH ANCHORING METHODS

	TABLE 2. MULCH ANCHURING METHOL	75
	ANCHORING METHOD*	HOW TO APPLY
	MULCH ANCHORING TOOL OR FARM DISK (DULL, SERRATED, AND BLADES SET STRAIGHT)	CRIMP OR PUNCH THE STRAW OR HAY TWO TO FOUR INCHES INTO THE SOIL. OPERATE MACHINERY ON THE CONTOUR OF THE SLOPE.
	CLEATING WITH DOZER TRACKS	OPERATE DOZER UP AND DOWN SLOPE TO PREVENT FORMATION OF RILLS BY DOZER CLEATS.
	WOOD HYDROMULCH FIBERS	APPLY ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
	SYNTHETIC TACKIFIERS, BINDERS, OR SOIL STABILIZERS	APPLY ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
0	NETTING (SYNTHETIC OR BIODEGRADABLE MATERIAL)	INSTALL NETTING IMMEDIATELY AFTER APPLYING MULCH. ANCHOR NETTING WITH STAPLES. EDGES OF NETTING STRIPS SHOULD OVERLAP WITH EACH UP—SLOPE STRIP OVERLAPPING FOUR TO SIX INCHES OVER THE ADJACENT DOWN—SLOPE STRIP. BEST SUITED TO SLOPE APPLICATIONS. IN MOST INSTANCES, INSTALLATION DETAILS ARE SITE SPECIFIC, SO MANUFACTURER'S RECOMMENDATIONS SHOULD BE FOLLOWED.

*ALL FORMS OF MULCH MUST BE ANCHORED TO PREVENT DISPLACEMENT BY WIND AND/OR WATER.

MULCH APPLICATION

1. APPLY MULCH AT THE RECOMMENDED RATE SHOWN IN TABLE 1. SPREAD THE MULCH MATERIAL UNIFORMLY BY HAND, HAYFORK, MULCH BLOWER, OR HYDRAULIC MULCH MACHINE. AFTER SPREADING, NO MORE THAN 25 PERCENT OF THE

GROUND SHOULD BE VISIBLE. ANCHOR STRAW OR HAY MULCH IMMEDIATELY AFTER APPLICATION. THE MULCH CAN BE ANCHORED USING ONE OF THE METHODS LISTED BELOW:

a. CRIMP WITH A MULCH ANCHORING TOOL, A WEIGHTED FARM DISK WITH DULL SERRATED BLADES SET STRAIGHT, OR TRACK CLEATS OF A BULLDOZER,

b. APPLY HYDRAULIC MULCH WITH SHORT CELLULOSE FIBERS, c. APPLY A LIQUID TACKIFIER, OR

d. COVER WITH NETTING SECURED BY STAPLES.

MULCH MAINTENANCE

• INSPECT WITHIN 24 HOURS OF EACH RAIN EVENT AND AT LEAST ONCE EVERY SEVEN CALENDAR DAYS. APPLY NEW MULCH AND ANCHOR THE MULCH IN PLACE.

• CONTINUE INSPECTIONS UNTIL VEGETATION IS FIRMLY ESTABLISHED. IF EROSION IS SEVER OR RECURRING, USE EROSION CONTROL BLANKETS OR OTHER MORE SUBSTANTIAL STABILIZATION METHODS TO PROTECT THE AREA.

TEMPORARY SEEDING

NOT TO SCALE

#	Revision	Date
1	ADDENDUM #2	02.21.202

Project #: 20-700-151-2


Designed By: MSO Drawn By: JLB

Checked By: CJR

Date: 12/29/2021

NOT FOR CONSTRUCTION

EROSION CONTROL DETAILS



MAINTENANCE:

NOTE: CONTRACTOR TO USE FLEXSTORM CATCH-IT INLET PROTECTOR, DANDY BAG OR APPROVED ALTERNATE.

DROP BAG INLET PROTECTION

NOT TO SCALE

• REMOVE ALL ACCUMULATED SEDIMENT AFTER EACH STORM EVENT. DISPOSE OF SEDIMENT IN

LIFT THE UNIT OUT OF THE INLET BY USING THE LIFTING STRAPS AND REMOVE THE GRATE. • WHEN CONTRIBUTING DRAINAGE AREA HAD BEEN STABILIZED, REMOVE INLET PROTECTION.

AN AREA WHERE IT WILL NOT REENTER THE PAVED AREA OR STORM DRAINS. TO EMPTY UNIT,

The following materials may be staged or stored on site at various points during construction:

4. Precast concrete, HDPE, or PVC drainage and sanitary structures

1. Structural fill 2. Pavement base stone

3. HDPE, PVC, RCP, or Ductile Iron Pipe

The property is located approximately 0.35 miles north and 0.4 miles west of the intersection of E. Elkhorn Rd and S Decker Rd in All parties defined as owners must submit a Notice of Intent (NOI) at least 48 hours prior to commencement of on-site construction discharges that occur after permit coverage is granted. Unpermitted discharges may be subject to enforcement actions by the EPA. 1) The party has operational control over the construction plans and specifications, including the ability to make modifications to 2) The party has day-to-day operational control of those activities at a project that are necessary to ensure compliance with a The project consists of the construction of a XXX,XXX square foot (type) building, asphalt parking lots and drives, and (other items?). Stormwater drainage from the site will be conveyed via sheet flow, storm sewer, and vegetated swales to an on-site dry detention The project site is located within Zone B as indicated on the Knox County, IN (Unincorporated Areas) Flood Insurance Rate Map The Natural Resources Conservation Service (NRCS) Web Soil Survey of Knox County, Indiana indicates (Brookston silty clay loam The on-site soil will be treated as recommended by the geotechnical engineer if the conditions are unsuitable for the proposed Excess soil shall be immediately stockpiled, surrounded with silt fence, and seeded where indicated in grading plan in accordance

B2 SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION RELATIVE TO LAND-DISTURBING ACTIVITIES 1. The exact locations of all existing utilities within the project limits are to verified prior to construction. 2. Schedule pre-construction meeting with local stormwater authority 48 hours prior to start of construction. 3. Install protection fencing for existing trees to remain in place within the project limits

Construction Site Access 1. Install gravel construction entrance 2. Post the NOI and contact information at the construction entrance. NOI to remain posted for duration of the project. 3. Install construction staging pads, fueling station, material storage areas, concrete washout, construction parking areas, and stabilize construction routes

1. Utilize the gravel construction entrance for installation of the perimeter silt fence. Add stone if needed. Initial Land Clearing and Grading Activities 1. Add protection measures to existing inlets 2. Strip the topsoil and stabilize the topsoil stockpile.

1. Begin site grading/construction of detention basins (if applicable) and stabilize any soil stockpiles that will be left dormant for more than 10 days 2. Complete the cut and fills on the site. Final grade and seed the pond slopes (if applicable). Stabilize slopes with erosion

control blanket. 3. Install storm sewer system and install inlet protection immediately upon complete of the inlet and install rip-rap outlet protection prior to installing outlets.

1. Apply temporary seeding and stabilize slopes in areas where rough grading has been completed. 2. Apply permanent seeding and stabilize slopes in areas where final grading has been completed.

1. Prior to building construction install stone surface for paved areas. 2. Building pads left dormant for more than 10 days, must be temporarily seeded. 3. Start building construction. Install staging area for building materials and stabilize.

1. Utilize topsoil salvage in applicable areas and apply permanent seeding. 2. Apply permanent seeding around the perimeter of the site. 3. Complete utility installation, curbs, paving, and building construction. 4. Install landscaping plant material and stabilize all disturbed areas. 5. Remove all erosion and sediment control practices when areas have a uniform grass cover.

B3 STABLE CONSTRUCTION ENTRANCE LOCATIONS AND SPECIFICATIONS Construction entrances will be in place prior to any site construction or demolition. Entrances are shown on the Erosion Control

Plan. Refer to the Erosion Control Details for details. B4 SEDIMENT CONTROL MEASURES FOR SHEET FLOW AREAS

Sheet flow areas will be protected by seed and mulch or hydroseeding. Erosion control blankets will be installed on sloped areas where the slope exceeds 4:1 (horizontal to vertical). Silt fencing will be utilized to prevent sedimentation from leaving the site. Refer to the Erosion Control Plan for locations and the Erosion Control Details for details.

B5 SEDIMENT CONTROL MEASURES FOR CONCENTRATED FLOW AREAS Proposed swales will be stabilized with erosion control blankets. Straw bales and silt fences will not be allowed as concentrated flow protection measures. Refer to the Erosion Control Plan for locations and the Erosion Control Details for details.

B6 STORM SEWER INLET PROTECTION MEASURE LOCATIONS AND SPECIFICATIONS The contractor shall install appropriate inlet protection measures at each inlet. Refer to the Erosion Control Plan for locations and

the Erosion Control Details for details. Straw bales will not be allowed as inlet protection measures. These inlet protection measures should be installed as soon as the inlets are installed or shortly thereafter.

B7 RUNOFF CONTROL MEASURES

B8 STORMWATER OUTLET PROTECTION MEASURES Riprap aprons will be used at the detention pond outlet to prevent erosion.

B9 GRADE STABILIZATION STRUCTURE LOCATIONS

B10 LOCATION, DIMENSIONS, SPECIFICATIONS, AND CONSTRUCTION DETAILS OF EACH STORMWATER QUALITY MEASURE Refer to the Erosion Control Plan for locations of each stormwater quality measure and the Erosion Control Details and Site

B11 TEMPORARY SURFACE STABILIZATION METHODS APPROPRIATE FOR EACH SEASON

Surface stabilization is required on any bare or thinly vegetated areas that is scheduled or likely to remain inactive for a period of 10 days or more. Refer to the Temporary Seeding Detail within the Erosion Control Details for specifics on soil amendments, se mixtures, and mulching. The surface stabilization for the lots needs to be established as soon as possible to prevent dirt wash-out into the streets. If this is not possible, then silt fencing will need to be installed along the back of curbs.

B12 PERMANENT SURFACE STABILIZATION SPECIFICATIONS 1.) Loosen lawn area to a minimum depth of 6 inches. Mix soil amendments and fertilizers with topsoil at rates specified. Organic soil amendments such as peat, compost, or manure shall be applied at 2" depth evenly over soil and incorporated into the top 6" of topsoil. Provide fertilizer with percentage of nitrogen required to provide not less than 1 pound of actual nitrogen per 1,000 square feet of lawn area and not less than 4 percent phosphoric acid and 2 percent potassium. At least 50 percent of nitrogen to

be organic form. Delay mixing of fertilizer if planting will not follow placing of planting soil within a few days. 2.) Fertilizer for lawns: provide a fast release fertilizer with a composition of 1 lb per 1,000 square feet of actual nitrogen, 4 percent phosphorous, and 2 percent potassium by weight. 3.) Slow-release fertilizer for trees and shrubs: granular fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorous and potassium made up of a composition by weight of 5 percent.

4.) Grade lawn and grass areas to a smooth, even surface with loose, uniformly fine texture. Limit fine grading to areas that can be planted within immediate future. Remove trash, debris, stones larger than 1 inch diameter, and other objects that may interfere with planting or maintenance operations. Sow seed using a spreader of seeding machine. Do not seed when wind velocity exceeds 5 miles per hour.

5.) Distribute seed evenly over entire area by sowing equal quantity in 2 directions at right angles to each other. 6.) Rake seed lightly into top 1/8 inch of soil, roll lightly, and water with a fine spray. 7.) Install erosion control blankets as indicated on the Erosion Control Plan. 8.) Protect seeded areas against erosion by spreading clean, seed-free straw mulch after completion of speeding operations. Spread uniformly to form a continuous blanket not less than 1-1/2 inches loose measurements over seeded areas.

9.) Water newly planted lawn areas and keep moist until new grass is established. Immediately repair any lawn areas disturbed by construction activities including tree and shrub installation. 10.) Refer to the Permanent Seeding Details within the Erosion Control Detail Sheet, for timing of permanent seeding, grass seed specifications and mulching specifications.

B13 MATERIAL HANDLING AND SPILL PREVENTION PLAN

No solid material, including building materials, is permitted to be discharged to surface waters or buried on site. All solid waste materials, including disposable materials incidental to construction activity, must be collected in containers or closed dumpsters. The collection containers must be emptied periodically and the collected material hauled to a landfill permitted by the State and/or appropriate local municipality to accept the waste for disposal.

A foreman or supervisor should be designated in writing to oversee, enforce, and instruct construction workers on proper solid

waste procedures. Whenever possible, minimize the use of hazardous materials and generation of hazardous wastes. All hazardous waste materials

will be disposed in the manner specified by federal, state, or local regulations or by the manufacturer. Use containment berms in fueling and maintenance areas and where potential for spills is high.

A foreman or supervisor should be designated in writing to oversee, enforce, and instruct construction workers on proper hazardous waste procedures. The location of any hazardous waste storage areas should be indicated on the stormwater pollution prevention plan by the operator following on-site location of the facility.

Dust Control/Off-Site Vehicle Tracking During construction, water trucks should be used, as needed, by each contractor or subcontractor to reduce dust. After construction, the site should stabilized to reduce dust.

Construction traffic should enter and exit the site at a Construction Entrance with a rock pad or equivalent device. The purpose of the rock pad is to minimize the amount of soil and mud that is tracked onto existing street. If sediment escapes the construction site, off-site accumulations of sediment must be removed a frequency sufficient to minimize off-site impacts.

Contractors and subcontractors must comply with all state and local sanitary sewer, portable toilet, or septic system regulations. Sanitary facilities shall be provided at the site by each contractor or subcontractor throughout construction activities. The sanitary facilities should be utilized by all construction personnel and be serviced regularly. All expenses

associated with providing sanitary facilities are the responsibility of the contractors and subcontractors. The location of B15 EROSION AND SEDIMENT CONTROL SPECIFICATIONS FOR INDIVIDUAL BUILDING LOTS any sanitary facilities should be indicated on the stormwater pollution prevention plan by the operator following on-site location of said facilities.

Water used to establish and maintain grass, to control dust, and for other construction purposes must originate from a public water supply or private well approved by the State or local health department.

Equipment fueling, maintenance, and cleaning should only be completed in protected areas (i.e., bermed area). Leaking equipment and maintenance fluids will be collected and not allowed to discharge onto soil where they may be washed away during a rain event.

Equipment wash-down (except wheel washes) should take place within an area surrounded by a berm. The use of detergents is prohibited.

Chemicals, paint, solvents, fertilizers, and other toxic or hazardous materials should be stored in their original containers (if original container is not resealable, store the products in a clearly labeled, waterproof container). Except during application, the containers should be kept in trucks or in bermed areas within covered storage facilities. Runoff containing such materials shall be collected, removed from the site, and disposed of in accordance with the federal state, and local

As may be required by federal, state or local regulations, the Contractor should have a Hazardous Materials Management Plan and/or Hazardous Materials Spill and Prevention Program in place. A foreman or supervisor should be designated in writing to oversee, enforce, and instruct construction workers on proper hazardous materials storage and handling procedures. The location of any hazardous material storage areas should be indicated on the stormwater pollution prevention plan by the operator following on-site location of the storage areas.

Discharge of hazardous substances or oil into stormwater is subject to reporting requirements. In the event of a spill of ahazardous substance, the operator is required to notify the National Response Center (1-800-424-8802) to properly report the spill. In addition, the operator shall submit a written description of the release (including the type and amount of material released, the date of the release, the circumstances of the release, and the steps to be taken to prevent future spill) to the local governing authority. The SWPPP must be revised within 14 calendar days after the release to reflect the release, stating the information above along with modifications minimize the possibility of future occurrences. Each contractor and subcontactor is responsible for complying with these reporting requirements.

All concrete trucks waste material shall be completely contained and disposed in accordance with all local, state, and federal regulations. A pit or container is required when cleaning concrete chutes.

Minor - Small spills that typically involve oil, gasoline, paint, hydraulic fluid, etc. can be controlled by the first responder at the discovery of the spill. • Contain spill to prevent material from entering storm or groundwater. Do not flush with water or bury. • Use absorbent material to clean-up spill material and any subsequently contaminated soil and dispose of properly.

Semi-Significant Spills - Approximately ten gallons or less of pollutant with no contamination of ground or surface waters. Minor spills can be generally controlled by the first responder with help from other site personnel. This response may require other operations to stop to make sure the spill is quickly and safely addressed. At the discovery of the spill: • Contain spill to prevent material from entering storm or ground water. Do not flush with water or bury. • Use absorbent material to clean-up spills and dispose of properly. Spills on impervious surfaces should be disposed of as soon as possible to prevent migration deeper into the soil and groundwater. Dispose of contaminated soils or

absorbents properly. Contact 911 if the spill could be a safety issue Contact supervisors and designated site inspectors, including MS4 personnel, immediately.

 Contaminated solids are to be removed to an approved landfill Major or Hazardous Spills - More than ten gallons, there is the potential for death, injury or illness to humans or animals, or has the potential for surface or groundwater pollution. • Control or contain the spill without risking bodily harm. Temporarily plug storm drains if possible to prevent migration

of the spill into the stormwater system Immediately contact the local Fire Department at 911 to report any hazardous material spill. • Contact supervisors and designated site inspectors immediately. Governing authorities, including MS4 personnel, responsible for stormeater facilities should be contacted as well. The contractor is responsible for having these contact

numbers available at the job site. A written report should be submitted to the owner as soon as possible. • As soon as possible but within 2 hours of discovery, contact the local agency responsible for spill management. The following information should be noted for future reports to the agency:

•• The location of the spill •• The time of the spill •• Identification of the spilled substance

• Name, address and phone number of person making the spill report

•• Approximate quantity of the substance that has been spilled or may be further spilled

•• The duration and source of the spill •• Name and location of the damaged waters Name of spill response organization

•• What measures were taken in the spill response Other information that may be significant

Additional regulations or requirement may be present. A spill response professional should be consulted to make sure all appropriate and required steps have been taken. Contaminated solids should only be removed from the site after

B14 MONITORING AND MAINTENANCE GUIDELINES FOR EACH PROPOSED STORMWATER QUALITY MEASURE

All impacted areas, as well as all erosion and sediment control devices, will be inspected every seven (7) calendar days and within 24 hours after a rianfall of 0.5 inch or greater. Where sites have been final or temporarily stabilized or on sites where runoff is unlikely due to winter conditions (e.g. site is covered with snow, ice, or frozen ground exists), such inspections shall be conducted at least once every month.

Inspections shall be conducted and a written report prepared, by a designated and qualified person familiar with the USEPA NPDES Storm Water General Permit, this SWPPP, and the Project

Inspection reports shall be completed including scope of the inspection, name(s) and qualifications of personnel making the inspection, the date of the inspection, observations relating to the implementation of the SWPPP, and any actions taken as a result of incidents of noncompliance noted during the inspection. The inspection report should state whether the site was in compliance or identify and incidents of noncompliance. The contractor shall keep a copy of the inspection reports on site and permanently for a period of two years following construction. The on-site reports may be requested by inspections conducted by the local governing authority.

Locations where vehicles exit the site shall be inspected for evidence of off-site sediment tracking. Each contractor and subcontractor shall be responsible for maintaining the Construction Entrance and other controls as described in this

Material Storage Inspections Inspectors must evaluate areas used for storage of materials that are exposed to precipitation. The purpose is to ensure that materials are protected and/or impounded so that pollutants cannot discharge from storage areas. Off-site material storage areas used solely b the subject project are considered to be part of the project and must be included in the erosion control plans and site inspection reports.

Seeded areas will be inspected to confirm that a healthy stand of vegetation is maintained. The site has achieved final stabilization once all areas are covered with pavement or have a stand of vegetation with at least 70% of the background vegetation density. The density of 70% or greater must be maintained to be considered as stabilized. The operator or their representative will water, fertilize, and reseed disturbed areas as needed to achieve this goal.

Erosion and Sediment Control Inspection All controls should be inspected at least once every seven (7) calendar days and following any storm event of 0.5 inch or greater. The following is a list of inspection/maintenance practices that will be used for specific controls:

1. Geotextiles/Erosion Control Mats: Missing or loose matting must be replaced or re-anchored. 2. Inlet Protection: If silt fence inlet protection is to be used, sediment should be removed when it reaches approximately one-half the height of the fence. If a sump is used, sediment should be removed when the volume of the basin is reduced by 50%.

3. Mulching: Inspect for thin or bare spots caused by natural decomposition or weather-related events. Mulch in high traffic areas should be replaced on a regular basis to maintain uniform protection. 4. Silt Fence: Removal of built-up sediment will occur when the sediment reaches one-third the height of the fence.

5. Stabilized Construction Entrance: Periodic re-grading and top dressing with additional stone. 6. Vegetation: Protect newly seeded areas from excessive runoff and traffic until vegetation is established. Establish a watering and fertilizing schedule. 7. Good Housekeeping: Litter, construction debris, and construction chemicals exposed to stormwater shall be

prevented from becoming a pollutant source for stormwater discharges through screening of outfalls and daily pickup

In the event that sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize adverse impacts. An example of this may be the situation where sediment has washed into the street and could be carried into the storm sewers by the next rainfall and/or pose a safety hazard to user of public

Modifications/Revisions to SWPPP Based on inspection results, any necessary modification to this SWPPP shall be implemented within seven (7) calendar

days of the inspection. A modification is necessary if a control measure or operational procedure does not provide adequate pollutant control. All revisions shall be recorded on a Record of Revisions within seven (7) calendar days of the

It is the responsibility of the operator to maintain effective pollutant discharge controls. Physical site conditions or contractor/subcontractor practices could make it necessary to install more control than were originally planned. Fore example, localized concentrations of surface runoff or unusually steep areas could required additional silt barrier or other structural controls. Assessing the need for and installing additional controls will be a continuing contractor/subcontractor responsibility until final stabilization is achieved. Contractors and subcontractors implementing this SWPPP must remain alert to the need to periodically refine and update this SWPPP in order to accomplish the intended goals.

Compliance of the site with the General Construction Permit remains the responsibility of all operators that have submitted an NOI until such time as they have submitted a Notice of Termination (NOT). The permittee's authorization to discharge under the General Construction Permit terminates at midnight of the day the NOT is signed.

All permittees must submit an NOT within thirty (30) days after one or more of the following conditions have been met: 1. Final stabilization has been achieved on all portions of the site for which the permittee was responsbile.

2. Another operator/permittee has assumed control over all areas of the site that have not been finally stabilized. 3. In residential construction operations, temporary stabilization has been completed and the residence has been transferred to the homeowner.

The site is not currently subdivided, therefore the entire site is on this plan's Erosion Control Plan.

C1 DESCRIPTION OF POLLUTANTS AND THEIR SOURCES ASSOCIATED WITH THE PROPOSED LAND USE

The proposed land use is for the expansion of the Knox County Justice Facility. The pollutants and sources of each pollutant normally expected from this type of land use are:

Pollutant Source: Passenger vehicles, delivery vehicles. Type of Pollutant: Oil, gasoline, diesel fuel, any hydrocarbon associated with vehicular fuels and lubricants, grease, antifreeze, windshield cleaner solution, brake fluid, dust, rubber, glass, metal and plastic fragments, grit, road de-icing

Pollutant Source: Building Type of Pollutant: Cleaning solutions or solvents, leaks from HVAC equipment, grit from roof drainage, aggregate or rubber fragments from roofing system.

Type of Pollutant: Cleaning solutions or solvents, litter (paper, plastic, general refuse associated with distribution operations), uneaten food products, bacteria.

Pollutant Source: Parking Lot Type of Pollutant: Any pollutant associated with vehicular sources, grit from asphalt wearing surface, bituminous compounds from periodic maintenance (sealing, resurfacing, and patching), pavement de-icing materials, paint fragments from parking stall striping, concrete fragments, wind-blown litter from off-site sources, elevated water temperatures from

contact with impervious surfaces. Pollutant Source: Lawn and Landscape Areas

Type of Pollutant: Fertilizers, soil, organic material (leaves, mulch, grass clippings)

C2 SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION The grass-lined channels and swales will serve as the permanent water quality features after construction is complete. The purpose of these features is to filter pollutants and sediment.

C3 DESCRIPTION OF PROPOSED POST-CONSTRUCTION STORMWATER QUALITY MEASURES

Vegetated swales are designed to reduce pollutant and sediment loads in stormwater runoff. Stormwater runoff is directioned in the swale which conveys the runoff from the site. While moving through the swale, runoff velocity is greatly decreased allowing biofiltration (uptake of nutrients by plants), infiltration (percolation of water through the swale's porous soil substrate), and sedimentation (settling of later suspended particles).

Topsoil will be placed in lawn areas and seeded with grass, and graded not to exceed 3:1 slopes. Proposed landscape trees and shrubs will also be added. These bio areas will act as a natural filter strip to help improve stormwater quality. The vegetated areas will slow the velocities of stormwater runoff, reduce sediment runoff, and reduce problems associated with mud or dust from bare soils.

Good housekeeping measures such as regular street or pavement sweeping, installation of trash receptacles, and

reduction in fertilizer overspray can be incorporated by the owner and/or occupant. C4 LOCATION, DIMENSIONS, SPECIFICATIONS, AND CONSTRUCTION DETAILS OF EACH STORMWATER QUALITY MEASURE

Refer to the Erosion Control Plans for locations and Erosion Control Details for details.

C5 DESCRIPTION OF MAINTENANCE GUIDELINES FOR POST-CONSTRUCTION STORMWATER QUALITY MEASURES

Maintenance requirements for the stormwater quality measures which will remain in place after construction is complete are described below.

Vegetated swales require little maintenance if properly designed. Mow as needed during the growing season; inspect for erosion control problems twice during the first year, annually thereafter; and removed sediment, trash and debris annually

or more frequently if needed.

Remove debris and sediment from entire pond when necessary. Inspect perimeter of basin annually and after major storm events. Regrade soil if gullies form and replant ground. Inspect inlet and outlet devices and structures annually and after major storm events.

SOILS MAP

Brookston Silty Clay Loam, 0 to 2 percent slopes (Br) Hydrologic Soils Group C (HSG B) Crosby Silt Loam, New Castle Till Plain, 0 to 2 percent slopes (CrA) Hydrologic Soils Group C (HSG C) Miami Silt Loam, 2 to 6 percent slopes, eroded (MmB2) Hydrologic Soils Group C (HSG C)



ш Z S S

Revision Date ADDENDUM #2 02.21.2022

Ž

Project #: 20-700-151-2

Drawn By: JLB


Date: 12/29/2021

Checked By: CJR

Designed By: MSO

NOT FOR CONSTRUCTION

STORMWATER



2'-0" FROM EDGE SIDE VIEW

PAVEMENT

NOT TO SCALE

NOTES:

1. OR APPROVED EQUAL

PRECAST CONCRETE WHEELSTOP


SECTION A-A


" COMPACTED #53 STONE AGGREGATE


- COMPACTED SUBGRADE

NOTES: 1. PREPARED SUBGRADE PER INDOT

SPECIFICATIONS, LATEST EDITION









PAINTED CROSSWALKS 4" SOLID YELLOW LINE PAVEMENT MARKINGS

4" SOLID BLUE LINE PAVEMENT MARKINGS FOR ADA ISLANDS. 4" SOLID YELLOW LINE PAVEMENT MARKINGS FOR NON-ADA

ADA PARKING SIGN DETAIL PAVEMENT STRIPING DETAIL NOT TO SCALE





PLASTIC PIPE BEDDING SECTION NOT TO SCALE

GRADE (NEW OR EXISTING) -- PAVEMENT SECTION — TOP OF CURB — TRANSVERSE EXPANSION JOINTS igwidth CONTRACTION JOINTS ON RADII TRANSVERSE CONTRACTION JOINTS — (5' MAX. SPACING) (10' MAX SPACING) **CURB JOINT DETAIL**


NOT TO SCALE

NOT TO SCALE

- 3" HOLES FOR STEEL

ELEVATION





SECTION A (TYP.)


CONCRETE SIDEWALK DETAIL

NOT TO SCALE

ALL STRIPS TO BE PAINTED 4" BLUE


ADA PARKING SYMBOL DETAIL

NOT TO SCALE




CONCRETE PAVING JOINT DETAILS

NOT TO SCALE



ADA PARKING STALLS WITH SIDEWALK DETAIL

NOT TO SCALE



PAD SIZE SHALL BE AS SHOWN ON THE PLANS OR AS INDICATED BY THE EQUIPMENT MANUFACTURER. 2. THE SIZE, NUMBER, TYPE, LOCATION OF THE ANCHOR BOLTS SHALL BE DETERMINED BY THE EQUIPMENT MANUFACTURER AND AS APPROVED BY THE ENGINEER. 3. HEIGHT OF PADS SHALL BE MINIMUM REQUIRED FOR ANCHOR BOLT CLEARANCE (SEE TABLE BELOW)

EQUIPMENT

-#5 @ 12" O.C. E.W. CENTERED

ANCHORS AS PER :

NOTE BELOW

ANCHORØ (IN)	5/8	3/4	7/8	1	1 1/2
MIN. PAD THICKNESS (IN)	8 1/2	10	11	12 1/2	18

4. AT CONTRACTORS OPTION, CONCRETE ANCHORS MAY BE USED IN-LIEU OF CAST-IN-PLACE ANCHORS ANCHORS 3/4" OR LESS IN DIA. THIS REQUIRES APPROVAL FROM EQUIPMENT MANUFACTURER & THE ENGINEER. ANCHORS SHALL BE INSTALLED WITH 4" MIN. EDGE DISTANCE.

> **EQUPMENT PAD DETAIL** NOT TO SCALE

COMMISSIONER 0 ARD \Box COUNTY KNOX

ı			

Revision

ADDENDUM #2 02.21.2022

Date

Project #: 20-700-151-2 Designed By: MSO


Drawn By: JLB Checked By: CJR


Date: 12/29/2021


- 6" MIN.

NOT FOR CONSTRUCTION

CONSTRUCTION **DETAILS**







NOT TO SCALE



COUNTY BOARD OF COMMISSIONERS X COUNTY JUSTICE CAMPUS

#	Revision	Date
1	ADDENDUM #2	02.21.2022

KNOX

Project #: 20-700-151-2
Designed By: MSO


Drawn By: JLB

Checked By: CJR

Date: 12/29/2021

NOT FOR CONSTRUCTION

CONSTRUCTION DETAILS





OX COUNTY JAIL

BID

Revision Date
1 ADDENDUM #2 21 FEB 2021

Project #: 20-700-151-2

Designed By: NBV

Drawn By: JLB


Checked By: NBV


Date: 01/28/2022

PE11500269
STATE OF
NO.
PENSONAL ENGINEERS

WALLENGTON

CONSTRUCTION DETAILS






A2 Addendum #2 02.21.2022

Project #: 20-700-151-2




These Drawings and Specifications, and all copies thereof are and shall remain the property and copyright of the Architect. They shall be used only with respect to this Project and are not to be used




FIRST FLOOR PIPING PLAN

M310B






on any other Project or Work without prior written



FIRST FLOOR PIPING PLAN



Revision 02.14.2022 A2 Addendum #2 02.21.2022


Project #: 20-700-151-2

Drawn By: N.J.H.




These Drawings and Specifications, and all copies thereof are and shall remain the property and copyright of the Architect. They shall be used only with respect to this Project and are not to be used


on any other Project or Work without prior written permission from the Architect





FIRST FLOOR PIPING PLAN


M310F















A2 ADDENDUM 2 02-21-2022

Project #: 20-700-151-2

Designed By: D.K. BENELL


These Drawings and Specifications, and all copies


thereof are and shall remain the property and copyright of the Architect. They shall be used only with respect to this Project and are not to be used on any other Project or Work without prior written





FOUNDATION PLUMBING


P200A























ELECTRONICALLY FILE YOUR PROJECT WITH STATE OF INDIANA at http://www.in.gov/dhs/2650.htm.

This on-line filing is through a secure site, you can use it to submit your project information, pay the fees and upload your project plans.

Use Internet Browser to View this report, other browsers are not compatible to view this report



CONSTRUCTION DESIGN RELEASE

State Form 41191 (R9/5-98)

Report Printed on: May 4, 2021

Indiana Department of Homeland Security DIVISION OF FIRE & BUILDING SAFETY PLAN REVIEW DIVISION 402 W. Washington St., Room E245 Indianapolis, IN 46204



To: Owner / Architect / Engineer
Delv Design Studio LLC
Christopher W Lake AR10400187
212 W 10th Street Ste F125
Suite F125

Indianapolis IN 46202

Fax & e-mail: 0000000000, chris@delvdesign.com

Project number		Release date			
422423		05/04/21			
Construction type	Occupar	ncy classification			
V-B, SPK	R-2, A	ADD, REM			
Scope of release					
ARCH ELEC FA FDN PLUM STR	MECH				
Type of release					
Standard					
Project name					
Gamma Gamma Of Ato, Inc - Rose-Hulman					
Street address					
5500 Wabash Ave.					
City	County				
TERRE HAUTE	VIGO				

The plans, specifications and application submitted for the above referenced project have been reviewed for compliance with the applicable rules of the Fire Prevention and Building Safety Commission. The project is released for construction subject to, but not necessarily limited to, the conditions listed below. THIS IS NOT A BUILDING PERMIT. All required local permits and licenses must be obtained prior to beginning construction work. All construction work must be in full compliance with all applicable State rules. Any changes in the released plans and/or specifications must be filed with and released by this Office before any work is altered. This release may be suspended or revoked if it is determined to be issued in error, in violation of any rules of the Commission or if it is based on incorrect or insufficient information. This release shall expire by limitation, and become null and void, if the work authorized is not commenced within one (1) year from the above date. CONDITIONS:

Note :(A1A & A1B): In accordance with the affidavit sworn under penalties of perjury in the application for construction design release the plans and specifications filed in conjunction with this project shall comply with all of the applicable rules and laws of Fire Prevention and Building Safety Commission. Providing false information constitutes an act of perjury, which is a Class D felony punishable by a prison term and a fine up to \$10,000.

In accordance with Section 19 of the General Administrative Rules (675 IAC 12-6-19) a complete set of plans and specifications that conform exactly to the design that was released by the office of the state building commissioner shall be maintained on the construction jobsite as well as a copy of the design release.

14B	This project has been reviewed under the 2014 Indiana Building Code.	
4G0603AF	Detailed plans and specifications for the revised fire suppression system shall be filed with the required application and appropriate fees in accordance with 675 IAC 12-6- 3(a), 675 IAC 12-6-7(g)(17), and 675 IAC 13-1-8. (N.F.P.A. 13)	
A2	An elevator installation permit shall be obtained from the Elevator Safety Division in accordance with IESC (675 IAC 21-1-1). Please visit: http://www.in.gov/dhs/2374.htm	
AREL	Pursuant to 675 IAC 12-6-21, the issuance of a design release does not relieve the owner from required compliance with all applicable rules of the commission, even if noncompliant conditions appear in the plans and specifications that have been filed with the division. The owner is responsible for correcting any and all areas of noncompliance even if they are discovered subsequent to the issuing of this design release.	

This order is effective upon service. If you would like to request informal review of this order, please complete the informal review form located at https://www.in.gov/dhs/4149.htm. Following receipt of this form, the Department may modify or reverse the order, however, a request for an informal review does not extend the deadline for filing a petition for review with the Fire Prevention and Building Safety Commission (Commission). Additionally, if you have any questions regarding this order, you may contact that Department at (317) 232-2222.

If you desire a formal administrative review of this order by the Commission, you must comply with the requirements of Indiana Code § 4-21.5-3-7 and file a written petition for review within 15 days of the date this order was served, however, this period is extended to 18 days if service is made by mail. Your petition for review must state facts demonstrating that you are: (1) a person to whom the order is specifically directed; (2) aggrieved or adversely affected by the order; or (3) entitled to review under any law. You may submit your petition by the following methods:

U.S. MAIL OR PERSONAL SERVICE Fire Prevention and Building Safety Commission c/o Legal Counsel 302 W. Washington Street, Rm. E208 Indianapolis, IN 46204 ONLINE
By completing the form at https://www.in.gov/dhs/4148.htm

For additional information about the administrative review process and applicable templates that may be used for filings, visit the following link https://www.in.gov/dhs/appeals.htm.

ELECTRONICALLY FILE YOUR PROJECT WITH STATE OF INDIANA at http://www.in.gov/dhs/2650.htm.

This on-line filing is through a secure site, you can use it to submit your project information, pay the fees and upload your project plans.

Use Internet Browser to View this report, other browsers are not compatible to view this report

Code review official ROBIN PHILLIPS rphillips@dhs.in.gov	Indiana State Building Commissioner
Address (name,title of local official,street,city,state and ZIP code BUILDING COMMISSIONER Daniel Bell I7 HARDING AVENUE ROOM 203	CB.
TERRE HAUTE, IN 47807 Fax & e-mail: 8122343973, daniel.bell@terrehaute.in.gov	1 0



